

AMERICAN TOWER®


ATC SITE NAME: LIBERTY UT ATC SITE NUMBER: 280216 T-MOBILE SITE NAME: ATC, WOLF CREEK, EDEN UT T-MOBILE SITE NUMBER: SL03051A SITE ADDRESS: 4909 N WILLOWBROOKE LN EDEN, UT 84310-9651



LOCATION MAP

T-MOBILE ANCHOR AMENDMENT PLAN 67D53998E_1xAIR+1OP CONFIGURATION

| | | | | SHEET INDEX | | | | |
|---|--|---|-----------|--------------------------------|------|----------|-----|--|
| COMPLIANCE CODE | PROJECT SUMMARY | PROJECT DESCRIPTION | | | | | | |
| ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE | <u>SITE ADDRESS:</u> 4909 N WILLOWBROOKE LN | THE PROPOSED PROJECT INCLUDES MODIFYING GROUND BASED AND TOWER MOUNTED EQUIPMENT AS INDICATED PER BELOW: | SHEET NO: | DESCRIPTION: | REV: | DATE: | BY: | |
| FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNMENT AUTHORITIES, NOTHING IN THESE PLANS IS | EDEN, UT 84310-9651 | TOWER WORK: | G-001 | TITLE SHEET | 0 | 12/13/24 | SSP | |
| TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES. | COUNTY: WEBER | REMOVE (3) ANTENNA(S), (6) RRU(s), AND (1) 1-3/8" (35.0MM) HYBRID CABLE(S). | G-002 | GENERAL NOTES | 0 | 12/13/24 | SSP | |
| 1. 2021 INTERNATIONAL BUILDING CODE (IBC) | GEOGRAPHIC COORDINATES: | INSTALL (3) ANTENNA(S), (3) RRU(s), AND (2) 2.00" (50.8MM) HYBRID | C-001 | OVERALL SITE PLAN | 0 | 12/13/24 | SSP | |
| 2. 2020 NATIONAL ELECTRIC CODE (NEC) | LATITUDE: 41.31935 | TRUNK(S). | C-101 | DETAILED SITE PLAN | 0 | 12/13/24 | SSP | |
| 3. LOCAL BUILDING CODE | LONGITUDE: -111.82952 | EXISTING (3) ANTENNA(S), (3) RRU(s), AND (1) 1.54" (39.2MM) HYBRID | | | | | | |
| 4. CITY/COUNTY ORDINANCES | GROUND ELEVATION: 5,069' AMSL | CABLE(S) TO REMAIN. | C-102 | DETAILED EQUIPMENT LAYOUT | 0 | 12/13/24 | SSP | |
| | ZONING INFORMATION: | GROUND WORK: | C-201 | TOWER ELEVATION | 0 | 12/13/24 | SSP | |
| | JURISDICTION: WEBER COUNTY | REMOVE (1) RBS 6102 MU AC CABINET(S), (1) BB 5216(s), AND (1) DUW30(s). | C-401 | ANTENNA INFORMATION & SCHEDULE | 0 | 12/13/24 | SSP | |
| | PARCEL ID: 223000002 | INSTALL (2) RP6651(s), (2) 19 INCH RACK(S), AND (1) POWER 6230(s). | C-501 | CONSTRUCTION DETAILS | 0 | 12/13/24 | SSP | |
| | | | E-501 | GROUNDING DETAIL | 0 | 12/13/24 | SSP | |
| | PROJECT TEAM | EXISTING (1) BB 6630(s) AND (1) CSR IXRE V2(s) TO BE INSTALLED IN NEW 19" RACK. | R-601 | SUPPLEMENTAL | | | | |
| | TOWER OWNER: APPLICANT: | | R-602 | SUPPLEMENTAL | | | | |
| | AMERICAN TOWER T-MOBILE WEST LLC | | R-603 | SUPPLEMENTAL | | | | |
| | 10 PRESIDENTIAL WAY 3650 131ST AVE SE WOBURN, MA 01801 BELLEVUE, WA 98006 | | R-604 | SUPPLEMENTAL | | | | |
| | | | R-605 | SUPPLEMENTAL | | | | |
| | ENGINEER: PROPERTY OWNER: TEP VALLEY STORAGE OF EDEN LI | PROJECT NOTES | R-606 | SUPPLEMENTAL | | | | |
| UTILITY COMPANIES | 326 TRYON RD 939 DEER MEADOW DRIVE RALEIGH, NC 27603 NORTH OGDEN, UT 84414293 | 1. THE FACILITY IS UNMANNED. | R-607 | SUPPLEMENTAL | | | | |
| POWER COMPANY: PACIFICORP | | MONTH FOR ROUTINE INSPECTION AND MAINTENANCE. 3. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT LAND | | | | | | |
| PHONE: (888) 221-7070 | PROJECT LOCATION DIRECTIONS | DISTURBANCE OR EFFECT OF STORM WATER DRAINAGE. 4. NO SANITARY SEWER, POTABLE WATER OR TRASH DISPOSAL | | | | | | |
| TELEPHONE COMPANY: CENTURYLINK PHONE: (800) 603-6000 | FROM SLC DRIVE NORTH ON I-15 FOR 16 MILES TO EXIT 324 ANI | IS REQUIRED. 5. HANDICAP ACCESS IS NOT REQUIRED. 6. THE DROLEGY DEPIDITED IN THESE READS ON ALLERS AS AN | | | | | | |
| Know what below. Call before you dig. | DRIVE NORTH ON HWY 89 FOR 10.4 MILES AND TURN RIGHT ON I FOR 4.4 MILES TO EXIT 92 AND DRIVE UNDER FREEWAY AND TUR RIGHT ONTO SR-167 FOR 2.8 MILES AND TURN RIGHT ONTO SR-1 TRAPPERS LOOP AND DRIVE 8.2 MILES AND TURN LEFT ONTO SR-39 FOR 3.7 MILES AND STAY RIGHT ONTO SR-158 AND DRIVI FOR 5 MILES TO THE STORAGE UNITS ON THE LEFT HAND SIDE | 64 ELIGIBLE FACILITIES REQUEST ENTITLED TO EXPEDITED RN REVIEW UNDER 47 U.S.C. § 1455(A) AS A MODIFICATION OF AN 67 EXISTING WIRELESS TOWER THAT INVOLVES THE 67 COLLOCATION, REMOVAL, AND/OR REPLACEMENT OF 68 THAT INVOLVES THE | | | | | | |



GENERAL CONSTRUCTION NOTES:

- OWNER FURNISHED MATERIALS, T-MOBILE "THE COMPANY" WILL PROVIDE AND THE CONTRACTOR WILL INSTALL
 - A. BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND BUILD/CO-LOCATE ONLY)
 - AC/TELCO INTERFACE BOX (PPC)
 - ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-LOCATE ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)
 - D. TOWERS, MONOPOLES
 - TOWER LIGHTING
 - GENERATORS & LIQUID PROPANE TANK
 - ANTENNA STANDARD BRACKETS, FRAMES AND PIPES FOR MOUNTING ANTENNAS (INSTALLED BY OTHERS)
 - TRANSMISSION LINE
 - TRANSMISSION LINE JUMPERS
 - TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS
 - TRANSMISSION LINE GROUND KITS
 - HANGERS
 - HOISTING GRIPS
- O. BTS EQUIPMENT
- 2 THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM, ROOFING LABOR AND MATERIALS, GROUNDING RINGS, GROUNDING WIRES COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE, TEMPORARY ELECTRICAL POWER, CONDUIT, LANDSCAPING COMPOUND STONE, CRANES, CORE DRILLING, SI EEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSONS, PADS AND/OR AUGER MOUNTS, MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF T-MOBILE TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF REQUIRED PERMITS
- ALL WORK SHALL CONFORM TO ALL CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL CODES, INCLUDING ANSI/EIA/TIA-222, AND COMPLY WITH ATC CONSTRUCTION SPECIFICATIONS
- CONTRACTOR SHALL CONTACT LOCAL 811 FOR IDENTIFICATION OF UNDERGROUND UTILITIES PRIOR TO START OF CONSTRUCTION
- CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED INSPECTIONS.
- ALL DIMENSIONS TO, OF, AND ON EXISTING BUILDINGS, DRAINAGE STRUCTURES, AND SITE IMPROVEMENTS SHALL BE VERIFIED IN FIELD BY CONTRACTOR WITH ALL DISCREPANCIES REPORTED TO THE ENGINEER.
- DO NOT CHANGE SIZE OR SPACING OF STRUCTURAL ELEMENTS 7
- 8 DETAILS SHOWN ARE TYPICAL: SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS UNLESS
- THESE DRAWINGS DO NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION 9. SAFETY WHICH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR
- CONTRACTOR SHALL BRACE STRUCTURES UNTIL ALL STRUCTURAL ELEMENTS NEEDED 10. FOR STABILITY ARE INSTALLED. THESE ELEMENTS ARE AS FOLLOWS: LATERAL BRACING, ANCHOR BOLTS, ETC.
- CONTRACTOR SHALL DETERMINE EXACT LOCATION OF EXISTING UTILITIES. GROUNDS 11. DRAINS, DRAIN PIPES, VENTS, ETC, BEFORE COMMENCING WORK
- INCORRECTLY FABRICATED, DAMAGED, OR OTHERWISE MISFITTING OR NONCONFORMING MATERIALS OR CONDITIONS SHALL BE REPORTED TO THE T-MOBILE 12. REP PRIOR TO REMEDIAL OR CORRECTIVE ACTION, ANY SUCH REMEDIAL ACTION SHALL REQUIRE WRITTEN APPROVAL BY THE T-MOBILE REP PRIOR TO PROCEEDING.
- EACH CONTRACTOR SHALL COOPERATE WITH THE T-MOBILE REP, AND COORDINATE HIS WORK WITH THE WORK OF OTHERS. 13.
- CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED BY CONSTRUCTION OF THIS 14. PROJECT TO MATCH EXISTING PRE-CONSTRUCTION CONDITIONS TO THE SATISFACTION OF THE T-MOBILE CONSTRUCTION MANAGER
- ALL CABLE/CONDUIT ENTRY/EXIT PORTS SHALL BE WEATHERPROOFED DURING 15. INSTALLATION LISING A SILICONE SEALANT
- WHERE EXISTING CONDITIONS DO NOT MATCH THOSE SHOWN IN THIS PLAN SET. 16. CONTRACTOR SHALL NOTIFY THE T-MOBILE REP AND ENGINEER OF RECORD IMMEDIATELY
- CONTRACTOR SHALL ENSURE ALL SUBCONTRACTORS ARE PROVIDED WITH A COMPLETE 17. AND CURRENT SET OF DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
- 18. CONTRACTOR SHALL REMOVE ALL RUBBISH AND DEBRIS FROM THE SITE AT THE END OF EACH DAY
- CONTRACTOR SHALL COORDINATE WORK SCHEDULE WITH AMERICAN TOWER 19. CORPORATION (ATC) AND TAKE PRECAUTIONS TO MINIMIZE IMPACT AND DISRUPTION OF OTHER OCCUPANTS OF THE FACILITY.
- CONTRACTOR SHALL FURNISH T-MOBILE AND AMERICAN TOWER CORPORATION (ATC) 20. /ITH A PDF MARKED UP AS-BUILT SET OF DRAWINGS UPON COMPLETION OF WORK
- 21. PRIOR TO SUBMISSION OF BID. CONTRACTOR SHALL COORDINATE WITH T-MOBILE. REP. TO DETERMINE WHAT, IF ANY, ITEMS WILL BE PROVIDED. ALL ITEMS NOT PROVIDED SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR. CONTRACTOR WILL INSTALL ALL ITEMS PROVIDED.

22. PRIOR TO SUBMISSION OF BID. CONTRACTOR SHALL COORDINATE WITH T-MOBILE. REP. TO DETERMINE IF ANY PERMITS WILL BE OBTAINED BY CONTRACTOR. ALL REQUIRED PERMITS NOT OBTAINED BY T-MOBILE MUST BE OBTAINED, AND PAID FOR, BY THE CONTRACTOR

23. CONTRACTOR SHALL INSTALL ALL SITE SIGNAGE IN ACCORDANCE WITH T-MOBILE SPECIFICATIONS AND REQUIREMENTS

CONTRACTOR SHALL SUBMIT ALL SHOP DRAWINGS TO T-MOBILE FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.

ALL EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND LOCATED ACCORDING TO T-MOBILE SPECIFICATIONS, AND AS SHOWN IN THESE PLANS

THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL THE CONSTRUCTION MEANS METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT

27. CONTRACTOR SHALL NOTIFY T-MOBILE REP A MINIMUM OF 48 HOURS IN ADVANCE OF POURING CONCRETE OR BACKFILLING ANY UNDERGROUND UTILITIES, FOUNDATIONS OR SEALING ANY WALL, FLOOR OR ROOF PENETRATIONS FOR ENGINEERING REVIEW AND APPROVAL

28 WHEN THE PROJECT SCOPE REQUIRES THE USE OF THE SAFETY CLIMB. THE GENERAL CONTRACTOR SHALL ENSURE THE SAFETY CLIMB IS REED FOR STRUCTIONS, NOT RUBBING ON OR TRAPPED BY ANY INSTALLED CUSTOMER EQUIPMENT, IS VISUALLY TAUT, MEETS MANUFACTURER INSTALLATION SPECIFICATIONS, AND IS FIRMLY SECURED AT ALL CABLE GUIDE LOCATIONS UPON PROJECT COMPLETION.

COMPLETION OF PROJECT SHALL NOT OBSTRUCT, TRAP, LOOSEN, OR OTHERWISE 29. CAUSE FAILURE TO MEET MANUFACTURER INSTALLATION REQUIREMENTS FOR THE SAFETY CLIMB.

CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY INCLUDING COMPLIANCE WITH ALL APPLICABLE OSHA STANDARDS AND RECOMMENDATIONS AND SHALL PROVIDE ALL NECESSARY SAFETY DEVICES INCLUDING PPE AND PPM AND CONSTRUCTION DEVICES SUCH AS WELDING AND FIRE PREVENTION, TEMPORARY SHORING, SCAFFOLDING, TRENCH BOXES/SLOPING, BARRIERS, ETC

31. THE CONTRACTOR SHALL PROTECT AT HIS OWN EXPENSE, ALL EXISTING FACILITIES AND SUCH OF HIS NEW WORK LIABLE TO INJURY DURING THE CONSTRUCTION PERIOD. ANY DAMAGE CAUSED BY NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, OR BY THE ELEMENTS DUE TO NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, EITHER TO THE EXISTING WORK, OR TO HIS WORK OR THE WORK OF ANY OTHER CONTRACTOR, SHALL BE REPAIRED AT HIS EXPENSE TO THE OWNER'S SATISFACTION

ALL WORK SHALL BE INSTALLED IN A FIRST CLASS, NEAT AND WORKMANLIKE MANNER BY MECHANICS SKILLED IN THE TRADE INVOLVED. THE QUALITY OF WORKMANSHIP SHALL BE SUBJECT TO THE APPROVAL OF THE T-MOBILE REP. ANY WORK FOUND BY THE T-MOBILE REP TO BE OF INFERIOR QUALITY AND/OR WORKMANSHIP SHALL BE REPLACED AND/OR REWORKED AT CONTRACTOR EXPENSE UNTIL APPROVAL IS OBTAINED.

33 IN ORDER TO ESTABLISH STANDARDS OF QUALITY AND PERFORMANCE, ALL TYPES OF MATERIALS LISTED HEREINAFTER BY MANUFACTURER'S NAMES AND/OR MANUFACTURER'S CATALOG NUMBER SHALL BE PROVIDED BY THESE MANUFACTURERS AS SPECIFIED.

T-MOBILE FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE T-MOBILE WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED STORED UNCRATE PROTECTED AND INSTALLED BY THE CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING IT UP

35. T-MOBILE OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY EQUIPMENT OR MATERIALS WHICH, IN HIS OWN OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS, EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO T-MOBILE OR THEIR ARCHITECT/ENGINEER

SPECIAL CONSTRUCTION ANTENNA INSTALLATION NOTES:

WORK INCLUDED:


- ANTENNA AND COAXIAI /HYBRID CABLES ARE FURNISHED BY T-MOBILE LINDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OF COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF PERSONNE
- INSTALL ANTENNAS AS INDICATED ON DRAWINGS AND T-MOBILE SPECIFICATIONS
- INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.
- INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE.

INSTALL COAXIAL/HYBRID CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTIONS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS. TERMINATE ALL COAXIAL/HYBRID CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.


2. ANTENNA AND COAXIAL/HYBRID CABLE GROUNDING:


ALL EXTERIOR #6 GREEN GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE WEATHER SEALED WITH RFS CONNECTORS/SPLICE WEATHERPROOFING KIT #221213 OR FOUAL

ALL COAXIAL/HYBRID CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL/HYBRID CABLE (NOT WITHIN BENDS



ALL DISCREPANCIES FROM WHAT IS SHOWN ON THESE CONSTRUCTION DRAWINGS SHALL BE COMMUNICATED TO ATC ENGINEERING IMMEDIATELY FOR CORRECTION OR RE-DESIGN. FAILURE TO COMMUNICATE DIRECTLY WITH ATC ENGINEERING OR ANY CHANGES FROM THE DESIGN CONDUCTED WITHOUT PRIOR APPROVAL FROM ATC ENGINEERING SHALL BE THE SOLE **RESPONSIBILITY OF THE GENERAL CONTRACTOR.**






SITE PLAN NOTES:

- THIS SITE PLAN REPRESENTS THE BEST PRESENT KNOWLEDGE AVAILABLE TO THE ENGINEER AT THE TIME OF THIS DESIGN. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO CONSTRUCTION AND VERIFY ALL EXISTING CONDITIONS RELATED TO THE SCOPE OF WORK FOR THIS PROJECT
- ICE BRIDGE, CABLE LADDER, COAX PORT, AND COAX CABLE ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM THE EXACT LOCATION OF ALL PROPOSED AND EXISTING EQUIPMENT AND STRUCTURES DEPICTED ON THIS PLAN. BEFORE UTILIZING EXISTING CABLE SUPPORTS, COAX PORTS, INSTALLING NEW PORTS OR ANY OTHER EQUIPMENT. CONTRACTOR SHALL VERIFY ALL ASPECTS OF THE COMPONENTS MEET THE ATC SPECIFICATIONS.
- THIS CONSTRUCTION DRAWING SET IS NOT INTENDED TO ADDRESS ANY ELECTRICAL UPGRADES NEEDED. ANY ELECTRICAL UPGRADES WILL BE SHOWN IN A SEPARATE CONSTRUCTION DRAWING SET.


LEGEND


| 8 | GROUNDING TEST WELL |
|--------|---------------------------|
| ATS | AUTOMATIC TRANSFER SWITCH |
| В | BOLLARD |
| CSC | CELL SITE CABINET |
| D | DISCONNECT |
| E | ELECTRICAL |
| F | FIBER |
| GEN | GENERATOR |
| G | GENERATOR RECEPTACLE |
| HH, V | HAND HOLE, VAULT |
| IB | ICE BRIDGE |
| К | KENTROX BOX |
| LC | LIGHTING CONTROL |
| М | METER |
| PB | PULL BOX |
| PP | POWER POLE |
| Т | TELCO |
| TRN | TRANSFORMER |
| 00 | CHAINLINK FENCE |
| | |



PROPOSED CABLE NOTES:


- ESTIMATED LENGTH OF PROPOSED CABLE IS <u>125</u>'. ESTIMATED LENGTH OF CABLE WAS PROVIDED BY CUSTOMER OR CALCULATED BY ADDING THE RAD CENTER AND THE DISTANCE FROM THE SHELTER ENTRY PLATE TO THE TOWER (ALONG THE ICE BRIDGE) AND A SAFETY FACTOR MEASUREMENT OF 15% (OF THE TWO PREVIOUS VALUES), CDS DEFER TO GREATEST CABLE LENGTH.
- ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER.







EXISTING 10' NO SPARK BUFFER ZONE BY OTHERS

EXISTING ICE BRIDGE BY OTHERS (TYP.)








PROPOSED T-MOBILE POWER 6230 CABINET R-605

- PROPOSED T-MOBILE EQUIPMENT TO BE INSTALLED ON 19" INCH RACK: (2) RP6651
- PROPOSED 19 INCH RACK (ANCHOR TO CONCRETE PAD) (1) (TYP. 2)
- EXISTING RELOCATED T–MOBILE EQUIPMENT INSTALLED INSIDE PROPOSED 19 INCH RACK: (1) BB 6630 (1) CSR IXRE V2
- EXISTING HVAC UNIT (TYP. 2)




PER MOUNT ANALYSIS COMPLETED BY SMJ INTERNATIONAL, DATED NOVEMBER 7, 2024 THE EXISTING MOUNT CAN ADEQUATELY SUPPORT THE PROPOSED LOADING.


IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM WITH THE PROJECT MANAGER THAT THEY HAVE THE MOST RECENT VERSION OF THE STRUCTURAL ANALYSIS BEFORE COMMENCING WORK. EXISTING AND PROPOSED TOWER APPURTENANCES, MOUNTS, AND ANTENNAS ARE SHOWN BASED ON THE STRUCTURAL ANALYSIS.

WHERE APPLICABLE, ALL NEW ANTENNAS, EQUIPMENT, MOUNTS, CABLING, ETC. SHALL BE PAINTED/SOCKED TO MATCH EXISTING EQUIPMENT IN ACCORDANCE WITH FAA, JURISDICTION, AND/OR OTHER LOCAL REQUIREMENTS.

3. ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE

TOWER ELEVATION DEPICTION MAY NOT REFLECT ALL EQUIPMENT INCLUDED IN STRUCTURAL ANALYSIS. REFER TO STRUCTURAL ANALYSIS FOR FULL TOWER LOADING.





| | | | | EXI | STING ANTENNA SCHED | ULE | | | | NOTES | | | | | FI | NAL ANTENNA SCHEDU | LE | |
|--------|--------|------|-------------|----------------------------|---------------------|----------------------|--------|---------------------------------------|------------|---|---------------------------------------|----------|---------|----------|---------------------------|---|---------------------------------------|---------------|
| LO | CATION | I | | ANT | ENNA SUMMARY | | | NON ANTENNA SUM | MARY | 1. CONFIRM WITH T-MOBILE REP | LOC | ATION | | | ANT | ENNA SUMMARY | | |
| SECTOR | RAD | AZ | POS | ANTENNA | BAND | MECH/ ELEC D-TILT | STATUS | ADDITIONAL TOWER MOUNTED EQUIPMENT | STATUS | MOST RECENT RFDS FOR NSN | SECTOR | RAD | AZ | POS | ANTENNA | BAND | MECH/ ELEC D-TILT | STATU |
| | | | A1 | CMA-BDHH/6521/E0-6/RET/B05 | U1900/L1900 | -4°/2°,2° | RMV | (1) RRUS11 B4 RRU | RMV | CONFIGURATION (CONFIG). GC TO CAP ALL UNUSED PORTS. | | .PHA 85' | | A1 | AIR 6419 B41 | N2500 | 0°/2°,2° | ADD |
| | | | A2 | _ | _ | _ | - | _ | - | 2. CONFIRM SPACING OF | | | | A2 | - | - | - | - |
| ALPHA | 85' | 20° | A3 | APXVAARR24_43-U-NA20 | L700/L600/N600 | -6°/2°,2° | RMN | (1) RADIO 2217 B2 (1) 4449 B71+B85 | RMV RMN | PROPOSED EQUIP DOES NOT CAUSE TOWER CONFLICTS NOR IMPEDE TOWER CLIMBING | ALPHA | | 20° | A3 | APXVAARR24_43-U-NA20 | N600/L700/L600 LAWS3/N1900/N1900 /L2100 | -6°/2°,2°, 2 °, 2 ° | RMN |
| | | | A4 | - | - | - | - | - | - | PEGS. 3. TEP DID NOT VERIFY THE | | | | A4 | _ | - | _ | - |
| | | | B1 | CMA-BDHH/6521/E0-6/RET/B05 | U1900/L1900 | 0°/2°,2° | RMV | (1) RRUS11 B4 RRU | RMV | EXISTING LOADING. LOADING DATA PROVIDED BY ATC AND | | | | B1 | AIR 6419 B41 | N2500 | 0°/2°,2° | ADD |
| | | | B2 | - | - | - | - | - | - | | DATA PROVIDED BY ATC AND T-MOBILE. | | 5' 140° | L | | | , | |
| BETA | 85' | 140° | B3 | APXVAARR24_43-U-NA20 | L700/L600/N600 | 0°/2°,2° | RMN | (1) RADIO 2217 B2 (1) 4449 B71+B85 | RMV RMN | STATUS ABBREVIATIONS | BETA | 85' | | B2 B3 | - APXVAARR24 43-U-NA20 | - N600/L700/L600 | - 0°/2°,2°, 2 °, 2 ° | - RMN |
| | | | B4 | - | _ | - | - | _ | - | RMV: TO BE REMOVED | | | | 83 | APXVAARR24_4J-U-NAZU | LAWS3/N1900/N1900 /L2100 | 0/2,2,2,2 | i <i>RM</i> N |
| | | | C1 | CMA-BDHH/6521/E0-6/RET/B05 | U1900/L1900 | 0°/2°,2° | RMV | (1) RRUS11 B4 RRU | RMV | RMN: TO REMAIN | | | | B4 | - | - | - | - |
| | | | - | | | , | | , | | REL: TO BE RELOCATED ADD: TO BE ADDED | | | | C1 | AIR 6419 B41 | N2500 | 0°/2°,2° | ADD |
| GAMMA | 85' | 260 | , <u>C2</u> | - | _ | - | - | - | - | | | | | C2 | - | - | - | - 1 |
| | | | C3 | APXVAARR24_43-U-NA20 | L700/L600/N600 | 0°/2°,2° | RMN | (1) RADIO 2217 B2 (1) 4449 B71+B85 | RMV RMN | CABLE LENGTHS FOR JUMPERS | GAMMA | 85' | 260° | | | N600/L700/L600 | | |
| | | | C4 | _ | _ | _ | - | - | - | JUNCTION BOX TO RRU: 15' RRU TO ANTENNA: 10' | 0, 1111, 1 | | 200 | C3 | APXVAARR24_43-U-NA20 | LAWS3/N1900/N1900 /L2100 | <i>0°/2°,2°,</i> 2°,2° | RMN |
| | | | | | | | | | | | | | | C4 | - | - | - | - 1 |

(3)

EQUIPMENT SCHEDULES

| EXISTING FIBER DISTRIBUTION/O | EXISTING CABLING SUMMARY | | | |
|-------------------------------|--------------------------|------|---------------------|--------|
| MODEL NUMBER | STATUS | COAX | HYBRID | STATUS |
| - | _ | - | (1) 1.54" (39.2MM) | RMN |
| - | - | - | (1) 1-3/8" (35.0MM) | RMV |

PROPOSED FIBER DISTRIBUTION/OVP BOX MODEL NUMBER STATUS COAX _

AMERICAN TOWER® 326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net TEP IS A FAMILY OF COMPANIES LICENSED TO PROVIDE DIFFERENT SERVICES DIFFERENT JURISDICTIONS. DEPENDING ON THE JURISDICTION, PROFESSION ENGINEERING AND LAND SURVEYING SERVICES ARE PROVIDED BY TEP OP LLC, A DELAWARE LIMITED LIABILITY COMPANY, TEP ENGINEERING, LLC, A NOR CAROLINA PROFESSIONAL LIMITED LIABILITY COMPANY, OR MAH HEGNIGERIN UARCIAINE FOR ESSIONAL LIMITED LIABILITY COMPANY, CK MARIE HENDIGEENI LLC, A NEW YORK PROFESSIONAL LIMITED LIABILITY COMPANY, GENER CONTRACTOR SERVICES ARE PROVIDED BY TEP OPCO LLC, A DELAWA LIMITED LIABILITY COMPANY, WE ACQUIRE THE REQUISITE LICENSES IN EA STATE. ADDITIONAL INFORMATION CAN BE OBTAINED FROM THE COMPANY. DESCRIPTION BY DATE PRELIMINARY SSG 11/15/24 100% CONSTRUCTION SSP 12/13/24 ATC SITE NUMBER: 280216 ATC SITE NAME: LIBERTY UT T-MOBILE SITE NAME: SL03051A SITE ADDRESS: 4909 N WILLOWBROOKE LN EDEN, UT 84310-9651 No. 135612 ANDREW FA BERGLUND STATE OF UTAL 12/13/24 T-Mobile

PLANS PREPARED BY:

TEP OPCO, LL

| DATE DRAWN: | 12/13/24 |
|----------------|--------------------------|
| ATC JOB NO: | 14911687 |
| CUSTOMER NAME: | ATC, WOLF CREEK, EDEN UT |
| CUSTOMER ID: | SL03051A |
| | |


ANTENNA INFORMATION & SCHEDULE

SHEET NUMBER: C-401


| REVISION |
|----------|
| 0 |


| P. 3) STING RA 1+B85 R | –43–U–NA2O ANTENN DIO 4449 RU SHOWN STACKED FOR CLARITY (TYP. 3) | IA | | APPeness |
|------------------------------|---|------------|-----------------------------------|----------------------------------|
| B1 | | | ENG LLC, CAR LLC, CON | IS A F/ FERENT A DEL V. |
| | | | 3 | TEP OF |
| | NON ANTENNA SUM | MARY | | |
| STATUS | ADDITIONAL TOWER MOUNTED EQUIPMENT | STATUS | | A |
| ADD | - | - | | å |
| - | - | - | | ä |
| RMN | (1) 4449 B71+B85 (1) 4460 B25+B66 | RMN ADD | | 2000- |
| - | - | - | | 21 |
| ADD | - | - | | |
| - | - | - | | |
| RMN | (1) 4449 B71+B85 (1) 4460 B25+B66 | RMN ADD | SE | AL: |
| - | - | - | | _ |
| ADD | - | - | | 1 |
| - | - | - | | -1 |
| RMN | (1) 4449 B71+B85 (1) 4460 B25+B66 | RMN ADD | | |
| - | - | - | | TE I |
| | | | | CJU |

| PROPOSED CABLING SUMMARY | | | | | | |
|--------------------------|--------------------|--------|--|--|--|--|
| х | HYBRID | STATUS | | | | |
| | (1) 1.54" (39.2MM) | RMN | | | | |
| | (2) 2.00" (50.8MM) | ADD | | | | |
| | | | | | | |
















NOTE:


INSTALL SIMPSON STRONG-TIE® STRONG-BOLT® 2 WEDGE ANCHOR(S) STRICTLY PER INSTALLATION INSTRUCTIONS INCLUDED WITH PRODUCT OR FOUND ONLINE AT WWW.STRONGTIE.COM. PROPER INSTALLATION IS CRITICAL FOR FULL PERFORMANCE.




EXISTING RRU

PROPOSED MOUNTING PIPE







GROUND BAR NOTES:

GROUND BAR KITS COME WITH ALL HARDWARE, NUTS, BOLTS, WASHERS, ETC. EXCEPT THE STRUCTURAL MOUNTING MEMBER(S).

Q)

0

2. GROUND BAR TO BE BONDED DIRECTLY TO TOWER.




ELECTRICAL NOTES:


SCALE: N.T.S.

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE 1. WITH THE T-MOBILE REPRESENTATIVE AND LOCAL UTILITY COMPANY FOR THE INSTALLATION OF CONDUITS, CONDUCTORS, BREAKERS, DISCONNECTS, OR ANY OTHER EQUIPMENT REQUIRED FOR ELECTRICAL SERVICE. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH LATEST EDITION OF THE STATE AND NATIONAL CODES, ORDINANCES AND REGULATIONS APPLICABLE TO THIS PROJECT.
- 2. ATC HAS NOT VERIFIED ANY EXISTING T-MOBILE GROUND EQUIPMENT OR ELECTRICAL LOADING. PROPOSED WORK BASED ON INSTALLATION CONFIGURATION PROVIDED BY T-MOBILE. CONTRACTOR TO VERIEV EXISTING T-MOBILE PANEL HAS SUFFICIENT SPACE FOR PROPOSED BREAKER. PROPOSED CABLE AND CONDUIT SHALL BE MINIMUM SIZE PER BELOW IN CHART.
- FOR SPECIFIC CABINET / ANCILLARY EQUIPMENT WIRING 3. REQUIREMENTS, THE T-MOBILE CONTRACTOR SHOULD REFERENCE DESIGN DOCUMENTS PROVIDED BY T-MOBILE FOR THIS CURRENT PROJECT CONFIGURATION. IN ACCORDANCE WITH LOCAL JURISDICTION REQUIREMENTS & NEC STANDARDS & PRACTICES

| VOLTS | OCPD SIZE | WIRE SIZE | GROUND | CONDUIT |
|----------|-----------|------------|--------|---------|
| | 80A/2P | 3-#3 AWG | #8 AWG | 1-1/4" |
| 120/240V | 100/2P | 3-#2 AWG | #8 AWG | 1-1/4" |
| OR | 125A/2P | 3-#3/0 AWG | #6 AWG | 2" |
| 120/208V | 150A/2P | 3-#3/0 AWG | #6 AWG | 2" |
| | 200A/2P | 3-#3/0 AWG | #6 AWG | 2" |
| | 80A/2P | 2-#3 AWG | #8 AWG | 1-1/4" |
| 240V | 100/2P | 2-#2 AWG | #8 AWG | 1-1/4" |
| OR | 125A/2P | 2-#3/0 AWG | #6 AWG | 2" |
| 208V | 150A/2P | 2-#3/0 AWG | #6 AWG | 2" |
| | 200A/2P | 2-#3/0 AWG | #6 AWG | 2" |















| RRU SPECIFICATIONS | | | | | |
|--------------------|-------|-------|-------|-----------------|--|
| RRU MODEL | А | В | С | WEIGHT (LBS) | |
| RADIO 4460 B25+B66 | 19.6" | 15.7" | 12.1" | 109.0 | |



| ANTENNA SPECIFICATIONS | | | | | |
|------------------------|-------|-------|------|-----------------|--|
| ANTENNA MODEL | A | В | С | WEIGHT (LBS) | |
| AIR 6419 B41 | 33.6" | 20.0" | 6.3" | 68.5 | |





Section 5 - RAN Equipment

| | Existing RAN Equipment | | | | | |
|------------------------|---|----------------------------------|--|--|--|--|
| | Template: | | | | | |
| Enclosure | 1 | 2 | | | | |
| Enclosure Type | RBS 6102 MU AC | Ancillary Equipment (Ericsson) | | | | |
| Baseband | BB 5216 BB 6630 DUW30 L2100 L600 U1900 (DECOMMISSIONED) L700 L700 | | | | | |
| Transport System | CSR IXRe V2 (Gen2) | | | | | |
| Hybrid Cable System | | Ericsson 6x12 HCS 6AWG 40m (x 2) | | | | |

(1)

EXISTING CABINET CONFIGURATION SCALE: N.T.S.

| | P | roposed RAN Equipment | |
|------------------------|--|---|---------------|
| | | Template: 67D5D3998E Indoor | |
| Enclosure | 1 | 2 | 3 |
| Enclosure Type | Ericsson - 19 Inch Rack | Ericsson - 19 Inch Rack | Power 6230 v2 |
| Baseband | BB 6630 N600 L600 L700 RP 6651 N1900 L1900 L2100 LAWS3 | | |
| Transport System | CSR IXRe V2 (Gen2) | | |
| Hybrid Cable System | | Ericsson 6x12 HCS 6AWG 40m Hybrid Trunk 6/24 4AWG 40m (x2) | |
| RAN Scope of Work | c | | |
| ſ | | | |




PROPOSED CABINET CONFIGURATION SCALE: N.T.S.


| AS CREATED BY OTHERS AND PROVIDED |
|-----------------------------------|
| ST OF THE CUSTOMER WITHOUT EDIT. |



REVISION: -








2 PROPOSED ANTENNA CONFIGURATION SCALE: N.T.S.


NOTE: THIS SHEET WA

| VS.jpg | | |
|---|-------------|---|
| Radio 4449 | | |
| ound | | |
| | SUPPLEMENTA | |
| AS CREATED BY OTHERS AND PROVIDED ST OF THE CUSTOMER WITHOUT EDIT. | R-603 | - |





REVISION:




(1)

SCALE: N.T.S.



SHEET NUMBER:





| MANUE | ACTURER | ERICSON | | | |
|---------------|---------|--------------------|--|--|--|
| MOD | EL NO.: | RP 6651 | | | |
| DIME | NSIONS: | TOTAL MERCHER | | | |
| | 1.75* | TOTAL WEIGHT: | | | |
| 19" 13.85" | | 16.53 LBS (7.5 KG) | | | |

| G. | Vx 2.0 | - A | - THER. + B + 1 | c • D | A +1 | 3 + C | +D | +E . | +0 | +# + | 3 | ٠K | + L. | • M • | A 1 | 16 A-018 7 山村市 | | 1.27 | 0 |
|-----|--------|-------|--------------------|-------|------|-------|----|------|----|------|---|-----|------|-------|------|-------------------|------|------|----|
| | | | | | | | | | JL | | | | | | | | | 3 | |
| 먹면 | 65 | 22222 | | | | | | | | | | 888 | | | 1 | | | 0051 | j. |
| 0 8 | | | | | | | | | | | | | | | 1222 | 10000 | 8888 | 8 | C |



REVISION:




This report was prepared for American Tower Corporation by



Antenna Mount Analysis Report

| Mount Type | : 12.5 ft Platform with Handrails |
|------------------------|-----------------------------------|
| ATC Asset Name | : LIBERTY UT, UT |
| ATC Asset Number | : 280216 |
| Engineering Number | : 14911687_C8_01 |
| Mount Elevation | : 82 ft |
| Carrier | : T-Mobile |
| Carrier Site Name | : ATC, Wolf Creek, Eden UT |
| Carrier Site Number | : SL03051A |
| Site Location | : 4780 Wolf Creek Drive |
| | Eden, UT 84310-9651 |
| | 41.3194, -111.8295 |
| County | : Weber |
| Date | : November 7, 2024 |
| Max Usage | : 49% |
| Result | : Pass 82965 |
| | |
| Prepared By: | Reviewed By: |
| Dmitriy Albul | Sector ATE OF |
| Professional Engineer | n B |
| | |





SMJ International, LLC - 49030 Pontiac Trail, Suite 100 - Wixom, MI 48393 - 616.745.4777 Office - info@smj-llc.com



Introduction

The purpose of this report is to summarize the results of the antenna mount analysis performed for T-Mobile at 82 ft.

Supporting Documents

| RFDS | RFDS Version 4, dated October 15, 2024 |
|-------------|---|
| Photos | Site photos from 2023 |
| Other | Preview Exhibit by American Tower Corporation, dated Oc |
| Spec. Sheet | Spec Sheet for Site Pro 1 F3P-12W, dated August 8, 2017 |

Analysis

This antenna mount was analyzed using RISA-3D v22 analysis software.

| Basic Wind Speed: | 103 mph (3-Second Gust) |
|-------------------------------------|---|
| Basic Wind Speed w/ Ice: | 40 mph (3-Second Gust) w/ 0.25" radial ice concurrent |
| Codes: | ANSI/TIA-222-H / 2021 IBC / 2021 Utah Building Code |
| Structure Class: | П |
| Exposure Category: | С |
| Topographic Procedure: | Method II |
| Topographic Feature: | Flat |
| Crest Height: | Oft |
| Crest Length: | Oft |
| Spectral Response: | $Ss = 0.955, S_1 = 0.34$ |
| Site Class: | D – Stiff Soil – Default |
| Live Loads*: | Lm = 500 lbs, Lv = 250 lbs |
| Live Load(s) reduction is confirmed | to either not govern or not be applicable. |


*Live Load(s) reduction is confirmed to either not govern or not be applicable

Conclusion

Based on the analysis results, the antenna mount meets the requirements per the applicable codes listed. The mount can support the equipment as described in this report.

If you have any questions or require additional information, please reach out to your American Tower contact. If you do not have an American Tower contact and have an Engineering question, please contact MountAnalysis@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

SMJ International, LLC - 49030 Pontiac Trail, Suite 100 - Wixom, MI 48393 - 616.745.4777 Office - info@smj-llc.com



NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF THE CUSTOMER WITHOUT EDIT. PLEASE REFERENCE THE MOUNT ANALYSIS REPORT FOR COMPLETE MOUNT ANALYSIS CALCULATIONS AND DETAILS. SUPPLEMENTAL PAGES INCLUDED IN THE CONSTRUCTION DRAWINGS ARE FOR REFERENCE ONLY. GENERAL CONTRACTOR IS TO VERIFY THEY HAVE THE MOST RECENT MOUNT ANALYSIS PRIOR TO CONSTRUCTION.

November 7, 2024 Page 3 ctober 28, 2024





REVISION: -