

**ADDENDUM FOR REMEDIATION OF SLIDE MATERIAL
THE SUMMIT AT SKI LAKE PHASE 13
VIA CORTINA
WEBER COUNTY, UTAH 84317**

DEVELOPER: Ray Bowden

ENGINEER'S ESTIMATE
\$19,541.00

PROPOSAL

I (We), the undersigned Contractor propose to do the following described work in strict compliance with the Standard Weber County Standards and Technical Specifications at the prices shown. The Contractor shall be licensed to perform such work by the State of Utah and Weber County. The Contractor shall also provide sufficient insurance to hold the owner free from all liabilities. The Contractor shall furnish guarantee that the improvements contemplated by this proposal will remain in good condition for the one year period from the date of acceptance by Weber County. The determination of the necessity for repairs to restore the improvement to good condition rests entirely with the Owner.

	<u>QUANTITY</u>		<u>UNIT PRICE</u>		<u>TOTAL AMOUNT</u>
<u>Addendum Items</u>					
1 Remove Existing Material and Import Structural Fill	800	CY	\$ 12.00	CY	\$ <u>9,600.00</u>
2 Const. 4" Perf HDPE Land Drain in 2' Wide Gravel Trench with Mirafi Surrounding Gravel	206	LF	\$ 20.00	LF	<u>4,120.00</u>
3 Const. 4" Solid HDPE Drain Pipe	367	LF	\$ 13.00	LF	<u>4,771.00</u>
4 Const. 4" Cleanout	3	EA	\$ 350.00	EA	<u>1,050.00</u>
	<u>Total Addendum Items</u>				\$ <u>19,541.00</u>