

PROJECT SITE W 300 N VICINITY MAP NOT TO SCALE

LISA ESTATES SUBDIVISION PHASE 2

PART OF THE SOUTHEAST QUARTER OF SECTION 7, TOWNSHIP 6 NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY WEBER COUNTY, UTAH OCTOBER, 2011

BOUNDARY DESCRIPTION

PART OF THE SOUTHEAST QUARTER OF SECTION 7. TOWNSHIP 6 NORTH. RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY. DESCRIBED AS FOLLOWS:

BEGINNING AT THE SOUTH QUARTER CORNER OF SECTION 7: SAID POINT ALSO BEING ON THE CENTERLINE OF 5500 WEST STREET; THENCE NO0°18'53"E ALONG SAID CENTERLINE OF 5500 WEST STREET 549.39 FEET; THENCE N89°49'40"E 381.60 FEET; THENCE S01°45'02"W 237.31 FEET; THENCE S29°34'30"W 67.84 FEET; THENCE S01°45'02"W 258.28 FEET;

BASIS OF BEARINGS

THE BASIS OF BEARINGS FOR THIS PLAT IS THE LINE BETWEEN THE CENTER OF SECTION 7, TOWNSHIP 6 NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY AND A FOUND WITNESS CORNER. SHOWN HEREON AS: S85°37'31"E

STATEMENT

Subdivider:

ALLAN KARRAS

CENTURY 21

PERMITTED AT ANY TIME INCLUDING THE ALLOWED AGRICULTURAL USE SHALL BE SUBJECT TO RESTRICTION ON THE BASIS THAT IT INTERFERES WITH ACTIVITIES OF (AMD. ORD. #3-82, JANUARY 26, 1982;

2609 N MAIN **NARRATIVE** SUNSET, UT 80415 THENCE N89°20'44"W 336.01 FEET TO THE POINT OF BEGINNING. THE PURPOSE OF THIS PLAT IS TO DIVIDE THE BELOW DESCRIBED FUTURE RESIDENTS OF THIS SUBDIVISION." PROPERTY INTO LOTS AND STREETS AS SHOWN. ALL LOT CORNERS TO CONTAINING 197709 SQUARE FEET OR 4.539 ACRES CENTER OF SECTION 7, BE SET WITH A 5/8" X 24" REBAR AND RED PLASTIC CAP STAMPED TOWNSHIP 6 NORTH, RANGE 2 ORD., #2002-3, MARCH 05, 2002) "REEVE & ASSOCIATES". WEST, SALT LAKE BASE AND MERIDIAN, US SURVEY. FOUND WEBER COUNTY BRASS CAP MONUMENT 1. A FLOOD PLAIN DEVELOPMENT PERMIT IS REQUIRED PRIOR TO CONSTRUCTION. FOUND WITNESS -CORNER 139.57 EAST QUARTER CORNER OF RIVER WOOD BEND SECTION 7, TOWNSHIP 6 $\overline{}$ NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, US SURVEY. CALCULATED **LEGEND** *\N89°49'40"E_381.60" = SECTION CORNER = STREET CENTERLINE MONUMENT TO BE SET UPON COMPLETION What vertical OF IMPROVEMENTS datum? = 40001 S.F. 40001 S.F. \bullet = 5/8" X 24" REBAR AND [0.918 ACRES 6 0.918 ACRES RED PLASTIC CAP TO BE SET BFE=4219.7 BFE=4219.9 STAMPED "REEVE & ASSOCIATES" FFE=4221.7 FFE=4221.9 = SOIL EXPLORATION HOLE 5482 WEST BFE = BASE FLOOD ELEVATION 5458 WEST —— 170.62**'**— FFE = FINISHED FLOOR ELEVATION S88°14'58"E 359.17' 33.92'-= BOUNDARY LINE REMAINDER PARCEL S29°34'30"W 326.16 NOT APPROVED FOR DEVELOPMENT 33.92'— --- - = ADJOINING PROPERTY — -155.58**'**— — — -153.99'- ------= EASEMENTS 5485 WEST 5465 WEST ——— = SECTION TIE LINE 55' TEMPORARY 40000 S.F. 40000 S.F. TURN AROUND - X X = EXISTING FENCELINE 0.918 ACRES 0.918 ACRES BFE=4219.5 BFE=4219.7 _FFE=4221.5 <u></u> FFE=4221.7 = EXISTING PAVEMENT = ROAD DEDICATION FOR 5500 WEST STREET = EXISTING DIRT ROAD SOUTH QUARTER CORNER OF SECTION 7. TOWNSHIP 6 NORTH RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, US SURVEY. FOUND WEBER COUNTY BRASS

AGRICULTURAL

"AGRICULTURE IS THE PREFERRED USE IN THE AGRICULTURAL ZONES. AGRICULTURAL OPERATIONS AS SPECIFIED IN THE ZONING ORDINANCE FOR A PARTICULAR ZONE ARE OPERATION OF FARM MACHINERY AND NO

OWNERS DEDICATION AND CERTIFICATION

ROBERT D. KUNZ

SURVEYOR'S CERTIFICATE

ROBERT D. KUNZ, DO HEREBY CERTIFY THAT I AM A REGISTERED PROFESSIONAL LAND

17-23-17 AND HAVE VERIFIED ALL MEASUREMENTS, AND HAVE PLACED MONUMENTS AS REPRESENTED ON THIS PLAT, AND THAT THIS PLAT OF <u>LISA ESTATES SUBDIVISION PHASE 2</u> IN <u>Weber county</u>, utah, has been drawn correctly to the designated scale and is

A TRUE AND CORRECT REPRESENTATION OF THE HEREIN DESCRIBED LANDS INCLUDED IN SAID SUBDIVISION, BASED UPON DATA COMPILED FROM RECORDS IN THE WEBER COUNTY

RECORDER'S OFFICE AND FROM SAID SURVEY MADE BY ME ON THE GROUND, I FURTHER CERTIFY THAT THE REQUIREMENTS OF ALL APPLICABLE STATUTES AND ORDINANCES OF WEBER COUNTY CONCERNING ZONING REQUIREMENTS REGARDING LOT MEASUREMENTS HAVE

SIGNED THIS _____, DAY OF _____, 20___.

BEEN COMPLIED WITH.

150228

UTAH LICENSE NUMBER

SURVEYOR IN THE STATE OF UTAH IN ACCORDANCE WITH TITLE 58, CHAPTER 22, PROFESSIONAL ENGINEERS AND LAND SURVEYORS ACT; AND THAT I HAVE COMPLETED A SURVEY OF THE PROPERTY DESCRIBED ON THIS PLAT IN ACCORDANCE WITH SECTION

WE THE UNDERSIGNED OWNERS OF THE HEREIN DESCRIBED TRACT OF LAND. DO HEREBY SET APART AND SUBDIVIDE THE SAME INTO LOTS AND STREETS AS SHOWN ON THE PLAT AND NAME SAID TRACT **LISA ESTATES SUBDIVISION PHASE 2**, AND DO HEREBY DEDICATE TO PUBLIC USE ALL THOSE PARTS OR PORTIONS OF SAID TRACT OF LAND DESIGNATED AS STREETS, THE SAME TO BE USED AS PUBLIC THOROUGHFARES AND ALSO TO GRANT AND DEDICATE A PERPETUAL RIGHT AND EASEMENT OVER, UPON AND UNDER THE LANDS DESIGNATED HEREON AS PUBLIC UTILITY, STORM WATER DETENTION PONDS DRAINAGE EASEMENTS AND CANAL MAINTENANCE EASEMENT, THE SAME TO BE USED FOR THE INSTALLATION MAINTENANCE AND OPERATION OF PUBLIC UTILITY SERVICE LINE, STORM DRAINAGE FACILITIES, IRRIGATION CANALS OR FOR THE PERPETUAL PRESERVATION OF WATER CHANNELS IN THEIR NATURAL STATE WHICHEVER IS APPLICABLE AS MAY BE AUTHORIZED BY THE GOVERNING AUTHORITY, WITH NO BUILDINGS OR STRUCTURES BEING ERECTED WITHIN SUCH EASEMENTS

SIGNED THIS DAY OF	, 20
ALLAN KARRAS	JARED PREISLER
LISA PREISLER	

ACKNOWLEDGMENT

COUNTY OF)	
ON THE DAY OF	, 20, PERSONALLY APPEARED
BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC,	(AND)
SIGNER(S) OF THE ABOVE OWNER	
WHO BEING BY ME DULY SWORN, DID ACKNOWLEDGE	
FREELY, VOLUNTARILY, AND FOR THE PURPOSES THER	REIN MENTIONED.

OMMISSION	FXPIRES

NOTARY PUBLIC

ACKNOWLEDGMENT

STATE OF UTAH COUNTY OF _____ ON THE ______ DAY OF _____, 20___, PERSONALLY APPEARED BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, ____ ___ BEING BY ME DULY SWORN, ACKNOWLEDGED TO ME THEY ARE AND _____ OF SAID CORPORATION AND THAT THEY

SIGNED THE ABOVE OWNER'S DEDICATION AND CERTIFICATION FREELY. VOLUNTARILY. AND

IN BEHALF OF SAID CORPORATION FOR THE PURPOSES THEREIN MENTIONED.

COMMISSION EXPIRES

STATE OF UTAH

NOTARY PUBLIC



N. ANDERSON Begin Date:

Project Info.

SUBDIVISION PHASE 2 Number: 1714-27 Scale: 1"=100' Checked:___

WEBER COUNTY PLANNING COMMISSION APPROVAL

CAP MARKED 1981

THIS IS TO CERTIFY THAT THIS SUBDIVISION PLAT WAS DULY APPROVED BY THE WEBER COUNTY PLANNING COMMISSION. SIGNED THIS _____, DAY OF _____, 20__.

CHAIRMAN, WEBER COUNTY PLANNING COMMISSION

WEBER COUNTY ENGINEER

HEREBY CERTIFY THAT THE REQUIRED PUBLIC IMPROVEMENT STANDARDS AND DRAWINGS FOR THIS SUBDIVISION CONFORM WITH THE COUNTY STANDARDS AND THE AMOUNT OF THE FINANCIAL GUARANTEE IS SUFFICIENT FOR THE INSTALLATION OF THESE IMPROVEMENTS.

WEBER COUNTY ENGINEER

WEBER COUNTY COMMISSION ACCEPTANCE

THIS IS TO CERTIFY THAT THIS SUBDIVISION PLAT. THE DEDICATION OF STREETS AND OTHER PUBLIC WAYS AND FINANCIAL GUARANTEE OF PUBLIC IMPROVEMENTS ASSOCIATED WITH THIS SUBDIVISION, THEREON ARE HEREBY APPROVED AND ACCEPTED BY THE COMMISSIONERS OF WEBER COUNTY, UTAH. SIGNED THIS _____, DAY OF _____,

CHAIRMAN, WEBER COUNTY COMMISSION

ATTEST

WEBER COUNTY SURVEYOR

HEREBY CERTIFY THAT THE WEBER COUNTY SURVEYOR'S OFFICE HAS REVIEWED THIS PLAT FOR MATHEMATICAL CORRECTNESS, SECTION CORNER DATA, AND FOR HARMONY WITH LINES AND MONUMENTS ON RECORD IN COUNTY OFFICES. THE APPROVAL OF THIS PLAT BY THE WEBER COUNTY SURVEYOR DOES NOT RELIEVE THE LICENSED LAND SURVEYOR WHO EXECUTED THIS PLAT FROM THE RESPONSIBILITIES AND/OR LIABILITIES ASSOCIATED THEREWITH. SIGNED THIS _____, 20___.

WEBER COUNTY SURVEYOR

SIGNED THIS _____, 20___, 20___.

Scale: 1" = 100'

HAVE EXAMINED THE FINANCIAL GUARANTEE AND OTHER

IN MY OPINION THEY CONFORM WITH THE COUNTY

DOCUMENTS ASSOCIATED WITH THIS SUBDIVISION PLAT, AND

ORDINANCE APPLICABLE THERETO AND NOW IN FORCE AND

WEBER COUNTY ATTORNEY

WEBER-MORGAN HEALTH DEPARTMENT

I HEREBY CERTIFY THAT THE SOILS. PERCOLATION RATES. AND SITE CONDITIONS FOR THIS SUBDIVISION HAVE BEEN INVESTIGATED BY THIS OFFICE AND ARE APPROVED FOR ON-SITE WASTEWATER DISPOSAL SYSTEMS.

SIGNED THIS _____, DAY OF _____, 20___.

WEBER-MORGAN HEALTH DEPARTMENT

Weber County Recorder Entry No.____ Fee Paid ___ Filed For Record And Recorded, _____

At _____ In Book _____ Of The Official Records, Page Recorded For:

Weber County Recorder

_____ Deputy.

General Notes

CONSTRUCTION STAKING TO BE PROVIDED BY REEVE & ASSOCIATES, INC.

IMPROVEMENT DRAWINGS SHALL BE RESUBMITTED AND APPROVED BY THE

SANITARY SEWER SERVICE LINES.

OF CONNECTING SEWER PIPING.

AND WRAPPED IN 8-MIL POLYETHYLENE.

IMPROVEMENTS DURING CONSTRUCTION.

OR DAMAGE TO EXISTING UTILITIES.

CONTRACTOR PRIOR TO EXCAVATION.

TRANSPORTATION ENGINEERS' MANUAL.

PRIOR TO COMMENCING CONSTRUCTION.

SPECIFICATIONS AND DRAWINGS.

AND PAVEMENT RESTORATION.

PERMITTING REQUIREMENTS.

PREVENT BLOWING.

PVC PIPING.

SIX INCHES THICK.

UNLESS OTHERWISE DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.

. ANY MODIFICATION TO THIS CONSTRUCTION PACKAGE OR TO THE CONSTRUCTION SCHEDULE SHALL BE APPROVED BY THE ENGINEER. PRIOR TO SAID APPROVAL, ALL

3. THE CONTRACTOR SHALL LOCATE, RETAIN AND PROTECT ALL EXISTING UTILITIES

4. THE CONTRACTOR SHALL MAINTAIN 10 FOOT HORIZONTAL AND 18 INCH VERTICAL SEPARATION, CULINARY WATER LINES, SANITARY SEWER, AND STORM DRAIN LINES. 5. THE CONTRACTOR SHALL INSTALL ALL SANITARY SEWER MAINS, SERVICE LINES AND STORM DRAIN LINES PRIOR TO INSTALLING ANY WATER SYSTEM IMPROVEMENTS. ADJUST WATER MAINS FROM 4'-6" TO 6'-6" OF COVER AS REQUIRED TO AVOID

6. SIDEWALKS SHALL BE FOUR INCHES THICK, UNLESS FRONTING DRIVEWAY, THEN

RESPECTIVE UTILITY COMPANY. OWNER SHALL PAY ALL ASSOCIATED UTILITY COMPANY

9. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER SLOPE AND CONSTRUCTION

10. CONTRACTOR SHALL BE RESPONSIBLE OF PROPER BACKFILLING, COMPACTING,

12. ALL THRUST BLOCKS SHALL BE POURED IN PLACE AGAINST UNDISTURBED SOIL.

15. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ADJACENT SURFACE

16. CONTRACTOR SHALL BE RESPONSIBLE FOR CORRECTING ANY SETTLEMENT OF

17. ALL EXISTING ASPHALT SHALL BE SAW CUT IN NEAT STRAIGHT LINES BY THE

18. CONTRACTOR TO INSTALL MAGNETIC LOCATING TAPE CONTINUOUSLY OVER ALL

19. THE CONTRACTOR IS RESPONSIBLE TO FURNISH ALL MATERIALS TO COMPLETE

21. A UPDES GENERAL CONSTRUCTION STORM WATER PERMIT MUST BE OBTAINED

22. ALL WORK SHALL CONFORM TO THE CURRENT EDITION OF THE APWA AND CITY

20. TRAFFIC CONTROL IS TO CONFORM TO THE CURRENT CITY AND/OR STATE

13. ALL EXPOSED NUTS AND BOLTS WILL BE COATED WITH A NON-OXIDE WASH

14. CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ACCORDING TO GOVERNING AGENTS STANDARDS. WET DOWN DRY MATERIALS AND RUBBISH TO

11. CONTRACTOR TO OBTAIN ALL NECESSARY PERMIT(S) AND COMPLY WITH ALL

ALL VALVES, FITTINGS, AND APPURTENANCES TO BE BLOCKED.

7. CONTRACTOR SHALL NOTIFY ENGINEER OF ALL UTILITY CONFLICTS UPON

ELECTRICAL, TELEPHONE, NATURAL GAS AND CABLE TV SERVICES WITH THE

8. CONTRACTOR SHALL COORDINATE CONSTRUCTION AND INSTALLATION OF


1) 4/1/11 RH - PREPARED PLANS FOR CLIENT 2) 4/14/11 RH - REVISED PLANS PER COUNTY COMMENTS. 4) 9/29/11 RH - REVISED PLANS PER COUNTY COMMENTS.


6) 9/25/12 RH - REVISED PLANS PER COUNTY COMMENTS.

LISA ESTATES SUBDIVISION


Phase-1 & Phase-2 Improvement Plans

WARREN, WEBER COUNTY, UTAH MARCH, 2011





Vicinity Map



Sheet Index

Sheet 1 - Cover/Index Sheet

Sheet 2 - Street Cross-Sections/Legend/Notes


Sheet 3 - 350 North Street 10+00.00 - 15+50.00 Sheet 4 - Overall Secondary Water Plan

& 5500 West Ditch Piping Plan

Sheet 5 - Storm Water Pollution Prevention Plan Sheet 6 - Storm Water Pollution Prevention Plan



S S S **(1)** ဟ 🗗



Project Info.

Begin Date:

Drafter:

<u>J. NATE REEVE, P.E.</u>

R. HANSEN

Engineer's Notice To Contractors

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM AVAILABLE INFORMATION PROVIDED BY OTHERS. THE LOCATIONS SHOWN ARE APPROXIMATE AND SHALL BE CONFIRMED IN THE FIELD BY THE CONTRACTOR, SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO CONTACT THE UTILITY COMPANIES AND TAKE DUE PRECAUTIONARY MEASURE TO PROTECT ANY UTILITY LINES SHOWN, AND ANY OTHER LINES OBTAINED BY THE CONTRACTOR'S RESEARCH, AND OTHERS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.

Contact: Allan Karras


Century 21 2609 N. Main Sunset, Utah 84015

Blue Stakes Location Center Call: Toll Free 1-800-662-4111 Two Working Days Before You Dig

MARCH 18, 2011 LISA ESTATES SUBDIVISION PHASE 1 & 2 Number: <u>1714–27</u>

Sheet Sheets

\РН: (801) 564—0909 THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF REEVE & ASSOCIATES, INC., 4155 S. HARRISON BLVD. EXECUTIVE BLDG. #310, OGDEN, UTAH 84403, AND SHALL NOT BE PHOTOCOPIED, RE-DRAWN, OR USED ON ANY PROJECT OTHER THAN THE PROJECT OT



Legend

Reeve & Associates, Inc. - Solutions You Can Build On

			9 9 9 9 9 9		
W	- = PROPOSED CULINARY WATER LINE		= EXISTING CATCH BASIN	L.F.	= LINEAR FEET
— —EX.W — — —	- = EXISTING CULINARY WATER LINE	•	= EXISTING SPRINKLER	NG	= NATURAL GRADE
——SS ——	- = PROPOSED SANITARY SEWER LINE	•	= PLUG W/ 2" BLOW-OFF	O.C.	= ON CENTER
——EX.SS — —	- = EXISTING SANITARY SEWER LINE	•	= AIR-VAC ASSEMBLY	PC	= POINT OF CURVE
——SD ——	- = PROPOSED STORM DRAIN LINE	•	= PROPOSED REDUCER	PRC	= POINT OF REVERSE CURVE
— —EX.SD — —	- = EXISTING STORM DRAIN LINE	山	= PLUG & BLOCK	PRVC	= POINT OF REVERSE VERTICAL CURVE
——LD ——	- = PROPOSED LAND DRAIN LINE		= STREET LIGHT	PT	= POINT OF TANGENT
— —EX.LD — —	- = EXISTING LAND DRAIN LINE	-	= SIGN	PP	= POWER/UTILITY POLE
———SW ———	- = PROPOSED SECONDARY WATER LINE	BLDG	= BUILDING	P.U.E.	= PUBLIC UTILITY EASEMENT
— —EX.SW — —	- = EXISTING SECONDARY WATER LINE	BVC	= BEGIN VERTICAL CURVE	R/C	= REBAR & CAP
——IRR——	- = PROPOSED IRRIGATION LINE	C&G	= CURB & GUTTER	RCB	= REINFORCED CONCRETE BOX
— —EX.IRR— —	- = EXISTING IRRIGATION LINE	СВ	= CATCH BASIN	RCP	= REINFORCED CONCRETE PIPE
OHP	- = EXISTING OVERHEAD POWER LINE	C.F.	= CUBIC FEET	RIM	= RIM OF MANHOLE
TEL	- = EXISTING TELEPHONE LINE	C.F.S.	= CUBIC FEET PER SECOND	R.O.W.	= RIGHT-OF-WAY
GAS	- = EXISTING NATURAL GAS LINE	CL	= CENTERLINE	SD	= STORM DRAIN
	- = EXISTING EDGE OF PAVEMENT	DI	= DUCTILE IRON	SS	= SANITARY SEWER
\times \times \rightarrow	X = FENCE LINE	EP	= EDGE OF PAVEMENT	SW	= SECONDARY WATER
	= MASONRY BLOCK/RETAINING WALL	EVC	= END VERTICAL CURVE	TBC	= TOP BACK OF CURB
· ·	- = DITCH/SWALE FLOWLINE	FC	= FENCE CORNER	TOE	= TOE OF SLOPE
$leve{lat}$	= PROPOSED FIRE HYDRANT	FF	= FINISH FLOOR	TOP	= TOP OF SLOPE
Ø	= EXISTING FIRE HYDRANT	FFE	= FINISH FLOOR ELEVATION	TOW	= TOP OF WALL
•	= PROPOSED MANHOLE	FG	= FINISHED GRADE	TSW	= TOP OF SIDEWALK
\bigcirc	= EXISTING MANHOLE	FH	= FIRE HYDRANT	VPI	= VERTICAL POINT OF INTERSECT.
•	= PROPOSED SEWER CLEAN-OUT	FL	= FLOW LINE	W	= CULINARY WATER
X	= PROPOSED GATE VALVE	GB	= GRADE BREAK	WM	= WATER METER
X	= EXISTING GATE VALVE	HDPE	= HIGH DENSITY POLYETHYLENE PIPE		= NEW PAVEMENT
	= PROPOSED WATER METER	INV	= INVERT		
	= EXISTING WATER METER	IRR	=IRRIGATION		= NEW CONCRETE
	= PROPOSED CATCH BASIN	LD	= LAND DRAIN	_	

General Notes

- 1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE DEVELOPMENT STANDARDS OF WEBER COUNTY AND THE STANDARD DRAWINGS CONTAINED THEREIN. WEBER COUNTY PUBLIC WORKS REQUIREMENTS SHALL BE MET.
- 2. THE LOCATION OF EXISTING UTILITIES SHOWN ARE APPROXIMATE ONLY AND THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UTILITIES SHOWN OR NOT SHOWN ON THESE PLANS.
- 3. THE STREET STRUCTURAL CROSS SECTION IS PER WEBER COUNTY DETAILS CONTAINED WITHIN THESE PLANS.
- 4. WATER LINE PIPE SHALL BE PVC C-900 CLASS 200. WASHOUT ASSEMBLIES SHALL CONSIST OF A KUPFERLE FOUNDRY CO. 2" BLOW-OFF HYDRANT (OR COUNTY-APPROVED EQUIV.).
- 5. SECONDARY WATER LINE SHALL BE PVC C-900 CLASS 200. ALL SECONDARY WATER VALVE LIDS SHALL BE STAMPED "IRRIGATION".






	8	REVISIONS	
DATE		DES	DESCRIPTION
4-14-11 RH	RH		County Comments
6-15-11 RH	R H	County	County Comments
9-29-11 RH	RH	County	County Comments
6-29-12 RH	RH	County	County Comments
8-01-12 RH	RH	County	County Comments
9-25-12 RH	RH	County	County Comments

Keeve α Associates, inc Solutions i ou can build	tates Subdivision hase 1 & 2 ken, weber county, utah	Cross-Sections/
	tato has Ren, w	Cr

/pu Street Maste


Ø




Project Info.	
Engineer: J. NATE REEVE, P.E.	
Drafter: R. HANSEN	
Begin Date: MARCH 18, 2011	

LISA ESTATES SUBDIVISION PHASE 1 & 2 Number: <u>1714–27</u> Sheet

Sheets






Construction Notes:

ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.

SW/6 - 6" PVC C-900 SECONDARY


DATE 4-14-11 6-15-11 9-29-11 6-29-12 8-01-12 9-25-12

Lubdivision You Car Subdivision & 2 JNTY, UTAH Street 3+50.00 **2**00 50 00



Project Info. <u>J. NATE REEVE, P.E.</u> Begin Date: MARCH 18, 2011 LISA ESTATES PHASE 1 & 2 Number: <u>1714–27</u>

Sheet 3 Sheets





Revised 9-25-12

LISA ESTATES SUBDIVISION Phono-1 & Phono-2

Phase-1 & Phase-2 Storm Water Pollution Prevention Plan Exhibit

WARREN, WEBER COUNTY, UTAH MARCH, 2011





Vicinity Map

NOT TO SCALE

G ASSOCIATES, ITALES, ITAC.

4155 S. HARRISON BLVD., SUITE 310, OGDEN, UTAH 84403
TEL: (801) 621–3100 FAX: (801) 621–2666 www.reeve-assoc.com
LAND PLANNERS * CMIL ENGINEERS * LAND SURVEYORS

TRAFFIC ENGINEERS * STRUCTURAL ENGINEERS * LANDSCAPE ARCHITECT




	DESCRIPTION	County Comments					
REVISIONS		County	County	County	County	County	
<u> </u>		문	RH H	RH	RH	RH	
	DATE 11 11 PU	6-15-11 RH	9-29-11 RH	6-29-12 RH	8-01-12 RH	9-25-12 RH	

Phase 1 & 2

warren, weber COUNTY, UTAH

torm Water Pollution
revention Plan Exhibit

S



	ATE OF UTE	
	<u>Project Info.</u>	
	Engineer: J. NATE REEVE, P.E. Drafter: R. HANSEN	
Begin Date: MARCH 18, 2011		
	MARCH 18, 2011	

Number: 1714-27

Sheet 6
Sheets

LISA ESTATES

SUBDIVISION
PHASE 1 & 2

Scale: 1" = 80'

All storm water inlets to be protected by straw wattle barriers, or gravel bags (see detail).

Describe BMP's to eliminate/reduce contamination of storm water from:

Equipment / building / concrete wash areas: To be performed in designated areas only and surrounded with silt fence barriers.

Soil contaminated by soil amendments: If any contaminates are found or generated, contact environmental engineer and contacts listed.

If any contaminates are found or generated, contact environmental engineer and contacts listed.

Fueling area:

To be performed in designated areas only and surrounded with silt fence. Vehicle maintenance areas:

To be performed in designated areas only and surrounded with silt fence. Vehicle parking areas:

To be performed in designated areas only and surrounded with silt fence.

Equipment storage areas: To be performed in designated areas only and surrounded with silt fence.

Materials storage areas:

To be performed in designated areas only and surrounded with silt fence.

Waste containment areas: To be performed in designated areas only and surrounded with silt fence.

To be performed in designated areas only and surrounded with silt fence.

BMP's for wind erosion:

Stockpiles and site as needed to be watered regularly to eliminate / control wind erosion

Construction Vehicles and Equipment:

a. Maintenance

Maintain all construction equipment to prevent oil or other fluid leaks.

Keep vehicles and equipment clean, prevent excessive build—up of oil and grease. Regularly inspect on—site vehicles and equipment for leaks, and repair immediately.

- Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment on-site.

- Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic, and transmission fluids.

If fueling must occur on—site, use designated areas away from drainage.

- Locate on-site fuel storage tanks within a bermed area designed to hold the tank volume.

- Cover retention area with an impervious material and install in in a manner to ensure that any spills will be contained in the retention area. To catch spills or leaks when removing or changing fluids. Use drip pans for any oil or fluid changes.

— Use as little water as possible to avoid installing erosion and sediment controls for the wash area.

- If washing must occur on—site, use designated, bermed wash areas to prevent waste water discharge into storm water, creaks, rivers, and other water bodies.

Use phosphate-free, biodegradable soaps.

Do not permit steam cleaning on—site.

Spill Prevention and Control a. Minor Spills:

Minor spills are those which are likely to be controlled by on—site personnel. After contacting local emergency response agencies, the following actions should occur upon discovery of a minor spill: Contain the spread of the spill.

- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (i.e. absorbent

materials, cat litter, and / or rags). — If the spill occurs in dirt areas, immediately contain the spill by constructing an earth dike. Dig up property

dispose of contaminated soil. - If the spill occurs during rain, cover the impacted area to avoid runoff.

- Record all steps taken to report and contain spill.

On—site personnel should not attempt to control major spills until the appropriate and qualified emergency response staff have arrived at the site. For spills of federal reportable quantities, also notify the National Response Center at (800) 424-8802. A written report should be sent to all notified authorities. Failure to report major spills can result in significant fines and penalties.

Post Roadway / Utility Construction

Maintain good housekeeping practices.

Enclose or cover building material storage areas. Properly store materials such as paints and solvents.

Store dry and wet materials under cover, away from drainage areas. Avoid mixing excess amounts of fresh concrete or cement on-site.

Perform washout of concrete trucks offsite or in designated areas only.

Do not wash out concrete trucks into storm drains, open ditches, streets or streams. Do not place material or debris into streams, gutters or catch basins that stop or reduce the flow of runoff

All public streets and storm drain facilities shall be maintained free of building materials, mud and debris

caused by grading or construction operations. Roads will be swept within 1000' of construction entrance daily,

Install straw wattle around all inlets contained within the development and all others that receive runoff from the

development. Erosion Control Plan Notes

The contractor will designate an emergency contact that can be reached 24 hours a day 7 days a week. A stand—by crew for emergency work shall be available at all times during potential rain or snow runoff events.

Necessary materials shall be available on site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain or runoff is eminent.

Erosion control devices shown on the plans and approved for the project may not be removed without approval of the engineer of record. If devices are removed, no work may continue that have the potential of erosion without consulting the engineer of record. If deemed necessary erosion control should be reestablished before this work begins.

d. Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of the slope at the conclusion of each working day. this should be confirmed by survey or other means acceptable to the engineer of

All silt and debris shall be removed from all devices within 24 hours after each rain or runoff event. Except as otherwise approved by the inspector, all removable protective devices shown shall be in place at the end of


each working day and through weekends until removal of the system is approved. All loose soil and debris, which may create a potential hazard to offsite property, shall be removed from the site as directed by the Engineer of record of the governing agency.

The placement of additional devices to reduce erosion damage within the site is left to the discretion of the Engineer of Desilting basins may not be removed or made inoperable without the approval of the engineer of record and the


Erosion control devices will be modified as need as the project progresses, and plans of these changes submitted for approval by the engineer of record and the governing agency.


Conduct a minimum of one inspection of the erosion and sediment controls every two weeks. Maintain documentation on site. Part III.D.4 of general permit UTR300000 identifies the minimum inspection requirements.

Part II.D.4.C identifies the minimum inspection report requirements. failure to complete and/or document storm water inspections is a violation of part III.D.4 of Utah General Permit UTR



Cross Section 50' x 20' Construction Entrance





Section

-2 TO 1 SLOPE

Perspective View

The silt fence should be installed prior to major soil disturbances in the drainage area. The fence should be placed across the slope along a line of force the geotextile, it shall have a minimum uniform elevation wherever flow of sediment is anticipated. Table 1 shows generally—recommended maximum slope lengths (slope spacing between fences) at various site grades for most silt fence applications.

Reeve & Associates, Inc. - Solutions You Can Build On

	TABLE 1: Recommended Maximum Slope Lengths for Silt Fence					
	(Richardson & N	Middlebrooks, 1991)				
	Slope Steepness (%)	Max. Slope Length m (ft)				
	<2%	30.5m (100ft)				
	2-5%	22.9m (75ft)				
	5-10%	15.2m (50ft)				
	10-20%	7.6m (25ft)				
	>20%	4.5m (15ft)				
_						

PREFABRICATED SILT FENCE ROLLS *Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location. *Unroll the silt fence, positioning the post against the downstream wall of the trench. Adjacent rolls of silt fence should be joined be nesting the end post of one fence into the other. Before nesting the end posts, rotate each post until the geotextile is wrapped completely around the post, then abut the end posts to create a tight seal as shown in Figure 1. *Drive posts into the ground until the required fence height and/or anchorage depth is

*Bury the loose geotextile at the bottom of the fence in the upstream trench and backfill with natural soil, tamping the backfill to provide good compaction and anchorage. Figure 2 illustrates a typical silt fence installation and anchor trench placement.

Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location. *Drive wooden posts, or steel posts with fastening projections, against the downstream wall of the trench. Maximum post spacing should be 2.4-3.0m (8-10ft). Post spacing

should generally be less than three (3) times *If a steel or plastic mesh is required to reinmesh opening of 15.2cm (6"). *Fasten the mesh to the upslope side of the posts using heavy duty wire staples, tie wires or hog strings. Extend the mesh into the bottom


of the trench. *The geotextile shall then be stapled or wired to the posts. An extra 20-50cm (8-20") of geotextile shall extend into the trench.

*Inspect the silt fence daily during periods of rainfall, immediately after significant rainfall event and weekly during periods of no rainfall. Make any repairs immediately. *When sediment deposits behind the silt fence are one—third of the fence height, remove and properly dispose of the silt accumulations. Avoid damage to the fabric during cleanout.


Silt Fence Detail

10 MIL PLASTIC LINER –

*Silt fence should not be removed until construction ceases and the upslope area has been properly stablized and/or revegetated.



Roll-to-Roll Connection



Inlet Box Protection SEE STAKE DETAIL STRAW WATTLE SEE STAKE DETAIL STORM DRAIN — DROP INLET


ANCHOR THROUGH

STORM DRAIN INLET-


ANCHOR THROUGH

NETTING


Plan View



Drop Inlet Protection



Concrete Washout Area w/ 10 mil Plastic Liner






-GRAVEL BAGS

14-15-15-15-10-1-25-25-25-4 9 9 9 9 9

ivision lution Exhibit db %

at to SP



Project Info. J. NATE REEVE, P.E. Drafter: R. HANSEN Begin Date: MARCH 18, 2011 LISA ESTATES SUBDIVISION PHASE 1 & 2 Number: <u>1714–27</u>

6

Sheets

Sheet

6