MATCH LINE - SEE SHEET S1.02

9 | 10 | 11 | 12 | 13

8'-0" | 21'-0" | 20'-0"

FACE o/ STRUCT SHT'G A

FACE OF CONCRETE B

FACE o/ STRUCT SHT'G C

FACE o/ STRUCT SHT'G D

-1'-11" B.O. FTG.
-3'-11" B.O. FTG.
+1'-1" B.O. FTG.
-0'-11" B.O. FTG.
+7'-1" B.O. FTG.
+5'-1" B.O. FTG.
+3'-1" B.O. FTG.
STEP
WF-2
WF-3
1'-0"
TYP. 6 S4.10
3 S3.10
STAIRS PER ARCH'L DRAWINGS - TYP.
5" CONC. FLOOR SLAB w/ #3 @ 16" O.C. MAX. CHAIRED AT SLAB MIDHEIGHT, OVER VAPOR BARRIER AND 3" INSULATION PER ARCH., OVER 4" COMPACTED GRAVEL PER GEOTECH REPORT. TYP., U.N.O.
-2'-11" B.O. FTG.
WF-5
10 S3.10 TYP.
5'-0"
P4
+1'-1" FIN. SLAB
-0'-11" FIN. SLAB
+3'-1" FIN. SLAB
WF-8
3A S3.10
-1'-11" B.O. FTG.
WF-7
2 S3.10
4'-10"
P1
WF-1
2 S3.11 TYP.
-3'-11" B.O. FTG.
-5'-5" B.O. FTG.
+1'-7" T.O. CONC.
19'-4" x 7'-4" x 24" THK FTG. w/ (7)#7 LONGIT. AND (17)#7 TRANSVERSE, BOT.
1 S3.10
+3'-7" T.O. CONC.
15'-0" x 8'-0" x 24" THK FTG. w/ (7)#7 LONGIT. AND (13)#7 TRANSVERSE, BOT.
P2
WF-2
6"
1 S3.11 TYP.
STEP SILL WALL AT BREAK BTWN UNITS, TYP.
SIMPSON "HDU14-SDS2.5" TO 6x8 POST EA. END OF WALL PANEL w/ 1"ø ANCHOR BOLT w/ DOUBLE NUT EMBEDDED MINIMUM 24" INTO STEM WALL.
+5'-7" T.O. CONC.
1'-6"

MATCH LINE - SEE SHEET S1.02

FOUNDATION PLAN NOTES:

1. SEE SHEETS S0.10 & S0.11 FOR:
   - A. GENERAL STRUCTURAL NOTES
   - B. TYPICAL EXCAVATION ADJACENT TO FOOTING
   - C. TYPICAL SLAB JOINT DETAILS
   - D. TYPICAL STEPPED FOOTING DETAIL
2. P1 - DENOTES WOOD POST MARK - SEE SCHED. ON SHEET S0.12.
3. WF1 - DENOTES WALL FOOTING MARK - SEE SCHED. ON SHEET S0.12.
4. SW1 - DENOTES SHEARWALL SHEATHING PER SCHED. ON SHEET S0.12.
5. ALL SLABS ON GRADE ARE TO BE JOINTED AS SHOWN. PROVIDE (2) #4 x 4'-0" MID-HEIGHT SLAB BARS ADJACENT TO ALL DISCONTINUOUS JOINT LOCATIONS. ALL COLUMN ISOLATION JOINT CORNERS ARE TO BE INTERSECTED BY A SLAB JOINT OR REINFORCED WITH SLAB BARS PER ABOVE.
6. CONTRACTOR TO VERIFY ALL DIMENSIONS AND ELEVATIONS WITH ARCHITECTURAL DRAWINGS PRIOR TO CONSTRUCTION. SEE ARCHITECTURAL FOR ALL DIMENSIONS, SLAB SLOPES & DEPRESSIONS NOT NOTED.
7. SEE ARCH'L DRAWINGS FOR ALL DIMENSIONS NOT INDICATED.
8. FIN. FLR. DATUM: +0'-0" = 8600.5'

architect
STUDIO MA
130 N Central Avenue No.300
Phoenix, Arizona 85004
T 602 251 3800

sma project no.
16-101

sma project name
POWDERCAT

COPYRIGHT 2017 STUDIO MA
This document is an instrument of service and shall remain the property of the Architect, who shall retain all common law, statutory and other reserved rights, including the copyright thereto.

OWNER
orr powdercat th development, llc
11180 sunrise valley drive, ste 300
reston, va 20191
t (703) 289-2125

CIVIL
talisman civil consultants
5217 south state st, ste 200
murray, ut 84107
t (801) 743-1308

STRUCTURAL
rudow+berry, inc.
4032 n miller rd. a100
scottsdale, az 85255
t (480) 946-8171

MECH/PLBG/ELEC
peterson associates consulting engineers, inc.
7201 n dreamy draw dr, ste 200
phoenix, az 85020
t (602) 388-1732

LANDSCAPE
langvardt design group
328 W 200 S
salt lake city, ut 84101
t (801) 583-1295

PROFESSIONAL ENGINEER
9250862-2202
MARK A. RUDOW
07/12/17
STATE OF UTAH

s1.03
FOUNDATION PLAN LOWER LEVEL

KEYMAP

1/4" = 1'-0"
scale

2

PERMIT SET
phase / rev

2017.06.01
date

AutoCAD Version: 2017
July 12, 2017 10:21:44 a.m.
Drawing Name: C:\Users\mwberry\Documents\Revit Projects\Powdercat\S1.03.DWG (A4B)
Xrefs: XH-FDNNOTES XR-MAIN-16126 XT-16126