

3985 N 2975 W FARR WEST UTAH

CONSULTANT SCHEDULE									
PHONE NUMBER	CONTACT INFO.	REMARKS							
(801) 298-2240	BLAIR/ MIKE	DESIGNER/ DRAFTER							
(801) 876-3501	KELBY YORK	STRUCTUAL ENGINEER							
	PHONE NUMBER (801) 298-2240	PHONE NUMBER CONTACT INFO. (801) 298-2240 BLAIR/ MIKE							

DRAWING SCHEDULE COVER SHEET & DRAWING SCHEDULE SITE PLAN SWPP PLAN BASEMENT FLOOR & FOOTING AND FOUNDATION PLAN GENERAL NOTES & DETAILS MAIN FLOOR PLAN EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS FRAMING PLANS AND BEAMS FRAMING SECTIONS FRAMING SECTIONS & ROOF DRAINAGE PLAN ELECTRICAL, MECHANICAL, & PLUMBING PLAN ELECTRICAL, MECHANICAL, & PLUMBING PLAN ADDITONAL NOTES & DETAILS ADDITONAL NOTES & DETAILS

DEFERRED SUBMITTAL	SC	QUARE	FOOTAGE		
ALL DEFERRED SUBMITTALS AND CHANGES TO PLANS MUST BE-	-LOC	CATION=	-SQUARE FOOTAGE-		
A. FIRST APPROVED BY THE DESIGNER OF RECORD	MAIN	LEVEL	2264		
PRIOR TO SUBMITTING TO BUILDING OFFICIAL. B. APPROVED BY THE STRUCTURAL ENGINEER OF RECORD	LOWER	R LEVEL	2139		
FOR ANY STUCTURAL ITEMS FOR DEFERRED SUBMITTALS	STORAG	SE AREAS	10/4		
-ITEMS- 1FIRE SPRINKLER PLANS (MOD. NFPA 13D) 2RADIANT HEAT DESIGN (LAYOUT PLANS, CALCS, & SPECS. 3GAS PIPING SCHEMATIC-PROVIDED BY MECH. CONTRACTOR 4TRUSS PLANS & CALCS. (IF APPICABLE)	-TOTAL	_ LIVING-	45 <i>0</i> T		
5STUCCO SYSTEM. (IF APPLICABLE)	COVERED	EXT. AREAS	121		
6FIREPLACE PRODUCT INFO. (IF APPLICABLE) 1CONSTRUCTION MITIGATION PLAN.	GAF	RAGES	1016		
8GEOTCH, SURVEY (IF APPLICABLE AS DETERMINED BY BUILDING OFFICIAL) 9LANDSCAPE PLAN (IF APPLICABLE)	CODE ANALYSIS				
10SPECIAL INSPECTIONS FOR WELDING ON THIS PROJECT (IF APPLICABLE)	-UTAH 9	STATE ADOPTED CO	DDES AS OF JULY 1, 2013- BUILDING OCCUPANCY		
IICONTRACTOR TO PROVIDE EXTERIOR LIGHTING SPECS. PRIOR TO FOUR-WAY INSPECTION	2015 IBC	2015 IMC	R-3 TYPE 5		
12POOL DESIGN BY OTHERS (IF APPLICABLE)	2Ø14 NEC	2015 IFGC	B-CONSTRUCTION 2015 RES CHECK		

GENERAL NOTES

- A. EXCAVATION, BACK FILL, GRADING & DAMPROOFING
- 1. All excavations for footings shall be to natural undisturbed soil. 2. All back filling shall be done with granular free draining material. Existing site material may be used so long as existing soils are free from clay soils and any construction debris. Compact all back fill material in 10" lifts to 95% of maximum soil density.
- 3. Finish grading shall be done so as to provide positive drainage away from all building foundations. A minimum slope of 6" per 10'-0" and shall be maintained with a 1% slope thereafter to approved drainage areas.
- 4. All raingutter downspouts shall be piped away from the home to an approved drainage area. No raingutters shall drain in window wells, or rock light wells.
- 5. If any ground water is encountered during excavation, a qualified soils Engineer shall be retained to make an on-site assesment of the situation.
- 6. Footing drains shall be placed around all exterior footings and gravity fed to an approved drainage area.

B. WINDOWS

- 1. All windows in rooms used for sleeping shall have sills not more than 44" above the floor with an operable opening of not less than 5.7 square feet. The height of the window shall not be less than 24" with a net clear width of not less than 20". Exception: grade floor openings shall have a min. net clear opening of 5.0 sq. ft.
- 2. Habitable rooms require 8% of floor area to be glazing with 1/2 of that glazing to be operable
- 3. All windows to be double pane insulated glazing of 3/16" double strength "B" grade glass minimun.

. VENTILATION

- 1. Natural ventilation shall be provided to every habitable room with equal to 4% of floor area with operable windows which will provide (.35) fresh air changes per hour.
- 2. No gas connections allowed in any rooms used for sleeping or in any corridors leading to or through any sleeping room.
- 3. Ventilation shall be provided into all crawl spaces by means of screened vents measuring not less than 7" x 14" spaced not more than 25' apart and placed so as to provided cross ventilation.
- 4. Provide (2) combustion air ducts to furnace rooms (1) placed at 18" above floor and (1) placed at 12" below the ceiling with an area of not less than (1) square inch per 1,000 BTUH input.
- 5. provide attic ventilation equal to 1/150 of the area of the space ventilated.
- 6. Mechanical ventilation may be provided in habitable rooms, where not required for emergency escape. System will be able to provide (.35) fresh air changes per hour.

D. FIRE PROTECTION & WARNING

- I. Provide $\frac{5}{6}$ " type "X" gyp. bd. on all supporting walls and ceilings of the garage adjacent to living areas. Nail all 5/8" type "X" gyp. bd. at 6" o.c.. (One hour fire rated) 2. Provide ½" type "X" gyp. bd. on walls and under side of stairs under any stairway
- area used for storage. Fire block walls at all stair stringers.
- 3. Doors leading from the garage into the house shall be solid core wood or honeycomb metal doors not less than 13% thick
- 4. Smoke detectors are required in all hallways leading to sleeping rooms, sleeping rooms, unfinished areas, with a minimum of (1) one each story. Wire all smoke detectors to sound
- simultaneously. Smoke detectors must have battery back-up. 5. A minimum of 30" shall be provided above all ranged, grills, or cook tops to combustibles.

- :. HANDRAILS & GUARDRAILS 1. Handrails are required at all stairways having (2) or more risers.
- 2. Handrails shall be placed not less than 2'-10" above stair nosing and not more than
- 3. Handrail gap size shall have a circular cross section of $1\frac{1}{4}$ " minimum $2\frac{5}{8}$ " max. Edges shall
- have a minimum radius of $\frac{1}{6}$ ". Handrails may project $4\frac{1}{2}$ " into the stairway on both sides. Continuous handrails shall be permitted to be interrupted by a newel post at a turn and the use of a volute turn or starting easing shall be allowed on lowest tread. 4. Guardrails are required at all landings or decks or floor levels more than 30" apart.
- 5. Balusters for guardrails shall be spaced such that a 4" diameter sphere shall not pass through.
- 6. When a guardrail is combined with a handrail on al open side of stairs, guardrail


Š

NOTE

PLAN,


SITE

REVISIONS ADDRESS 10-19-18




ENGINEER OF RECORD CAD TECH

RELEASE DATE



4000 NORTH STREET



ADDRESS: 3985 N 2975 W FARR WEST UTAH

LINE LEGEND

SITE PLAN GENERAL NOTES

- DUST, MUD AND EROSION SHALL BE CONTROLLED BY WHATEVER MEANS NECESSARY, AND THE ROADWAY SHALL BE KEPT FREE OF MUD AND DEBRIS, AT ALL TIMES.
- * BUILDER/OWNER SHALL SECURE AN EXCAVATION PERMIT PRIOR TO DOING ANY WORK IN THE PUBLIC RIGHT-OF-WAY. TRAFFIC PLAN, BONDING AND INSURANCE WILL BE REQUIRED.
- * PROVIDE FINISH GRADING AWAY FROM THE HOUSE ON ALL SIDES AT A MINIMUM OF 6" IN.FIRST 10'-0" HORIZONTAL SLOPE IN LANDSCAPED AREAS. THEN MAINTAIN 2% MIN.HORIZONTAL SLOPE IN GRADE THEREAFTER TO APPROVED DRAINAGE AREAS.
- * IF RETAINING WALLS REQUIRED, A PROFESSIONAL ENGINEER, CURRENTLY LICENSED IN UTAH, SHALL INSPECT AND APPROVE ANY RETAINING WALL THAT IS HIGHER THAN (4) FEET FROM BOTTOM FINISH GRADE TO TOP OF WALL, ONCE CONSTRUCTED. * PROVIDE ON SITE RETENTION OF ALL STORM RUN OFF, BY WHATEVER MEANS NECESSARY DURING CONSTRUCTION.
- SHOULD GROUND WATER BE INCURRED DURING EXCAYATION, A QUALIFIED SOILS ENGINEERHALL BE RETAINED TO DESIGN AND APPROVE A CONTINUOUS FRENCH DRAIN AT FOUNDATION, ON SITE.
- MAINTAIN NATURAL EXISTING GRADE AT ALL SIDES OF LOT TO RETAIN STORM WATER ON SITE FOR NATURAL PERCOLATION.


SITE REVISIONS

CHEDULE


S

NOTES

ENGINEER OF RECORD CAD TECH RELEASE DATE



4000 NORTH STREET



ADDRESS: 3984 N 2975 W FARR WEST UTAH

SWPP GENERAL NOTES

NOTE: ALL STORM WATER AND DIRT WILL BE
KEPT ON SITE DURING CONSTRUCTION UNTIL
FINAL LANDSCAPING IS DONE, GENERAL CONTRACTOR
WILL BE HELD RESPONSIBLE FOR KEEPING DIRT/MUD
ON SITE DURING BAD WEATHER AND FOR CLEANING UP
AFTER SUBCONTRACTORS

NOTE: STREET CURB AND GUTTER WILL BE INSPECTED AND CLEANED AT THE END OF EVERY DAY.

NOTE: GRAVEL BAGS TO BE PLACED AND MAINTAINED AROUND ANY STORM DRAIN INLET ADJACENT TO OR IMMEDIATELY FROM SITE DURING CONSTRUCTION

NOTE: BERMS OR SWALES MAY BE REQUIRED ALONG PROPERTY LINES TO PREVENT STORM WATER FLOW ONTO ADJACENT LOTS FINAL GRADING SHAL BLEND WITH ADJACENT LOTS.

NOTE: A LINED CONCRETE WASHOUT MUST BE PROVIDED AT THE CONSTRUCTION SITE FOR ALL CONCRETE WORK WASHOUT INTO THE FOUNDATION OR ON THE GROUND IS PROHIBITED.

- LOCATION OF TRUCK
 WASH-OFF PROVIDE A
 4" GRAVEL BED
- 2 LOCATION OF PORTABLE TOILET
- 3 CONSTRUCTION MATERIALS STORAGE AREA
- DESIGNATED
 CONCRETE
 WASHOUT
 LOCATION OF DUMPSTER
 (FOR CONSTRUCTION DEBRISE)

REVISIONS date item

10-19-18

ADDR


SCHEDULE

REVISIONS
date item

10-19-18 ADDRESS


ENGINEER
OF
RECORD
CAD TECH M.H.F
RELEASE
DATE
9/25

STORM WATER POLLUTION PREVENTION PLAN



REVISIONS

date ADDRESS 10-19-18



ENGINEER OF RECORD CAD TECH

DATE

FOOTING AND FOUNDATION GENERAL NOTES

- ALL EXTERIOR FLAT WORK CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH EQUAL TO AT LEAST 3500 PSI WITHIN 28 DAYS AFTER PLACING. FOOTINGS AND FOUNDATION WALLS SHALL BE AT LEAST 3000 PSI.
- ALL METAL REINFORCEMENT SHALL CONFORM TO A.S.T.M. A615-68 GRADE 60, WITH A MINIMUM YIELD STRENGTH OF 60,000 PSI.
- ALL REINFORCING BARS SHALL BE DETAILED, BOLSTERED AND SUPPORTED IN ACCORDANCE WITH ACI 315
- ALL REINFORCEMENT BARS SHALL BE SECURELY ANCHORED TO THE FORMS AND SPACED FROM TDOUG AS FOLLOWS: (a) FOR CONCRETE NOT EXPOSED DIRECTLY TO THE GROUND OR WEATHER, 3/4 IN.IN SLABS AND WALLS. (b) FOR CONCRETE EXPOSED TO THE GROUND OR WEATHER, 2 IN. IN WALLS, 3 IN. ABOVE BOTTOM OF FOOTINGS.
- · ALL SPLICES IN CONTINUOUS REINFORCING BARS SHALL LAP 36 BAR DIAMETERS.
- 6 . ALL SUCH SPLICES SHALL BE MADE IN A REGION OF COMPRESSION UNLESS SHOWN OTHERWISE.
- UNLESS OTHERWISE SHOWN, MAKE ALL CONCRETE SLABS ON EARTH AT LEAST 4 IN. THICK
- PROVIDE 2 IN. X 4 IN. X CONT. KEY IN ALL WALL FOOTINGS WHERE GROUND WATER IS PRESENT.
- L LARGE AREAS OF SLAB ON GRADE SHALL BE PLACED IN STRIPS SUBDIVIDED BY CONTRACTION OR CONSTRUCTION JOINTS INTO ROUGHLY SQUARES WHOSE SIDES SHALL NOT EXCEED 25 FT. IN EITHER DIRECTION.

PLACE FOOTINGS AS TO PROVIDE 30" MIN. FROST PROTECTION

- ALL STRUCTURAL STEEL AND STRUCTURAL STEEL WORK SHALL COMPLY WITH "SPECIFICA- TIONS FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILD - INGS OF THE A.I.S.C."
- · ALL STRUCTURAL AND MISCELLANEOUS STEEL SHALL BE ASTM GRADE 50
- ALL WELDS AND WELDING SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS OF "THE AMERICAN WELDING SOCIETY," USING ETØXX ELECTRODES.

2,500 PSI CC	ONCRETE		F	'OU	NI	OAT	Ί(NC	1 .	SC	H	Œ	DU	LE		60,000	PSI STEEL
MAXIMUM WALL HEIGHT FROM	TOP EDGE	MIN. WALL		RTICAL L REINF.		RIZONTAL L REINF.			R O	PENIN	VGS		MAX. LINTEL	MIN. LINTEL	SIZE	ITIONAL FTG.	
	SUPPORT	MIDTH	SIZE	SPACING	SIZE	SPACING	AB NO.	OVE SIZE	SII NO.	OES SIZE	BE NO.	LOW SIZE	LENGTH	DEPTH	WIDTH	LENGTH	FOUNDATION BOLTS
2'-Ø" TO 5'-Ø"	NONE	8"	#4	24" O.C.	#4	18" O.C.	2	#4	1	#4	1	#4	2'	6"		TG. SCHED.	1/2" × 10" @ 32" O.C.
5'-1" TO 6'-0"	NONE	8"	#4	18" O.C.	#4	18" O.C.	2	#4	1	#4	1	#4	3'	6"	36"	4 #4 × CONT	1/2" × 10" @ 32" O.C.
6'-1" TO T'-0"	NONE	8"	#4	12" O.C.	#4	18" O.C.	2	#4	1	#4	1	#4	4'	8"	42"	5 #4 × CONT.	1/2" × 10" @ 32" O.C.
7'-10" TO 8'-0"	FLOOR	8"	#4	24" O.C.	#4	18" O.C.	2	#4	1	#4	1	#4	5'	10"	SEE	TG, SCHED,	1/2" × 10" @ 32" O.C.
8'-1" TO 9'-0"	FLOOR	8"	#4	16" O.C.	#4	18" O.C.	2	#4	1	#4	1	#4	6'	12 "	SEE F	FTG, SCHED,	1/2" × 1Ø" @ 32" O.C.
9'-1" TO 10'-0"	FLOOR	8"	#4	11" O.C.	#4	11" O.C.	2	#4	1	#4	1	#4	6'	12 "	24"	2 #4 × CONT.	5/8" × 12" @ 24" O.C.
>10'-1"+	REQ. ENG																REQ. ENG

- REBAR TO BE PLACED IN THE CENTER OF THE WALL AND EXTEND FROM THE FOOTING TO WITHIN 3" OF THE TOP OF THE WALL. . *4 FOOTING DOWELS SHALL EXTEND 24" INTO THE FOUNDATION AND MATCH VERTICAL STEEL. . ONE BAR SHALL BE LOCATED IN THE TOP 3" AND ONE BAR IN THE BOTTOM 3" OF THE FOUNDATION WALL.
- THE REMAINING EQUALLY SPACED BETWEEN) 4. BARS SHALL BE PLACED WITHIN 2" OF THE OPENING AND EXTEND 24" BEYOND THE EDGE OF THE OPENING. . THIS TABLE ASSUMES A MINIMUM OF 1500 PSF BEARING CAPACITY, 38 PSF EQUIVALENT FLUID PRESSURE AND A
- GLOBALLY STABLE SITE
- . ALL FOUNDATION STEPS SHALL BE 2'-0" MINIMUM.
- . USE 3" imes 3" imes 1/4" WASHERS, IF SLOTTED WASHER IS USED, ADD CUT WASHER. 3. J-ANCHOR BOLTS MAY BE REPLACED WITH #4 BARS @ 12" O.C. EXTENDING 24" OUT OF FND CAST INTO SUSPENDED SLAB . LARGER FOOTINGS SPECIFIED ON 5'-1" TO 7'-0" WALL MAY BE REDUCED TO SIZE SPECIFIED ON THE FOOTING SCHEDULE, AND VERTICAL REBAR SPACING OF 24" O.C. FOR FOUNDATION WALL MAY BE USED PROVIED THE FOLLOWING CONDITIONS EXIST:
- A. 5'-1"-7'-1" WALL LENGTH NOT TO EXCEED 10'-0" B. UNBALANCED BACKFILL DOES NOT EXCEED 4'-0" MINIMUM STRENGTH REQUIRES 2,500 PSI CONCRETE, HOWEVER, AS PER IRC 402.2 3,000 PSI CONCRETE SHALL BE USED

Н	OL	DOWN	SCHEDULE:	2015 IRC
	MARK	SIMPSON MODEL #	MIN. REQUIRED ATTACHMENT	NOTES/ COMMENTS:
		STHD8/8RJ ⁽²⁾	(24) 16d SINKERS	
	(H2)	STHD10/10RJ ⁽²⁾	(28) 16d SINKERS	
0 T 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	H3	STHD14/14RJ ⁽²⁾	(38) 16d SINKERS	
SHEARWALL TO FOUNDATION HOLDOWNS	44	HTT5	(26) 16d COMMON	5/8"¢ THREADED ROD EPOXY INSTALLED IN A 3/4"¢ x 12" DEEP HOLE
971178 1001 101	H5	HDUII	(3Ø) SDS 1/4" x 2 1/2" WOOD SCREW	1"¢ THREADED ROD EPOXY INSTALLED IN A 1 1/8"¢ x 18" DEEP HOLE
**	H6	HDU14	(36) SDS 1/4" x 2 1/2" WOOD SCREW	1"¢ THREADED ROD EPOXY INSTALLED IN A 1 1/8"¢ x 24" DEEP HOLE
0 4 C 7 C 7 R 0 R	H7	MST48	(34) 16d SINKERS	CENTER STRAP SO EQUAL LENGTHS ARE ON UPPER AND LOWER WALLS
UPPER TO LOWER WALL TIE ANCHORS	(SH)	MST72	(48) 16d SINKERS	CENTER STRAP SO EQUAL LENGTHS ARE ON UPPER AND LOWER WALLS
LOU TIE,	(P)	HDU8	(20) SDS 1/4 x 2 1/2" WOODSCREWS	1/8" FTHREADED ROD BETWEEN FLOORS INSTALL ON 4x (MIN) POST @ BOTH FLOORS

- 1, ALL FOUNDATION "HOLDOWNS" AND BETWEEN LEVEL TIES SHALL BE ATTACHED TO A MINIMUM OF (2) $2 \times OR$ A $4 \times MEMBER$. 2. 'RJ' AFTER MODEL INDICATES STHD'S FOR RIM JOIST APPLICATIONS. USE RJ MODELS a ALL RIM JOIST APPLICATIONS
- 3. USE STANDARD WASHERS WHEN BOLTING HD'S TO THE STUDS OPPOSITE THE "HOLDOWN". HD'S MUST BE LOCATED ON THE STUDS TO PROVIDE A MINIMUM OF I BOLT DIAMETERS BETWEEN THE HOLE AND THE END OF THE STUDS.
- 4. FOUNDATION CONCRETE STRENGTH SHALL BE 2,500 PSI. INSTALL A MINIMUM OF (1) *4 HORIZONTAL
- REBAR IN SHEAR CONE ON ALL FOUNDATION "HOLDOWNS". 5. 16d SINKERS MAY BE REPLACED w/ 10d COMMON NAILS w/ NO REDUCTIONS (16d SINKERS = 0.148" \$ x 3 1/4" LONG, 10d COMMON = 0.148" ϕ x 3"). 'GUN NAILS' MAY NOT BE USED UNLESS SPECIFICALLY NOTED.
- 6. REFER TO ATTACHED CONCRETE SECTIONS AND DETAILS SHEET OR TO SIMPSON CATALOG C-2009 FOR APPLICABLE DETAILS AND ADDITIONAL INSTALLATION INSTRUCTIONS.
- 1. ALL HOLDOWNS ON THIS SCHEDULE MAY NOT BE APPLICABLE TO THIS PLAN.

FOOTING SCHEDULE									ALL FOOTINGS ON THIS SCHEDULE MAY NOT BE USED FOR THIS PLAN			
			CROSSWISE REINF. LENGTHWISE REINF.				NOTES					
MARK	MIDTH	LENGTH	THICK	NO.	SIZE	LENGTH	SPACE	NO.	SIZE	LENGTH	SPACE	
F-1	1'-8"	CONT.	10"	NONE				(2)	#4	CONT.	14"	PERIMETER FTG.
F-2	1'-8"	CONT.	10"	NONE	_			(2)	#4	CONT.	14"	INTERIOR FOOTING UNDER SLAB
F-3	2'-0"	CONT.	12"	NONE				(3)	#4	CONT.	9"	PERIMETER FTG.
F-4	2'-6"	CONT.	12"	NONE				(4)	#4	CONT.	8"	PERIMETER FTG.
F-5	3'-Ø"	3'-Ø"	12"	(4)	#4	2'-6"	10"	(3)	#4	2'-6"	15"	SPOT FTG.
F-6	4'-0"	4'-0"	12"	(5)	#4	3'-6"	101/21	(4)	#4	3'-6"	101/2"	SPOT FTG.
F-7	5'-0"	5'-Ø"	12"	(5)	#4	4'-6"	131/2"	(7)	#4	4'-6"	131/2"	SPOT FTG.
F-8	4'-0"	CONT.	12 "	NONE	_			(5)	#4	CONT.	101/2"	PERIMETER FTG.

FRAMING GENERAL NOTES 2015 I.R.C.

- ALL BEARING HEADERS, JOISTS AND BEAMS SHALL BE DOUG FIR #2 OR BETTER. ALL BEARING COLUMNS SHALL BE DOUG FIR #2 OR BETTER. ALL BEARING STUDS & TRIMMERS SHALL BE DOUG FIR #2 OR BETTER FOR MAX. HEIGHTS ALLOWED SEE STUD WALL HEIGHT SCHEDULE.
- GLU-LAMINATED TIMBER MEMBERS SHALL HAVE A MINIMUM ALL ALLOWABLE BENDING STRESS OF 2,400 psi (24F-V4) LAMINATED VENEER LUMBER SHALL HAVE A MINIMUM ALLOWABLE BENDING STRESS OF 2,000 psi PROVIDE SOLID BLOCKING AT LEAST 2 IN. THICK AND FULL DEPTH OF JOIST @ ENDS AND AT EACH SUPPORT OF JOIST. PROVIDE SOLID BLOCKING @ BEARING ENDS OF TRUSSES.
- 3. LAMINATED BUILT-UP BEAMS OF 2X MEMBERS SHALL BE SPIKED TOGETHER WITH NOT LESS THAN (2) ROWS 16d SPIKES AT SIXTEEN-INCH (16 IN.) CENTERS, STAGGERED, USE (2) ROWS 16d COMMON NAILS AT 3" OFF TOP AND BOTTOM OF BUILT UP BEAM. STAGGER TOP AND BOTTOM ROWS OF NAILS.
- 4. ALL STRUCTURAL SHEATHING SHALL BE A.P.A. RATED AND SHALL NOT EXCEED MAXIMUM SPAN RATING. ROOF SHEATHING SHALL BE 7/16 STRUC II WITH A SPAN RATING OF 24/16. ROOF SHEATHING SHALL BE FASTENED TO FRAMING WITH 8d @ 6" O.C. @ BOUNDARY AND EDGES, & W/8d @ 12" O.C. @ FIELD. FLOOR SHEATHING SHALL BE 34" STRUCT II T&G WITH A SPAN RATING OF 40/20. FLOOR SHEATHING SHALL BE FASTENED TO FRAMING WITH 8d @ 6" O.C. @ BOUNDARY AND EDGES, & W/ 8d @ 12" O.C. @ FIELD.
- 5. TRUSSES TO BE DESIGNED & ENGINEERED BY MANUFACTURER AND GUARANTEED TO WITHSTAND LOADS AS SHOWN IN DESIGN BASIS BELOW. TRUSS MANUFACTURER TO DESIGN TRUSSES FOR ALL APPLICABLE SNOW LOADING CONDITIONS PER IRC 2009.
- 6. PROVIDE FIRE BLOCKING IN ANY STUD CAVITIES GREATER THAN 10'-0'.
- I. PROVIDE SIMPSON HI ANCHORS @ EACH TRUSS ON BEARING ENDS OF ALL TRUSSES & RAFTERS. 8. PROVIDE JOIST HANGERS WHERE SHOWN, OR WHERE APPLICABLE.
- 9. PROVIDE TRIMMERS/STUDS UNDER BEARING ENDS OF GIRDER TRUSSES & BEAMS EQUIVALENT TO THE WIDTH OF THE MEMBER SUPPORTED, OR AS SPECIFIED ON FRAMING PLANS.
- 10. PROVIDE GABLE END TRUSSES AS REQUIRED.
- II. ALL NONBEARING INTERIOR FRAMING @ 16" O.C.
- 12. FRAMING TO INCLUDE ALL FURR DOWNS, PLANT SHELVES & CEILING RAFTERS AS PER PLAN.
- 13. ALL WOOD BEAMS AND HEADERS SHALL BEAR ON MINIMUM OF (1) TRIMMER STUD AT EACH END UNLESS
- PROVIDE SOLID BLOCKING IN FLOORS TO TRANSFER COLUMN POINT LOADS THROUGH FLOOR (1³4" x 9¹/₂", 11¹/₈", AND 14" L.V.L.'s) TO MATCH FLOOR SYSTEM.
- 15. HOT TUBS OR OTHER OWNER INSTALLED ITEMS THAT IMPOSE HEAVY LOADS ON STRUCTURAL MEMBERS WILL


DESIGN BASIS	
GOVERNING BUILDING CODE	I.R.C, I.B.C. 2015
SEISMIC DESIGN SECTION	1613.5.6.2 (ASCET) CAT. D
WIND DESIGN BASIC WIND SPEED	115 М.Р.Н.
DESIGN SOIL BEARING PRESSURE	1500 P.S.F.
ROOF LIVE LOADDEAD LOAD	
SUSPENDED FLOOR LIVE LOAD	40 PSF.
DEAD LOAD	15 P.S.F.


Sl	HEAR	WAI	ALL SHEARWALLS NOTED MAY NOT BE USED IN THIS PLAN			
ALL O.	7/16" APA RATED 0.5.B.	EDGE NAILING	BOLT SPACING	SOLE PLATE TO SOLID RIM JOIST	STAPLES 16 GA ONLY	NOTES
7	ONE SIDE	8d @ 6"	32"	16d a 6"	a 3"	
2	ONE SIDE	8d @ 4"	32"	16d a 4"	a 2"	
3	ONE SIDE	8d @ 3"	24"	16d @ 3"	NOT ALLOWED	REQUIRES DOUBLE STUDS CENTERED AT PANEL EDGES-SEE NOTE 8.
1	ONE SIDE	8d @ 2"	24"	16d @ 2"	NOT ALLOWED	REQUIRES DOUBLE STUDS CENTERED AT PANEL EDGES-SEE NOTE 8.
\LL >.	5/8" APA RATED 0.5.B.	EDGE NAILING	BOLT SPACING	SOLE PLATE TO SOLID RIM JOIST	NOT ALLOWED	
	ONE SIDE	100d @ 3"	24"	16d a 3"	NOT ALLOWED	REQUIRES DOUBLE STUDS CENTERED AT PANEL EDGES-SEE NOTE 8.
). 1 1 1	1/2" GYPSUM BOARD	NAILING	BOLT SPACING	SOLE PLATE TO SOLID RIM JOIST	NOT ALLOWED	
	ONE SIDE	5d @ 7"	ALL STUDS	N/A	NOT ALLOWED	COOLER OR WALL BRD. NAILS @ ALL TOP & BOTTOM PLATES, & BLOCKING.

- SHEATHING SHALL BE STRUCTURAL II, OSB EXTERIOR GRADE. SHEATHING PANEL EDGES SHALL BE BLOCKED. PANELS TO BE CONTINUOUS ACROSS FLOOR/WALL CONNECTIONS. PANEL JOINT TO BE IN WALL W/BLOCKING.
- , J-ANCHOR BOLTS SHALL BE ASTM A307, 1/2" DIA. imes 10" LONG, WITH A MINIMUM EMBEDMENT OF T" INTO CONCRETE FOUNDATIONS, J-ANCHOR BOLTS @ 32" O.C. U.N.O. BY SHEARWALL SCHEDULE, INSTALL 3"x3"x1/4" PLATE WASHER ON EACH J-ANCHOR BOLT
- , ALL INTERIOR BEARING WALLS TO HAVE POWDER ACTUATED NAILS AT 16" O.C. 4. SILL PLATE NAILS MAY BE 16d SINKER NAILS OR 16d COMMON NAILS.
- 5. MAXIMUM STUD SPACING IS 16 INCHES ON CENTER.
- 6.PROVIDE 8d @ IØ INCHES ON CENTER AT INTERMEDIATE SUPPORTS. ALL SHEATHING SHALL SPAN ACROSS MAIN FLOOR JOISTS AND NAIL INTO SILL PLATE OR ACROSS UPPER
- FLOOR JOISTS AND INTO MAIN FLOOR WALLS. BLOCK PANEL EDGES AT MAIN AND UPPER FLOOR WALLS. 3, SHEAR WALL 3,4 \$ 6 REQUIRES DOUBLE STUDS CENTERED AT ADJOINING PANEL EDGES. FOR SHEETING NAILING SEE SHEARWALL SCHEDULE.

2015 REScheck COMPLIANCE UTAH ENERGY CONSERVATION CODE

DESCRIPTION	INSULATION R-VALUE	DOOR/ WINDOW U-VALUE, SHGC VALUE
EXTERIOR OR FURRED BASEMENT WALLD 2x4 STUDS	R-11 W/ R-1 URETHANE	R-15 TOTAL
EXTERIOR STUD WALLS 2x6 STUDS	R-19 W/ R-1 URETHANE	R-25 TOTAL
BLOWN INSULATION OVER LIVING AREA	R-50	PROVIDE INSULATION DEPTH MARKERS EVERY 300 SQ.FT. OF ATTIC AREA
NON-VENTED ROOF INSULATION OVER LIVING AREA	R-19 BATT + 3" CLOSED CELL FOAM (R-21) = R-40 TOTAL	
INSULATED FLOOR OVER GARAGE AREA & CANTILEVERS	R-3Ø	
CONC. STEM WALL	R-10 RIGID	3'-0" EA WAY (STEM WALL/ UNDER SLAB)
WINDOWS		U-0.320 SHGC-0.240
EXTERIOR DOORS SOLID/GLASS		U-0.250 SHGC-0.240
FURNACE EFFICIENCY	BASEMENT AND MA	IN FLOOR = 90%








TAIL


Z

NO

REVISIONS ADDRESS 10-19-18



ENGINEER RECORD CAD TECH RELEASE DATE








MAIN FLOOR PLAN

ALCAMED PLAN

CAMED PLAN

REVISIONS date item

10-19-18 ADDRESS




ENGINEER OF RECORD CAD TECH

TECH M.H.H.

EASE 9/25/18

A3





EXTERIOR ELEVATIONS

A CAMEO PLAN

CAMEO PLAN

CAMEO PLAN

REVISIONS
date item

10-19-18 ADDRESS

ENGINEER
OF
RECORD


CAD TECH


M.H.H.

RELEASE
DATE

9/25/18

A4






RO	OF BE	AM SCH	IEDULE
MARK	TYPE	SIZE	NOTES
RB-1	DIM.	6×10	TOP OF BEAM = BOTTOM OF RAFTERS OR (2) 1^34 " \times $9^{1}2$ " LVL's
RB-2	DIM.	(2) 2×1Ø's	TOP OF BEAM = BOTTOM OF RAFTERS
RB-3	L.V.L.	$(2) 1^{3}/4 \times 9^{1}/2$	TOP OF BEAM = BOTTOM OF RAFTERS SEE SECTION
RB-4	DIM.	(2) 2×1Ø's	HEADER OR (2) 2x10's
RB-5	L.V.L.	(2) 1 ³ /4" × 11 ⁷ /8"	HEADER (EXT. TO END OF WALL PER DETAIL)
RB-6	GLB	51/8×18	HEADER OPT. (3) 16" LVLS
RB-7	DIM.	(3) 2×1Ø's	HEADER OPT. (2) 91/2" LVLS
RB-8	DIM.	(2) 2×1Ø's	
RB-9	DIM.	(2) 2×1Ø's	HEADER
RB-10	DIM.	(2) 2×1Ø's	HEADER
RB-11	DIM.	(2) 2×1Ø's	HEADER
RB-12			
RB-13	DIM.	(2) 2×1Ø's	HEADER
RB-14	L.V.L.	$(2) ^{3}/_{4} \times 9 _{2}$	TOP OF BEAM = BOTTOM OF TRUSSES
RB-15			
RB-16			


TRUSS TYPES

SCALE: 1/8" = 1'-0"

TRUSS NOTE:

IT IS THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL TRUSS TYPES SHAPES, SIZES, LAYOUT & PITCH, AND TO COORDINATE W/ ELEVATIONS AND SECTIONS PRIOR TO ORDERING FROM MANUFACTURER.







OVE	ERFRAMING SCHEDULE				
SPAN	FRAMING MEMBERS 40 LB SNOW LOAD				
Ø' TO 8'	2 x 6's @ 24" O.C.				
8' TO 10'	2 x 8's @ 24" <i>O.C.</i>				
10' TO 12'	2 x 10's @ 24" O.C.				
12' TO 14'	2 x 12's @ 24" O.C.				
FOR RIDGE & HIP BEAMS USE (1) MEMBER ONE SIZE LARGER THAN MEMBER USED FOR RAFTERS. (1.E. FOR A 2 x 6 RAFTER, USE A 2 x 8 FOR RIDGE & HIP BEAMS)					

A6 / SCALE: 34" = 1'-0"

FL	OOR BI			
MARK	TYPE	SIZE	NOTES	
MFB-1	DIM.	(2) 2×1Ø's	TOP OF BEAM = BOTTOM OF JOISTS	
MFB-2	DIM.	(2) 2×1Ø's	TOP OF BEAM = BOTTOM OF JOISTS	
MFB-3	L.Y.L.	(1) 1 ³ / ₄ " × 11 ⁷ / ₈ "	TOP OF BEAM = TOP OF JOISTS	
MFB-4	L.Y.L.	$(2) ^{3}/_{4} \times 9^{1}/_{2}$	TOP OF BEAM = BOTTOM OF JOISTS	> BOLT TOGETHER W/ (2) ROWS 1/2"¢ THRU-BOLTS @24" O.C.
MFB-5	L.Y.L.	(3) ³ / ₄ " × ⁷ / ₈ "	TOP OF BEAM = BOTTOM OF JOISTS OR (4) 3/4" x 91/2" LVL'5	72 V TANG-BOLTO W24 O.C.
MFB-6	L.Y.L.	$(2) ^{3}/_{4} \times ^{1}/_{8}$	TOP OF BEAM = TOP OF JOISTS	
MFB-7	L.Y.L.	$(2) 1^{3}/4 \times 9^{1}/2$	HEADER	
MFB-8	DIM.	(2) 2×1Ø's	HEADER	
MFB-9	GLB	31/2" × 12"	TOP OF BEAM = TOP OF DECK JOISTS EXT. GRADE	
MFB-10				



ROOF FRAMING PLAN



SCALE: 1/8" = 1'-0"

FLOOR DIAPHRAGM:

3/4" A.P.A. RATED T&G O.S.B. SHEETING
GLUED & NAILED W/8d @ 6" O.C. @
DIAPHRAGM BOUNDARIES & SUPPORTED
EDGES & W/8d @ 12" O.C. @ FIELD.

HEADER NOTE:

ALL EXTERIOR BEARING HEADERS TO
BE (2) 2×10'5 UNLESS NOTED OTHERWISE.

ALL INTERIOR BEARING HEADERS TO
BE (2) 2×10'5 UNLESS NOTED OTHERWISE.

TANDFORMS DESIGN, ALL RIGHTS ARE RESERVED, AN SHALL NOT BE REPRODUCED OR COPIED WITHOUT THE EXPRESSED WRITTEN CONSENT OF LANDFORMS DESIGN, INDER PENALTY OF PROSECUTION, THESE PRINTS ARE SITE DESCRIBED AS:

ODRESS 3985 N 2975 W


TY FARR WEST

EASE NOTIFY LANDFORMS DESIGN OF ANY UNLAWFUL UNLA



REVISIONS
date item

10-19-18 ADDRESS



ENGINEER
OF
RECORD


CAD TECH


M.H.H.

RELEASE
DATE

9/25/18










ítem 10-19-18 | ADDRESS

ENGINEER YORK OF RECORD CAD TECH 9/25/18 DATE

FRAMING SECTION AS SCALE: 1/4' = 1'-0'



ENGINEER
OF
RECORD

CAD TECH

M.H.H.

RELEASE
DATE

9/25/18

A8

PLUMBING GENERAL NOTES


- I. ALL WORK PERFORMED SHALL COMPLY WITH ALL CURRENT NATIONAL AND LOCAL BUILDING CODES
- 2. PLUMBING CONTRACTOR TO OBTAIN CITY/STATE BUSINESS LICENSE BEFORE STARTING WORK.
 3. PLUMBING CONTRACTOR SHALL PROVIDE $1\frac{1}{4}$ " COPPER SUPPLY LINE FROM WATER METER TO
- FURNACE ROOM, WATER LINE TO BE PLACED UNDER SLAB WHERE APPLICABLE.
- 4. PLUMBING CONTRACTOR SHALL VERIFY SIZE & LOCATIONS OF UNDERGROUND UTILITIES. COORDINATE WITH ALL OTHER TRADES PRIOR TO MAKING FINAL CONNECTIONS.
- 5. REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION OF ALL FIXTURES.
- 6. INTERIOR WASTE AND VENT LINES TO BE A.B.S.
- INTERIOR COPPER TO BE TYPE "M" INSTALLED WITH PLASTIC ISOLATORS.
 NO SUBSTITUTIONS FROM FIXTURE SCHEDULE ARE ALLOWED, EXCEPT BY OWNERS APPROVAL
- 9. PROVIDE C.P. ESCUTCHEONS AT PIPE SLEEVES FOR EXPOSED BARE PIPE.
 PACK ANNULUS AT I HOUR FIRE WALLS, PLUMBING LINES through GARAGE FIRE WALLS MUST BE
 METAL PIPING. THIS INCLUDES WASTE LINES, VACUUM LINES, AND SUPPLY LINES. AN APPROVED
- METAL PIPING. THIS INCLUDES WASTE LINES, VACUUM LINES, AND SUPPLY LINES. AN APPROVED FIRE STOP MATERIAL MUST BE USED.
- 10. PROVIDE A PRESSURE REGULATOR AND SHUTOFF VALVE, FOR LOCATION SEE PLUMBING PLAN.
- OFFSET ALL VENT STACKS IN ATTIC SPACE TO REAR OF ROOF WHERE POSSIBLE.
 PROVIDE 1.6 GALLON PER FLUSH TOILETS & 2.5 GALLON PER MINUTE SHOWER HEADS.
- 13. PROVIDE EXPANSION TANKS FOR WATER HEATERS AS PER LOCAL JURISDICTION.
- 14. NO SLIP JOINT PLUMBING CONNECTIONS IN CONCEALED CONSTRUCTION AREAS (BATH TUBS).
- 15. INDIVIDUALLY INSULATE ALL PLUMBING, SUPPLY AND DRAIN LINES IN AREAS SUBJECT TO FREEZING (EXTERIOR WALLS), ATTICS, CRAWL SPACES, GARAGES AND EXTERIOR WALLS). SPRAY IN URETHANE HAS BEEN SHOWN TO PREVENT FREEZING PROBLEMS.
- 16. PLUMBING PENETRATIONS THROUGH GARAGE FIRE WALLS MUST BE METAL PIPING OR HAVE AN APPROVED THROUGH PENETRATION FIRE STOP INSTALLED
- 17. PROVIDE ANTI-SCALD SHOWER VALVES ON ALL SHOWER AND TUB COMBINATION INSTALLATIONS.
- 18. PROVIDE 21" CLEARENCE IN FRONT OF SINKS, WATER CLOSETS, AND TUBS. PROVIDE 24" CLEARANCE IN FRONT OF SHOWER DOORS. SHOWER DOORS TO BE A MIN. OF 22" WIDE.
- 19. IF PLUMBING MANIFOLD SYSTEM IS BEING USED, SYSTEM MUST BE ACCESSIBLE BYH LOCAL OFFICALS
- 20. BATHTUBS & WHIRLPOOL TUB VALVES SHALL LIMIT THE TEMP. TO A MAX. OF 120° F.
- 21. ALL BASEMENT FIXTURES MUST PASS THROUGH A BACKWATER VALVE UNLESS IT IS EST. THAT A FIXTURE IN THE BASEMENT OR LOWEST LEVEL OF THE HOME IS NOT BELOW THE ELEVATION OF THE UPSTREAM MANHOLE COVER. THIS WILL REQIRE BASEMENTS TO BE PLUMBED INDEPENDANTLY FOM UPPER FLOORS, BACKWATER VALVES MUST BE ACCESSIBLE.

MECHANICAL GENERAL NOTES

- 1. ALL WORK PERFORMED SHALL COMPLY WITH ALL CURRENT NATIONAL AND LOCAL BULDING CODES.
- 2. MECHANICAL CONTRACTOR TO OBTAIN CITY/STATE BUSINESS LICENSE BEFORE STARTING WORK.
- 3. MECHANICAL CONTRACTOR TO PROVIDE COMBUSTION AIR TO FURNACE AREA IN ACCORDANCE WITH CURRENT NATURAL GAS COMPANY SPECIFICATIONS, COMBUSTION AIR TO BE PLACED PER LOCATION SHOWN ON MECHANICAL PLAN, PROVIDE WHITE METAL EXTERIOR GRILLE.
- 4. ALL MECHANICAL SYSTEMS SHALL BE SIZED LARGE ENOUGH TO HEAT/COOL BASEMENTS WHEN FINISHED.
- 5. ALL SUPPLY AND RETURN AIR PLENUMS ARE SHOWN IN APPROXIMATE LOCATIONS. MECHANICAL CONTRACTOR TO PROVIDE EXPERTISE IN ACTUAL LOCATIONS OF PLENUMS TO MINIMIZE FURR-DOWNS IN FUTURE BASEMENT AREA.
- 6. MECHANICAL CONTRACTOR TO PROVIDE 4" METAL DUCTING FROM REST ROOM FANS TO EXTENSIVE WITH WHITE METAL TERMINATION CAP. SEE MECHANICAL PLAN FOR
- 1. FOR CONDENSER LOCATIONS SEE MECHANICAL PLANS.
- 8. VERIFY "FIT" OF DUCTS AND PIPING PRIOR TO FABRICATION.
- 9. OFFSET FLU STACKS IN ATTIC SPACE TO REAR OF ROOF WHERE POSSIBLE. PAINT ALL FLU STACKS TO MATCH SHINGLE COLOR.
- 10. MECHANICAL CONTRACTOR TO PROVIDE 4" DIA. METAL DUCTING FROM DRYER LOCATION TO EXTERIOR WITH WHITE TERMINATION CAP. DUCTS TO BE METAL WITH SMOOTH INTERIOR SURFACES EQUIPPED W/BACK DRAFT DAMPERS, TERMINATE AT THE EEXTERIOR OF THE BUILDING, AND NOT BE INSTALLED WITH SHEET METAL SCREWS. MAXIMUM DRYER DUCT LENGTH DETERMINED BY IRC MISO2.4
- 11. ALL GAS LINES MUST BE PRESSURE TESTED AT ROUGH INSPECTION. QUESTAR GAS NO LONGER PROVIDES THIS SERVICE AND IS THEREFORE REQUIRED BY THE HYAC CONTRACTOR AT ROUGH INSPECTION.
- 12. GAS LOG APPLIANCES WITHOUT A FLAME SAFEGUARD DEVICE (AUTO LIGHTING DEVICE OR PILOT) SHALL NOT BE PERMITTED. GAS LOGS AND GAS APPLIANCES SHALL HAVE A SHUT-OFF VALVE WITHIN 6 FEET OF THE APPLIANCE. -IRC G2420
- 13. FIREPLACE FLUES SHALL BE SEPARATED FROM ATTIC SPACES BY A SHAFT OF "SHEET ROCK OR 34 " STRAND BOARD OR PLYWOOD.
- 14. CSST STAINLESS STEEL GAS LINE MAY BE USED BUT MUST BE SIZED AND APPROVED BEFORE INSTALLATION. ANY CSST INSTALLED MUST BE VISUALLY INSPECTED AND PRESSURE TESTED BEFORE BEING CONCEALED WITHIN CONSTRUCTION.
- 15. NO CLOTH TYPE DUCT TAPE IS ALLOWED. METALLIC OR FOIL TAPE MUST BE USED.
- 16. ALL JOINTS, TRANSVERSE AND LONGITUDINAL SEAMS AND CONNECTIONS MUST BE PROPERLY SEALED WITH TAPE OR MASTIC.
- 17. GAS LINES SHALL NOT PASS THROUGH OR PENETRATE ANY DUCT OR PLENUM
- 18. GAS PIPING SHALL NOT PENETRATE A BUILDING FOUNDATION BELOW GRADE.

 19. VENTS FOR FURNACES AND WATER HEATERS SHALL BE SIZED IN ACCORDANCE WITH THE GAMMA VENT TABLES 803 TO 804 AS LISTED IN THE 2012 IRC.
- THE GALLIA VENT TABLES SESTION SET AS LISTED IN THE 2012 IRC.
- 20. IF FORCED AIR UNIT IS LOCATED WHERE CONDENSATION MAY DAMAGE BUILDING COMPONENTS, A WATER DETECTION DEVICE MUST BE INSTALLED OR RUN SECONDARY LINE TO OBSERVABLE LOCATION

 21. RANGE HOODS THAT ARE CAPABLE OF EXHAUSTING AIR TO THE OUTSIDE IN EXCESS OF 400 CFM REQUIRE MAKEUP AIR.
- 22. DRYERS IN CLOSETS THAT ARE CAPABLE OF EXHAUSTING AIR TO THE OUTSIDE IN EXCESS OF 400 CFM REQUIRE MAKEUP AIR.



BASEMENT FLOOR ELECTRICAL, MECHANICAL, & PLUMBING PLAN

SCALE: 1/4" = 1'-0"



IMBING

AN

Щ

ᆸ

REVISIONS

ADDRES

(5) TON 13 SEER A.C. -UNIT FOR MAIN FLOOR HOSE BIB PROVIDE WHIRLPOOL-PUMP ACCESS DOOR PROOF TRIM KIT GF1+18 ACCESS, GFI W.F TO GARAGE SOFFIT FLUE RISER GFI+18 ROUGH-N FOR FUTURE 6 PROVIDE C.T. PAN-W/FLOOR DRAIN \$ VENT DRYER -7'-0" VERTICAL & 1'-0" HORIZONTAL TO EXTERIOR W/ (2) 90°

MAIN FLOOR ELECTRICAL, MECHANICAL, & PLUMBING PLAN

ELBOWS

SOFFIT

ELECTRICAL GENERAL NOTES

- 1. ALL WORK PERFORMED SHALL COMPLY WITH ALL NATIONAL AND LOCAL BUILDING CODES.
- 2. ELECTRICAL CONTRACTOR TO OBTAIN CITY/STATE BUSINESS LICENSE BEFORE STARTING WORK.
- 3. ALL TELEVISION OUTLETS ARE TO BE INSTALLED WITH A SEPARATE COAXIAL CABLE TO MECHANICAL ROOM, PROVIDE ANTENNA IN ATTIC WITH SINGLE COAXIAL CABLE TO MECHANICAL ROOM. PROVIDE COAXIAL CABLE FROM MECHANICAL ROOM TO EXTERIOR FOR FUTURE CABLE TELEVISION HOOKUP. HOOK UP TELEVISION CABLES IN MECHANICAL ROOM TO DESIRED (ANTENNA, CABLE) CHOICE. PROVIDE T.V. CONNECTION PANEL ON WALL IN MECHANICAL ROOM.
- 4. ELECTRICAL CONTRACTOR TO PROVIDE A MINIMUM OF 200 AMP SERVICE TO HOME.
- 5. ALL EXHAUST FANS SHALL BE VENTED TO EXTERIOR WITH METAL DUCT W/ BACK DRAFT DAMPER. PROVIDE WHITE METAL EXTERIOR TERMINATION CAP. EXHAUST FANS NOT TO BE DISCHARGED INTO VENTED SOFFITS.
- 6. ALL SMOKE DETECTORS SHALL BE WIRED TOGETHER FOR SIMULTANEOUS ALERT SOUNDING. DETECTORS SHALL ALSO BE WIRED TO BUILDING PRIMARY POWER WITH BATTERY BACKUP. ALL SLEEPING ROOMS AT ALL LEVELS TO HAVE SMOKE DETECTORS.
- 1. SIZE ELECTRICAL PANEL SUFFICIENTLY LARGE ENOUGH TO HANDLE FUTURE BREAKERS WHEN BASEMENT IS FINISHED.
- 8. PROVIDE (4) PAIR CABLE TO ALL TELEPHONE OUTLETS. HOME RUN ALL TELEPHONE LINES TO MECHANICAL ROOM. PROVIDE 66 STYLE PUNCH DOWN BLOCK WALL MOUNTED FOR FINAL
- 9. ALL BATHROOM OUTLETS TO BE ON SEPARATE 20 AMP BREAKERS NOT TO EXCEED 2011 N.E.C. REQUIREMENTS
- 10. CEILING FANS REQUIRE SPECIAL APPROVED BOXES AND ADDITIONAL FRAMING SUPPORT.
- 11. GARAGE ELECTRICAL OUTLETS TO BE 18" ABOVE FLOOR.
- PROVIDE A CONCRETE ENCASED ELECTRODE (UFER GROUND) AT FIRST POINT OF DISCONNECT (METER) FOR USE AS A GROUNDING ELECTRODE FOR THE HOUSE WHICH MEETS REQUIREMENTS OF 2014 N.E.C. SECTION 250-50 (C). USE *4 REBAR WIRE TIED TO FOOTING STEEL.
- 13. ALL 125-YOLT, 15 AND 20 AMP RECEPTACLES INSTALLED INSIDE OR OUTSIDE OF A DWELLING SHALL BE LISTED TAMPER-RESISTANT RECEPTACLES. I.R.C. E4002.14
- 14. A MINIMUM OF 50 PERCENT OF THE LAMPS IN PERMANENTLY INSTALLED LIGHTING FIXTURES SHALL BE HIGH-EFFICIENCY LAMPS. -NII04.
- 15. ALL 15- AND 20- AMPERE RECEPTACLES IN EVERY KITCHEN, FAMILY ROOM, DINING ROOM, LIVING ROOM, PARLOR, LIBRARY, DEN, SUN ROOM, BEDROOM, RECREATION ROOM, OR SIMILAR ROOM OR AREA OF DWELLING UNITS SHALL BE LISTED TAMPER-RESISTANT RECEPTACLES. -E4002.14 -E3901.1
- 16. ALL 125-VOLT, SINGLE PHASE, 15- OR 20- AMPERE RECEPTACLES INSTALLED IN GARAGES SHALL HAVE GROUND-FAULT CIRCUIT-INTERRUPTER PROTECTION FOR PERSONNEL. -E3902.2
- 17. IN KITCHEN, A MINIMUM OF (2) 20 AMP SMALL-APPLICANCE BRANCH CIRCUITS SHALL SERVE ALL WALL & FLOOR RECEPTACLE OUTLETS
- 18. RECESSED LIGHTS MAY BE INSTALLED IN THE CEILINGS (BUILDING ENVELOPE) OF ANY ATTIC TRUSS ONLY IF THE REQUIRED INSULATION DEPTH OR THICKNESS CAN BE INSTALLED OVER SUCH RECESSED LIGHTS. ALL SUCH RECESSED LIGHTS MUST BE IC RATED.
- 19. ALL RECEPTACLES SERVING KITCHEN COUTNERTOPS, IN GARAGES, BATHS, UNFINISHED BASEMENTS AND OUTSIDE RECEPTACLES SHALL BE GFCI PROTECTED. - IRC E3902
- 20. PROVIDE AT LEGAT TWO OUTSIDE GRADE LEVEL RECEPTACLEG- ONE IN THE FRONT YARD AND ONE IN THE REAR YARD. - IRC E3901.7
- 21. ALL BRACH CIRCUITS THAT SUPPLY ELECTRICAL IN BEDROOMS NEED TO BE PROVIDED WITH ARC-FAULT PROTECTION. - IRC E3902.1.1

SCALE: 1/4" = 1'-0"

GF1+18

GFI W.P.

SOFFIT

ANTI SYPHON

- 4"x10" SUPPLY AIR

BY OWNER PROVIDE

INSULATED DUCTWORK

REGISTER COLOR

IN FLOOR

OF RECORD


JMBIN

CTRIC/

REVISIONS

ADDRESS

date



STI SCALE: NOT TO SCALE

STI / SCALE: NOT TO SCALE

STI / SCALE: NOT TO SCALE

STI / SCALE: NOT TO SCALE (NOT USED THESE DRAWINGS)

RELEASE 9/25/18

ST

STI SCALE: 1/2" = 1'-0" SECTION

MICHAEL C.
DENT

ADDRESS

COMMON OR BOX NAILS MAY BE USED EXCEPT WHERE OTHERWISE STATED

"NAILS SPACED AT 6" INCHES (152mm) ON CENTER AT EDGES, 12" (305mm) AT INTERMEDIATE SUPPORTS EXCEPT 6" (152mm) AT ALL SUPPORTS WHERE SPANS ARE 48" (1219mm) OR MORE, for NAILING OF WOOD STRUCTURAL PANEL AND PARTICLEBOARD DIAPHRAGMS AND SHEAR WALLS, REFER TO SECTION

2315.3.3 AND 2315.4 NAILS FOR WALL SHEATHING MAY BE COMMON, BOX OR CASING. ³common or deformed shank

4COMMON ⁵DEFORMED SHANK

GCORROSION-RESISTANT SIDING OR CASING NAILS CONFORMING TO THE REQUIREMENTS OF SECTION 2304.3 FASTENERS SPACED 3" (76mm) ON CENTER AT EXTERIOR EDGES AND 6" (152mm) ON CENTER AT INTERMEDIATE SUPPORTS

⁹CORROSION-RESISTANT ROOFING NAILS WITH 1/16" DIAMETER (11mm) HEAD AND 1 1/2" (38mm) LENGTH FOR 1/2" (12.7mm) SHEATHING AND 1 3/4" (44mm) LENGTH FOR 25/32" (20mm) SHEATHING CONFORMING TO THE REQUIREMENTS OF SECTION 2304.3

³CORROSION-RESISTANT STAPLES WITH NOMINAL 7/16" (11mm) CROWN AND 1 1/8" (29mm) LENGTH FOR 1/2" (12.7mm) SHEATHING AND 1 1/2" (38mm) LENGTH FOR 25/32" (20mm) SHEATHING CONFORMING TO THE


REQUIREMENTS OF SECTION 2304.3 100 PANEL SUPPORTS AT 16" (406mm)(20" (508mm) IF STRENGTH AXIS IN THE LONG DIRECTION OF THE PANEL,

UNLESS OTHERWISE MARKED). CASING OR FINISH NAILS SPACED 6" (152mm) ON PANEL EDGES, 12" (305mm) AT INTERMEDIATE SUPPORTS.

PANEL SUPPORTS AT 24" (610mm). CASING OR FINISH NAILS SPACED 6" (152mm) ON PANEL EDGES, 12" (305mm) AT INTERMEDIATE SUPPORTS


TIES MAY BE INSTALLED O/ EXTERIOR SHEAT'G


ONLY DETAILS REFERENCED SPECIFIC TO THIS SET OF DRAWINGS ARE APPLICABLE SEE DRAWINGS FOR DETAIL FLAG LOCATIONS ANY DETAILS NOT FLAGGED ON DRAWINGS ARE NOT APPLICABLE




VENEER O/ LOW ROOF

ST2 SCALE: NTS










GARAGE HEADER DETAIL ST2 SCALE: NTS















DECK TO FLOOR DETAIL









JOISTS SEE FRAMING

-STEEL BEAM (TOP OF

 $(2)^{1/2}$ " $\phi \times 4$ " LAG BOLTS

WOOD COLUMN SEE

FRAMING PLAN


ST2 / SCALE: NTS

THROUGH FLANGE INTO


WOOD COLUMN BEYOND


BEAM = 11/2 " BELOW


TOP OF JOISTS)



















MICHAEL C.
DENT ENGINEER OF RECORD CAD TECH

前名のの可能

REVISIONS

10-19-18

ADDRESS

date

RELEASE 9/25/18 DATE