






NOT TO SCALE
VICINITY MAP
 PROJECT LOCATION



COORDINATION SET - NOT FOR CONSTRUCTION



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for any other use or construction. No part of this drawing may be reproduced without the express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851




JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN


Rev. #	Rev. Date	Rev. Desc.
PROJECT NO:	120138	
DESIGN BY:	JWS	
DRAWN BY:	AWF	
CHECKED BY:	JWS	
DATE:	3/10/2021	

**EX. TOPO
 SURVEY**


C-1.1



COORDINATION SET - NOT FOR CONSTRUCTION



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use or construction. Any other use without the written permission of an authorized DRI representative is strictly prohibited. contact number: 435-764-6851




JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	3/10/2021


SITE PLAN

C-1.2




SUMMIT PASS PRIVATE ROAD

COORDINATION SET - NOT FOR CONSTRUCTION



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for any other use or construction. Any reproduction or use of these drawings without the express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN

Rev. Date Rev. Desc.


PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	3/10/2021

UTILITY PLAN


C-1.3



COORDINATION SET - NOT FOR CONSTRUCTION



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for any other use or construction. Any reproduction or use of these drawings without the express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.


MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN





Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	3/10/2021

GRADING PLAN

C-1.4





DRI

This design and any ideas portrayed here, is as the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851

JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.


PROJECT NO: 120138
 DESIGN BY: JWS
 DRAWN BY: AWF
 CHECKED BY: JWS
 DATE: 3/10/2021

PLAN & PROFILE

C-1.5

COORDINATION SET - NOT FOR CONSTRUCTION


STANDARD SET OWNER ###
3/10/2021 13:24:58
PMS/10/2021



JACOBS LADDER ROAD PROFILE
 HORIZ SCALE: 1" = 30"; VERT SCALE: 1" = 10'

DRI

This design and any ideas portrayed here, in any form, are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.


PROJECT NO: 120138
 DESIGN BY: JWS
 DRAWN BY: AWF
 CHECKED BY: JWS
 DATE: 4/9/2021

PLAN & PROFILE

C-1.6

STANDARD SET OWNER ###
 4/9/2021 11:38:24
 AM462021

COORDINATION SET - NOT FOR CONSTRUCTION



No.	ITEM	DESCRIPTION
(A)	FIRE HYDRANT	MUELLER SUPER CENTURION
(B)	VALVE BOX WITH LID	2-PIECE CAST IRON
(C)	GATE VALVE WITH 2"x2" NUT	AWWA C509
(D)	TEE WITH 12# FLANGE	AWWA C110


SECTION

	FIRE HYDRANT WITH VALVE	PLAN NO. 511S
--	-------------------------	------------------


FIRE HYDRANT WITH VALVE

- GENERAL**
 - BEFORE BACKFILLING, SECURE INSPECTION BY ENGINEER.
 - ADDITIONAL REQUIREMENTS ARE SPECIFIED IN APWA SECTION 33 11 00.
- PRODUCTS**
 - HYDRANT: DRY BARREL, AWWA C502.
 - THRUST BLOCK: CONCRETE CLASS 4000, APWA SECTION 03 30 04.
 - REINFORCEMENT: DEFORMED, 60KSI YIELD GRADE STEEL, ASTM A 615.
 - BACKFILL: APWA SECTION 31 05 13, MAXIMUM PARTICLE SIZE 2-INCHES.
 - SEWER ROCK: ASTM SIZE NO. 3 (2" TO 1") OR LARGER.
 - OTHER TYPE OF COMMON FILL: CONTRACTOR'S CHOICE.
 - GEOTEXTILE: STABILIZATION-SEPARATION FABRIC, APWA SECTION 31 05 19.
- EXECUTION**
 - INSTALLATION:**
 - PROVIDE AT LEAST 1 CUBIC YARD OF SEWER ROCK AROUND DRAIN HOLE AT BASE OF HYDRANT SPOOL. WRAP GEOTEXTILE AROUND SEWER ROCK AND TAPE GEOTEXTILE TO HYDRANT SPOOL TO PREVENT SILTING OF SEWER ROCK.
 - PAINT FIRE HYDRANT RED.
 - APPLY NON-OXIDE GREASE TO ALL BURIED METAL SURFACES. WRAP WITH POLYETHYLENE SHEET AND TAPE WRAP.
 - NOTIFY FIRE DEPARTMENT AS SOON AS HYDRANT IS PLACE IN SERVICE.
 - THRUST BLOCKS:**
 - BEFORE POURING CONCRETE, WRAP PIPE SYSTEM WITH POLYETHYLENE SHEET TO PREVENT BONDING OF CONCRETE TO PIPE SYSTEM.
 - REQUIRED FOR FLANGE OR WELDED PIPE SYSTEMS UNLESS APPROVED BY DISTRICT ENGINEER.
 - BACKFILL:**
 - MAXIMUM LIFT THICKNESS IS 8-INCHES BEFORE COMPACTION. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY, APWA SECTION 31 23 26.

	FIRE HYDRANT WITH VALVE	PLANNO. 511S
--	-------------------------	-----------------



	27" FRAME AND WATER COVER	PLAN NO. 502S
--	---------------------------	------------------




- NOTES:**
- METER BOXES SHALL BE 18" DIA. BY 90" DEEP MUELLER-THERMAL-COIL PVC BOXES FOR 1" SINGLE METERS (MUELLER 330C5189WFB83N).
 - POLYETHYLENE PIPE FOR WATER SERVICES SHALL BE PE 3405 TUBING, SDR-9, COPPER TUBING SIZE AND NSF APPROVED FOR POTABLE WATER.
 - METER SHALL BE INSTALLED IN HORIZONTAL ALIGNMENT, WITH METER FACING UP, ONLY.
 - ALL PIPE, FITTING, AND VALVES SHALL COMPLY WITH NSF STANDARD NO. 14 FOR USE WITH POTABLE WATER.
 - THE CUSTOMER IS RESPONSIBLE FOR PROPERLY SIZING THE SERVICE TO DELIVER FLOWS REQUIRED FOR FIRE SPRINKLER SYSTEMS. THE SERVICE FROM THE METER TO THE BUILDING CAN BE UPSIZED FROM 1" DIAMETER, IF NECESSARY. CONNECTING FIRE SPRINKLER LINES TO THE 2" SERVICE BEFORE THE METER MAY BE APPROVED BY THE DISTRICT ENGINEER ONLY IF THE REQUIRED FIRE SPRINKLER CANNOT BE DELIVERED THROUGH THE METER.
 - THE DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE SERVICE FROM THE MAIN TO THE METER BOX, INCLUDING THE SERVICE SADDLE, CORP STOP, CURB STOP BOX, AND METER BOX.
 - BASED UPON OBSERVATIONS DURING WINTER CONDITIONS, THE DISTRICT HAS DETERMINED THAT 9" (MIN) OF COVER OVER WATER MAINS AND SERVICES IS REQUIRED TO PROTECT AGAINST FREEZING.

TYPICAL METER PIT DETAIL		
---------------------------------	--	--

DRI

This design and any ideas portrayed herein are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without the express written consent of DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.
--------	-----------	------------

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	3/3/2021

CIVIL DETAILS


C-5.1

PERMIT SET

Direct bearing thrust block

1. GENERAL
 - A. Thrust design for pipe sizes or configurations not shown require special design.
 - B. Bearing areas, volumes, and special thrust blocking details shown on Drawings take precedence over this plan.
 - C. Restraint sizing is based upon a maximum operating pressure of 150 psi and a test pressure of 200 psi, and a minimum soil bearing strength of 2,000 psf. Operating pressures in excess of 150 psi or soils with less than 2,000 pound bearing strength will require special design.
 - D. Before backfilling around thrust block, secure inspection of installation by ENGINEER.
2. PRODUCTS
 - A. Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - B. Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - C. Thrust Blocks: Concrete Class 4000, APWA Section 03 30 04.
 - D. Grease: Non-oxide poly-FM.
3. EXECUTION
 - A. Pour concrete against undisturbed soil.
 - B. Pipe Joints: Do not cover with concrete. Leave completely accessible.
 - C. Grease: Apply grease to all buried metal surfaces. Wrap with polyethylene sheet and tape wrap.
 - D. Locking restraint devices may be used in conjunction with concrete thrust blocking (at discretion of ENGINEER).
 - E. Base Course and Backfill Placement: Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.

268



MINIMUM BEARING AREA IN SQ. FT.					
SIZE OF PIPE	TEES, VALVES DEAD ENDS	90° BENDS	45° BENDS	22 1/2° BENDS	1 1/4° BENDS
4"	2	3	2	2	2
6"	4	5.5	3	1.5	1
8"	6.5	9.5	5	2.75	1.5
12"	14	20	11	5.5	3
14"	19	26.5	14.5	7.5	4
16"	24	34	18.5	9.5	6
20"	27	52	26.5	14.5	15
24"	53	74	41	21	53
30"	81	114	62	32	16

Direct bearing thrust block

Plan 561


August 2010

287

Direct bearing thrust block


1. GENERAL
 - A. Thrust design for pipe sizes or configurations not shown require special design.
 - B. Bearing areas, volumes, and special thrust blocking details shown on Drawings take precedence over this plan.
 - C. Restraint sizing is based upon a maximum operating pressure of 150 psi and a test pressure of 200 psi, and a minimum soil bearing strength of 2,000 psf. Operating pressures in excess of 150 psi or soils with less than 2,000 pound bearing strength will require special design.
 - D. Before backfilling around thrust block, secure inspection of installation by ENGINEER.
2. PRODUCTS
 - A. Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - B. Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - C. Thrust Blocks: Concrete Class 4000, APWA Section 03 30 04.
 - D. Grease: Non-oxide poly-FM.
3. EXECUTION
 - A. Pour concrete against undisturbed soil.
 - B. Pipe Joints: Do not cover with concrete. Leave completely accessible.
 - C. Grease: Apply grease to all buried metal surfaces. Wrap with polyethylene sheet and tape wrap.
 - D. Locking restraint devices may be used in conjunction with concrete thrust blocking (at discretion of ENGINEER).
 - E. Base Course and Backfill Placement: Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.

266



DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. Contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. # Rev. Date Rev. Desc.




PROJECT NO: 120138
DESIGN BY: JWS
DRAWN BY: AWF
CHECKED BY: JWS
DATE: 3/3/2021

CIVIL DETAILS



C-5.2

PERMIT SET

STANDARD SET Owner ### 3/3/2021 3:56:21 PM 3/3/2021



April 2011
213
Sanitary sewer manhole
212



- 1. GENERAL**
- A. The drawing shows typical pipe connections. Refer to construction drawings for connection locations or refer to field location of existing piping when engineering pipe connection to the manhole.
 - B. Manhole size.
 - 1) Diameter is 4 feet: For sewers under 12" diameter.
 - 2) Diameter is 5 feet: For sewers 12" and larger, or when 3 or more pipes intersect the manhole.
- 2. PRODUCTS**
- A. Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - B. Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - C. Concrete: Class 4000, APWA Section 03 30 04.
 - D. Riser and Reducing Riser: ASTM C 478.
 - E. Reinforcement: Deformed, 60 ksi yield grade steel, ASTM A 615.
 - F. Grout: 2 parts sand to 1 part cement mortar, ASTM C 1329.
 - G. Stabilization-Separation Geotextile: Moderate or high at CONTRACTOR's choice, APWA Section 31 05 19.
- 3. EXECUTION**
- A. Foundation Stabilization: Get ENGINEER's permission to use a sewer rock or a granular backfill borrow in a geotextile wrap to stabilize an unstable foundation.
 - B. Base Course Placement: APWA Section 32 11 23. Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.
 - C. Invert Cover. During construction, place invert covers over the top of pipe in manholes that currently convey sewerage. See Plan 412.
 - D. Pipe Connections: Grout around all pipe openings.
 - E. Pipe Seal: Install rubber-based pipe seals on all plastic pipes when connecting plastic pipes to manholes. Hold water-stop in place with stainless steel bands.
 - F. Joints: Place flexible gasket-type sealant in all riser joints. Finish with grout.
 - G. Adjustment: If the required manhole adjustment is more than 1'-0", remove the cone and grade rings and adjust the manhole elevation with the appropriate manhole section, the cone section, and the grade rings or plastic form to make frame and lid match finish grade.
 - H. Finish: Provide smooth and neat finishes on interior of cones, shafts, and rings. Imperfect moldings or honeycombs will not be accepted.
 - I. Backfill: Provide backfill against the manhole shaft. Pea gravel and recycled RAP aggregate is NOT ALLOWED. Water jetting is NOT allowed. Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a standard proctor density, APWA Section 31 23 26.

NOTES:


1. INLET BOX DETAILS SHOWN ON THESE PLANS WERE PROVIDED BY OLDCASTLE PRECAST (AMCOR) AS A COURTESY. CONTRACTOR MAY CHOOSE ANOTHER PRECAST MANUFACTURER. HOWEVER, ALL BOXES, GRATES OR LIDS MUST BE HS20 RATED AND INSTALLED AS PER APWA STANDARDS AND SPECIFICATIONS. THIS INCLUDES BACKFILL AND BEDDING OF THE CONCRETE BOXES, AND GROUTING ALL PIPE CONNECTIONS WATERTIGHT.

NOTES:

1. CONCRETE PIPE INSTALLATION MUST CONFORM TO GEOTECHNICAL ENGINEER'S RECOMMENDATIONS, APWA STD'S & THE AMERICAN CONCRETE PIPE ASSOCIATION DESIGN MANUAL.
2. COMPACT BACKFILL AS SHOWN PROVIDE SUFFICIENT TRENCH WIDTH TO FIT COMPACTION EQUIPMENT.
3. FILL AND COMPACT HAUNCH AREAS UNDER PIPE ACCORDING TO SPECIFICATIONS. REMOVE ANY VOIDS WITHOUT DISTURBING THE PIPE FROM SPECIFIED LINE AND GRADE.
4. SEAL ALL CONNECTIONS TO JUNCTION BOXES, MANHOLES AND INLETS AS PER MANUFACTURER'S RECOMMENDATIONS.
5. PROTECT PIPE DURING CONSTRUCTION. REMOVE AND REPLACE DAMAGED PIPE.
6. REMOVE ALL UNSTABLE OR UNYIELDING SOILS AS DIRECTED BY THE GEOTECHNICAL ENGINEER.

DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without the written permission of the Professional Engineer or representative is strictly prohibited. Contact number: 435-764-6857



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN


Rev. #	Rev. Date	Rev. Desc.

PROJECT NO: 120138
DESIGN BY: JWS
DRAWN BY: AWF
CHECKED BY: JWS
DATE: 3/3/2021


PERMIT SET

CIVIL DETAILS

C-5.3



SILT FENCE ISOMETRIC VIEW



SILT FENCE TYPICAL SECTION

NOTES:

1. THE GEOTEXTILE FABRIC SHALL BE PLACED IN THE EXCAVATED TRENCH, BACKFILLED, AND COMPACTED TO THE EXISTING GROUND SURFACE.
2. WOODEN SUPPORT POSTS SHALL BE A MINIMUM DIMENSION OF 1-1/8" x 1-1/8" AIR OR KILN DRIED OF HICKORY OR OAK AND 4 FEET LONG. STEEL POSTS SHALL BE STUDDED "TEE" OR "U" TYPE WITH A MINIMUM WEIGHT OF 1.3 POUNDS PER LINEAL FOOT AND 5 FEET LONG. POST SPACING SHALL BE A MAXIMUM OF 8 FEET FOR WOVEN FABRIC AND 3 FEET FOR NON-WOVEN FABRIC.
3. THE GEOTEXTILE FABRIC SHALL BE ATTACHED DIRECTLY TO THE UPSLOPE SIDE OF WOODEN POSTS WITH 0.5 INCH STAPLES IN AT LEAST 3 PLACES, OR WITH WOODEN LATH AND NAILS. ATTACHMENT TO STEEL POSTS WILL BE BY WIRE FASTENERS OR 50 POUND PLASTIC TIE STRAPS ON THE UPSLOPE SIDE.
4. THE GEOTEXTILE FABRIC SHALL CONSIST OF EITHER WOVEN OR NON-WOVEN POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE, OR POLYVINYLIDENE CHLORIDE. NON-WOVEN FABRIC MAY BE NEEDLE PUNCHED, HEAT BONDED, RESIN BONDED, OR COMBINATIONS THEREOF. ALL FABRIC SHALL MEET THE FOLLOWING REQUIREMENTS:

TEST REQUIREMENT	METHOD	VALUE *
MINIMUM GRAB TENSILE STRENGTH IN THE MACHINE DIRECTION	ASTM D 4632	120 LBS.
MINIMUM GRAB TENSILE STRENGTH IN THE CROSS MACHINE DIRECTION	ASTM D 4632	100 LBS.
MAXIMUM APPARENT OPENING SIZE EQUIVALENT STANDARD SIEVE	ASTM D 4751	NO. 30
MINIMUM PERMITTIVITY	ASTM D 4491	0.05 SEC ⁻¹
MAXIMUM PERMITTIVITY	ASTM D 4491	0.135 SEC ⁻¹ OR 10 gpm/sq ft at 50 mm constant head.
MINIMUM ULTRAVIOLET STABILITY PERCENTAGE OF STRENGTH RETAINED AFTER 500 HOURS OF EXPOSURE	ASTM D 4355	70%

* ALL NUMERICAL VALUES REPRESENT MINIMUM/MAXIMUM AVERAGE ROLL VALUES. (FOR EXAMPLE, THE AVERAGE OF MINIMUM TEST RESULTS ON ANY ROLL IN A LOT SHOULD MEET OR EXCEED THE MINIMUM SPECIFIED VALUES.)

1 SILT FENCE DETAIL
C109 NO SCALE


NON-IRRIGATED EROSION CONTROL SEED MIX

COMMON NAME	LB/LIVE SEED/ACRE
SLENDER WHEATGRASS	3.00
INDIAN RICEGRASS-NEZPAR	3.00
BLUEBUNCH WHEATGRASS	3.00
SANDBERG BLUEGRASS	0.50
FOURWING SALTBRUSH	1.00
ANTELOPE BITTIERBRUSH	1.00
MOUNTAIN BIG SAGE	1.00
TOTAL	10.50 LB/ACRE


NON-IRRIGATED WILDFLOWER SEED MIX

COMMON NAME	LB/LIVE SEED/ACRE
GLOBEMALLOW-GOOSEBERRY LEAF	0.50
ROCKY MOUNTAIN BEEPLANT	2.00
SULFUR FLOWER	2.00
SCARLET GILIA	1.00
NORTHERN SWEETVETCH	0.50
MAPLE GROVE BLUE FLAX	0.50
WHITE EVENING PRIMROSE	0.50
PALMER PENSTEMON	0.50
WASATCH PENSTEMON	0.50
SCARLET GLOBEMALLOW	0.50
TOTAL	8.50 LB/ACRE

2 LONG TERM EROSION CONTROL SEED MIX
C109 NO SCALE



FIBER ROLL DROP INLET BARRIER PLAN




SECTION

NOTES:

1. KEY-IN FIBER ROLLS 2 INCH DEEP AROUND THE PERIMETER OF THE DROP INLET STRUCTURE AND STAKE AS SHOWN.
2. OVERLAP THE ENDS OF THE FIBER ROLL AT LEAST 18 INCHES.
3. CONSTRUCT ROLLS IN MEDIAN AREAS SO THAT THE TOPS OF THE ROLLS ARE NOT HIGHER THAN THE ADJACENT ROADWAY.
4. MAINTAIN A PROPERLY FUNCTIONING FIBER LOG BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
5. REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.

3 INLET PROTECTION DETAILS
C109 NTS




STABILIZED CONSTRUCTION ENTRANCE


4 STABILIZED CONSTRUCTION ENTRANCED - DETAIL
C109 NO SCALE

NOTES FOR STABILIZED CONSTRUCTION ENTRANCE:

1. PLACE STABILIZED CONSTRUCTION ENTRANCES AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
2. MAINTAIN A PROPERLY FUNCTIONING CONSTRUCTION ENTRANCE THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS HAVE BEEN PAVED.
3. DO NOT ALLOW VEHICLES LEAVING THE CONSTRUCTION SITE TO TRACK MUD ONTO PAVED ROADS.




SILT FENCE DROP INLET BARRIER PLAN




SECTION

NOTES:

1. ENTRENCH THE BOTTOM 18 INCH OF SILT FENCE SECURELY IN THE GROUND AROUND THE PERIMETER OF THE DROP INLET.
2. DRIVE POSTS AT EACH CORNER OF THE INLET STRUCTURE. PLACE ANOTHER POST(S) BETWEEN THEM IF THE DISTANCE BETWEEN CORNER POSTS EXCEEDS 4 FT.
3. CROSS-BRACE THE TOPS OF ALL POSTS WITH A WOODEN FRAME MADE OF 2 x 4 STUDS. USE NAILS OR SCREWS FOR FASTENING.
4. CONSTRUCT SILT FENCE IN MEDIAN AREAS SO THAT THE TOPS OF THE SILT FENCE ARE NOT HIGHER THAN THE ADJACENT ROADWAY.
5. MAINTAIN A PROPERLY FUNCTIONING SILT FENCE BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
6. REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.



SECTION B-B




GUTTER INLET BARRIER PLAN


NOTES FOR GUTTER INLET BARRIER:

1. PLACE FIBER ROLL AND SAND BAGS AS SHOWN AROUND GUTTER INLETS AND AVOID PLACING THE BARRIER IN THE TRAVEL LANE.
2. USE GUTTER INLET BARRIERS ONLY WHERE THERE IS THE POTENTIAL OF SEDIMENT FROM NON-STABILIZED AREAS GETTING INTO THE INLET.
3. MAINTAIN A PROPERLY FUNCTIONING GUTTER INLET BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
4. REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.

5 GUTTER INLET PROTECTION DETAIL
C109 NTS




6 CONCRETE WASHOUT DETAIL
C109 NO SCALE




A SECTION A-A
NO SCALE

NOTES:

- DO NOT WASH OUT CONCRETE INTO STORM DRAINS, OPEN DITCHES, STREETS OR STREAMS.
- WHEN WASHING CONCRETE TO REMOVE FINE PARTICLES, AVOID CREATING RUNOFF, ONLY WASH CONCRETE EQUIPMENT IN DESIGNATED AREAS.
- INSPECT AND MAINTAIN CONCRETE WASHOUT AREA WEEKLY AND REMOVE HARDENED CONCRETE ON A REGULAR BASIS.



7 TEMPORARY SANITARY FACILITY DETAIL
C109 NO SCALE




B SECTION A-A
NO SCALE

NOTES:

- PORTABLE TOILETS MUST BE MAINTAINED IN GOOD WORKING ORDER WITH DAILY OBSERVATION FOR LEAK DETECTION.
- REGULAR WASTE COLLECTION MUST BE ARRANGED WITH LICENSED SERVICE.
- ALL WASTE COLLECTION MUST BE DEPOSITED IN A SANITARY SEWER SYSTEM FOR TREATMENT WITH APPROPRIATE AGENCY APPROVAL.

DRI

This design and any ideas portrayed herein are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. Contact number: 435-766-6651



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. # Rev. Date Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	3/3/2021

CIVIL DETAILS

C-5.4

PERMIT SET