



ENGINEERING • ENVIRONMENTAL (ESA I & II)
MATERIALS TESTING • SPECIAL INSPECTIONS
ORGANIC CHEMISTRY

GEOTECHNICAL ENGINEERING STUDY

Suncrest Meadows Development

About 4700 West 2550 South
Taylor, Weber County, Utah

Prepared For:
Mr. Carson Jones
Blackburn Jones
905 24th Street
Ogden, Utah 84401

CMT Project No. 10830
March 27, 2018

CMT ENGINEERING LABORATORIES

March 27, 2018

Mr. Carson Jones
Blackburn Jones
905 24th Street
Ogden, Utah 84401

Subject: Geotechnical Engineering Study
Suncrest Meadows Development
About 4700 West 2550 South
Taylor, Weber County, Utah
CMT Project Number: 10830

Mr. Jones:

Submitted herewith is the report of our geotechnical engineering study for the subject site. This report contains the results of our findings and an engineering interpretation of the results with respect to the available project characteristics. It also contains recommendations to aid in the design and construction of the earth related phases of this project.


On January 12, 2018, a CMT Engineering Laboratories (CMT) engineer was on-site and supervised the excavation of 16 test pits extending to depths of about 10 to 11 feet below the existing ground surface. Soil samples were obtained during the field operations and subsequently transported to our laboratory for further testing and observation. Shallow groundwater was measured between 2.4 and 5.5 feet below the ground surface at the test pit locations.

Conventional spread and/or continuous footings may be utilized to support the proposed residences, provided the recommendations in this report are followed. A detailed discussion of design and construction criteria is presented in this report.

We appreciate the opportunity to work with you at this stage of the project. CMT offers a full range of Geotechnical Engineering, Geological, Material Testing, Special Inspection services, and Phase I and II Environmental Site Assessments. With 8 offices throughout Utah and Arizona, our staff is capable of efficiently serving your project needs. If we can be of further assistance or if you have any questions regarding this project, please do not hesitate to contact us at (801) 870-6730.

Sincerely,
CMT Engineering Laboratories

Jeffrey J. Egbert, P.E., LEED A.P., M. ASCE
Senior Geotechnical Engineer



Reviewed by:

Bryan N. Roberts, P.E.
Senior Geotechnical Engineer

ENGINEERING • ENVIRONMENTAL (ESA I & II) • MATERIALS TESTING • SPECIAL INSPECTIONS • ORGANIC CHEMISTRY

LOGAN OFFICE: 2005 NORTH 600 WEST, SUITE A, LOGAN, UTAH 84321 • TEL: (435) 753-6815 • FAX: (435) 787-4983
OGDEN OFFICE: 707 24th STREET, SUITE 1A, OGDEN, UTAH 84401 • TEL: (801) 870-6730
SALT LAKE CITY OFFICE: 2796 S. REDWOOD ROAD, SALT LAKE CITY, UTAH 84119 • TEL: (801) 908-5954 • FAX: (801) 972-9075
UTAH COUNTY OFFICE: 496 EAST 1750 NORTH, SUITE B, VINEYARD, UTAH 84057 • TEL: (801) 492-4132
ATL/ARIZONA OFFICE: 2921 NORTH 30th AVENUE, PHOENIX, ARIZONA 85017 • TEL: (602) 241-1097 • FAX: (602) 2771306
EMAIL = cmt@cmtlaboratories.com

Table of Contents

1.0 INTRODUCTION	2
<u>1.1 General</u>	2
<u>1.2 Objectives, Scope and Authorization</u>	2
<u>1.3 Description of Proposed Construction</u>	2
<u>1.4 Executive Summary</u>	2
2.0 FIELD EXPLORATION	3
3.0 LABORATORY TESTING	3
<u>3.1 General</u>	3
<u>3.2 Lab Summary</u>	4
4.0 GEOLOGIC & SEISMIC CONDITIONS	5
<u>4.1 Geologic Setting</u>	5
<u>4.2 Faulting</u>	6
<u>4.3 Seismicity</u>	7
4.3.1 Site Class	7
4.3.2 Seismic Design Category	7
4.3.3 Liquefaction	7
<u>4.4 Other Geologic Hazards</u>	7
5.0 SITE CONDITIONS	8
<u>5.1 Surface Conditions</u>	8
<u>5.2 Subsurface Soils</u>	8
<u>5.3 Groundwater</u>	8
<u>5.4 Design Groundwater</u>	9
<u>5.5 Site Subsurface Variations</u>	10
6.0 SITE PREPARATION AND GRADING	10
<u>6.1 General</u>	10
<u>6.2 Temporary Excavations</u>	11
<u>6.3 Fill Material</u>	12
<u>6.4 Fill Placement and Compaction</u>	12
<u>6.5 Utility Trenches</u>	13
<u>6.6 Stabilization</u>	13
7.0 FOUNDATION RECOMMENDATIONS	14
<u>7.1 Foundation Recommendations</u>	14
<u>7.2 Installation</u>	14
<u>7.3 Estimated Settlement</u>	15
<u>7.4 Lateral Resistance</u>	15
8.0 LATERAL EARTH PRESSURES.....	15
10.0 DRAINAGE RECOMMENDATIONS	17
<u>10.1 Surface Drainage</u>	17
<u>10.2 Foundation Subdrains</u>	17
10.2.1 General.....	17
10.2.2 Subdrain Design	17
11.0 PAVEMENTS	18
12.0 QUALITY CONTROL.....	19
<u>12.1 Field Observations</u>	19
<u>12.2 Fill Compaction</u>	19
<u>12.3 Excavations</u>	19
13.0 LIMITATIONS	19

APPENDIX

Figure 1: Site Map

Figures 2 -17: Test Pit Logs

Figure 18: Key to Symbols

1.0 INTRODUCTION

1.1 General

CMT Engineering Laboratories (CMT) was retained to conduct a geotechnical subsurface study for the proposed Suncrest Meadows Development. The parcel is situated at about 4700 West 2550 South in Taylor, Weber County, Utah, as shown in the **Vicinity Map** below.



Vicinity Map

1.2 Objectives, Scope and Authorization

The objectives and scope of our study were planned in discussions between Mr. Carson Jones of Blackburn Jones, and Mr. Andrew Harris of CMT Engineering Laboratories (CMT). In general, the objectives of this study were to define and evaluate the subsurface soil and groundwater conditions at the site, and provide appropriate foundation, earthwork, and pavement design recommendations, and geo-seismic information to be utilized in the design and construction of the proposed development.

In accomplishing these objectives, our scope of work has included performing field exploration, which consisted of the excavating/logging/sampling of 16 test pits, performing laboratory testing on representative samples, and conducting an office program, which consisted of correlating available data, performing engineering

analyses, and preparing this summary report. This scope of work was authorized by returning a signed copy of our proposal dated January 10, 2018.

1.3 Description of Proposed Construction

We understand that the development of a 47-lot residential subdivision is planned for the parcel. Structures are to be of wood-framed construction and founded on spread footings. Due to shallow groundwater encountered across the site, basement levels will not be practical unless an extensive area subdrain is installed and individual residential foundation drains are constructed and tied into the area subdrain.

Maximum continuous wall and column loads are anticipated to be 1 to 3 kips per lineal foot and 10 to 25 kips, respectively. If the loading conditions are different than we have projected, please notify us so that any appropriate modifications to our conclusions and recommendations contained herein can be made.

We project that asphalt-paved residential streets will be constructed as part of the development. Traffic is projected to consist of a light volume of automobiles and pickup trucks, a few medium-weight delivery trucks, some school busses, a weekly garbage truck, and an occasional fire truck.

Site development will require some earthwork in the form of minor cutting and filling. A site grading plan was not available at the time of this report. We recommend that site grading cuts be minimized to that required to remove vegetation, topsoil, disturbed soils, non-engineered fill, and other unsuitable soils due to shallow groundwater. Site grading fills to achieve design grades may be on the order of 2 to 3 feet. Larger cuts and fills may be required in isolated areas. Fills larger than about 4 feet must be identified and CMT informed to review settlements.

1.4 Executive Summary

Our evaluation indicates that proposed residences can be supported upon conventional spread and continuous wall foundations established upon suitable, undisturbed, natural soils and/or upon structural fill extending to suitable natural soils. The most significant geotechnical aspects regarding site development include the following:

1. Up to 10 inches of topsoil and/or disturbed soils are present on the surface of the site;
2. Groundwater was encountered at shallow depths ranging from 2.4 to 5.5 feet below the surface. Land drains and footing drains would be required if basements are planned for the site; and
3. There are existing building which are to be removed.

Structures should not be placed on undocumented fill, topsoil, or other unsuitable soils, which could otherwise translate to settlement and subsequent damage to structures.

The shallow groundwater encountered at the site is likely to affect the installation of utilities, foundations and any sublevel construction. It is recommended that the top of the lowest habitable slab be kept a minimum of 3.0 feet above the measured groundwater level. If a land drain is constructed within the development, the top

of slabs within the lowest habitable level are recommended to be at least 1.5 feet above the level controlled by individual foundation subdrains tied into land drains within the development.

CMT must assess that topsoil, undocumented fills, debris, disturbed or unsuitable soils have been removed and that suitable soils have been encountered prior to placing site grading fills, footings, slabs, and pavements.

In the following sections, detailed discussions pertaining to the site and subsurface descriptions, geologic/seismic setting, earthwork, foundations, lateral resistance, lateral pressure, floor slabs, and pavements are provided.

2.0 FIELD EXPLORATION

In order to define and evaluate the subsurface soil and groundwater conditions at the site, 16 test pits were excavated with a backhoe throughout the site to depths of approximately 10 to 11 feet below the existing ground surface. Locations of the test pits are presented on **Figure 1, Site Map**. The field exploration was performed under the supervision of an experienced member of our geotechnical staff.

Representative soil samples were collected by obtaining disturbed "grab" samples and utilizing a 2.5-inch outside diameter thin-wall drive sampler from within the test pits. The samples were placed in sealed plastic bags and containers prior to transport to the laboratory.

The subsurface soils encountered in the test pits were logged and described in general accordance with ASTM¹ D-2488. Soil samples were collected as described above, and were classified in the field based upon visual and textural examination. These field classifications were supplemented by subsequent examination and testing of select samples in our laboratory. Graphical representations of the subsurface conditions encountered are presented on each individual Test Pit Log, **Figures 2 through 17**, included in the Appendix. A Key to Symbols defining the terms and symbols used on the logs, is provided as **Figure 18** in the Appendix.

Following completion of excavation operations and prior to backfilling, 1.25-inch diameter slotted PVC pipe was installed in each test pit to allow subsequent water level measurements.

When backfilling the test pits, only minimal effort was made to compact the backfill and no compaction testing was performed. Thus, the backfill must be considered as non-engineered fill and settlement of the backfill in the test pits over time should be anticipated.

3.0 LABORATORY TESTING

3.1 General

Selected samples of the subsurface soils were subjected to various laboratory tests to assess pertinent engineering properties, as follows:

¹American Society for Testing and Materials

1. Moisture Content, ASTM D-2216, Percent moisture representative of field conditions
2. Dry Density, ASTM D-2937, Dry unit weight representing field conditions
3. Atterberg Limits, ASTM D-4318, Plasticity and workability
4. Gradation Analysis, ASTM D-1140/C-117, Grain Size Analysis
5. One Dimension Consolidation, ASTM D-2435, Consolidation properties
6. Moisture-Density Relationship (Proctor), ASTM D-1557

3.2 Lab Summary

Laboratory test results are presented on the test pit logs (**Figures 2 through 17**) and in the following Lab Summary tables:

Lab Summary Tables

Test Pit	Depth (feet)	Soil Class	Sample Type	Moisture Content (%)	Dry Density (pcf)	Gradation			Atterberg Limits			Collapse (-) or Expansion (+)
						Grav	Sand	Fines	LL	PL	PI	
TP-1	3		Thin Wall	30.7	94							
	6	SP-SM	Bag	27.1				8				
TP-2	2.5	SM	Bag	26				38				
	9.5	CL	Bag	26.2				92				
TP-3	3	ML	Bag	24.5				67		NP		
	9	SC	Bag	28.4				49				
TP-4	3	SM	Thin Wall	29.7	94			14				
TP-5	2.5	CL	Bag	28				70				
	6	CL	Bag	35.5				96	34	21	13	
TP-6	6	CL	Bag	33.9				70				
TP-7	2	SM	Thin Wall	16.6	112							
	9	ML	Bag	25.4				63		NP		
TP-8	2.5	SM	Thin Wall	21.6	99							0.5
TP-9	2	SC	Thin Wall	17.5	102			41				
TP-11	5	CL	Thin Wall	32.8	96							0.5
TP-12	10	SM	Bag	14.6				40				
TP-13	6.5	SM	Bag	26.9				41				
TP-14	7	CL	Bag	30.8				95	35	20	15	
TP-15	3	ML	Bag	23.9				67	28	26	2	
TP-16	2.5	SM	Bag	17.5				45				
TP-16	7.5	SM	Bag	31.7				48				

Consolidation test results indicate the silt/clay soils at this site are moderately over-consolidated and moderately compressible under additional loading. Detailed information regarding the consolidation testing is maintained within our files and can be provided upon request.

A compaction (modified proctor) test was performed on a near surface bulk sample in accordance with the (ASTM² D-1557) specifications. The bulk sample was made up of composite material from two test pits with similar soil type (sand). The results of the compaction test are presented in the following table:

Test Pit	Depth (feet)	Soil Classification	Optimum Moisture Content (percent)	Maximum Dry Density (ASTM D-1557) (pcf)
TP-9 and TP-12 Composite	1.5 to 3.0	SC/SM	13.5	113.6

4.0 GEOLOGIC & SEISMIC CONDITIONS


4.1 Geologic Setting

The subject site is located in the west-central portion of Weber County in north-central Utah. The elevation on the central portion of the site is approximately 4,224 feet above sea level. The site is located in a valley bound by the Wasatch Mountains on the east and Antelope Island (Great Salt Lake) and the Promontory Mountains to the west. The valley is a deep, sediment-filled basin that is part of the Basin and Range Physiographic Province. The valley was formed by extensional tectonic processes during the Tertiary and Quaternary geologic time periods. The Valley is located within the Intermountain Seismic Belt, a zone of ongoing tectonism and seismic activity extending from southwestern Montana to southwestern Utah. The active (evidence of movement in the last 10,000 years) Wasatch Fault Zone is part of the Intermountain Seismic Belt and extends from southeastern Idaho to central Utah along the western base of the Wasatch Mountain Range.

Much of northwestern Utah, including the valley in which the subject site is located, was also previously covered by the Pleistocene age Lake Bonneville. The Great Salt Lake, located along the western margin of the valley and beyond, is a remnant of this ancient fresh water lake. Lake Bonneville reached a high-stand elevation of between approximately 5,100 and 5,200 feet above sea level at between 18,500 and 17,400 years ago. Approximately 17,400 years ago, the lake breached its basin in southeastern Idaho and dropped by almost 300 feet relatively fast as water drained into the Snake River. Following this catastrophic release, the lake level continued to drop slowly over time, primarily driven by drier climatic conditions, until reaching the current level of the Great Salt Lake. Shoreline terraces formed at the high-stand elevation of the lake and several subsequent lower lake levels are visible in places on the mountain slopes surrounding the valley. Much of the sediment within the Valley was deposited as lacustrine sediments during both the transgressive (rise) and regressive (fall) phases of Lake Bonneville.

The geology of the USGS Roy, Utah 7.5 Minute Quadrangle, that includes the location of the subject site, has been mapped by Sack. The surficial geology on the eastern half of the subject site and adjacent properties is mapped as "Undifferentiated lacustrine and alluvial deposits" (Map Unit Q1a) dated to be Holocene to uppermost Pleistocene. On the western half of the site and adjacent properties the geology is mapped as "Fine grained deltaic deposits" (Map Unit Qd2), dated as early Holocene. No fill has been mapped at the location of the site on the geologic map. Unit Q1a is described on the referenced map as "Fluvially reworked lake sediments

and intermingled lake and alluvial fan deposits. Sandy fines through gravelly sand deposited from about 12.6 ka to the present. Thickness generally less than 10 feet (3 m).” Unit Qd2 is described as “Muddy to sandy fines deposited between about 9.7 and 9.4 ka. Estimated thickness 10 to 20 feet (3-6 m).” Refer to the **Geologic Map.**, shown below.



Geologic Map

4.2 Faulting

No surface fault traces are shown on the referenced geologic map crossing or projecting toward the subject site. No landslide deposits or features, including lateral spread deposits, are mapped on or adjacent to the site. The site is not located within a known or mapped potential debris flow, stream flooding, or rock fall hazard area. The nearest mapped active fault trace appears to be the Weber segment of the Wasatch fault located about 9 miles east of the site.

The Wasatch Fault is considered a “normal” fault because movement along the fault is typically vertical. The east side of the fault, or the mountain block, typically moves upward relative to the valley block on the west side of the fault. The fault generally dips to the west below the valleys. In an earthquake, the point where the fault initially ruptures is called the “focus” and generally occurs about 10 miles below the surface. The point on the surface directly above the focus, the epicenter, typically out in the valley, is usually where the strongest ground shaking occurs. The Wasatch Fault is one of the longest and most active normal faults in the world.

4.3 Seismicity

4.3.1 Site Class

Utah has adopted the International Building Code (IBC) 2015. IBC 2015 determines the seismic hazard for a site based upon 2008 mapping of bedrock accelerations prepared by the United States Geologic Survey (USGS) and the soil site class. The USGS values are presented on maps incorporated into the IBC code and are also available based on latitude and longitude coordinates (grid points). For site class definitions, IBC 2015 (Section 1613.3.2) refers to Chapter 20, Site Classification Procedure for Seismic Design, of ASCE³ 7. Given the subsurface soils at the site, including our projection of soils within the upper 100 feet of the soil profile, it is our opinion the site best fits Site Class D – Stiff Soil Profile, which we recommend for seismic structural design.

4.3.2 Seismic Design Category

The 2008 USGS mapping utilized by the IBC provides values of peak ground, short period and long period accelerations for the Site Class B boundary and the Maximum Considered Earthquake (MCE). This Site Class B boundary represents average bedrock values for the Western United States and must be corrected for local soil conditions. The Seismic Design Categories in the International Residential Code (IRC 2015) are based upon the Site Class as addressed in the previous section. For Site Class D at site grid coordinates of 41.21812 degrees north latitude and 112.097869 degrees west longitude, S_{DS} is 0.803, and the **Seismic Design Category** is D₁.

4.3.3 Liquefaction

The site is located within an area designated by the Utah Geologic Survey⁴ as having “High” liquefaction potential. Liquefaction is defined as the condition when saturated, loose, sandy soils lose their support capabilities because of excessive pore water pressure which develops during a seismic event. Clayey soils, even if saturated, will generally not liquefy during a major seismic event.

A special liquefaction study was not completed as part of this study and would require drilling with Standard Penetration Test sampling (SPT) to a minimum depth of 30 feet below the ground surface and/or Cone Penetrometer Testing (CPT) in order to evaluate the saturated sand soils.. Many of the natural soils encountered in the test pits were clays, typically considered non-liquefiable. However, we also encountered some layers of saturated sand, which we generally estimated to be in a medium dense state. Some of these layers could potentially liquefy during a strong earthquake.

4.4 Other Geologic Hazards

No landslide deposits or features, including lateral spread deposits, are mapped on or adjacent to the site. The site is not located within a currently known or mapped potential debris flow, stream flooding, or rock fall hazard area.

³ American Society of Civil Engineers

⁴ Utah Geological Survey, "Liquefaction-Potential Map for a Part of Weber County, Utah," Utah Geological Survey Public Information Series 27, August 1994. <https://geology.utah.gov/hazards/earthquakes-faults/liquefaction/#tab-id-2>

5.0 SITE CONDITIONS

5.1 Surface Conditions

At the time the test pits were excavated the site consisted of fields vegetated with alfalfa and some grasses and weeds. A few mature trees were observed on portions of the site. The site grade sloped downward to the west with an overall gradient of about 10 to 15 feet. There are several structures in the northwest portion of the site which we anticipate will be removed. Based upon aerial photos readily available online dating back to 1997, the site appears to have remained relatively unchanged. The site is bounded on the north by residential development and 2550 South Street, on the west by residential development and 4700 West, and on the remaining sides by residential development and vacant, undeveloped land (see **Vicinity Map** in **Section 1.1** above).

5.2 Subsurface Soils

The subsurface soil conditions encountered within the test pits completed across the site were variable. At the locations of the test pits we encountered approximately 3 to 10 inches of loose topsoil and disturbed/fill soils. Natural soils were observed beneath the topsoil and fill soils, consisting of brown Silty Fine SAND (SM) with occasional silty clay layers, Clayey SAND (SC), and SAND (SP, SP-SM) layers, and brown CLAY (CL) and SILT (ML) layers, with varying amounts of fine sand, extending to the bottom of the test pits. The clay and silt soils were moist to wet, and estimated to have medium stiff consistency. The sand soils were slightly moist to wet and estimated to be in a medium dense state. In test pit TP-12, at about 4.5 feet below the surface, the natural clay soils appeared to contain a significant amount of organic material (peat).

For a more descriptive interpretation of subsurface conditions, please refer to the test pit logs, **Figures 2 through 17**, which graphically represent the subsurface conditions encountered. The lines designating the interface between soil types on the logs generally represent approximate boundaries - in situ, the transition between soil types may be gradual. A key to the symbols and terms on the logs is included as **Figure 18**.

5.3 Groundwater

Groundwater was encountered at about 3.25 to 9.5 feet below ground surface while excavating the test pits. On January 23, 2018, CMT personnel returned to the site to measure groundwater levels within installed PVC pipes at each test pit. The stabilized/static water levels are tabulated on the following page:

Test Pit No.	Static Groundwater Level Below Existing Grade (feet)
	January 23, 2018
TP-1	3.4
TP-2	3.3
TP-3	2.9
TP-4	3.1
TP-5	3.6
TP-6	2.4
TP-7	3.0
TP-8	5.5
TP-9	5.3
TP-10	2.7
TP-11	3.3
TP-12	5.3
TP-13	2.6
TP-14	4.5
TP-15	3.1
TP-16	4.6

These depths to groundwater will affect the installation of utilities at the site and the practical depth of basements. The contractor must be prepared to dewater excavations as needed.

Groundwater levels can fluctuate as much as 1.5 to 2 feet seasonally. Numerous other factors such as heavy precipitation, irrigation of neighboring land, and other unforeseen factors, may also influence ground water elevations at the site. The detailed evaluation of these and other factors, which may be responsible for ground water fluctuations, is beyond the scope of this study.

5.4 Design Groundwater

Very shallow static groundwater was measured at this site. As a result, measures will be required to control groundwater levels within the development if sublevels are desired. Such measures may include the construction of an extensive land drain system throughout the development. If a land drain is not constructed within the development, the static groundwater level must be determined on each individual lot and the lowest habitable floor slab embedment should be kept a minimum of 3 feet above measured static groundwater levels.

5.5 Site Subsurface Variations

Based on the results of the subsurface explorations and our experience, variations in the continuity and nature of subsurface conditions should be anticipated. Due to the heterogeneous characteristics of natural soils, care should be taken in interpolating or extrapolating subsurface conditions between or beyond the exploratory locations.

Also, when logging and sampling of the test pits was completed, the test pits were backfilled with the excavated soils but minimal to no effort was made to compact these soils. Thus, the backfill soils must be considered as non-engineered and settlement of the backfill in the test pits over time should be anticipated.

6.0 SITE PREPARATION AND GRADING

6.1 General

Initial site preparation will consist of the removal of existing structures (including below grade portions), surface vegetation, topsoil, any other deleterious materials, non-engineered fills, if encountered, and loose/disturbed surface soils from beneath an area extending out at least 3 feet from the perimeter of the proposed residences, and from beneath an area extending out at least 2 feet beyond pavements and exterior flatwork areas. Disturbed soils may remain below flexible pavements and flatwork if less than 2 feet in total thickness and if properly prepared. Proper preparation consists of scarifying the upper 9 inches of disturbed soils, moisture conditioning, and compacting the soils to the requirements of structural fill.

Based upon the conditions observed in the test pits there is topsoil and disturbed/fill on the surface of the site which we estimated to be about 3 to 10 inches in thickness. When stripping and grubbing, topsoil should be distinguished by the apparent organic content and not solely by color; thus we estimate that topsoil stripping will need to include the upper 3 to 10 inches. However, given the past agricultural uses of the site, the upper 12 to 15 inches may have been disturbed during farming.

Also, loose and disturbed soils and possibly vegetation could be encountered at the test pit locations. If these conditions are encountered, the loose/disturbed soils and vegetation should be completely removed.

Due to shallow groundwater conditions, we strongly recommend that land drains, if utilized, as well as major utilities be installed as far in advance as possible prior to roadway and residential construction. Further it is recommended that site grading cuts be kept to the minimum to remove vegetation, topsoil, disturbed soils and any other unsuitable soils. Ideally roadway structural sections would be designed at least two feet above the groundwater level to reduce potential subgrade stabilization needs. The earthwork contractor must be prepared to dewater and likely begin dewatering prior to major excavating. Further, some stabilization of very moist to saturated subgrade soils must be anticipated. Stabilization recommendations are provided later in this report.

Subsequent to stripping and prior to the placement of structural site grading fill, pavements, floor slabs, or footings, the exposed subgrade shall be proof rolled by running moderate-weight rubber tire-mounted construction equipment uniformly over the surface at least three times. An exception to this would be where the exposed subgrade is within 2 feet of groundwater. If excessively soft or otherwise unsuitable soils are encountered beneath footings, they must be totally removed and/or stabilized. If removal depth required is more than 2 feet or at groundwater level, CMT must be notified to provide additional recommendations. In pavement areas, outside flatwork areas, and in most cases below floor slabs, unsuitable natural soils shall be removed to a maximum depth of 2 feet and replaced with compacted granular structural fill. Additional removal below floor slabs may be required depending on conditions encountered.

The site should be examined by a CMT geotechnical engineer to assess that suitable natural soils have been exposed and any deleterious materials, loose and/or disturbed soils have been removed, prior to placing site grading fills, footings, slabs, and pavements.

Fill placed over large areas to raise overall site grades can induce settlements in the underlying natural soils. If more than 4 feet of site grading fill is anticipated over the natural ground surface, we should be notified to assess potential settlements and provide additional recommendations as needed. These recommendations may include placement of the site grading fill far in advance to allow potential settlements to occur prior to construction.

6.2 Temporary Excavations

Relatively shallow groundwater was encountered and later measured at this site. Static/stabilized groundwater was measured at depths of 2.4 to 5.5 feet below the existing ground surface. We anticipate that excavations extending to within these depths will likely encounter groundwater, and dewatering of such excavations may be required.

In cohesive (clayey) soils, temporary construction excavations not exceeding 4 feet in depth may be constructed with near-vertical side slopes. Temporary excavations up to 8 feet deep, above or below groundwater, may be constructed with side slopes no steeper than one-half horizontal to one vertical (0.5H:1V). Excavations deeper than 8 feet are not anticipated at the site.

For cohesionless (sandy/gravelly) soils, temporary construction excavations not exceeding 4 feet in depth and above the groundwater should be no steeper than one-half horizontal to one vertical (0.5H:1V). For excavations up to 8 feet and above groundwater, side slopes should be no steeper than one horizontal to one vertical (1H:1V). Excavations encountering saturated cohesionless soils will be very difficult to maintain, and will require very flat side slopes and/or shoring, bracing and dewatering as these soils will tend to flow into the excavation.

To reduce disturbance of the natural soils during excavation, we recommend that smooth edge buckets/blades be utilized.

All excavations must be inspected periodically by qualified personnel. If any signs of instability or excessive sloughing are noted, immediate remedial action must be initiated. All excavations should be made following OSHA safety guidelines.

6.3 Fill Material

Following are our recommendations for the various fill types we anticipate will be used at this site:

Fill Material Type	Description/Recommended Specification
Structural Fill	Placed below structures, flatwork and pavement. Well-graded sand/gravel mixture, with maximum particle size of 4 inches, a minimum 70% passing 3/4-inch sieve, a maximum 20% passing a minimum 15% passing the No. 200 sieve, and a maximum Plasticity Index of 10.
Site Grading Fill	Placed over larger areas to raise the site grade. Sandy to gravelly soil, with a maximum particle size of 6 inches, a minimum 70% passing 3/4-inch sieve, and a maximum 40% passing No. 200 sieve.
Non-Structural Fill	Placed below non-structural areas, such as landscaping. On-site soils or imported soils, with a maximum particle size of 8 inches, including silt/clay soils not containing excessive amounts of degradable/organic material (see discussion below).
Stabilization Fill	Placed to stabilize soft areas prior to placing structural fill and/or site grading fill. Coarse angular gravels and cobbles 1 inch to 8 inches in size. May also use 1.5- to 2.0-inch gravel placed on stabilization fabric, such as Mirafi RS280i , or equivalent (see Section 6.6).

On-site soils may be used as site grading fill and non-structural fill if they meet the requirements for such. Please note however that the fine-grained soils are inherently more difficult to work with in proper moisture conditioning (they are very sensitive to changes in moisture content), requiring very close moisture control during placement and compaction. This will be very difficult, if not impossible, during wet and cold periods of the year. In addition, with the shallow depth to groundwater, the onsite soils are likely above optimum moisture content and would require significant drying prior to re-utilization. We also recommend that the maximum site grading fill thickness using on-site silt/clay soils be 3 feet below structures, to minimize potential settlements.

All fill material should be approved by a CMT geotechnical engineer prior to placement.

6.4 Fill Placement and Compaction

The various types of compaction equipment available have their limitations as to the maximum lift thickness that can be compacted. For example, hand operated equipment is limited to lifts of about 4 inches and most “trench compactors” have a maximum, consistent compaction depth of about 6 inches. Large rollers, depending on soil and moisture conditions, can achieve compaction at 8 to 12 inches. The full thickness of each lift should be compacted to at least the following percentages of the maximum dry density as determined by ASTM D-1557 (or AASHTO⁵ T-180) in accordance with the following recommendations:

⁵ American Association of State Highway and Transportation Officials

Location	Total Fill Thickness (feet)	Minimum Percentage of Maximum Dry Density
Beneath an area extending at least 3 feet beyond the perimeter of structures, and below flatwork and pavement (applies to structural fill and site grading fill)	0 to 5	95
	5 to 8	98
Site grading fill outside area defined above	0 to 5	92
	5 to 8	95
Utility trenches within structural areas	--	96
Roadbase and subbase	-	96
Non-structural fill	0 to 5	90
	5 to 8	92

Structural fills greater than 8 feet thick are not anticipated at the site. For best compaction results, we recommend that the moisture content for structural fill/backfill be within 2% of optimum. Field density tests should be performed on each lift as necessary to verify that proper compaction is being achieved.

6.5 Utility Trenches

For the bedding zone around the utility, we recommend utilizing sand bedding fill material that meets current APWA⁶ requirements.

All utility trench backfill material below structurally loaded facilities (foundations, floor slabs, flatwork, parking lots/drive areas, etc.) shall be placed at the same density requirements established for structural fill in the previous section.

Most utility companies and local governments are requiring Type A-1a or A-1b (AASHTO Designation) soils (sand/gravel soils with limited fines) be used as backfill over utilities within public rights of way, and the backfill be compacted over the full depth above the bedding zone to at least 96% of the maximum dry density as determined by AASHTO T-180 (ASTM D-1557).

Where the utility does not underlie structurally loaded facilities and public rights of way, on-site fill and natural soils may be utilized as trench backfill above the bedding layer, provided they are properly moisture conditioned and compacted to the minimum requirements stated above in **Section 6.4**. Achieving proper compaction using the natural soils as trench backfill will be difficult as discussed in **Section 6.3**.

6.6 Stabilization

The natural silt/clay soils at this site will likely be susceptible to rutting and pumping. The likelihood of disturbance or rutting and/or pumping of the existing natural soils is a function of the load applied to the surface, as well as the frequency of the load. Consequently, rutting and pumping can be minimized by avoiding concentrated traffic, minimizing the load applied to the surface by using lighter equipment and/or partial loads,

⁶ American Public Works Association

by working in drier times of the year, or by providing a working surface for the equipment. Rubber-tired equipment particularly, because of high pressures, promotes instability in moist/wet, soft soils.

If rutting or pumping occurs, traffic should be stopped and the disturbed soils should be removed and replaced with stabilization material. Typically, a minimum of 18 inches of the disturbed soils must be removed to be effective. However, deeper removal is sometimes required.

To stabilize soft subgrade conditions (if encountered), a mixture of coarse, clean, angular gravels and cobbles and/or 1.5- to 2.0-inch clean gravel should be utilized, as indicated above in **Section 6.3**. Often the amount of gravelly material can be reduced with the use of a geotextile fabric such as Mirafi RS280i, or equivalent. Its use will also help avoid mixing of the subgrade soils with the gravelly material. After excavating the soft/disturbed soils, the fabric should be spread across the bottom of the excavation and up the sides a minimum of 18 inches. Otherwise, it should be placed in accordance with the manufacturer's recommendation, including proper overlaps. The gravel material can then be placed over the fabric in compacted lifts as described above.

7.0 FOUNDATION RECOMMENDATIONS

The following recommendations have been developed on the basis of the previously described project characteristics, the subsurface conditions observed in the field and the laboratory test data, as well as common geotechnical engineering practice.

7.1 Foundation Recommendations

Based on our geotechnical engineering analyses, the proposed residential structures may be supported upon conventional spread and/or continuous wall foundations placed on suitable, undisturbed natural soils and/or on structural fill extending to suitable natural soils. Footings may be designed using a net bearing pressure of 2,000 psf if placed on suitable, undisturbed, natural soils or 2,500 psf if placed on a minimum 18 inches of structural fill. The term "net bearing pressure" refers to the pressure imposed by the portion of the structure located above lowest adjacent final grade, thus the weight of the footing and backfill to lowest adjacent final grade need not be considered. The allowable bearing pressure may be increased by 1/3 for temporary loads such as wind and seismic forces.

We also recommend the following:

1. Exterior footings subject to frost should be placed at least 30 inches below final grade.
2. Interior footings not subject to frost should be placed at least 16 inches below grade.
3. Continuous footing widths should be maintained at a minimum of 18 inches.
4. Spot footings should be a minimum of 24 inches wide.

7.2 Installation

Foundations shall not be placed on topsoil with organics, undocumented fill, rubbish, construction debris, other deleterious materials, frozen soils, or within ponded water. If excessively soft or otherwise unsuitable soils are

encountered beneath footings, they must be totally removed and/or stabilized. If removal depth required is less than 2 feet above or at groundwater level, CMT must be notified to provide additional recommendations.

Deep, large roots may be encountered where trees and larger bushes occupy, or once occupied portions of the site; such large roots should be removed. Excavation bottoms should be examined by a CMT geotechnical engineer to confirm that suitable bearing materials soils have been exposed.

Where shallow groundwater was encountered at the site, dewatering of the footing trenches may be necessary and may also require stabilization. To reduce stabilization needs, dewatering the site area a minimum of 2 feet below the bearing elevation should significantly help.

All structural fill should meet the requirements for such, and should be placed and compacted in accordance with **Section 6** above. The width of structural replacement fill below footings should be equal to the width of the footing plus 1 foot for each foot of fill thickness. For instance, if the footing width is 2 feet and the structural fill depth beneath the footing is 2 feet, the fill replacement width should be 4 feet, centered beneath the footing.

The minimum thickness of structural fill below footings should be equivalent to one-third the thickness of structural fill below any other portion of the foundations. For example, if footings will cross over an area where an old basement was backfilled, and the maximum depth of structural fill used for the backfill is 6 feet, all footings for the new structure should be underlain by a minimum 2 feet of structural fill.

7.3 Estimated Settlement

Foundations designed and constructed in accordance with our recommendations could experience some settlement, but we anticipate that total settlements of footings founded as recommended above will not exceed 1 inch, with differential settlements on the order of 0.5 inches over a distance of 25 feet. We expect approximately 50% of the total settlement to initially take place during construction.

7.4 Lateral Resistance

Lateral loads imposed upon foundations due to wind or seismic forces may be resisted by the development of passive earth pressures and friction between the base of the footings and the supporting soils. In determining frictional resistance, a coefficient of 0.30 for natural soils or 0.40 for structural fill, may be utilized for design. Passive resistance provided by properly placed and compacted structural fill above the water table may be considered equivalent to a fluid with a density of 250 pcf. A combination of passive earth resistance and friction may be utilized if the friction component of the total is divided by 1.5.

8.0 LATERAL EARTH PRESSURES

Due to shallow ground water, sublevels may or may not be constructed and will vary in depth if constructed. The lateral earth pressure values given below are for a backfill material that will consist of drained sand/gravel soils (less than 10% passing No. 200 sieve) placed and compacted in accordance with the recommendations presented herein. If other soil types will be used as backfill, we should be notified so that appropriate modifications to these values can be provided, as needed.

The lateral pressures imposed upon subgrade facilities will, therefore, be basically dependent upon the relative rigidity and movement of the backfilled structure. For active walls, such as retaining walls which can move outward (away from the backfill), backfill may be considered equivalent to a fluid with a density of 45 pounds per cubic foot in computing lateral pressures. For more rigid walls (moderately yielding), backfill may be considered equivalent to a fluid with a density of 55 pounds per cubic foot. For very rigid non-yielding walls, backfill should be considered equivalent to a fluid with a density of at least 65 pounds per cubic foot. The above values assume that the surface of the soils slope behind the wall is horizontal and that the fill within 3 feet of the wall will be compacted with hand-operated compacting equipment.

For seismic loading of retaining/below-grade walls, the following uniform lateral pressures, in pounds per square foot (psf), should be added based on wall depth and wall case.

Uniform Lateral Pressures			
Wall Height (Feet)	Active Pressure Case (psf)	Moderately Yielding Case (psf)	At Rest/Non-Yielding Case (psf)
4	33	63	93
6	50	95	140
8	67	127	187

9.0 FLOOR SLABS

Floor slabs may be established upon suitable, undisturbed, natural soils or on structural fill extending to suitable natural soils (same as for foundations). Under no circumstances shall floor slabs be established directly on topsoil, non-engineered fills, loose or disturbed soils, sod, rubbish, construction debris, other deleterious materials, frozen soils, or within ponded water.

In order to facilitate curing of the concrete, we recommend that floor slabs be directly underlain by at least 4 inches of "free-draining" fill, such as "pea" gravel or 3/4-inch quarters to 1-inch minus, clean, gap-graded gravel. To help control normal shrinkage and stress cracking, the floor slabs may include the following features:

1. Adequate reinforcement for the anticipated floor loads with the reinforcement continuous through interior floor joints;
2. Frequent crack control joints; and
3. Non-rigid attachment of the slabs to foundation walls and bearing slabs.

The tops of all floor slabs in habitable areas must be established at least 3 feet above the measured static water level or a minimum 18 inches above levels controlled by subdrains.

10.0 DRAINAGE RECOMMENDATIONS

10.1 Surface Drainage

It is important to the long-term performance of foundations and floor slabs that water not be allowed to collect near the foundation walls and infiltrate into the underlying soils. We recommend the following:

1. All areas around each residence should be sloped to provide drainage away from the foundations. We recommend a minimum slope of 4 inches in the first 10 feet away from the structure. This slope should be maintained throughout the lifetime of the structure.
2. All roof drainage should be collected in rain gutters with downspouts designed to discharge at least 10 feet from the foundation walls or well beyond the backfill limits, whichever is greater.
3. Adequate compaction of the foundation backfill should be provided. We suggest a minimum of 90% of the maximum laboratory density as determined by ASTM D-1557. Water consolidation methods should not be used under any circumstances.
4. Landscape sprinklers should be aimed away from the foundation walls. The sprinkling systems should be designed with proper drainage and be well-maintained. Over watering should be avoided.
5. Other precautions that may become evident during construction.

10.2 Foundation Subdrains

10.2.1 General

Groundwater at this site is shallow and variable across the site. If habitable floor slabs are to be placed less than 3 feet above measured groundwater, then a foundation drain tied to a suitable down gradient land drain or another disposal system must be installed. Due to the variation in measured groundwater levels, it is recommended that the depth to groundwater be determined for each individual home if a land drain is not installed and lowest floor slab elevation be kept at least three feet above the measured static groundwater level.

10.2.2 Subdrain Design

Foundation subdrains shall consist of a 4-inch diameter perforated or slotted plastic or PVC pipe enclosed in clean gravel surrounding the home foundation. The invert of the subdrain should be at least 18 inches below the top of the lowest adjacent floor slab. The gravel portion of the drain should extend 2 inches laterally and below the perforated pipe and at least 1 foot above the top of the lowest adjacent floor slab. The gravel zone must be installed immediately adjacent to the perimeter footings and the foundation walls. To reduce the possibility of plugging, the gravel with drain pipe must be wrapped with a geotextile, such as Mirafi 140N or equivalent. Above the subdrain, a minimum 12-inch-wide zone of "free-draining" sand/gravel should be placed adjacent to the foundation walls and extend to within 2 feet of final grade and similarly separated from adjacent

soils with a geotextile such as Mirafi 140N or equivalent. The upper 1 foot of soils should consist of a compacted low permeable soil where possible to reduce surface water infiltration into the drain. As an alternative to the zone of permeable sand/gravel, a prefabricated “drainage board,” such as Miradrain or equivalent, may be placed adjacent to the exterior below-grade walls. Prior to the installation of the footing subdrain, the below-grade walls should be waterproofed. The slope of the subdrain should be at least 0.3 percent. The gravel placed around the drain pipe should be clean 0.75-inch to 1.0-inch minus gap-graded gravel and/or “pea” gravel. The foundation subdrains shall be discharged into the area subdrains or other suitable down-gradient location. Further it is recommended that a minimum 8 inches of gravel be placed below the floor slab which is hydraulically tied to the perimeter foundation drain through either drain pipes or a minimum 4-inch gravel layer extending out and below the foundation and connecting to the perimeter drain.

11.0 PAVEMENTS

We anticipate the natural soils will exhibit poor pavement support characteristics when saturated or nearly saturated. Based on laboratory testing, our pavement design utilized a California Bearing Ratio (CBR) of 4 for the natural soils.

In roadway areas, the subgrade must be prepared as recommended in **Section 6.1**. Subsequent to stripping of topsoil and preparation of disturbed soils, and prior to the placement of pavement materials, the exposed subgrade must be proof rolled by passing moderate-weight rubber tire-mounted construction equipment over the surface at least twice. If excessively soft or otherwise unsuitable soils are encountered, we recommend they be removed to a maximum of 24 inches below the subgrade level and replaced with structural fill.

Given the projected traffic as discussed above in **Section 1.3**, the following pavement sections are recommended for the given ESAL's (18-kip equivalent single-axle loads) per day:

Material	Pavement Section Thickness (inches)	
	Residential Street (9 ESAL's per day)	
Asphalt	3	3
Road-Base	12	6
Subbase	0	8
Total Thickness	15	17

Untreated base course (UTBC) should conform to city specifications, or to 1-inch-minus UDOT specifications for A-1-a/NP, and have a minimum CBR value of 70%. Subbase shall have a minimum CBR value of 30%. Material meeting our specification for structural fill may likely be used for subbase, as long as the fines content (percent passing No. 200 sieve) does not exceed 15%. Roadbase and subbase material should be compacted as recommended above in **Section 6.4**. Asphalt material generally should conform to APWA requirements, having a ½-inch maximum aggregate size, a 75-gradation Superpave mix containing no more than 15% of recycled asphalt (RAP) and a PG58-28 binder.

12.0 QUALITY CONTROL

We recommend that CMT be retained to as part of a comprehensive quality control testing and observation program. With CMT onsite we can help facilitate implementation of our recommendations and address, in a timely manner, any subsurface conditions encountered which vary from those described in this report. Without such a program CMT cannot be responsible for application of our recommendations to subsurface conditions which may vary from those described herein. This program may include, but not necessarily be limited to, the following:

12.1 Field Observations

Observations should be completed during all phases of construction such as site preparation, foundation excavation, structural fill placement and concrete placement.

12.2 Fill Compaction

Compaction testing by CMT is required for all structural supporting fill materials. Maximum Dry Density (Modified Proctor, ASTM D-1557) tests should be requested by the contractor immediately after delivery of any fill materials. The maximum density information should then be used for field density tests on each lift as necessary to ensure that the required compaction is being achieved.

12.3 Excavations

All excavation procedures and processes should be observed by a geotechnical engineer from CMT or their representative. In addition, for the recommendations in this report to be valid, all backfill and structural fill placed in trenches and all pavements should be density tested by CMT. We recommend that freshly mixed concrete be tested by CMT in accordance with ASTM designations.


13.0 LIMITATIONS

The recommendations provided herein were developed by evaluating the information obtained from the subsurface explorations and soils encountered therein. The exploration logs reflect the subsurface conditions only at the specific location at the particular time designated on the logs. Soil and ground water conditions may differ from conditions encountered at the actual exploration locations. The nature and extent of any variation in the explorations may not become evident until during the course of construction. If variations do appear, it may become necessary to re-evaluate the recommendations of this report after we have observed the variation.

Our professional services have been performed, our findings obtained, and our recommendations prepared in accordance with generally accepted geotechnical engineering principles and practices. This warranty is in lieu of all other warranties, either expressed or implied.

We appreciate the opportunity to be of service to you on this project. If we can be of further assistance or if you have any questions regarding this project, please do not hesitate to contact us at (801) 870-6730. To schedule materials testing, please call (801) 381-5141.

Appendix



Suncrest Meadows
2550 S 4700 W, Taylor, Utah

CMT ENGINEERING
LABORATORIES

Site Plan

Date:	18-Jan-18
Job #	10830

Figure:

1

Suncrest Meadows

Test Pit Log

TP-1

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 4.5', 3.4'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown										
		Brown Fine SAND (SP-SM), some silt moilst, medium dense (estimated)										
1												
2												
3												
4												
5			wet medium dense (estimated)									
6				2	27.1					8		
7												
8			grades with silty clay layers up to 6" thick									
9												
10		END AT 10'	3									
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 4.5 feet and measured on 1/23/18 at 3.4 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

2

Suncrest Meadows

Test Pit Log

TP-2

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 3.25', 3.3'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg			
							Gravel %	Sand %	Fines %	LL	PL	PI	
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"											
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)											
2													
3					4	26				38			
4				wet									
5					5								
6													
7													
8													
9		Brown CLAY (CL), some fine sand wet, medium stiff (estimated)											
10				6	26.2				92				
11		END AT 10'											
12													
13													
14													

Remarks: Groundwater encountered during excavating at 3.25 feet and measured on 1/23/18 at 3.3 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

3

Suncrest Meadows

Test Pit Log

TP-3

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 4', 2.9'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
2		Brown SILT (ML) with fine sand very moist, medium stiff (estimated)										
3				7	24.5				67		NP	NP
4												
5												
6		Brown Clayey Fine SAND (SC), occasional silty clay layers up to 3" thick wet, medium dense (estimated)		8								
7												
8												
9				9	28.4				49			
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 4 feet and measured on 1/23/18 at 2.9 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-4

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 5', 3.1'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg			
							Gravel %	Sand %	Fines %	LL	PL	PI	
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"											
		Brown Silty Fine SAND (SM) moist, medium dense (estimated)											
1													
2													
3													
4													
5													
6													
7													
8													
9													
10			END AT 10'										
11													
12													
13													
14													

Remarks: Groundwater encountered during excavating at 5 feet and measured on 1/23/18 at 3.1 feet.
Slotted PVC pipe installed to depth of 10 feet to facilitate water level measurements.

Figure:



Excavated By: Owner Provided
Logged By: Hogan Wright
Page: 1 of 1

5

Suncrest Meadows

Test Pit Log

TP-5

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 11'
Water Depth: 7.5', 3.6'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10"										
1		Brown CLAY (CL) with fine sand moist, medium stiff (estimated)										
3				13	28				70			
4												
5												
6		Brown CLAY (CL), trace fine sand very moist, medium stiff (estimated)		14	35.5				96	34	21	13
7												
8												
9												
10				15								
11		END AT 11'										
12												
13												
14												

Remarks: Groundwater encountered during excavating at 7.5 feet and measured on 1/23/18 at 3.6 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-6

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 3.5', 2.4'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0	TOPSOIL: 3", Sand, silt, clay, roots, organics, brown Brown CLAY (CL) with fine sand	loose to 6" moist, medium stiff (estimated)										
1												
2												
3				16								
4			wet									
5												
6				17	33.9				70			
7												
8												
9				18								
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 3.5 feet and measured on 1/23/18 at 2.4 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.



Excavated By: Owner Provided
Logged By: Hogan Wright
Page: 1 of 1

Figure:

7

Suncrest Meadows

Test Pit Log

TP-7

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 4.5', 3'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"										
1		Brown Silty CLAY (CL), with some fine sand moist, medium stiff (estimated)										
2		Brown Silty Fine SAND (SM) very moist, medium dense (estimated)		19	16.6	112						
4												
5		wet										
6		Brown SILT (ML), some fine sand wet, medium stiff (estimated)		20								
7												
8												
9												
10		END AT 10'		21	25.4			63		NP	NP	
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 4.5 feet and measured on 1/23/18 at 3 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-8

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 11'
Water Depth: 4.25', 5.5'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown Clayey Fine SAND / Sandy CLAY (SC/CL), some silt moist, medium dense (estimated)										
2												
3			very moist	22	21.6	98.7						
4			wet									
5												
6				23								
7												
8												
9												
10				24								
11		END AT 11'										
12												
13												
14												

Remarks: Groundwater encountered during excavating at 4.25 feet and measured on 1/23/18 at 5.5 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-9

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 7.5', 5.3'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown Clayey Fine SAND (SC), some silt medium dense (estimated)										
2				25	17.5	102			41			
3		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
4												
5		Brown CLAY (CL), some fine sand very moist, medium stiff (estimated)		26								
6												
7												
8												
9				27								
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 7.5 feet and measured on 1/23/18 at 5.3 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-10

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 4.5', 2.7'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
2												
3					28							
4		grades with occasional silty clay layers up to 3" thick	wet									
5												
6					29							
7		clay layers grade out										
8												
9					30							
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 4.5 feet and measured on 1/23/18 at 2.7 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-11

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 3.75', 3.3'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown CLAY (CL), some fine sand moist, medium stiff (estimated)										
2		Brown Fine SAND (SP), some silt very moist, medium dense (estimated)										
3				31								
4		Brown CLAY (CL), some fine sand wet medium stiff (estimated)										
5				32								
6												
7												
8		Brown Silty Fine SAND (SM) wet, medium dense (estimated)										
9				33								
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 3.75 feet and measured on 1/23/18 at 3.3 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-12

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 11'
Water Depth: 5.5', 5.3'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
3				34								
5		Brown CLAY (CL) with abundant peat very moist to wet, soft (estimated) wet		35								
6		Brown Silty Fine SAND (SM) wet, medium dense (estimated)										
10				36	14.6				40			
11		END AT 11'										
12												
13												
14												

Remarks: Groundwater encountered during excavating at 5.5 feet and measured on 1/23/18 at 5.3 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-13

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 6', 2.6'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
3				37								
6			wet	38	26.9				41			
8		Brown CLAY (CL), some fine sand wet, medium stiff (estimated)										
9				39								
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during excavating at 6 feet and measured on 1/23/18 at 2.6 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-14

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 11'
Water Depth: 8.25', 4.5'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
3				40								
7		Brown CLAY (CL), some fine sand very moist, medium stiff (estimated)		41	30.8			95	35	20	15	
8		Gray / Brown Silty Fine SAND (SM) wet medium dense (estimated)										
9		Brown CLAY (CL), some fine sand wet, medium stiff (estimated)										
10				42								
11		END AT 11'										

Remarks: Groundwater encountered during excavating at 8.25 feet and measured on 1/23/18 at 4.5 feet.

Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log













TP-15

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 11'
Water Depth: 3.1'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		FILL / DISTURBED SOIL, 10" loose to 10"										
1		Brown SILT (ML), some fine sand moist, medium stiff (estimated)										
2		grades with increasing sand										
3				43	23.9				67	28	26	2
4												
5												
6		grades with decreasing sand										
7		grades black		44								
8												
9		Brown CLAY (CL), some fine sand moist, medium stiff (estimated)										
10				45								
11		END AT 11'										
12												
13												
14												

Remarks: Groundwater encountered during excavating at feet and measured on 1/23/18 at 3.1 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

Test Pit Log

TP-16

2550 S. 4700 W., Taylor, Weber County, Utah

Equipment: Rubber Tire Backhoe
Surface Elev. (approx):

Total Depth: 10'
Water Depth: 9.5', 4.6'

Date: 1/12/18
Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI
0		TOPSOIL: 3", Sand, silt, clay, roots, organics, brown loose to 6"										
1		Brown Silty Fine SAND (SM) moist, medium dense (estimated)										
2		hard										
3				46	17.5				45			
4												
5				47								
6		grades gray / blue in color										
7												
8				48	31.7				48			
9			Brown CLAY (CL), some fine sand very moist, medium dense (estimated) wet									
10		END AT 10'										
11												
12												
13												
14												

Remarks: Groundwater encountered during drilling at depth of 9.5 feet and measured on 1/23/18 at depth of 4.6 feet.
Slotted PVC pipe installed to depth of 10.0 feet to facilitate water level measurements.

Figure:

Suncrest Meadows

2550 S. 4700 W., Taylor, Weber County, Utah

Key to Symbols

Date: 1/12/18

Job #: 10830

Depth (ft)	GRAPHIC LOG	Soil Description	Sample Type	Sample #	Moisture (%)	Dry Density (pcf)	Gradation			Atterberg		
							Gravel %	Sand %	Fines %	LL	PL	PI

COLUMN DESCRIPTIONS

Depth (ft.): Depth (feet) below the ground surface (including groundwater depth - see water symbol below).

Graphic Log: Graphic depicting type of soil encountered (see below).

Soil Description: Description of soils encountered, including Unified Soil Classification Symbol (see below).

Sample Type: Type of soil sample collected at depth interval shown; sampler symbols are explained below-right.

Sample #: Consecutive numbering of soil samples collected during field exploration.

Moisture (%): Water content of soil sample measured in laboratory (percentage of dry weight of sample).

Dry Density (pcf): The dry density of a soil measured in laboratory (pounds per cubic foot).

Gradation: Percentages of Gravel, Sand and Fines (Silt/Clay), obtained from lab test results of soil passing the No. 4 and No. 200 sieves.

Atterberg: Individual descriptions of Atterberg Tests are as follows:

LL = Liquid Limit (%): Water content at which a soil changes from plastic to liquid behavior.








PL = Plastic Limit (%): Water content at which a soil changes from liquid to plastic behavior.

PI = Plasticity Index (%): Range of water content at which a soil exhibits plastic properties (= Liquid Limit - Plastic Limit).



STRATIFICATION		MODIFIERS	MOISTURE CONTENT
Description	Thickness	Trace	Dry: Absence of moisture, dusty, dry to the touch.
Seam	Up to ½ inch	<5%	Moist: Damp / moist to the touch, but no visible water.
Lense	Up to 12 inches	Some	
Layer	Greater than 12 in.	5-12%	Saturated: Visible water, usually soil below groundwater.
Occasional	1 or less per foot	With	
Frequent	More than 1 per foot	> 12%	

UNIFIED SOIL CLASSIFICATION SYSTEM (USCS)	MAJOR DIVISIONS		USCS SYMBOLS	TYPICAL DESCRIPTIONS
	COARSE-GRAINED SOILS More than 50% of material is larger than No. 200 sieve size.	GRAVELS The coarse fraction retained on No. 4 sieve.	CLEAN GRAVELS (< 5% fines)	GW
GRAVELS WITH FINES (≥ 12% fines)			GP	Poorly-Graded Gravels, Gravel-Sand Mixtures, Little or No Fines
			GM	Silty Gravels, Gravel-Sand-Silt Mixtures
SANDS The coarse fraction passing through No. 4 sieve.			CLEAN SANDS (< 5% fines)	SW
		SANDS WITH FINES (≥ 12% fines)	SP	Poorly-Graded Sands, Gravelly Sands, Little or No Fines
SM			Silty Sands, Sand-Silt Mixtures	
SC			Clayey Sands, Sand-Clay Mixtures	
FINE-GRAINED SOILS More than 50% of material is smaller than No. 200 sieve size.			SILTS AND CLAYS Liquid Limit less than 50%	ML
		CL		Inorganic Clays of Low to Medium Plasticity, Gravelly Clays, Sandy Clays, Silty Clays, Lean Clays
		OL		Organic Silts and Organic Silty Clays of Low Plasticity
	SILTS AND CLAYS Liquid Limit greater than 50%	MH	Inorganic Silts, Micaceous or Diatomaceous Fine Sand or Silty Soils	
		CH	Inorganic Clays of High Plasticity, Fat Clays	
		OH	Organic Silts and Organic Clays of Medium to High Plasticity	
HIGHLY ORGANIC SOILS		PT	Peat, Soils with High Organic Contents	

SAMPLER SYMBOLS

-  Block Sample
-  Bulk/Bag Sample
-  Modified California Sampler
-  3.5" OD, 2.42" ID D&M Sampler
-  Rock Core
-  Standard Penetration Split Spoon Sampler
-  Thin Wall (Shelby Tube)

WATER SYMBOL

-  Encountered Water Level
 -  Measured Water Level
- (see Remarks on Logs)

Note: Dual Symbols are used to indicate borderline soil classifications (i.e. GP-GM, SC-SM, etc.).

- The results of laboratory tests on the samples collected are shown on the logs at the respective sample depths.
- The subsurface conditions represented on the logs are for the locations specified. Caution should be exercised if interpolating between or extrapolating beyond the exploration locations.
- The information presented on each log is subject to the limitations, conclusions, and recommendations presented in this report.

Figure:

18