

3026 East 4100 North
Liberty, UT 84310

Request is to install a property boundary fence around the perimeter of the property approximately 5' tall. The fence will be constructed of 3-1/2" square tube posts spaced approximately 10' apart with (4) horizontal 2-3/8" round tube rails equally spaced. The intent is to build a fence robust enough to withstand snow loads and freeze / thaw cycles, as well as handle pressure from livestock. Fence will be installed in phases with the first portion from the creek forward to be installed immediately and North of Chicken Creek to be installed at a later time. Fence will be installed and then sandblasted and painted black with a two part 30 yr coating system. Fence posts will be approximately 5' above ground and extending 3' below ground and encased in concrete below grade to help with stability.

Approximate Property Lines noted in red:



Similarly Constructed Fence:

