

PLANT SCHEDULE

TREES	CODE	BOTANICAL	COMMON	CONT	SIZE	QTY
	GLE SHA	Gleditsia triacanthos 'Shademaster'	Honey Locust 'Shademaster'	2"	CAL	7

2550 NORTH

1500 WEST

EXISTING
BUILDING
FF = 4221.20

EXISTING
BUILDING

PLANTING NOTES

- ALL PLANTS SHALL CONFORM TO THE MINIMUM STANDARDS OF HEIGHT, SIZE, CALIPER AND ETC. OF THE AMERICAN ASSOCIATIONS OF NURSERYMEN "AMERICAN STANDARDS FOR NURSERY STOCK".
- THIS CONTRACTOR SHALL SPREAD TOPSOIL TO A DEPTH OF 6" IN ALL LAWN PLANTING AREAS AND 12" IN ALL SHRUB AND PERENNIAL BEDS.
- ALL MOWSTRIPS ARE TO BE INSTALLED PRIOR TO THE INSTALLATION OF THE IRRIGATION SYSTEM SYSTEM AND THE LANDSCAPE PLANTING.
- INSTALL SHREDDED BARK MULCH IN ALL SHRUB PLANTING BEDS AFTER PLANT MATERIAL INSTALLATION.
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND INSTALLING THE REQUIRED AMOUNT OF TOPSOIL TO COMPLETE THE PROJECT. NEW TOPSOIL SHALL MATCH QUALITY AND TEXTURE OF THE EXISTING TOPSOIL ON SITE.

LEGEND

NOT ALL ITEMS IN THE LEGEND MAY BE APPLICABLE	
	BOUNDARY LINE
	CENTERLINE
	EASEMENT LINE/ROW
	SETBACK LINE
	NEW IRRIGATION LINE
	NEW LAND DRAIN
	NEW STORM DRAIN
	NEW SANITARY SEWER
	NEW SECONDARY WATERLINE
	NEW CULINARY WATERLINE
	EX. IRRIGATION LINE
	EX. LAND DRAIN
	EX. OVERHEAD POWER LINE
	EX. STORM DRAIN
	EX. SANITARY SEWER
	EX. SECONDARY WATERLINE
	EX. TELEPHONE LINE
	EX. GAS LINE
	EX. CULINARY WATERLINE
	SECTION CORNER MONUMENT
	CONTROL POINT
	EX. SPOT ELEVATION
	EG CONTOUR LINE
	FG CONTOUR LINE
	EXISTING ASPHALT
	NEW ASPHALT



REVISIONS

DATE: 10/29/2014
PROJECT: 12-031
DRAWN BY: R.B.
PLANT: 10-29-2014

DRAWING DESCRIPTION:
PLANTING PLAN

177 E. ANTELOPE DR. #B
LAYTON, UT 84041
PHONE: (801) 499-5054
FAX: (801) 499-5065

SILVERPEAK
ENGINEERING

BAUR STORAGE BUILDING
LOT 1B, WEBER INDUSTRIAL PARK
WEBER COUNTY, UTAH

SHEET NUMBER:

L1

PLANTING