


Project Narrative/Notes/Revisions

1. 02/28/2025 CK - COMPLETED DESIGN FOR CLIENT & CITY REVIEW.
2. 05/09/2025 CK - UPDATED SEWER DESIGN.

Brook View Subdivision
Phase 1 & 2
Improvement Plans



WEBER COUNTY, UTAH
FEBRUARY 2025



Sheet Index Key Map
NOT TO SCALE



Vicinity Map
NOT TO SCALE



Engineer's Notice To Contractors:

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM AVAILABLE INFORMATION PROVIDED BY OTHERS. THE LOCATIONS SHOWN ARE APPROXIMATE AND SHALL BE CONFIRMED IN THE FIELD BY THE CONTRACTOR, SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO CONTACT THE UTILITY COMPANIES AND TAKE DUE PRECAUTIONARY MEASURE TO PROTECT ANY UTILITY LINES SHOWN, AND ANY OTHER LINES OBTAINED BY THE CONTRACTOR'S RESEARCH, AND OTHERS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.



Surveyor:
Jason Felt
Reeve & Associates, Inc.
5160 South 1500 West
Riverdale, Utah, 84405
PH:(801) 621-3100

Project Contact:
Nate Reeve
Reeve & Associates, Inc.
5160 South 1500 West
Riverdale, Utah, 84405
PH:(801) 621-3100

Sheet Index

- Sheet 1 - Cover/Index Sheet
Sheet 2 - Notes/Legend/Street Cross-Section
Sheet 3 - A Street - 0+00.00 - 4+50.00
Sheet 4 - A Street - 4+50.00 - 9+30.00
Sheet 5 - A Street - 9+30.00 - 11+75.00
Sheet 6 - B Street - 0+00.00 - 4+50.00
Sheet 7 - B Street - 4+50.00 - 9+30.00
Sheet 8 - B Street - 9+30.00 - 14+10.00
Sheet 9 - C Street - 0+00.00 - 4+50.00
Sheet 10 - C Street - 4+50.00 - 7+75.75
Sheet 11 - D Street - 0+00.00 - 4+50.00
Sheet 12 - D Street - 4+50.00 - 9+25.00
Sheet 13 - E Street - 0+00.00 - 4+50.00
Sheet 14 - E Street - 4+50.00 - 7+73.00
Sheet 15 - F Street - 0+00.00 - 2+00.00
Sheet 16 - 1500 South Street - 0+00.00 - 4+50.00
Sheet 17 - 1575 South Street - 0+00.00 - 4+50.00
Sheet 18 - 1575 South Street - 4+50.00 - 9+30.00
Sheet 19 - 1575 South Street - 9+30.00 - 13+25.00
Sheet 20 - 1400 South Street - 0+00.00 - 4+50.00
Sheet 21 - 1400 South Street - 4+50.00 - 9+30.00
Sheet 22 - 1400 South Street - 9+30.00 - 13+26.00
Sheet 23 - Grading & Drainage Plan
Sheet 24 - Grading & Drainage Plan
Sheet 25 - Utility Plan
Sheet 26 - Utility Plan
Sheet 27 - Fire Plan
Sheet 28 - Irrigation Plan
Sheet 29 - Existing Site & Demolition Plan
Sheet 30 - Basin Details
Sheet 31 - Details
Sheet 32 - Details
Sheet 33 - Sewer Details
Sheet 34 - Storm Water Pollution Prevention Plan Exhibit
Sheet 35 - Storm Water Pollution Prevention Plan Details



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

Cover/Index Sheet




Project Info.
Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY
Begin Date:
FEBRUARY 2025
Name:
BROOKVIEW SUBDIVISION
Number: 8065-04


1. ALL CONSTRUCTION MUST STRICTLY FOLLOW THE STANDARDS AND SPECIFICATIONS SET FORTH BY: GOVERNING UTILITY MUNICIPALITY,
GOVERNING CITY OR COUNTY (IF UN-INCORPORATED), INDIVIDUAL PRODUCT MANUFACTURERS, AMERICAN PUBLIC WORKS
ASSOCIATION (APWA), AND THE DESIGN ENGINEER. THE ORDER LISTED ABOVE IS ARRANGED BY SENIORITY, IF A CONSTRUCTION
2. CONTRACTOR IS NOT REGISTERED FOR SUCH WORK, THE CONTRACTOR MUST CONTACT DESIGN ENGINEER FOR DIRECTION.
CONTRACTOR TO STRICTLY FOLLOW GEOTECHNICAL RECOMMENDATIONS FOR THIS PROJECT. ALL GRADING INCLUDING BUT NOT
LIMITED TO CUT, FILL, COMPACTION, ASPHALT SECTION, SUBBASE, TRENCH EXCAVATION/BACKFILL, SITE GRUBBING, RETAINING WALLS
AND FOOTINGS MUST BE COORDINATED DIRECTLY WITH THE PROJECT GEOTECHNICAL ENGINEER.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR SCHEDULING AND NOTIFYING ENGINEER TO CURRENT GOVERNING AGENCIES TRANSPORTATION ENGINEER'S MANUAL
AND MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
4. ANY AREA OUTSIDE THE LIMIT OF WORK THAT IS DISTURBED SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT NO COST TO
OWNER.
5. CONSULT ALL OF THE DRAWINGS AND SPECIFICATIONS FOR COORDINATION REQUIREMENTS BEFORE COMMENCING CONSTRUCTION.
6. AT ALL LOCATIONS WHERE EXISTING PAVEMENT ABUTS NEW CONSTRUCTION, THE EDGE OF THE EXISTING PAVEMENT SHALL BE
SAW-CUT TO A CLEAN, SMOOTH EDGE.
7. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE MOST RECENT, ADOPTED EDITION OF ADA ACCESSIBILITY
GUIDELINES.
8. PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING SURE THAT ALL REQUIRED PERMITS
AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED
THROUGHOUT REVIEWED PLANS AND OTHER DOCUMENTS AND APPROVED BY ALL OF THE PERMITTING AUTHORITIES.
9. COVERING OR EXCAVATION FOR SCHEDULING PURPOSES MUST BE NOTIFIED ENGINEER INSPECTING AUTHORITY 24 HOURS IN ADVANCE OF
COVERING UP ANY PHASE OF CONSTRUCTION REQUIRING OBSERVATION.
10. ANY WORK IN THE PUBLIC RIGHT-OF-WAY WILL REQUIRE PERMITS FROM THE APPROPRIATE CITY, COUNTY OR STATE AGENCY
AND THE STATE OF UTAH, INCLUDING OBTAINING REQUIRED INSPECTIONS.
11. ALL DIMENSIONS, GRADES & UTILITY DESIGNS SHOWN ON THE PLANS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO
CONSTRUCTION. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH CONSTRUCTION FOR
NECESSARY PLAN OR GRADE CHANGES.
12. MUST MEET ALL EXISTING CONDITIONS BEFORE BIDDING AND BRING UP ANY QUESTIONS BEFOREHAND.
13. SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET
FORTH BY THE GEOTECHNICAL ENGINEER.
14. CATCH SLOPES SHALL BE GRADED AS SPECIFIED ON GRADING PLANS.
15. ALL SLOPES SHALL BE RESPONSIBLE FOR ALL FLAGGING, CAUTION SIGNS, LIGHTS, BARRICADES, FLAGMEN, AND ALL OTHER
DEVICES NECESSARY FOR PUBLIC SAFETY.
16. CONTRACTOR SHALL, AT THE TIME OF BIDDING AND THROUGHOUT THE PERIOD OF THE CONTRACT, BE LICENSED IN THE STATE
WHERE THE PROJECT IS LOCATED AND SHALL BE BONDED FOR AN AMOUNT EQUAL TO, OR GREATER THAN THE AMOUNT BID AND
FOR THE TYPE OF WORK. THE CONTRACTOR SHALL BE A MEMBER OF THE NATIONAL ASSOCIATION OF PROFESSIONAL ENGINEERS AND REGULARLY
ENGAGED IN THE GENERAL CLASS AND TYPE OF WORK CALLED FOR IN THE PLANS AND SPECIFICATIONS.
17. CONTRACTOR SHALL INSPECT THE SITE OF THE WORK PRIOR TO BIDDING TO SATISFY HIMSELF BY PERSONAL EXAMINATION OR BY
SUCH OTHER MEANS AS HE MAY PREFER OF THE LOCATIONS OF THE PROPOSED WORK AND OF THE ACCESS CONDITIONS OF AND
TO THE TYPE OF WORK. DURING THE COURSE OF THE EXAMINATION, A BIDDER FINDS FACTS OR CONDITIONS WHICH APPEAR TO
HIM TO BE IN CONFLICT WITH THE LETTER OR SPIRIT OF THE PROJECT'S PLANS AND SPECIFICATIONS, HE SHALL CONTACT THE
ENGINEER FOR ADDITIONAL INFORMATION AND EXPLANATION BEFORE SUBMITTING HIS BID. SUBMISSION OF A BID BY THE
CONTRACTOR SHALL CONSTITUTE AN ACKNOWLEDGMENT OF THE ACCURACY OF THE INFORMATION AND SPECIFICATIONS ON HIS
OWN EXAMINATION OF (1) THE SITE OF THE WORK, (2) ACCESS TO THE SITE, AND (3) ALL OTHER DATA AND MATTERS RELATING
TO THE FULFILLMENT OF THE WORK AND ON HIS OWN KNOWLEDGE OF EXISTING FACILITIES ON AND IN THE VICINITY OF THE SITE
OF THE WORK TO BE CONSTRUCTED UNDER THIS CONTRACT. THE INFORMATION PROVIDED BY THE ENGINEER IS NOT INTENDED TO
BE A SUBSTITUTE FOR, OR SUPPLEMENT TO, THE INDEPENDENT VERIFICATION OF THE CONTRACTOR TO THE EXTENT THAT SUCH
INVESTIGATION OR INVESTIGATION OF SITE CONDITIONS IS CONSIDERED DESIRABLE BY THE CONTRACTOR. THE CONTRACTOR SHALL
ACKNOWLEDGE THAT HE HAS NOT RELIED SOLELY UPON OWNER- OR ENGINEER-FURNISHED INFORMATION REGARDING THE EXISTING
CONDITIONS IN PREPARING AND SUBMITTING HIS BID.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF WATER, POWER, SANITARY FACILITIES AND TELEPHONE SERVICES AS
REQUIRED FOR THE CONTRACTOR'S USE DURING CONSTRUCTION.
19. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES WITHOUT PRIOR WRITTEN AUTHORIZATION FROM THE
OWNER, ENGINEER, AND/OR GOVERNING AGENCIES.
20. CONTRACTOR SHALL EXERCISE DUE CAUTION AND SHALL CAREFULLY PRESERVE BENCH MARKS, CONTROL POINTS, REFERENCE
POINTS AND ALL SURVEY DATA. CONTRACTOR SHALL BEAR ALL EXPENSES FOR REPLACEMENT AND/OR ERRORS CAUSED BY THE
UNNECESSARY LOSS OR DISTURBANCE.
21. CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOBSITE CONDITIONS DURING THE COURSE OF
CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY
WHETHER OR NOT LIABILITY IS LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE
OWNER AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF
WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.
22. CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATELY SCHEDULING INSPECTION AND TESTING OF ALL FACILITIES CONSTRUCTED
UNDER THIS CONTRACT. TESTING SHALL CONFORM WITH THE REGULATORY AGENCY'S STANDARD SPECIFICATIONS. ALL TESTING AND
INSPECTION SHALL BE PAID FOR BY THE OWNER; ALL RE-TESTING AND/OR RE-INSPECTION SHALL BE PAID FOR BY THE
CONTRACTOR.
23. IF EXISTING IMPROVEMENTS NEED TO BE DISTURBED AND/OR REMOVED FOR THE PROPER PLACEMENT OF IMPROVEMENTS TO BE
CONSTRUCTED BY THE CONTRACTOR, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF SUCH IMPROVEMENTS. THE
COST OF REPLACING OR REPAIRING EXISTING IMPROVEMENTS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEMS
REQUIRING REMOVAL AND/OR REPLACEMENT. THERE WILL BE NO EXTRA COST DUE TO THE CONTRACTOR FOR REPLACING OR
REPAIRING EXISTING IMPROVEMENTS.
24. WHENEVER EXISTING FACILITIES ARE REMOVED, DAMAGED, BROKEN, OR CUT IN THE INSTALLATION OF THE WORK COVERED BY
THIS CONTRACT, THE CONTRACTOR SHALL REPLACE AND/OR FACILITIES SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE WITH MATERIALS EQUAL
TO OR BETTER THAN THE MATERIALS USED IN THE ORIGINAL EXISTING FACILITIES. THE FINISHED PRODUCT SHALL BE SUBJECT TO
THE APPROVAL OF THE OWNER, THE ENGINEER, AND THE RESPECTIVE REGULATORY AGENCY.
CONTRACTOR SHALL MAINTAIN A NEATLY MARKED SET OF FULL-SIZE AS-BUILT RECORD DRAWINGS SHOWING THE FINAL LOCATION
AND DEPTH OF ALL UTILITIES AND ADJUSTMENTS TO THE ORIGINAL DRAWINGS. THE DRAWINGS SHALL REFLECT CHANGE ORDERS,
ACCOMMODATIONS, AND ADJUSTMENTS TO ALL IMPROVEMENTS CONSTRUCTED. WHERE NECESSARY, SUPPLEMENTAL DRAWINGS SHALL
BE PREPARED AND SUBMITTED BY THE CONTRACTOR. PRIOR TO ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL DELIVER TO
ENGINEER A COMPLETE SET OF AS-BUILT RECORD DRAWINGS. THE AS-BUILT RECORD DRAWINGS SHALL BE PREPARED AND SUBMITTED
AS-BUILT RECORD DRAWINGS SHALL BE REVIEWED AND THE COMPLETE AS-BUILT RECORD DRAWING SET SHALL BE CURRENT WITH ALL
CHANGES AND DEVIATIONS REDLINED AS A PRECONDITION TO THE FINAL PROGRESS PAYMENT APPROVAL AND/OR FINAL
ACCEPTANCE.
25. WHERE THE PLANS OR SPECIFICATIONS DESCRIBE PORTIONS OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL, IT
IS UNDERSTOOD THAT ONLY THE BEST GENERAL PRACTICE IS TO PREVAIL AND THAT ONLY MATERIALS AND WORKMANSHIP OF THE
HIGHEST QUALITY ARE TO BE USED.
26. CONTRACTOR SHALL BE SKILLED AND REGULARLY ENGAGED IN THE GENERAL CLASS AND TYPE OF WORK CALLED FOR IN THE
PLANS AND SPECIFICATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RELIABLELY OBTAINING ALL MATERIALS, EQUIPMENT, AND
CONTRACTOR. PRICES PROVIDED WITHIN THE CONTRACT DOCUMENTS SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY AND
PROPER FOR THE WORK CONTEMPLATED AND THAT THE WORK BE COMPLETED IN ACCORDANCE WITH THE TRUE INTENT AND
PURPOSE OF THESE PLANS AND SPECIFICATIONS. THE CONTRACTOR SHALL BE COMPETENT, KNOWLEDGEABLE AND HAVE SPECIAL
SKILLS IN THE TYPE OF WORK TO BE CONSTRUCTED. THE CONTRACTOR SHALL BE AWARE OF THE SPECIAL CONDITIONS OF THE
PARTICULAR FACILITIES WHICH MAY CREATE, DURING THE CONSTRUCTION PROGRAM, UNUSUAL OR UNSAFE CONDITIONS HAZARDOUS
TO PERSONS, PROPERTY AND THE ENVIRONMENT. CONTRACTOR SHALL BE AWARE OF SUCH PRACTICE RISKS AND HAVE THE SKILL
AND KNOWLEDGE TO DESIGN AND ADOPT PROTECTIVE MEASURES TO ADEQUATELY AND SAFELY PERFORM THE CONSTRUCTION
WORK WITH RESPECT TO SUCH HAZARDS.
27. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL STRIPPING AND/OR PAVEMENT MARKINGS NECESSARY TO THE
EXISTING STRIPING INTO FUTURE STRIPING. METHOD OF REMOVAL SHALL BE BY GRINDING OR SANDBLASTING.
28. CONTRACTOR SHALL SHORTLY AFTER THE COMPLETION OF THE PROJECT, PROVIDE A PROTECTIVE WORKMAN FOR ALL
ALL AREAS TO BE EXCAVATED TO A DEPTH OF 4 FEET OR MORE. FOR EXCAVATIONS 4 FEET OR MORE IN DEPTH, THE
CONTRACTOR SHALL COMPLY WITH LOCAL, STATE AND NATIONAL SAFETY CODES, ORDINANCES, OR REQUIREMENTS FOR EXCAVATION
AND TRENCHES.
29. ALL FENCING GATES AND FENCES TO REMAIN UNLESS OTHERWISE NOTED ON PLANS. PROTECT ALL GATES AND FENCES FROM
DAMAGE.

1. CONTRACTOR SHALL COORDINATE LOCATION OF NEW "DRY UTILITIES" WITH THE APPROPRIATE UTILITY COMPANY, INCLUDING BUT NOT LIMITED TO: TELEPHONE SERVICE, GAS SERVICE, CABLE, POWER, INTERNET.
2. EXISTING UTILITIES HAVE BEEN SHOWN ON THE PLANS USING A COMBINATION OF ON-SITE SURVEYS (BY OTHERS), PRIOR TO EXCAVATION OF ANY NEW UTILITIES, AND TO HAVE EXISTING UTILITY COMPANY LOCATES. THE FIELD LOCATION OF EXISTING UTILITIES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO EXCAVATION. THE CONTRACTOR SHALL RECORD THE BLUE STAKES ORDER NUMBER AND FURNISH ORDER NUMBER TO OWNER AND ENGINEER PRIOR TO ANY EXCAVATION. IT WILL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO DIRECTLY CONTACT ANY OTHER UTILITY COMPANIES THAT ARE NOT MEMBERS OF BLUE STAKES. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROTECT ALL EXISTING UTILITIES SO THAT NO DAMAGE OCCURS TO THEM. IF ANY DAMAGE TO EXISTING UTILITIES IS NECESSARY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COSTS PAID FOR BY THE CONTRACTOR. THE CONTRACTOR SHALL BE REQUIRED TO COOPERATE WITH OTHER CONTRACTORS AND UTILITY COMPANIES INSTALLING NEW STRUCTURES, UTILITIES AND SERVICE TO THE PROJECT.
3. CONTRACTOR SHALL POT HOLE ALL UTILITIES TO DETERMINE IF CONFLICTS EXIST PRIOR TO BEGINNING ANY EXCAVATION. NOTIFY THE ENGINEER OF ANY CONFLICT. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EXISTING UTILITIES TO WHICH NEW UTILITIES WILL BE CONNECTED. PRIOR TO COMMENCING ANY EXCAVATION WORK THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES IN ACCORDANCE WITH THE REQUIRED PROCEDURES.
4. CARE SHOULD BE TAKEN IN ALL EXCAVATIONS DUE TO POSSIBLE EXISTENCE OF UNRECORDED UTILITY LINES. EXCAVATION REQUIRED TO VERIFY EXISTENCE OF EXISTING UTILITIES SHALL BE DONE BY HAND. CONTRACTOR SHALL REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT HIS EXPENSE.
5. ALL VALVES AND MANHOLE COVERS SHALL BE RAISED OR LOWERED TO MEET FINISHED GRADE.
6. CONTRACTOR SHALL CUT PIPES OFF FLUSH WITH THE INSIDE WALL OF THE BOX OR MANHOLE.
7. CONTRACTOR SHALL GROUT AT CONNECTION OF PIPE TO BOX WITH NON-SHRINKING GROUT, INCLUDING PIPE VOIDS LEFT BY CUTTING PROCESS, TO A SMOOTH FINISH.
8. CONTRACTOR SHALL GROUT WITH NON-SHRINK GROUT BETWEEN GRADE RINGS AND BETWEEN BOTTOM OF INLET LID FRAME AND TOP OF CONCRETE BOX.
9. SILL AND ALBERS IS TO BE CLEANED OUT OF ALL STORM DRAIN BOVS, CATCH BASINS ARE TO BE MAINTAINED IN A CLEANED CONDITION AS NECESSARY UNTIL AFTER THE FINAL BOND RELEASE INSPECTION.
10. CONTRACTOR SHALL CLEAN ASPHALT, TAR OR OTHER ADHESIVES OFF OF ALL MANHOLE LIDS AND INLET GRATES TO ALLOW ACCESS.
11. EACH TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND GRADE AS REQUIRED. THE TRENCH WALL SHALL BE SO BRACED THAT THE WORKMEN MAY WORK SAFELY AND EFFICIENTLY. ALL TRENCHES SHALL BE DRAINED SO THE PIPE LAYING MAY TAKE PLACE IN DE-WATERED CONDITIONS.
12. CONTRACTOR SHALL PROVIDE AND MAINTAIN AT ALL TIMES AMPLE MEANS AND DEVICES WITH WHICH TO REMOVE PROMPTLY AND TO PROPERLY DISPOSE OF ALL WATER EXPOSED DURING EXCAVATION.
13. MAINTAIN A MINIMUM 18" VERTICAL SEPARATION DISTANCE BETWEEN ALL UTILITY CROSSINGS.
14. CONTRACTOR SHALL START INSTALLATION AT LOW POINT OF ALL NEW GRAVITY UTILITY LINES.
15. ALL BOLTED FITTINGS MUST BE GREASED AND WRAPPED.
16. ALL SLEEVES, PARAPETS AND OTHER ACCESSORIES SHALL BE INSTALLED AND COVERED AT LEAST 2 FEET COVER OVER ALL STORM DRAIN LINES AT ALL TIMES (INCLUDING DURING CONSTRUCTION).
17. ALL WATER LINES SHALL BE INSTALLED A MINIMUM OF 60" BELOW FINISHED GRADE.
18. ALL SEWER LINES AND SEWER SERVICES SHALL HAVE A MINIMUM SEPARATION OF 10 FEET, PIPE EDGE TO PIPE EDGE, FROM THE WATER LINES. IF A 10 FOOT SEPARATION CAN NOT BE MAINTAINED, THE SEWER LINE AND WATER LINE SHALL BE LAID IN SEPARATE TRENCHES WITH A MINIMUM 18" VERTICAL SEPARATION BETWEEN THE TOP OF THE SEWER LINE AND THE TOP OF THE WATER LINE.
19. CONTRACTOR SHALL INSTALL THRUST BLOCKING AT ALL WATERLINE ANGLE POINTS AND TEES.
20. ALL UNDERGROUND UTILITIES SHALL BE IN PLACE PRIOR TO INSTALLATION OF CURB, GUTTER, SIDEWALK AND STREET PAVING.
21. CONTRACTOR SHALL INSTALL MAGNETIC LOCATING TAP CONTINUOUSLY OVER ALL NONMETALLIC PIPE.
22. ALL BOLTED FITTINGS SHALL BE GREASED AND WRAPPED. ALL BOLTED FITTINGS USING BLUE BOLTS SHALL BE PROTECTED ALL BOLTS FROM BEING ENCASED IN CONCRETE. INSTALL PER MANUFACTURER RECOMMENDATIONS.


*VERIFY LOCATION WITH PHONE GAS AND POWER COMPANIES



A Street 0+00.00 - 4+50.00




Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 2'



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
MINIMUM 6" SUMP UNLESS OTHERWISE
LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY
WATER LINE
SW - SECONDARY SERVICE LATERAL PER
COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE
COUNTY STANDARD DRAWINGS AND
SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND
COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER
OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN
NOT BE MAINTAINED FOR WATER LATERALS
CROSSING SEWER MAINS, SEWER MAIN MUST BE
SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN
NOT BE MAINTAINED FOR SEWER LATERALS
CROSSING WATER MAINS, SEWER LATERAL MUST
BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW
FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED
IN, MUST HAVE STRUCTURAL FILL IN ALL
RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER
PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS
REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C4	90°13'30"	20.00'	31.49'	20.08'	N45°43'11"E	28.34'
C25	92°42'45"	20.00'	32.36'	20.97'	S42°52'59"E	28.95'
C27	90°13'30"	20.00'	31.49'	20.08'	S45°43'11"W	28.34'
C31	89°46'30"	20.00'	31.34'	19.92'	S44°16'49"E	28.23'



Know what's below.
Call before you dig.

REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

A Street 0+00.00 - 4+50.00



Project Info.


Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY



Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION

Number: 8065-04




A Street 4+50.00 - 9+30.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/B - 8" PVC C900 DR-18 WATER LINE
 W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 LPSS/2 - 2" HDPE DR 11 LPSS MAIN
 LPSS/3 - 3" HDPE DR 11 LPSS MAIN
 LPSS/4 - 4" HDPE DR 11 LPSS MAIN
 1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
 MINIMUM 6" SUMP UNLESS OTHERWISE
 LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
 WATER LINE
 SW/12 - 12" PVC C-900 DR-14 SECONDARY
 WATER LINE
 SW - SECONDARY SERVICE LATERAL PER
 COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C2	89°54'21"	20.00'	31.38'	19.97'	N45°33'37"E	28.26'
C3	90°05'39"	20.00'	31.45'	20.03'	N44°26'23"W	28.31'
C21	89°48'28"	20.00'	31.35'	19.93'	S44°17'48"E	28.24'
C22	90°11'32"	20.00'	31.48'	20.07'	S45°42'12"W	28.33'

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 671-3100 www.reeve.co

REVISIONS	DATE	DESCRIPTION
	05-09-25 CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

A Street 4+50.00 - 9+30.00



Project Info.

Engineer:
 KENNETH H. HUNTER, P.E.
 Drafter:
 C. KINGSLEY

Begin Date:
 FEBRUARY 2025




Name:
 BROOKVIEW SUBDIVISION

Number: 8065-04



Know what's below.
 Call before you dig.

4
 35 Total Sheets

**A Street 9+30.00 - 11+72.84****Key Map**

NOT TO SCALE

**Construction Notes:****CULINARY WATER**

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
MINIMUM 6" SUMP UNLESS OTHERWISE
LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY
WATER LINE
SW - SECONDARY SERVICE LATERAL PER
COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	89°33'52"	20.00'	31.26'	19.85'	N44°10'30"W	28.18'
C14	90°26'08"	20.00'	31.57'	20.15'	S45°49'30"W	28.39'
C17	89°48'28"	20.00'	31.35'	19.93'	S44°17'48"E	28.24'
C18	90°11'32"	20.00'	31.48'	20.07'	S45°42'12"W	28.33'



Know what's below.
Call before you dig.

REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH




A Street 9+30.00 - 11+72.84**Project Info.**

Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION

Number: 8065-04

**B Street 0+00.00 - 4+50.00****Key Map**

NOT TO SCALE

**Construction Notes:****CULINARY WATER**

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
MINIMUM 6" SUMP UNLESS OTHERWISE
LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY
WATER LINE
SW - SECONDARY SERVICE LATERAL PER
COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data


#	Delta	Radius	Length	Tangent	Chord	CH Length
C7	89°52'23"	20.00'	31.37'	19.96'	N44°13'53"W	28.25'
C8	90°07'37"	20.00'	31.46'	20.04'	S45°46'07"W	28.32'
C9	89°52'23"	20.00'	31.37'	19.96'	S44°13'53"E	28.25'
C10	40°43'16"	130.00'	92.39'	48.24'	S21°03'57"W	90.46'
C29	40°43'16"	170.00'	120.82'	63.09'	S21°03'57"W	118.29'
C30	90°07'37"	20.00'	31.46'	20.04'	N45°46'07"E	28.32'

Centerline Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	40°43'16"	150.00'	106.61'	55.67'	N21°03'57"E	104.38'



Know what's below.
Call before you dig.




REVISIONS
DATE
05-09-25 CK
DESCRIPTION
Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

B Street 0+00.00 - 4+50.00

**Project Info.**

Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY


Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION



Number: 8065-04

6

35 Total Sheets




B Street 4+50.00 - 9+30.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C10	40°43'16"	130.00'	92.39'	48.24'	S21°03'57"W	90.46'
C11	90°05'40"	20.00'	31.45'	20.03'	S45°45'08"W	28.31'
C23	89°54'20"	20.00'	31.38'	19.97'	N44°14'52"W	28.26'
C24	90°07'38"	20.00'	31.46'	20.04'	N45°46'07"E	28.32'
C26	40°43'16"	220.00'	156.36'	81.64'	N21°03'56"E	153.09'
C28	109°34'58"	10.00'	19.13'	14.17'	N34°22'35"W	16.34'
C29	40°43'16"	170.00'	120.82'	63.09'	S21°03'57"W	118.29'

Centerline Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C2	40°43'16"	150.00'	106.61'	55.67'	N21°03'57"E	104.38'
C3	40°43'16"	200.00'	142.14'	74.22'	N21°03'56"E	139.17'




REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

B Street 4+50.00 - 9+30.00



Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY


Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION


Number: 8065-04

7

35 Total Sheets




B Street 9+30.00 - 14+10.00



TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C12	89°54'20"	20.00'	31.38'	19.97'	S44°14'52"E	28.26'
C13	90°20'16"	20.00'	31.53'	20.12'	S45°52'26"W	28.37'
C15	89°39'44"	20.00'	31.30'	19.88'	N44°07'34"W	28.20'
C16	90°05'40"	20.00'	31.45'	20.03'	N45°45'08"E	28.31'
C19	89°54'20"	20.00'	31.38'	19.97'	N44°14'52"W	28.26'
C20	90°05'40"	20.00'	31.45'	20.03'	N45°45'08"E	28.31'



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4" MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" PVC C900 DR-18 WATER LINE
 W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 LPSS/2 - 2" HDPE DR 11 LPSS MAIN
 LPSS/3 - 3" HDPE DR 11 LPSS MAIN
 LPSS/4 - 4" HDPE DR 11 LPSS MAIN
 1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
 MINIMUM 6" SUMP UNLESS OTHERWISE
 LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
 WATER LINE
 SW/12 - 12" PVC C-900 DR-14 SECONDARY
 WATER LINE
 SW - SECONDARY SERVICE LATERAL PER
 COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4" MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

B Street 9+30.00 - 14+10.00



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.
 Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION


Number: 8065-04





Know what's below.
Call before you dig.

8

35 Total Sheets



C Street 0+00.00 - 4+50.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/B - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C17	89°48'28"	20.00'	31.35'	19.93'	S44°17'48"E	28.24'
C18	90°11'32"	20.00'	31.48'	20.07'	S45°42'12"W	28.33'

Project Info.

Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY


Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION



Number: 8065-04



Know what's below.
Call before you dig.



C Street 4+50.00 - 7+75.75



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C16	90°05'40"	20.00'	31.45'	20.03'	N45°45'08"E	28.31'
C19	89°54'20"	20.00'	31.38'	19.97'	N44°14'52"W	28.26'

REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

C Street 4+50.00 - 7+75.75



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION

Number: 8065-04



Know what's below.
Call before you dig.


10

35 Total Sheets



Horizontal Scale: 1" = 20'

Vertical Scale: 1" = 2'



Reeve & Associates, Inc. - Solutions You Can Build On

The map shows a grid of streets. A red rectangle highlights a specific block bounded by 10th Street to the north, 11th Street to the south, and 12th Street to the east. The highlighted area is located between 10th and 11th Streets, and between 12th and 13th Streets.

CULINARY WATER

SANITARY SEWER

STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
MINIMUM 6" SUMP UNLESS OTHERWISE
LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY
WATER LINE
SW - SECONDARY SERVICE LATERAL PER
COUNTY STANDARDS

IRRIGATION WATER


IRR/18 -18" RCP CLASS III IRRIGATION PIPE


- NOTE:**
1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
 2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
 3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
 4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
 5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
 6. DEPTH OF WATER TO BE 4" MIN. BELOW FINISHED GRADE.
 7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
 8. PVC SLEEVES TO BE INSTALLED UNDER DRIVEWAY FOR SEWER LATERALS.
 9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:



CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data						
#	Delta	Radius	Length	Tangent	Chord	CH Length
C21	89°48'28"	20.00'	31.35'	19.93'	S44°17'48"E	28.24'
C22	90°11'32"	20.00'	31.48'	20.07'	S45°42'12"W	28.33'





D Street 4+50.00 - 9+25.00




TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C11	90°05'40"	20.00'	31.45'	20.03'	S45°45'08"W	28.31'
C12	89°54'20"	20.00'	31.38'	19.97'	S44°14'52"E	28.26'
C20	90°05'40"	20.00'	31.45'	20.03'	N45°45'08"E	28.31'
C23	89°54'20"	20.00'	31.38'	19.97'	N44°14'52"W	28.26'

Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/B - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER


IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:



- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING



E Street 0+00.00 - 4+50.00




TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C25	92°42'45"	20.00'	32.36'	20.97'	S42°52'59"E	28.95'
C27	90°13'30"	20.00'	31.49'	20.08'	S45°43'11"W	28.34'

Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

E Street 0+00.00 - 4+50.00



Project Info.


Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025



Name:
BROOKVIEW SUBDIVISION

Number: 8065-04





E Street 4+50.00 - 7+73.00



TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C24	90°07'38"	20.00'	31.46'	20.04'	N45°46'07"E	28.32'
C26	40°43'16"	220.00'	156.36'	81.64'	N21°03'56"E	153.09'
C28	109°34'58"	10.00'	19.13'	14.17'	N34°22'35"W	16.34'

Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/B - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

E Street 4+50.00 - 7+73.00



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION


Number: 8065-04





Know what's below.
Call before you dig.

14

35 Total Sheets



F Street 0+00.00 - 2+00.00



TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C5	89°59'57"	20.00'	31.42'	20.00'	N44°10'06"W	28.28'
C6	90°00'03"	20.00'	31.42'	20.00'	S45°49'54"W	28.28'

Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN = 12"x20" CENTERED AT CROSSING



Know what's below.
Call before you dig.

REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

F Street 0+00.00 - 2+00.00



Project Info.


Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY



Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION

Number: 8065-04




1500 South Street 0+00.00 - 4+50.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C2	89°54'21"	20.00'	31.38'	19.97'	N45°33'37"E	28.26'
C3	90°05'39"	20.00'	31.45'	20.03'	N44°26'23"W	28.31'



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

1500 South Street 0+00.00 - 4+50.00



Project Info.


Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY
Begin Date:
FEBRUARY 2025
Name:
BROOKVIEW SUBDIVISION
Number: 8065-04





Call before you dig.

16

35 Total Sheets



1575 South Street 0+00.00 - 4+50.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/B - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C4	90°13'30"	20.00'	31.49'	20.08'	N45°43'11"E	28.34'
C5	89°59'57"	20.00'	31.42'	20.00'	N44°10'06"W	28.28'
C6	90°00'03"	20.00'	31.42'	20.00'	S45°49'54"W	28.28'
C31	89°46'30"	20.00'	31.34'	19.92'	S44°16'49"E	28.23'



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

1575 South Street 0+00.00 - 4+50.00






Project Info.


Engineer:
KENNETH H. HUNTER, P.E.
 Drafter:
C. KINGSLEY
Begin Date:
FEBRUARY 2025
Name:
BROOKVIEW SUBDIVISION
Number: 8065-04

17

35 Total Sheets

**1575 South Street 4+50.00 - 9+30.00****Key Map**

NOT TO SCALE

**Construction Notes:****CULINARY WATER**

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES

W/8 - 8" PVC C900 DR-18 WATER LINE

W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL

SS/8 - 8" PVC SDR-35 SEWER LINE

LPSS/2 - 2" HDPE DR 11 LPSS MAIN

LPSS/3 - 3" HDPE DR 11 LPSS MAIN

LPSS/4 - 4" HDPE DR 11 LPSS MAIN

1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN

SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE

SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE

SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.

2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.

3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.

4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.

5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.

6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.

7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.

8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.

9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING

CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING

CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING

CASING 8" WATER MAIN = 12"x20" CENTERED AT CROSSING

TBC Curve Data


#	Delta	Radius	Length	Tangent	Chord	CH Length
C31	89°46'30"	20.00'	31.34'	19.92'	S44°16'49"E	28.23'

Know what's below.
Call before you dig.

REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

1575 South Street 4+50.00 - 9+30.00**Project Info.**

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

18**35** Total Sheets

REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

1575 South Street 9+30.00 - 13+25.00



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.
 Drafter:
C. KINGSLEY
 Begin Date:
FEBRUARY 2025
 Name:
BROOKVIEW SUBDIVISION
 Number: 8065-04

19

35 Total Sheets

Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" PVC C900 DR-18 WATER LINE
 W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 LPSS/2 - 2" HDPE DR 11 LPSS MAIN
 LPSS/3 - 3" HDPE DR 11 LPSS MAIN
 LPSS/4 - 4" HDPE DR 11 LPSS MAIN
 1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
 SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
 SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:


- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:



CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING


TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C7	89°52'23"	20.00'	31.37'	19.96'	N44°13'53"W	28.25'
C8	90°07'37"	20.00'	31.46'	20.04'	S45°46'07"W	28.32'
C9	89°52'23"	20.00'	31.37'	19.96'	S44°13'53"E	28.25'
C30	90°07'37"	20.00'	31.46'	20.04'	N45°46'07"E	28.32'





1575 South Street 9+30.00 - 13+25.00






1400 South Street 0+00.00 - 4+50.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" PVC C900 DR-18 WATER LINE
 W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 LPSS/2 - 2" HDPE DR 11 LPSS MAIN
 LPSS/3 - 3" HDPE DR 11 LPSS MAIN
 LPSS/4 - 4" HDPE DR 11 LPSS MAIN
 1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE
 SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE
 SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

- ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4" MIN. BELOW FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING


TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	89°33'52"	20.00'	31.26'	19.85'	N44°10'30"W	28.18'
C14	90°26'08"	20.00'	31.57'	20.15'	S45°49'30"W	28.39'

Brook View Subdivision

WEBER COUNTY, UTAH

1400 South Street 0+00.00 - 4+50.00



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.

Drafter:
C. KINGSLEY

Begin Date:
FEBRUARY 2025

Name:
BROOKVIEW SUBDIVISION


Number: 8065-04





Know what's below.
Call before you dig.

20

35 Total Sheets




1400 South Street 4+50.00 - 9+30.00



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES

W/8 - 8" PVC C900 DR-18 WATER LINE

W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL

SS/8 - 8" PVC SDR-35 SEWER LINE

LPSS/2 - 2" HDPE DR 11 LPSS MAIN

LPSS/3 - 3" HDPE DR 11 LPSS MAIN

LPSS/4 - 4" HDPE DR 11 LPSS MAIN

1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN

SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE MINIMUM 6" SUMP UNLESS OTHERWISE LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY WATER LINE

SW/12 - 12" PVC C-900 DR-14 SECONDARY WATER LINE

SW - SECONDARY SERVICE LATERAL PER COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:

1. ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.

2. CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS.

3. PROVIDE 18" VERTICAL CLEARANCE FOR WATER OVER/UNDER SEWER.

4. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR WATER LATERALS CROSSING SEWER MAINS, SEWER MAIN MUST BE SLEEVED 20" CENTERED AT CROSSING.

5. WHEN STANDARD 18" VERTICAL CLEARANCE CAN NOT BE MAINTAINED FOR SEWER LATERALS CROSSING WATER MAINS, SEWER LATERAL MUST BE SLEEVED 20" ON CENTER AT CROSSING.

6. DEPTH OF WATER TO BE 4' MIN. BELOW FINISHED GRADE.

7. ALL EXISTING DITCHES THAT ARE BEING FILLED IN, MUST HAVE STRUCTURAL FILL IN ALL RIGHT-OF-WAY AND BUILDING FOOTPRINTS.

8. PVC SLEEVES TO BE INSTALLED UNDER PATHWAY FOR SPRINKLER USE.

9. CONTRACTOR TO INSTALL ALL SLEEVES AS REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING

CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING

CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING

CASING 8" WATER MAIN = 12"x20" CENTERED AT CROSSING



REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

1400 South Street 4+50.00 - 9+30.00



Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafted: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04




Know what's below.

Call before you dig.

21


35 Total Sheets

REVISIONS	DATE	DESCRIPTION
	05-09-25	CK Sewer Design



Key Map

NOT TO SCALE



Construction Notes:

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
W/8 - 8" PVC C900 DR-18 WATER LINE
W - 1" SDR-9 POLY SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
SS/8 - 8" PVC SDR-35 SEWER LINE
LPSS/2 - 2" HDPE DR 11 LPSS MAIN
LPSS/3 - 3" HDPE DR 11 LPSS MAIN
LPSS/4 - 4" HDPE DR 11 LPSS MAIN
1.25" PRESSURE FROM EONE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
SD/18 - 18" RCP CLASS III STORM DRAIN

ALL STORM DRAIN STRUCTURES TO HAVE
MINIMUM 6" SUMP UNLESS OTHERWISE
LISTED.

SECONDARY WATER

SW/8 - 8" PVC C-900 DR-14 SECONDARY
WATER LINE
SW/12 - 12" PVC C-900 DR-14 SECONDARY
WATER LINE
SW - SECONDARY SERVICE LATERAL PER
COUNTY STANDARDS

IRRIGATION WATER

IRR/18 - 18" RCP CLASS III IRRIGATION PIPE

NOTE:


- ALL CONSTRUCTION IS TO CONFORM TO THE
COUNTY STANDARD DRAWINGS AND
SPECIFICATIONS.
- CONSTRUCT HANDICAP RAMP PER ADA AND
COUNTY REQUIREMENTS.
- PROVIDE 18" VERTICAL CLEARANCE FOR WATER
OVER/UNDER SEWER.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN
NOT BE MAINTAINED FOR WATER LATERALS
CROSSING SEWER MAINS, SEWER MAIN MUST BE
SLEEVED 20" CENTERED AT CROSSING.
- WHEN STANDARD 18" VERTICAL CLEARANCE CAN
NOT BE MAINTAINED FOR SEWER LATERALS
CROSSING WATER MAINS, SEWER LATERAL MUST
BE SLEEVED 20" ON CENTER AT CROSSING.
- DEPTH OF WATER TO BE 4' MIN. BELOW
FINISHED GRADE.
- ALL EXISTING DITCHES THAT ARE BEING FILLED
IN, MUST HAVE STRUCTURAL FILL IN ALL
RIGHT-OF-WAY AND BUILDING FOOTPRINTS.
- PVC SLEEVES TO BE INSTALLED UNDER
PATHWAY FOR SPRINKLER USE.
- CONTRACTOR TO INSTALL ALL SLEEVES AS
REQUIRED FOR THE RESIDENTIAL DEVELOPMENT.

MINIMUM SLEEVE SIZE REQUIREMENT:



CASING 4" SEWER LATERAL	= 8"x20" CENTERED AT CROSSING
CASING 8" SEWER MAIN	= 12"x20" CENTERED AT CROSSING
CASING 12" SEWER MAIN	= 16"x20" CENTERED AT CROSSING
CASING 8" WATER MAIN	= 12"x20" CENTERED AT CROSSING



TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C13	90°20'16"	20.00'	31.53'	20.12'	S45°52'26"W	28.37'
C15	89°39'44"	20.00'	31.30'	19.88'	N44°07'34"W	28.20'



1400 South Street 9+30.00 - 13+26.00






REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brookview Subdivision Grading & Drainage Plan

WEBER COUNTY, UTAH



Project Info.
 Engineer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
 Begin Date: FEBRUARY 2025
 Name: BROOKVIEW SUBDIVISION
 Number: 8065-04



Reeve & Associates, Inc.

LAND PLANNERS • CIVIL ENGINEERS • LANDSCAPE ARCHITECTS

1800 S. 1500 W. RIVERDALE, UT 84405
TEL: (801) 621-6211 FAX: (801) 621-6212

Reeve & Associates, Inc.

LAND PLANNERS • CIVIL ENGINEERS • LANDSCAPE ARCHITECTS

1800 S. 1500 W. RIVERDALE, UT 84405
TEL: (801) 621-6211 FAX: (801) 621-6212

Revisions

DATE	DESCRIPTION
05-09-25	OK Sewer Design

Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

Professional Engineer

KENNETH H. HUNTER, P.E.

375328

03/09/2025

STATE OF UTAH

Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

Project Info.

Engineer: KENNETH H. HUNTER, P.E.

Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04

Project Info.

Engineer: KENNETH H. HUNTER, P.E.



Drafter: C. KINGSLEY

Begin Date: FEBRUARY 2025

Name: BROOKVIEW SUBDIVISION

Number: 8065-04





ONE GRINDER UNITS
REQUIRED WHERE LATERAL
DEPTH IS INFEASIBLE DUE
TO BASEMENT DEPTHS



Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-3100 WWW.REVEE.CO

LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brookview Subdivision Utility Plan

WEBER COUNTY, UTAH



Project Info.
 Engineer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
 Begin Date: FEBRUARY 2025
 Name: BROOKVIEW SUBDIVISION
 Number: 8065-04



NOTE: DISTANCES REPRESENT TOTAL HOSE LENGTH ALONG ROADWAYS AS OPPOSED TO POINT TO POINT.



Reeve & Associates, Inc.
5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-3100 www.reeveco.com
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision
WEBER COUNTY, UTAH
Fire Plan



Project Info.
Engineer: KENNETH H. HUNTER, P.E.
Drafter: C. KINGSLEY
Begin Date: FEBRUARY 2025
Name: BROOKVIEW SUBDIVISION
Number: 8065-04
27
35 Total Sheets





REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision


WEBER COUNTY, UTAH

Irrigation Plan



Project Info.
Engineer: KENNETH H. HUNTER, P.E.
Drafter: C. KINGSLEY
Begin Date: FEBRUARY 2025
Name: BROOKVIEW SUBDIVISION
Number: 8065-04





REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design


Brook View Subdivision

WEBER COUNTY, UTAH


Existing Site & Demolition Plan




Engineer:	KENNETH H. HUNTER, P.E.
Drafter:	C. KINGSLEY
Begin Date:	FEBRUARY 2025
Name:	BROOKVIEW SUBDIVISION
Number:	8065-04



Cross Section B-B
SCALE: NONE




Cross Section A-A
SCALE: NONE



Plan View
SCALE: NONE

Control Box/ Combo Box

SCALE: NONE



Detention Basin Typical Section
SCALE: NONE



Storm Runoff Calculations

Brookview
8065-04
2/14/2025 rhh

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Weber City area taken from the NOAA Atlas 14 database. Calculations have been completed for the 100-yr 24-hr storm event. Storm water runoff has been calculated for a fully developed site and limited to a release rate of 0.1 cfs/acre.

The calculations are as follows:

Drainage Area:			
Total Area =	40.10	acre or	1,746,820 ft ²
Runoff Coefficients			
18% Paved Area	314,000		C = 0.9
16% Roof	278,400		C = 0.9
66% Landscaped Area	1,154,420		C = 0.2
Weighted Runoff Coefficient			C = 0.44

LID Retention:			
80 th Percentile Rainfall Event		0.6	in
Is the site Feasible for LID?		No	
Site Imperviousness		0.34	
NRCS Soil Group		C/D	
Rv Equation		0.89x1.22	
R _s		0.25	
V ₈₀		21,546	c.f.

Rainfall Intensities:			
10-yr intensity for a 30 minute TOC - Pipe Capacity		1.39	in/hr



Peak Run-off:			
Runoff Coefficient	C =	0.44	
Rainfall Intensity	i =	1.39 IN./HR.	
Acreage	A =	40.10 ACRES	
Q	Q =	24.38 cfs	

Volume of Run-off for 100-year Storm Event:

C =	0.44					
i =	See Below in/hr					
A =	1746820.00 ft ²					
Q(out) =	4.01 ft ³ /s	(0.1 cfs per acre)				
time (min)	time (sec)	i (in./hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0	0	0
5	300	6.59	116.55	34966	1203	33763
10	600	5.00	88.43	53059	2406	50653
15	900	4.14	73.22	68889	3609	62280
30	1800	2.79	49.34	89820	7218	81602
60	3600	1.72	30.42	109513	14437	95076
120	7200	0.94	16.70	120210	28873	91337
180	10800	0.64	11.35	122629	43310	78319
360	21600	0.36	6.33	136764	86619	50145
720	43200	0.22	3.89	168090	173238	-5149
1440	86400	0.12	2.19	189483	346477	-156994

Orifice Sizing:			
Given:	Q =	4.01 cfs	
	2g =	64.4 ft/s ²	
	H =	4.28 ft	
	Cd =	0.62	
	R =	SQRT((Q*pi)/(0.7*(64.4*H)*0.5))	for circular openings
	R =	0.35 feet	
	D =	4.23 inches	
	A =	8.45 inches ²	
		56.13 inches ²	
		0.3898 ft ²	

SUMMARY:			
The required 100-yr storage volume is	95,076	cubic feet	
The required LID Retention volume is	Not Feasible	cubic feet	
Orifice size is	8.5	inches	



REVISIONS	DESCRIPTION
DATE	05-09-25
CK	Sewer Design









Brook View Subdivision

WEBER COUNTY, UTAH

Basin Details



Project Info.
Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY
Begin Date:
FEBRUARY 2025
Name:
BROOKVIEW SUBDIVISION
Number:
8065-04



Reeve & Associates, Inc.

5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-3100 www.reeve.co

LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

Revisions






NO.	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Project Info.





Engineer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
Begin Date: FEBRUARY 2025
Name: BROOKVIEW SUBDIVISION
Number: 8065-04

35

Total Sheets



Force Main Details



REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design



Project Info.
Engineer: KENNETH H. HUNTER, P.E.
Drafter: C. KINGSLEY
Begin Date: FEBRUARY 2025
Name: BROOKVIEW SUBDIVISION
Number: 8065-04


Reeve & Associates, Inc. - Solutions You Can Build On

Brook View Subdivision

Phase 1 & 2

Storm Water Pollution Prevention Plan Exhibit


WEBER COUNTY, UTAH
FEBRUARY 2025



STREETS TO BE SWEEPED WITHIN 1000 FEET OF CONSTRUCTION ENTRANCE DAILY IF NECESSARY

ALL VEHICLES EXITING SITE TO PROCEED THROUGH CONSTRUCTION ENTRANCE TO REDUCE AMOUNTS OF SEDIMENT TRACKED ONTO ROADWAYS.

50'x20' CONSTRUCTION ENTRANCE W/8" CLEAN GRAVEL



SWPPP Legend

- = PORTABLE TOILET
- = INLET PROTECTION TYP. (SEE DETAIL)
- = SILT FENCE (SEE DETAIL)
- = 50'x20' CONSTRUCTION ENTRANCE W/8" CLEAN GRAVEL
- = CONCRETE WASH AREA (SEE DETAIL) OR AS SELECTED BY CONTRACTOR

- SWPPP NOTES:
- ALL VEHICLES EXITING SITE TO PROCEED THROUGH CONSTRUCTION ENTRANCE TO REDUCE AMOUNTS OF SEDIMENT TRACKED ONTO ROADWAYS.
 - STREETS TO BE SWEEPED WITHIN 1000 FEET OF CONSTRUCTION ENTRANCE DAILY IF NECESSARY

Construction Activity Schedule

- PROJECT LOCATION.....WEBER COUNTY, UTAH
- PROJECT BEGINNING DATE.....FEBRUARY 2025
- BMP'S DEPLOYMENT DATE.....FEBRUARY 2025
- STORM WATER MANAGEMENT CONTACT / INSPECTOR.....DAVE LALOLI (801) 698-0244
- SPECIFIC CONSTRUCTION SCHEDULE INCLUDING BMP CONSTRUCTION SCHEDULE TO BE INCLUDED WITH SWPPP BY OWNER/DEVELOPER

Reeve & Associates, Inc.
5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-3100 www.reeve.co

RA

LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • ENVIRONMENTAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
05-09-25	CK	Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH


Storm Water Pollution Prevention Plan Exhibit




Project Info.
Engineer: KENNETH H. HUNTER, P.E.
Drafter: C. KINGSLEY
Begin Date: FEBRUARY 2025
Name: BROOKVIEW SUBDIVISION
Number: 8065-04

Notes:

- Describe all BMP's to protect storm water inlets:
All storm water inlets to be protected by straw wattle barriers, or gravel bags (see detail).
- Describe BMP's to eliminate/reduce contamination of storm water from:
 - Equipment / building / concrete wash areas:
To be performed in designated areas only and surrounded with silt fence barriers.
 - Soil contaminated by soil amendments:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Areas of contaminated soil:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Fueling area:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle maintenance areas:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle parking areas:
To be performed in designated areas only and surrounded with silt fence.
 - Equipment storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Materials storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Waste containment areas:
To be performed in designated areas only and surrounded with silt fence.
 - Service areas:
To be performed in designated areas only and surrounded with silt fence.
- BMP's for wind erosion:
Stockpiles and site as needed to be watered regularly to eliminate / control wind erosion
- Construction Vehicles and Equipment:
 - Maintenance
 - Maintain all construction equipment to prevent oil or other fluid leaks.
 - Keep vehicles and equipment clean, prevent excessive build-up of oil and grease.
 - Regularly inspect on-site vehicles and equipment for leaks, and repair immediately.
 - Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment on-site.
 - Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic, and transmission fluids.
 - Fueling
 - If fueling must occur on-site, use designated areas away from drainage.
 - Locate on-site fuel storage tanks within a bermed area designed to hold the tank volume.
 - Cover retention area with an impervious material and install in a manner to ensure that any spills will be contained in the retention area. To catch spills or leaks when removing or changing fluids.
 - Use drip pans for any oil or fluid changes.
 - Washing
 - Use as little water as possible to avoid installing erosion and sediment controls for the wash area.
 - If washing must occur on-site, use designated, bermed wash areas to prevent waste water discharge into storm water, creeks, rivers, and other water bodies.
 - Use phosphate-free, biodegradable soaps.
 - Do not permit steam cleaning on-site.
- Spill Prevention and Control
 - Minor Spills:
Minor spills are those which are likely to be controlled by on-site personnel. After contacting local emergency response agencies, the following actions should occur upon discovery of a minor spill:
 - Contain the spread of the spill.
 - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (i.e. absorbent materials, cat litter, and / or rags).
 - If the spill occurs in dirt areas, immediately contain the spill by constructing an earth dike. Dig up and properly dispose of contaminated soil.
 - If the spill occurs during rain, cover the impacted area to avoid runoff.
 - Record all steps taken to report and contain spill.
 - Major Spills:
On-site personnel should not attempt to control major spills until the appropriate and qualified emergency response staff have arrived at the site. For spills of federal reportable quantities, also notify the National Response Center at (800) 424-8802. A written report should be sent to all notified authorities. Failure to report major spills can result in significant fines and penalties.
- Post Roadway / Utility Construction
 - Maintain good housekeeping practices.
 - Enclose or cover building material storage areas.
 - Properly store materials such as paints and solvents.
 - Store dry and wet materials under cover, away from drainage areas.
 - Avoid mixing excess amounts of fresh concrete or cement on-site.
 - Perform washout of concrete trucks offsite or in designated areas only.
 - Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
 - Do not place material or debris into streams, gutters, or catch basins that stop or reduce the flow of runoff water.
 - All public streets and storm drain facilities shall be maintained free of building materials, mud and debris caused by grading or construction operations. Roads will be swept within 1000' of construction entrance daily, if necessary.
 - Install straw wattle around all inlets contained within the development and all others that receive runoff from the development.
- Erosion Control Plan Notes
 - The contractor will designate an emergency contact that can be reached 24 hours a day 7 days a week.
 - A stand-by crew for emergency work shall be available at all times during potential rain or snow runoff events. Necessary materials shall be available on site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain or runoff is eminent.
 - Erosion control devices shown on the plans and approved for the project may not be removed without approval of the engineer of record. If devices are removed, no work may continue that have the potential of erosion without consulting the engineer of record. If deemed necessary erosion control should be reestablished before this work begins.
 - Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of the slope at the conclusion of each working day. This should be confirmed by survey or other means acceptable to the engineer of record.
 - All silt and debris shall be removed from all devices within 24 hours after each rain or runoff event.
 - Except as otherwise approved by the inspector, all removable protective devices shown shall be in place at the end of each working day and through weekends until removal of the system is approved.
 - All loose soil and debris which may create a potential hazard to offsite property shall be removed from the site as directed by the engineer of record of the governing agency.
 - The placement of additional devices to reduce erosion damage within the site is left to the discretion of the engineer of record.
 - Desilting basins may not be removed or made inoperable without the approval of the engineer of record and the governing agency.
 - Erosion control devices will be modified as need as the project progresses and plans of these changes submitted for approval by the engineer of record and the governing agency.
- Conduct a minimum of one inspection of the erosion and sediment controls every two weeks. Maintain documentation on site.
 - Part III.D.4 of general permit UTRC00000 identifies the minimum inspection requirements.
 - Part II.D.4.C identifies the minimum inspection report requirements.
 - Failure to complete and/or document storm water inspections is a violation of part III.D.4 of Utah General Permit UTR 300000.



Cross Section 50' x 20' Construction Entrance



Perspective View

Figure 2

INSTALLATION

The silt fence should be installed prior to major soil disturbances in the drainage area. The fence should be placed across the slope along a line of uniform elevation wherever flow of sediment is anticipated. Table 1 shows generally-recommended maximum slope lengths (slope spacing between fences), at various site grades for most silt fence applications.


TABLE 1: Recommended Maximum Slope Lengths for Silt Fence (Richardson & Middlebrooks, 1991)		
Slope Steepness (%)	Max. Slope Length m (ft)	
<2%	30.5m (100ft)	
2-5%	22.9m (75ft)	
5-10%	15.2m (50ft)	
10-20%	7.6m (25ft)	
>20%	4.5m (15ft)	

PREFABRICATED SILT FENCE ROLLS


- Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location.
- Unroll the silt fence, positioning the post against the downstream wall of the trench.
- Adjacent rolls of silt fence should be joined by nesting the end post of one fence into the other. Before nesting the end posts, rotate each post until the geotextile is wrapped completely around the post, then abut the end posts to create a tight seal as shown in Figure 1.
- Drive posts into the ground until the required fence height and/or anchorage depth is obtained.
- Buy the loose geotextile at the bottom of the fence in the upstream trench and backfill with natural soil, tamping the backfill to provide good compaction and anchorage. Figure 2 illustrates a typical silt fence installation and anchor trench placement.

FIELD ASSEMBLY:


- Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location.
- Drive wooden posts, or steel posts with fastening projections, against the downstream wall of the trench. Maximum post spacing should be 2.4-3.0m (8-10ft). Post spacing




Section



Inlet Box Protection



Plan View



Drop Inlet Protection





Figure 1:
Top View of
Roll-to-Roll Connection


Silt Fence Detail

SCALE: NONE



Concrete Washout Area
w/ 10 mil Plastic Liner

SCALE: NONE



Stake Detail

REVISIONS	DESCRIPTION
DATE	05-09-25 CK Sewer Design

Brook View Subdivision

WEBER COUNTY, UTAH

Storm Water Pollution Prevention Plan Details



Project Info.

Engineer:
KENNETH H. HUNTER, P.E.
Drafter:
C. KINGSLEY
Begin Date:
FEBRUARY 2025
Name:
BROOKVIEW SUBDIVISION
Number: 8065-04