


PAGE DESCRIPTION	SHEET NUMBER
COVER SHEET	1
PLAN VIEW	2
DESIGN CRITERIA	3
MATERIALS AND SPECS	APPENDIX A
CONSTRUCTION DRAWINGS	4
QUANTITY ESTIMATES	5
VERTI-BLOCK ELEVATIONS	APPENDIX B
WALL 1 ELEVATION VIEW	6 - 10
WALL 2 ELEVATION VIEW	11
WALL 3 ELEVATION VIEW	12 - 14
WALL 4 ELEVATION VIEW	15 - 16
WALL 5 ELEVATION VIEW	17 - 21
WALL 6 ELEVATION VIEW	22 - 23
WALL 7 ELEVATION VIEW	24 - 25
WALL 8 ELEVATION VIEW	26
WALL 9 ELEVATION VIEW	27
WALL 10 ELEVATION VIEW	28 - 31
WALL 11 ELEVATION VIEW	32 - 34
WALL 12 ELEVATION VIEW	35 - 39
VERTI-BLOCK CROSS SECTIONS	APPENDIX C
SECTION VIEW - WALL 1	40
SECTION VIEW - WALL 2	41
SECTION VIEW - WALL 3	42
SECTION VIEW - WALL 4	43
SECTION VIEW - WALLS 5 & 6	44
SECTION VIEW - WALL 7	45
SECTION VIEW - WALL 8	46
SECTION VIEW - WALLS 9, 10, & 12	47
SECTION VIEW - WALL 11	48
CALCULATIONS - STATIC & SEISMIC	APPENDIX D
GLOBAL STABILITY - STATIC & SEISMIC	APPENDIX E





VERTI-BLOCK RETAINING WALL DESIGN PACKAGE
SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD
EDEN, UTAH



Alan E Money Digitally signed by Alan E Money
Date: 2025.05.14 14:18:13 -07'00'

Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS COVER SHEET	SHEET NUMBER: 1	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Phone: 480 927-9696 Tempe, Arizona 85281 Fax: 480 927-9797 E-Mail: ammttec@ammtec.com www.ammttec.com Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Engineered By: Alan E. Money				
Scale: 1"=250'	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT			





Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS PLAN VIEW	SHEET NUMBER: 2	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Phone: 480 927-9696 Tempe, Arizona 85281 Fax: 480 927-9797 E-Mail: ammttec@ammtec.com www.ammtec.com		Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	Professional Engineer Seal for Alan E. Money, No. 174267-2202, State of Utah, dated May 14, 2025.	
Engineered By: Alan E. Money							PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT
Scale: 1"=60'							

GENERAL NOTES

BASIS OF DESIGN

1. BUILDING CODE 2018 INTERNATIONAL BUILDING CODE (IBC)

2. RETAINING WALL:

A. ANALYSIS USED IN DESIGN:

ANALYSIS	DESIGN REFERENCES/SOFTWARE
INTERNAL/EXTERNAL STABILITY	VERTI-BLOCK RETAINING WALLS, 2019 VERTICRETE WALL DESIGNER SOFTWARE
GLOBAL STABILITY	SLIDE 2: ROCSCIENCE, INC.

3. WALLS

A. WALL GEOMETRY AND LOADING CONDITIONS:

WALL	LENGTH (FT)	MAX. HEIGHT (FT)	BACKSLOPE CONDITIONS	SURCHARGE LOADING
1	582	25	VARIES	NONE
2	38	6	VARIES	NONE
3	384	19	VARIES	NONE
4	166	7	VARIES	NONE
5	586	28	VARIES	3,375 PSF WALL 1
6	144	12	VARIES	3,780 PSF WALL 5
7	156	14	VARIES	NONE
8	108	13	VARIES	NONE
9	72	12	VARIES	1,910 PSF WALL 12 & WALL 10
10	470	13	VARIES	1,890 PSF CONDO
11	306	29	VARIES	NONE
12	616	20	VARIES	3,915 PSF WALL 11

4. SOILS:

A. SOIL CONDITIONS USED IN DESIGN:

EARTH MATERIALS	FRICTION ANGLE	COHESION	UNIT WEIGHT
REINFORCED SOIL	38°	0 psf	135 pcf
WEATHERED ROCK, SHALE, ARGILLITE	25°	3,000 psf	155 pcf

B. COHESION USED ONLY DURING GLOBAL STABILITY ANALYSES

5. SEISMIC:

A. SEISMIC PARAMETERS USED IN DESIGN:

SEISMIC CRITERIA	INTERNAL, EXTERNAL & GLOBAL STABILITY	
	PGA _M	K _h
ASCE 7-16(IBC 2018)	0.448g	0.449g (INTERNAL) 0.187g (EXTERNAL) 0.224g (GLOBAL)

6. CONSTRUCTION MATERIALS:

- A. VERTI-BLOCK
- B. MIRAFI 5XT AND 8XT GEOGRID
- C. FILL MATERIAL
- D. CLEAN CRUSHED STONE/GRAVEL
- E. 4 INCH PERFORATED PVC PIPE
- F. NON-WOVEN GEOTEXTILE FILTER

7. CONSTRUCTION SPECIFICATIONS

- A. FOR VERTI-BLOCK CONSTRUCTION, REFERENCE THE VERTI-BLOCK RETAINING WALL DESIGN MANUAL.

Project Number: AZ 2025

Engineered By: Alan E. Money

DRAWING TITLE: DESIGN CRITERIA

SHEET NUMBER:
3


PROJECT NAME: SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT

AMMTec CONSULTANTS, PLLC

CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com











Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Appendix A

(Materials and Specs)



Construction Drawings Shown Used From
verti-block.com/design-resources/

Project Number: AZ 2025

Engineered By: Alan E. Money


DRAWING TITLE: VERTI-BLOCK RETAINING WALLS
CONSTRUCTION DRAWINGS

PROJECT NAME: SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT

SHEET NUMBER:
4

AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com
Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



VERTI-BLOCK RETAINING WALL ESTIMATED QUANTITIES														
MATERIAL	WALL 1	WALL 2	WALL 3	WALL 4	WALL 5	WALL 6	WALL 7	WALL 8	WALL 9	WALL 10	WALL 11	WALL 12	TOTAL	10% CONTINGENCY
TOTAL VERTI-BLOCK WALL AREA	6369.85 ft²	120.68 ft²	3442.23 ft²	527.92 ft²	5918.62 ft²	960.47 ft²	1075.90 ft²	801.72 ft²	540.99 ft²	3882.62 ft²	4394.96 ft²	4259.63 ft²	32295.59 ft²	35,525.15 ft²
TOP VERTI-BLOCK UNITS	70	8	51	28	71	14	16	11	5	64	34	82	454	500
36-INCH VERTI-BLOCK UNITS	719	15	474	61	1217	133	154	118	42	544	697	559	4733	5207
LEFT CORNER TOP VERTI-BLOCK UNITS	21	1	20	0	23	5	10	5	2	11	14	15	127	140
RIGHT CORNER TOP VERTI-BLOCK UNITS	10	1	0	4	5	0	1	0	4	0	0	0	25	28
1-FOOT STEP TOP VERTI-BLOCK UNITS	18	0	17	7	36	14	8	10	6	37	20	49	222	245
1-FOOT LEFT CORNER TOP VERTI-BLOCK UNITS	20	0	12	1	21	5	9	5	1	11	14	15	114	126
1-FOOT RIGHT CORNER TOP VERTI-BLOCK UNITS	9	0	0	4	4	1	0	1	2	1	1	1	24	27
MIRAFI 5XT GEOGRID	8241 yd²	0 yd²	2963 yd²	0 yd²	1209 yd²	938 yd²	872 yd²	530 yd²	177 yd²	2,470 yd²	6,340 yd²	110 yd²	23,850 yd²	26,235 yd²
MIRAFI 8XT GEOGRID	0 yd²	0 yd²	0 yd²	0 yd²	10989 yd²	0 yd²	0 yd²	0 yd²	0 yd²	0 yd²	0 yd²	4,165 yd²	15,154 yd²	16,670 yd²
GRANULAR FILL FOR REINFORCED ZONE	8000 yd³	17 yd³	3100 yd³	90 yd³	14100 yd³	1200 yd³	1300 yd³	650 yd³	280 yd³	2,900 yd³	6,800 yd³	6,400 yd³	44,837 yd³	49,321 yd³
DRAINAGE AND INFILL GRAVEL	400 yd³	11 yd³	241 yd³	41 yd³	581 yd³	70 yd³	82 yd³	62 yd³	25 yd³	278 yd³	329 yd³	297 yd³	297 yd³	327 yd³
LEVELING PAD CRUSHED STONE	45 yd³	3 yd³	29 yd³	13 yd³	44 yd³	11 yd³	12 yd³	8 yd³	6 yd³	35 yd³	23 yd³	46 yd³	2,417 yd³	2,659 yd³
4-INCH PERFORATED DRAINAGE PIPE	582 ft	38 ft	384 ft	166 ft	586 ft	144 ft	156 ft	108 ft	72 ft	470 ft	306 ft	616 ft	3,628 ft	3,991 ft
6-OZ NON-WOVEN GEOTEXTILE FABRIC	260 yd²	17 yd²	171 yd²	74 yd²	261 yd²	64 yd²	70 yd²	48 yd²	32 yd²	209 yd²	136 yd²	274 yd²	1,616 yd²	1,778 yd²


Project Number: AZ 2025
Engineered By: Alan E. Money

DRAWING TITLE: QUANTITY ESTIMATES	SHEET NUMBER: 5
PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Appendix B

(Verti-Block Wall Elevations)

Wall 1 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 1 ELEVATION VIEW-	SHEET NUMBER: 6
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 1 Elevation View

MATCHLINE STA. 11+25 (See Sheet S1)

MATCHLINE STA. 12+60 (See Sheet S3)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 1 ELEVATION VIEW–	SHEET NUMBER: 7
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com





Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A


PROFESSIONAL ENGINEER
No. 174267-2202
ALAN E. MONEY
STATE OF UTAH
May 14, 2025

Wall 1 Elevation View

MATCHLINE STA. 12+60 (See Sheet S2)



 LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT TALL 36-INCH TOP BLOCK	 MIRAFI 8XT GEOGRID
 36-INCH TOP BLOCK	 36-INCH BLOCK	 GEOGRID LENGTH (MINIMUM)	 MIRAFI 5XT GEOGRID
			 CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 1 ELEVATION VIEW–	SHEET NUMBER: 8
Engineered By: Alan E. Money		
Scale: 1”=10’-0”	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

PROFESSIONAL ENGINEER
No. 174267-2202
ALAN E. MONEY
STATE OF UTAH
May 14, 2025


Wall 1 Elevation View

MATCHLINE STA. 13+95 (See Sheet S3)

MATCHLINE STA. 15+30 (See Sheet S5)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
						CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 1 ELEVATION VIEW–	SHEET NUMBER: 9
Engineered By: Alan E. Money		
Scale: 1”=10’-0”	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com




Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

Wall 1 Elevation View

MATCHLINE STA. 15+30 (See Sheet S4)



 LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT TALL 36-INCH TOP BLOCK	 MIRAFI 8XT GEOGRID
 36-INCH TOP BLOCK	 36-INCH BLOCK	 GEOGRID LENGTH (MINIMUM)	 MIRAFI 5XT GEOGRID
			 CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 1 ELEVATION VIEW-	SHEET NUMBER: 10
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 2 Elevation View



	LEFT/RIGHT CORNER TOP BLOCK		1-FOOT LEFT/RIGHT CORNER TOP BLOCK		1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
	36-INCH TOP BLOCK		36-INCH BLOCK		GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 2 ELEVATION VIEW-	SHEET NUMBER: 11
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

Wall 3 Elevation View




LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 3 ELEVATION VIEW-	SHEET NUMBER: 12	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammtec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammtec.com	Engineered By: Alan E. Money	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Scale: 1"=10'-0"				PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT		


Wall 3 Elevation View

MATCHLINE STA. 31+25 (See Sheet S7)



MATCHLINE STA. 32+60 (See Sheet S9)

LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 3 ELEVATION VIEW-	SHEET NUMBER: 13
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC

CONSULTING ENGINEERING SERVICES

2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 3 Elevation View

MATCHLINE STA. 32+60 (See Sheet S8)

End Wall 3
STA. 33+84
TOW=8212.02
BOW=8212.02




LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 3 ELEVATION VIEW-	SHEET NUMBER: 14	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammttec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammttec.com	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	PROFESSIONAL ENGINEER No. 174267-2202 ALAN E. MONEY STATE OF UTAH 2025
Engineered By: Alan E. Money					
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT				

Wall 4 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
						CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 4 ELEVATION VIEW-	SHEET NUMBER: 15
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A


ALAN E. MONEY
May 14, 2025

Wall 4 Elevation View




LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 4 ELEVATION VIEW–	SHEET NUMBER: 16	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammtec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammtec.com		Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Engineered By: Alan E. Money						
Scale: 1"=10'-0"						
PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT						

Wall 5 Elevation View

ELEVATION (FEET)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 5 ELEVATION VIEW–	SHEET NUMBER: 17
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 5 Elevation View


MATCHLINE STA. 51+25 (See Sheet S12)

MATCHLINE STA. 52+60 (See Sheet S14)



Finish Grade at Toe of Wall (Typ.)

LEFT/RIGHT CORNER TOP BLOCK	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
36-INCH TOP BLOCK	36-INCH BLOCK	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
			CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 5 ELEVATION VIEW-	SHEET NUMBER: 18
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 5 Elevation View

MATCHLINE STA. 52+60 (See Sheet S13)

MATCHLINE STA. 53+95 (See Sheet S15)



LEFT/RIGHT CORNER TOP BLOCK	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
36-INCH TOP BLOCK	36-INCH BLOCK	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
			CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 5 ELEVATION VIEW-	SHEET NUMBER: 19
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 5 Elevation View

MATCHLINE STA. 53+95 (See Sheet S14)

MATCHLINE STA. 55+20 (See Sheet S16)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE	



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 5 ELEVATION VIEW-	SHEET NUMBER: 20
Engineered By: Alan E. Money		
Scale: 1"=10'-0"		
PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT		


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

Wall 5 Elevation View

MATCHLINE STA. 55+20 (See Sheet S16)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 5 ELEVATION VIEW-	SHEET NUMBER: 21
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 6 Elevation View



 LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT LEFT/ RIGHT CORNER TOP BLOCK	 1-FOOT TALL 36-INCH TOP BLOCK	 MIRAFI 8XT GEOGRID	
 36-INCH TOP BLOCK	 36-INCH BLOCK	 GEOGRID LENGTH (MINIMUM)	 MIRAFI 5XT GEOGRID	 CHANGE IN GEOGRID LENGTH/TYPE


SCALE 1" = 10'-0"

A horizontal scale bar with alternating black and white segments. Below the bar are numerical markers at 0, 5, 10, and 20, representing feet.

Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 6 ELEVATION VIEW-	SHEET NUMBER: 22
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
 2447 West 12th Street, Ste #1 Phone: 480 927-9696
 Tempe, Arizona 85281 Fax: 480 927-9797
 E-Mail: ammtec@ammtec.com www.ammtec.com

Prepared By: JAM/BMH
 Reviewed By: AEM
 Date: 05/14/25
 Revision: N/A




Wall 6 Elevation View

MATCHLINE STA. 60+85 (See Sheet S17)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 6 ELEVATION VIEW-	SHEET NUMBER: 23
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC

CONSULTING ENGINEERING SERVICES

2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

PROFESSIONAL ENGINEER

No. 174267-2202


ALAN E. MONEY

STATE OF UTAH


2025

Alan E. Money

Wall 7 Elevation View




LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 7 ELEVATION VIEW-	SHEET NUMBER: 24	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammtec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammtec.com	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	PROFESSIONAL ENGINEER No. 174267-2202 ALAN E. MONEY STATE OF UTAH 2025	
Engineered By: Alan E. Money						PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT
Scale: 1"=10'-0"						

Wall 7 Elevation View

MATCHLINE STA. 70+85 (See Sheet S19)



	LEFT/RIGHT CORNER TOP BLOCK		1-FOOT LEFT/RIGHT CORNER TOP BLOCK		1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
	36-INCH TOP BLOCK		36-INCH BLOCK		GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 7 ELEVATION VIEW-	SHEET NUMBER: 25
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 8 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/ RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 8 ELEVATION VIEW-	SHEET NUMBER: 26
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 9 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID	
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID	CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 9 ELEVATION VIEW-	SHEET NUMBER: 27
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 10 Elevation View



 LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT TALL 36-INCH TOP BLOCK	 MIRAFI 8XT GEOGRID	
 36-INCH TOP BLOCK	 36-INCH BLOCK	 GEOGRID LENGTH (MINIMUM)	 MIRAFI 5XT GEOGRID	 CHANGE IN GEOGRID LENGTH/TYPE

SCALE 1" = 10'-0"

A horizontal scale bar with a black and white checkerboard pattern. It is marked with the numbers 0, 5, 10, and 20, representing feet. The total length of the bar is 20 feet.

DRAWING TITLE: VERTI-BLOCK RETAINING WALLS
-WALL 10 ELEVATION VIEW-


PROJECT NAME: SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT

SHEET NUMBER:
28

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
 2447 West 12th Street, Ste #1 Phone: 480 927-9696
 Tempe, Arizona 85281 Fax: 480 927-9797
 E-Mail: ammttec@ammttec.com www.ammttec.com

Prepared By: JAM/BMH
 Reviewed By: AEM
 Date: 05/14/2015
 Revision: N/A


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A







Wall 10 Elevation View

MATCHLINE STA. 101+30 (See Sheet S23)

MATCHLINE STA. 102+65 (See Sheet S25)



 LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT LEFT/RIGHT CORNER TOP BLOCK	 1-FOOT TALL 36-INCH TOP BLOCK	 MIRAFI 8XT GEOGRID
 36-INCH TOP BLOCK	 36-INCH BLOCK	 GEOGRID LENGTH (MINIMUM)	 MIRAFI 5XT GEOGRID
			 CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 10 ELEVATION VIEW–	SHEET NUMBER: 29
Engineered By: Alan E. Money		
Scale: 1”=10’-0”	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 10 Elevation View

MATCHLINE STA. 102+65 (See Sheet S24)



MATCHLINE STA. 104+00 (See Sheet S26)

LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 10 ELEVATION VIEW-	SHEET NUMBER: 30
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 10 Elevation View

MATCHLINE STA. 104+00 (See Sheet S25)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 10 ELEVATION VIEW-	SHEET NUMBER: 31
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 11 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 11 ELEVATION VIEW-	SHEET NUMBER: 32
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 11 Elevation View

MATCHLINE STA. 111+30 (See Sheet S27)



MATCHLINE STA. 112+65 (See Sheet S29)

LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 11 ELEVATION VIEW-	SHEET NUMBER: 33
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 11 Elevation View

MATCHLINE STA. 112+65 (See Sheet S28)



LCT/RCT LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT 1-FOOT LEFT/ RIGHT CORNER TOP BLOCK	1' TOP 1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID	
TOP 36-INCH TOP BLOCK	36-INCH BLOCK	X.X' GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID	CHANGE IN GEOGRID LENGTH/TYPE




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS –WALL 11 ELEVATION VIEW–	SHEET NUMBER: 34
Engineered By: Alan E. Money		
Scale: 1”=10’-0”	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	


AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Wall 12 Elevation View



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 12 ELEVATION VIEW-	SHEET NUMBER: 35
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammttec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com


Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 12 Elevation View

MATCHLINE STA. 121+30 (See Sheet S30)

MATCHLINE STA. 122+65 (See Sheet S32)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 12 ELEVATION VIEW-	SHEET NUMBER: 36
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

Alan E. Money
May 14, 2025


Wall 12 Elevation View

MATCHLINE STA. 122+65 (See Sheet S31)



MATCHLINE STA. 124+00 (See Sheet S33)

LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE		




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 12 ELEVATION VIEW-	SHEET NUMBER: 37
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Wall 12 Elevation View

MATCHLINE STA. 124+00 (See Sheet S32)



MATCHLINE STA. 125+35 (See Sheet S34)

LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK		MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)		MIRAFI 5XT GEOGRID
							CHANGE IN GEOGRID LENGTH/TYPE



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 12 ELEVATION VIEW-	SHEET NUMBER: 38
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC

CONSULTING ENGINEERING SERVICES

2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com

Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A

PROFESSIONAL ENGINEER

No. 174267-2202


ALAN E. MONEY

STATE OF UTAH


2025

Wall 12 Elevation View

MATCHLINE STA. 125+35 (See Sheet S33)



LCT/RCT	LEFT/RIGHT CORNER TOP BLOCK	1' LCT 1' RCT	1-FOOT LEFT/RIGHT CORNER TOP BLOCK	1' TOP	1-FOOT TALL 36-INCH TOP BLOCK	MIRAFI 8XT GEOGRID
TOP	36-INCH TOP BLOCK		36-INCH BLOCK	X.X'	GEOGRID LENGTH (MINIMUM)	MIRAFI 5XT GEOGRID
					CHANGE IN GEOGRID LENGTH/TYPE	




Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 12 ELEVATION VIEW-	SHEET NUMBER: 39
Engineered By: Alan E. Money		
Scale: 1"=10'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	

AMMTec CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com


Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com

Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A



Appendix C

(Verti-Block Cross Sections)



Notes:

Typical Section Displayed

All other sections should adhere to these same specifications unless specifically indicated otherwise.

Excavation Safety

Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection

Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation

It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.

Section View - Wall 1

Scale: 1"=5'-0"

Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 1- PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	SHEET NUMBER: 40	AMMTec CONSULTANTS, PLLC <i>CONSULTING ENGINEERING SERVICES</i> 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammttec@ammttec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammttec.com	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A
Engineered By: Alan E. Money				
Scale: 1"=5'-0"				


Notes:

Typical Section Displayed
All other sections should adhere to these same specifications unless specifically indicated otherwise.


Excavation Safety
Soil excavation must be benched to meet OSHA compliance standards.


Retaining Wall Protection
Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation
It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.



Section View - Wall 2
Scale: 1"=2'-0"



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 2-	SHEET NUMBER: 41	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammtec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammtec.com		Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Engineered By: Alan E. Money						
Scale: 1"=2'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT					


Notes:

Typical Section Displayed
All other sections should adhere to these same specifications unless specifically indicated otherwise.


Excavation Safety
Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection
Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation
It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.




Section View - Wall 4
Scale: 1"=2'-0"



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 4-	SHEET NUMBER: 43	AMMTec CONSULTANTS, PLLC <i>CONSULTING ENGINEERING SERVICES</i> 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammtec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammtec.com	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Engineered By: Alan E. Money					
Scale: 1"=2'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT				

Section View - Walls 5 & 6

Scale: 1"=5'-0"



Notes:

Typical Section Displayed

All other sections should adhere to these same specifications unless specifically indicated otherwise.

Excavation Safety


Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection

Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation

It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.



Project Number: AZ 2025

Engineered By: Alan E. Money


Scale: 1"=5'-0"

DRAWING TITLE: VERTI-BLOCK RETAINING WALLS
-WALLS 5 & 6-

SHEET NUMBER:
44

PROJECT NAME: SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT

AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammtec@ammtec.com
Phone: 480 927-9696
Fax: 480 927-9797
www.ammtec.com
Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A




Notes:

Typical Section Displayed
All other sections should adhere to these same specifications unless specifically indicated otherwise.


Excavation Safety
Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection
Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation
It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.




Section View - Wall 7
Scale: 1"=4'-0"



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 7-	SHEET NUMBER: 45	AMMTec CONSULTANTS, PLLC <i>CONSULTING ENGINEERING SERVICES</i> 2447 West 12th Street, Ste #1 Tempe, Arizona 85281 E-Mail: ammttec@ammtec.com Phone: 480 927-9696 Fax: 480 927-9797 www.ammttec.com	Prepared By: JAM/BMH Reviewed By: AEM Date: 05/14/25 Revision: N/A	
Engineered By: Alan E. Money					
Scale: 1"=4'-0"	PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT				

It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.





SCALE 1" = 4'-0"

A horizontal scale bar with alternating black and white segments. Below the bar are numerical markers at 0, 2, 4, and 8, representing feet. The bar is divided into four equal segments, each representing 2 feet.

AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
 2447 West 12th Street, Ste #1 Phone: 480 927-9696
 Tempe, Arizona 85281 Fax: 480 927-9797
 E-Mail: ammtec@ammtec.com www.ammtec.com

Prepared By: JAM/BMH
 Reviewed By: AEM
 Date: 05/14/25
 Revision: N/A





Notes:

Typical Section Displayed

All other sections should adhere to these same specifications unless specifically indicated otherwise.

Excavation Safety


Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection

Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation

It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.



Project Number: AZ 2025

Engineered By: Alan E. Money


Scale: 1"=5'-0"


DRAWING TITLE: VERTI-BLOCK RETAINING WALLS
-WALLS 9, 10, & 12-

SHEET NUMBER:
47

PROJECT NAME: SUNDOWN CONDOS PHASE 2
6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT

AMMTEC CONSULTANTS, PLLC
CONSULTING ENGINEERING SERVICES
2447 West 12th Street, Ste #1
Tempe, Arizona 85281
E-Mail: ammttec@ammttec.com
Phone: 480 927-9696
Fax: 480 927-9797
www.ammttec.com
Prepared By: JAM/BMH
Reviewed By: AEM
Date: 05/14/25
Revision: N/A





Notes:

Typical Section Displayed

All other sections should adhere to these same specifications unless specifically indicated otherwise.

Excavation Safety


Soil excavation must be benched to meet OSHA compliance standards.

Retaining Wall Protection

Divert all surface water in a positive direction away from the wall. These protective measures should be implemented both during and after wall construction, and shall be maintained until all final drainage, landscaping, and paving work is finished.

Safety Barrier Recommendation

It is the responsibility the property owner to install a safety fence/barriers above the retaining wall. During fence/barrier installation, for properties, reactions, and utilities, contractor to maintain the integrity of Verti-Block members and related Geogrid systems and connections. AMMTEC should be contacted for any potential construction impacts to wall including surcharge additions prior to construction.



Project Number: AZ 2025	DRAWING TITLE: VERTI-BLOCK RETAINING WALLS -WALL 11-	SHEET NUMBER: 48	AMMTec CONSULTANTS, PLLC CONSULTING ENGINEERING SERVICES 2447 West 12th Street, Ste #1 Phone: 480 927-9696 Tempe, Arizona 85281 Fax: 480 927-9797 E-Mail: ammtec@ammtec.com www.ammtec.com		NO. 174207-2202 ALAN E. MONEY STATE OF UTAH MAR 14 2025			
Engineered By: Alan E. Money						PROJECT NAME: SUNDOWN CONDOS PHASE 2 6550 NORTH POWDER MOUNTAIN ROAD, EDEN, UT	Prepared By: JAM/BMH	Reviewed By: AEM
Scale: 1"=5'-0"							Date: 05/14/25	Revision: N/A


Appendix D

(Calculations - Static & Seismic)



REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 1 - 25 ft no SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	25.00 ft (23.75 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.25 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	30.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	4.28	FoS Overturning:	8.43
Bearing	3,119	FoS Bearing:	13.54
FoS Pullout	1.42 NG		
Total Pullout	147,999	FoS Total Pullout	15.07
Top FoSot:	12.77	FoS Connection:	1.93

ID	Height	Length	Name	Ta	Pa	TMax	FSStr	FSPo	FSSldg	GridEmbedment
11	22	18	5XT	1786	243	243	11.02	1.42/[243]	59.63	1.04
10	20	18	5XT	1786	304	304	8.82	4.21/[304]	30.04	2.31
9	18	18	5XT	1786	425	425	6.30	6.52/[425]	19.74	3.58
8	16	18	5XT	1786	547	547	4.90	8.84/[547]	14.63	4.84
7	14	18	5XT	1786	668	668	4.01	11.15/[668]	11.61	6.11
6	12	18	5XT	1786	790	790	3.39	13.47/[790]	9.62	7.38
5	10	18	5XT	1786	911	911	2.94	15.79/[911]	8.21	8.65
4	8	18	5XT	1786	1033	1033	2.59	18.10/[1033]	7.17	9.92
3	6	18	5XT	1786	1154	1154	2.32	20.42/[1154]	6.37	11.19
2	4	18	5XT	1786	1276	1276	2.10	22.73/[1276]	5.73	12.46
1	2	18	5XT	1786	1398	1398	1.92	25.05/[1398]	5.21 [4.28]	13.73


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional iner.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 2 - 6 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Infill Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
LvlPad / Drain Mat:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Crushed Stone Lvlng Pad			

GEOMETRY

Design Height:	6.00 ft	Live Load:	0.00 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	0.50 ft*	Live Load Width:	0.00 ft
Leveling Pad Depth:	0.50 ft		
Slope Angle:	0.0 deg	Dead Load:	0.0 lbf/ft ²
Slope Length:	20.0 ft	Dead Load Offset:	0.0 ft
Slope Toe Offset:	0.0 ft	Dead Load Width:	0.00 ft
Leveling Pad Width:	4.00 ft	D.L. Embedment:	0.00 ft

Vert δ on Single Dpth

* Note: For all designs the passive resistance in front of the wall units is ignored for sliding calculations.

FACTORS OF SAFETY

Sliding:	1.50	Overturning:	1.50
Bearing:	2.00		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

RESULTS

FoS Sliding: 2.75 (lvlpd) FoS Overturning: 3.59
 Bearing: 795.36 FoS Bearing: 12.52

Name	Elev.[dpth]	ka	Pa	PaT	FSsl	FoS OT	%D/H
TBLK	4.00[2.00]	0.254	64	64	20.54	19.62	150%
36	2.00[4.00]	0.219	219	219	8.36	7.18	75%
36	0.00[6.00]	0.219	493	493	2.75	3.59	50%

Design Approach:

The design is a 'top down' approach. The values shown in the table[ka, kae, Pa, etc.] are the values from the top of wall to the base of that row. For trial wedge analysis, the ka and kae are back-calculated from the Pa, Pae values.


Column Descriptions:

ka: active earth pressure coefficient
 Pa: active earth pressure
 Paq: live surcharge earth pressure
 Paq2: live load 2 surcharge earth pressure
 Paqd: dead surcharge earth pressure
 (PaC): reduction in load due to cohesion
 PaT: sum of all earth pressures
 FSsl(lvl Pad): factor of safety for sliding at each layer. (FS sliding below the leveling pad)
 FSot: factor of safety of overturning about the toe.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 3 - 19 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	19.00 ft (18.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	40.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	4.58	FoS Overturning:	9.39
Bearing	2,370	FoS Bearing:	14.37
FoS Pullout	1.84		
Total Pullout	63,145	FoS Total Pullout	11.13
Top FoSot:	12.77	FoS Connection:	2.48

ID	Height	Length	Name	Ta	Pa	TMax	FSStr	FSPo	FSSldg	GridEmbedment
8	16	14.5	5XT	1786	243	243	11.02	1.84/[243]	54.69	1.34
7	14	14.5	5XT	1786	304	304	8.82	4.77/[304]	27.08	2.61
6	12	14.5	5XT	1786	425	425	6.30	7.08/[425]	17.62	3.88
5	10	14.5	5XT	1786	547	547	4.90	9.40/[547]	12.98	5.15
4	8	14.5	5XT	1786	668	668	4.01	11.72/[668]	10.26	6.42
3	6	14.5	5XT	1786	790	790	3.39	14.03/[790]	8.48	7.69
2	4	14.5	5XT	1786	911	911	2.94	16.35/[911]	7.23	8.96
1	2	14.5	5XT	1786	1033	1033	2.59	18.66/[1033]	6.30 [4.58]	10.23

Column Descriptions:


- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 4 - 7 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36

SOIL PARAMETERS	Φ	coh	γ
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Infill Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
LvlPad / Drain Mat:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Crushed Stone Lvlng Pad			



GEOMETRY

Design Height:	7.00 ft	Live Load:	0.00 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	0.50 ft*	Live Load Width:	0.00 ft
Leveling Pad Depth:	0.50 ft		
Slope Angle:	16.0 deg	Dead Load:	0.0 lbf/ft ²
Slope Length:	50.0 ft	Dead Load Offset:	0.0 ft
Slope Toe Offset:	0.0 ft	Dead Load Width:	0.00 ft
Leveling Pad Width:	4.00 ft	D.L. Embedment:	0.00 ft

Vert δ on Single Dpth

* Note: For all designs the passive resistance in front of the wall units is ignored for sliding calculations.

FACTORS OF SAFETY

Sliding:	1.50	Overturning:	1.50
Bearing:	2.00		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

RESULTS

FoS Sliding: 2.12 (lvlpd) FoS Overturning: 2.50
 Bearing: 1119.50 FoS Bearing: 8.32

Name	Elev.[dpth]	ka	Pa	PaT	FSsl	FoS OT	%D/H
HSTB	6.00[1.00]	0.314	20	20	59.57	89.10	300%
36	4.00[3.00]	0.268	151	151	11.30	12.14	100%
36	2.00[5.00]	0.268	419	419	5.43	4.64	60%
36	0.00[7.00]	0.268	821	821	2.12	2.50	43%

Design Approach:

The design is a 'top down' approach. The values shown in the table[ka, kae, Pa, etc.] are the values from the top of wall to the base of that row. For trial wedge analysis, the ka and kae are back-calculated from the Pa, Pae values.

Column Descriptions:


ka: active earth pressure coefficient
 Pa: active earth pressure
 Paq: live surcharge earth pressure
 Paq2: live load 2 surcharge earth pressure
 Paqd: dead surcharge earth pressure
 (PaC): reduction in load due to cohesion
 PaT: sum of all earth pressures
 FSsl(lvl Pad): factor of safety for sliding at each layer. (FS sliding below the leveling pad)
 FSot: factor of safety of overturning about the toe.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 5a - 28 ft no SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36

SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		



GEOMETRY

Design Height:	28.00 ft (26.50 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.50 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	16.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	50.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	2.45	FoS Overturning:	4.78
Bearing	4.094	FoS Bearing:	12.23
FoS Pullout	2.98		
Total Pullout	294,131	FoS Total Pullout	18.97
Top FoSot:	4.91	FoS Connection:	1.58

ID	Height	Length	Name	Ta	Pa	TMax	FSStr	FSPo	FSSldg	GridEmbedment
12	24	23	5XT	1786	478	478	5.60	2.98/[478]	7.53	1.32
11	22	23	5XT	1786	459	459	5.84	7.95/[459]	6.44	2.88
10	20	23	5XT	1786	612	612	4.38	10.56/[612]	5.63	4.43
9	18	23	5XT	1786	765	765	3.50	12.91/[765]	4.99	5.99
8	16	23	5XT	1786	918	918	2.92	15.11/[918]	4.49	7.55
7	14	23	5XT	1786	1071	1071	2.50	17.24/[1071]	4.08	9.10
6	12	23	5XT	1786	1224	1224	2.19	19.32/[1224]	3.74	10.66
5	10	23	5XT	1786	1377	1377	1.95	21.36/[1377]	3.45	12.22
4	8	23	5XT	1786	1530	1530	1.75	23.39/[1530]	3.21	13.77
3	6	23	5XT	1786	1683	1683	1.59	25.39/[1683]	2.99	15.33
2	4	23	8XT	2812	1835	1835	2.30	27.39/[1835]	2.81	16.89
1	2	23	8XT	2812	1988	1988	2.12	29.47/[1988]	2.45 [2.47]	18.44


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional iner.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 5b - 28 ft w/wall 1 SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	28.00 ft (26.50 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.50 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	3,375 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	8.0 ft
Back Slope Length:	7.0 ft	Dead Load Width:	53.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	1.94	FoS Overturning:	3.92
Bearing	6,703	FoS Bearing:	6.52
FoS Pullout	1.78		
Total Pullout	535,968	FoS Total Pullout	44.85
Top FoSot:	6.18	FoS Connection:	1.55

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSstr	FSPo	FSSldg	GridEmbedment
12	24	23	8XT	2812	368	2277	2646	1.59	1.78/[2646]	8.42	1.32
11	22	23	8XT	2812	354	902	1256	3.36	8.67/[1256]	6.15	2.88
10	20	23	8XT	2812	472	1257	1729	2.44	10.27/[1729]	4.99	4.43
9	18	23	8XT	2812	590	1202	1792	2.35	14.13/[1792]	4.28	5.99
8	16	23	8XT	2812	707	1160	1867	2.26	17.98/[1867]	3.79	7.55
7	14	23	8XT	2812	825	1114	1940	2.17	21.92/[1940]	3.43	9.10
6	12	23	8XT	2812	943	1087	2030	2.08	25.69/[2030]	3.16	10.66
5	10	23	8XT	2812	1061	1058	2119	1.99	27.02/[2119]	2.94	12.22
4	8	23	8XT	2812	1179	1028	2208	1.91	28.47/[2208]	2.76	13.77
3	6	23	8XT	2812	1297	1021	2318	1.82	29.82/[2318]	2.60	15.33
2	4	23	8XT	2812	1415	991	2405	1.75	31.63/[2405]	2.47	16.89
1	2	23	8XT	2812	1533	959	2492	1.69	33.61/[2492]	2.22 [1.94]	18.44


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 6 - 12 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	12.00 ft (11.40 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	0.60 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	3,780 lbf/ft ²
Back Slope Angle:	6.0 deg	Dead Load Offset:	8.0 ft
Back Slope Length:	20.0 ft	Dead Load Width:	40.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	1.91	FoS Overturning:	5.97
Bearing	3,369	FoS Bearing:	9.49
FoS Pullout	18.90		
Total Pullout	102,262	FoS Total Pullout	49.73
Top FoSot:	5.75	FoS Connection:	3.19

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSstr	FSPo	FSSldg	GridEmbedment
4	8	16.5	5XT	1786	345	372	718	3.73	30.14/[718]	3.78	5.34
3	6	16.5	5XT	1786	331	922	1253	2.14	18.90/[1253]	2.84	7.38
2	4	16.5	5XT	1786	442	815	1256	2.13	21.17/[1256]	2.34	9.42
1	2	16.5	5XT	1786	552	735	1288	2.08	23.57/[1288]	2.03 [1.91]	11.46


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 7 - 14 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft2	120 lbf/ft3
Retained Soil:	34 deg	0 lbf/ft2	125 lbf/ft3
Foundation Soil:	34 deg	0 lbf/ft2	110 lbf/ft3
Leveling Pad:	40 deg	0 lbf/ft2	135 lbf/ft3
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	14.00 ft (13.00 ft Exp.)	Live Load:	0 lbf/ft2
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft2
Back Slope Angle:	24.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	30.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	2.06	FoS Overturning:	4.10
Bearing	2,232	FoS Bearing:	12.80
FoS Pullout	2.24		
Total Pullout	35,024	FoS Total Pullout	7.32
Top FoSot:	3.98	FoS Connection:	2.14

ID	Height	Length	Name	Ta	Pa	TMax	FSstr	FSPo	FSSldg	GridEmbedment
5	10	13.5	5XT	1786	590	590	4.54	2.24/[590]	4.99	1.41
4	8	13.5	5XT	1786	566	566	4.73	6.29/[566]	4.14	3.23
3	6	13.5	5XT	1786	755	755	3.55	8.48/[755]	3.54	5.05
2	4	13.5	5XT	1786	944	944	2.84	10.43/[944]	3.09	6.86
1	2	13.5	5XT	1786	1133	1133	2.36	12.26/[1133]	2.75 [2.06]	8.68


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 8 - 13 ft
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	13.00 ft (12.35 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	0.65 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	20.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	4.93	FoS Overturning:	10.40
Bearing	1,636	FoS Bearing:	14.86
FoS Pullout	1.58		
Total Pullout	17,138	FoS Total Pullout	6.45
Top FoSot:	12.77	FoS Connection:	3.61

ID	Height	Length	Name	Ta	Pa	TMax	FSstr	FSPo	FSSldg	GridEmbedment
5	10	10.5	5XT	1786	243	243	11.02	1.58/[243]	48.98	1.15
4	8	10.5	5XT	1786	304	304	8.82	4.42/[304]	23.66	2.42
3	6	10.5	5XT	1786	425	425	6.30	6.73/[425]	15.18	3.69
2	4	10.5	5XT	1786	547	547	4.90	9.05/[547]	11.08	4.96
1	2	10.5	5XT	1786	668	668	4.01	11.37/[668]	8.70 [4.93]	6.23


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 9a - 12 ft no SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	12.00 ft (11.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	12.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	30.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	3.05	FoS Overturning:	6.06
Bearing	1,640	FoS Bearing:	14.32
FoS Pullout	1.67		
Total Pullout	13,626	FoS Total Pullout	5.14
Top FoSot:	5.27	FoS Connection:	3.33

ID	Height	Length	Name	Ta	Pa	TMax	FSstr	FSPo	FSSldg	GridEmbedment
4	8	10	5XT	1786	445	445	6.02	1.67/[445]	12.62	1.25
3	6	10	5XT	1786	427	427	6.27	5.00/[427]	8.63	2.69
2	4	10	5XT	1786	570	570	4.70	7.20/[570]	6.55	4.12
1	2	10	5XT	1786	712	712	3.76	9.33/[712]	5.27 [3.05]	5.56


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 9b - 12 ft with Walls 12 and 10 SCs
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	12.00 ft (11.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	1,910 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	20.0 ft
Back Slope Length:	10.0 ft	Dead Load Width:	45.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	4.13	FoS Overturning:	8.61
Bearing	1,506	FoS Bearing:	15.45
FoS Pullout	1.65		
Total Pullout	11,721	FoS Total Pullout	5.18
Top FoSot:	6.18	FoS Connection:	3.90

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSStr	FSPo	FSSldg	GridEmbedment
4	8	9.5	5XT	1786	380	0	380	7.05	1.65/[380]	25.62	1.42
3	6	9.5	5XT	1786	365	0	365	7.35	4.90/[365]	14.81	2.69
2	4	9.5	5XT	1786	486	0	486	5.51	7.22/[486]	10.28	3.96
1	2	9.5	5XT	1786	608	0	608	4.41	9.54/[608]	7.84 [4.13]	5.23


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 10 - 13 ft with Condo SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	13.00 ft (12.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	1,890 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	13.0 ft
Back Slope Length:	12.0 ft	Dead Load Width:	14.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	2.25	FoS Overturning:	3.77
Bearing	2,005	FoS Bearing:	10.74
FoS Pullout	1.57		
Total Pullout	17,122	FoS Total Pullout	6.45
Top FoSot:	12.77	FoS Connection:	3.61

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSstr	FSPo	FSSldg	GridEmbedment
5	10	10.5	5XT	1786	243	0	243	11.02	1.57/[243]	42.32	1.14
4	8	10.5	5XT	1786	304	0	304	8.82	4.41/[304]	8.75	2.42
3	6	10.5	5XT	1786	425	0	425	6.30	6.73/[425]	5.15	3.69
2	4	10.5	5XT	1786	547	0	547	4.90	9.04/[547]	4.34	4.96
1	2	10.5	5XT	1786	668	0	668	4.01	11.36/[668]	3.72 [2.25]	6.23


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 11 - 29 ft no SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	29.00 ft (27.55 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.45 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	0 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	0.0 ft
Back Slope Length:	45.0 ft	Dead Load Width:	0.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	4.29	FoS Overturning:	8.55
Bearing	3,596	FoS Bearing:	13.75
FoS Pullout	2.05		
Total Pullout	248,230	FoS Total Pullout	18.79
Top FoSot:	12.77	FoS Connection:	1.71

ID	Height	Length	Name	Ta	Pa	TMax	FSStr	FSPo	FSSldg	GridEmbedment
13	26	21	5XT	1786	243	243	11.02	2.05/[243]	63.94	1.50
12	24	21	5XT	1786	304	304	8.82	5.05/[304]	32.63	2.77
11	22	21	5XT	1786	425	425	6.30	7.36/[425]	21.59	4.04
10	20	21	5XT	1786	547	547	4.90	9.68/[547]	16.07	5.31
9	18	21	5XT	1786	668	668	4.01	12.00/[668]	12.78	6.58
8	16	21	5XT	1786	790	790	3.39	14.31/[790]	10.61	7.84
7	14	21	5XT	1786	911	911	2.94	16.63/[911]	9.08	9.11
6	12	21	5XT	1786	1033	1033	2.59	18.94/[1033]	7.93	10.38
5	10	21	5XT	1786	1154	1154	2.32	21.26/[1154]	7.05	11.65
4	8	21	5XT	1786	1276	1276	2.10	23.57/[1276]	6.35	12.92
3	6	21	5XT	1786	1398	1398	1.92	25.89/[1398]	5.77	14.19
2	4	21	5XT	1786	1519	1519	1.76	28.21/[1519]	5.30	15.46
1	2	21	5XT	1786	1641	1641	1.63	30.52/[1641]	4.40 [4.29]	16.73


Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional iner.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 12a - 20 ft with Wall 10 SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	20.00 ft (19.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	1,755 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	8.0 ft
Back Slope Length:	8.0 ft	Dead Load Width:	25.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	2.07	FoS Overturning:	4.21
Bearing	3.826	FoS Bearing:	8.59
FoS Pullout	2.37		
Total Pullout	133,344	FoS Total Pullout	22.18
Top FoSot:	6.18	FoS Connection:	1.96

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSStr	FSPo	FSSldg	GridEmbedment
8	16	17	5XT	1786	363	550	914	2.93	2.37/[914]	7.00	1.05
7	14	17	5XT	1786	349	217	565	4.74	10.79/[565]	5.41	2.67
6	12	17	5XT	1786	465	542	1007	2.66	10.67/[1007]	4.56	4.29
5	10	17	5XT	1786	581	514	1096	2.45	13.78/[1096]	4.01	5.91
4	8	17	5XT	1786	698	485	1182	2.27	15.45/[1182]	3.62	7.52
3	6	17	5XT	1786	814	453	1267	2.12	17.49/[1267]	3.32	9.14
2	4	17	5XT	1786	930	434	1364	1.96	19.61/[1364]	3.08	10.76
1	2	17	5XT	1786	1046	415	1461	1.83	21.95/[1461]	2.25 [2.07]	12.38

Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkc, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

REA Analysis

Project: Sundown Condos Phase 2
 Location: 6550 North Powder Mountain Road
 Designer: JAM
 Date: 4/21/2025
 Section: Wall 12b - 20 ft with Wall 11 SC
 Design Method: NCMA_09_3rd_Ed, Ignore Vert. Force
 Design Unit: VertiBlock 4.0: 36



SOIL PARAMETERS	Φ	coh	γ
Reinforced Soil:	30 deg	0 lbf/ft ²	120 lbf/ft ³
Retained Soil:	34 deg	0 lbf/ft ²	125 lbf/ft ³
Foundation Soil:	34 deg	0 lbf/ft ²	110 lbf/ft ³
Leveling Pad:	40 deg	0 lbf/ft ²	135 lbf/ft ³
Leveling Pad:	Crushed Stone		

GEOMETRY

Design Height:	20.00 ft (19.00 ft Exp.)	Live Load:	0 lbf/ft ²
Wall Batter/Tilt:	5.20/ 0.00 deg	Live Load Offset:	0.00 ft
Embedment:	1.00 ft	LL2 Width:	0 ft
Leveling Pad Depth:	0.50 ft	Dead Load:	3,915 lbf/ft ²
Back Slope Angle:	0.0 deg	Dead Load Offset:	8.0 ft
Back Slope Length:	8.0 ft	Dead Load Width:	49.00 ft
Back Slope Toe Offset:	0.0 ft		
Vertical δ on Single Depth			

FACTORS OF SAFETY

Sliding:	1.50	Pullout:	1.50
Overturning:	2.00	Tension/Uncertainties:	1.50
Bearing:	2.00	Connection:	1.50
Unit/Unit Shear:	1.50		

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional engineer.

Verti-Block. Retaining Walls

RESULTS

FoS Sliding:	2.06	FoS Overturning:	4.77
Bearing	4.935	FoS Bearing:	7.07
FoS Pullout	2.66		
Total Pullout	222,468	FoS Total Pullout	38.44
Top FoSot:	6.18	FoS Connection:	1.94

ID	Height	Length	Name	Ta	Pa	DL	TMax	FSstr	FSPo	FSSldg	GridEmbedment
8	16	18	8XT	2812	350	1182	1532	2.75	2.66/[1532]	5.35	1.01
7	14	18	8XT	2812	336	465	801	5.27	14.73/[801]	3.99	2.75
6	12	18	8XT	2812	448	1213	1660	2.54	12.22/[1660]	3.30	4.50
5	10	18	8XT	2812	560	1131	1690	2.50	17.48/[1690]	2.87	6.25
4	8	18	8XT	2812	671	1068	1740	2.42	18.78/[1740]	2.58	8.00
3	6	18	8XT	2812	783	1031	1815	2.32	20.11/[1815]	2.36	9.75
2	4	18	8XT	2812	895	963	1859	2.27	22.12/[1859]	2.19	11.50
1	2	18	8XT	2812	1007	923	1930	2.18	24.08/[1930]	2.06 [2.10]	13.25

Column Descriptions:

- Ta: allowable geogrid strength
- Rc %: percent coverage for geosynthetics
- EP (Pa) internal active earth pressure
- LL (Pql) earth pressure due to live load surcharge
- DL (Pqd) earth pressure due to dead load surcharge
- Tmax maximum earth pressure on geosynthetic layer
- FSstr factor of safety on geogrid strength (LTDS/Tmax)
- Ta cn allowable tension on the connection
- FS Pkcn, factor of safety on the connection (PkCn/Tmax)
- FS PO, factor of safety on pullout (Pullout/(Tmax - LL)
- Grid Embedment, depth of embedment beyond the theoretical failure plane.

Note: Calculations and quantities are for PRELIMINARY ANALYTICAL USE ONLY and MUST NOT be used for design or construction without the independent review, verification, and approval by a qualified professional ineer.


Appendix E

(Global Stability - Static & Seismic)







Project	Sundown Condos Phase 2		
Group	Walls 1 and 5b Static	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




	Project		Sundown Condos Phase 2	
	Group	Walls 1 and 5b Seismic	Scenario	Master Scenario
	Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd
	SLIDEINTERPRET 9.038			




	Project		Sundown Condos Phase 2	
	Group	Wall 2 Static	Scenario	Master Scenario
	Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd
	SLIDEINTERPRET 9.038			




Project	Sundown Condos Phase 2		
Group	Wall 2 Seismic	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




 SLIDEINTERPRET 9.038	Project		Sundown Condos Phase 2	
	Group	Wall 3 Static	Scenario	Master Scenario
	Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




 SLIDEINTERPRET 9.038	Project		Sundown Condos Phase 2	
	Group	Wall 3 Seismic	Scenario	Master Scenario
	Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




Project	Sundown Condos Phase 2		
Group	Wall 4 Static	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




 SLIDEINTERPRET 9.038	Project		Sundown Condos Phase 2	
	Group	Wall 4 Seismic	Scenario	Master Scenario
	Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




Project	Sundown Condos Phase 2		
Group	Walls 5a and 6 Static	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




Project	Sundown Condos Phase 2		
Group	Walls 5a and 6 Seismic	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd




Project	Sundown Condos Phase 2		
Group	Wall 7 Static	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd







Project	Sundown Condos Phase 2		
Group	Wall 8 Static	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd





Project	Sundown Condos Phase 2		
Group	Wall 8 Seismic	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd





Project	Sundown Condos Phase 2		
Group	Walls 9,10, and 12a Seismic	Scenario	Master Scenario
Drawn By	JAM	Company	AMMTEC Consultants, PLLC.
Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd





 CONSULTING ENGINEERING SERVICES	Project		Sundown Condos Phase 2	
	Group		Walls 11 and 12b Seismic	Scenario
				Master Scenario
	Drawn By		JAM	Company
				AMMTEC Consultants, PLLC.
	Date	4/29/2025, 10:26:18 AM	File Name	Slope Stability Analysis.slmd

SLIDEINTERPRET 9.038