

1497 West 40 South Lindon, Utah - 84042 Phone (801) 225-5711 3662 West 2100 South Salt Lake City, Utah - 84120 Phone (801) 787-9138 1596 W. 2650 S. #108 **Ogden, Utah - 84401** Phone (801) 399-9516

Geotechnical Study Bill Rules Residence 4033 East Nordic Valley Drive Liberty, Utah

Project No. 177075

November 29, 2017

Prepared For:

Mr. Bill Rules 1700 West 2700 North, #33 Pleasant View, UT 84404

Prepared By:

EARTHTEC ENGINEERING
Ogden Office



TABLE OF CONTENTS

1.0	E>	KECUTIVE SUMMARY	
2.0	IN:	TRODUCTION	
3.0	PF	ROPOSED CONSTRUCTION	
4.0	GE 4.1 4.2	ENERAL SITE DESCRIPTIONSite DescriptionGeologic Setting	. 2
5.0	SL 5.1	JBSURFACE EXPLORATIONSoil Exploration	
6.0	LA	BORATORY TESTING	. 4
7.0	7.1 7.2	JBSURFACE CONDITIONSSoil TypesGroundwater Conditions	. 4
8.0	SI	TE GRADING	
	8.1 8.2 8.3 8.4 8.5	General Site Grading Temporary Excavations Fill Material Composition Fill Placement and Compaction Stabilization Recommendations	. 5
9.0	9.1 9.2 9.3	ISMIC AND GEOLOGIC CONSIDERATIONSSeismic DesignFaulting	. 8
10.	10.1 10.2 10.3	OUNDATIONSGeneralStrip/Spread FootingsEstimated SettlementsLateral Earth Pressures	. 9 10 10
11.0		OOR SLABS AND FLATWORK	
12.0	DR 12.1	Surface Drainage	12 12
13.0		OPE STABILITY1	
14.(NERAL CONDITIONS	



TABLE OF CONTENTS (CONTINUED)

TABLES	
Table 1: Lab	oratory Test Results
Table 2: Stru	uctural Fill Recommendations
Table 3: Fre	e-Draining Fill Recommendations
	sign Acceleration for Short Period
Table 5: Late	eral Earth Pressures (Static and Dynamic)
	7
ATTACHED I	FIGURES
No. 1	VICINITY MAP
No. 2	AERIAL PHOTOGRAPH SHOWING LOCATION OF TEST PITS AND
	SLOPE STABILITY CROSS-SECTION
Nos. 3 – 4	TEST PIT LOGS
No. 5	LEGEND
No. 6	CONSOLIDATION-SWELL TEST
No. 7	DIRECT SHEAR TEST
No 8 - 9	STARII TV DESLII TS



1.0 EXECUTIVE SUMMARY

This entire report presents the results of Earthtec Engineering's completed geotechnical study for the Bill Rules Residence in Liberty, Utah. This executive summary provides a general synopsis of our recommendations and findings. Details of our findings, conclusions, and recommendations are provided within the body of this report.

- The subject property is approximately 1 acre and is proposed to be developed with the construction of a single-family residence. The proposed structure will consist of conventionally framed, two-story residence with a basement. We anticipate foundation loads for the proposed structure will not exceed 5,000 pounds per linear foot for bearing wall, 30,000 pounds for column loads, and 100 pounds per square foot for floor slabs. (see Section 3)
- Our field exploration included the excavation of two (2) test pits to depths of 9 to 12 feet below the existing ground surface. Groundwater was not encountered within the excavations at the depths explored. (see Section 5)
- The native soils have a slight potential for expansion (heave) and a slight potential for compressibility under increased moisture contents and anticipated load conditions. (see Section 6)
- The subsurface soils encountered generally consisted of topsoil overlying near-surface stiff
 to very stiff clay and silt, and dense to very dense sand. All topsoil should be removed
 beneath the entire building footprints, exterior flatwork, and pavements prior to construction.
 (see Section 7)
- Conventional strip and spread footings may be used to support the structure, with foundations placed entirely on a minimum 18 inches of properly placed, compacted, and tested structural fill extending to undisturbed native soils. (see Section 10)

Based on the results of our field exploration, laboratory testing, and engineering analyses, it is our opinion that the subject site may be suitable for the proposed development, provided the recommendations presented in this report are followed and implemented during design and construction.

Failure to consult with Earthtec Engineering (Earthtec) regarding any changes made during design and/or construction of the project from those discussed herein relieves Earthtec from any liability arising from changed conditions at the site. We also strongly recommend that Earthtec observes the building excavations to verify the adequacy of our recommendations presented herein, and that Earthtec performs materials testing and special inspections for this project to provide continuity during construction.



Project No.: 177075

2.0 INTRODUCTION

The project is located at approximately 4033 East Nordic Valley Drive in Liberty, Utah. The general location of the site is shown on Figure No. 1, *Vicinity Map* and Figure No. 2, *Aerial Photograph Showing Location of Test Pits and Slope Stability Cross-section*, at the end of this report. The purposes of this study are to:

- Evaluate the subsurface soil conditions at the site.
- Assess the engineering characteristics of the subsurface soils, and
- Provide geotechnical recommendations for general site grading and the design and construction of foundations, and concrete floor slabs.

The scope of work completed for this study included field reconnaissance, subsurface exploration, field and laboratory soil testing, geotechnical engineering analysis, and the preparation of this report.

3.0 PROPOSED CONSTRUCTION

We understand that the proposed project, as described to us by Mr. Bill Rules, consists of developing the approximately 1-acre existing parcel with a residence. The proposed structure will consist of conventionally framed, two-story residence with a basement. We have based our recommendations in this report on the anticipated foundation loads for the proposed structures will not exceed 5,000 pounds per linear foot for bearing wall, 30,000 pounds for column loads, and 100 pounds per square foot for floor slabs. If structural loads will be greater Earthtec should be notified so that we may review our recommendations and make modifications, if necessary.

In addition to the construction described above, we anticipate that

- Utilities will be installed to service the proposed building, and
- Exterior concrete flatwork will be placed in the form of curb, gutter, sidewalks, and a driveway.

4.0 GENERAL SITE DESCRIPTION

4.1 Site Description

At the time of our subsurface exploration the site was an undeveloped lot partially vegetated with scrub oak trees. The future house and septic system areas were cleared from trees. The site is densely vegetated with scrub oak trees with a steep slope toward north. The ground surface appears to slope more than 15 percent grade, we anticipate up to 3 feet of cut and fill may be required for site grading. The lot was bounded on the north by Nordic Valley Drive and partially undeveloped land, on the east and west by developed residential lots, and on the south



Project No.: 177075

by partially developed lots.

4.2 Geologic Setting

The subject property is located in the foothill on northwest side of Ogden Valley. The subject lot is between approximately 5,245 and 5,330 feet above sea level. These foothills start form the southwestern margin of the Ogden Valley, a northwest to southeast trending valley located between the Wasatch Mountains to the west and the southern end of the Bear River Range to the east. The Ogden Valley is part of the Wasatch Hinterlands Section of the Middle Rocky Mountain Physiographic Province. Stokes describes the Wasatch Hinterlands as a belt of mixed, moderately rugged topography located on the east side of the Wasatch Range that has varied topography, with hilly areas dominating valley areas. The Ogden Valley is currently occupied by Pineview Reservoir, a manmade lake formed by damming the Ogden River and several of its tributaries, as well as the towns of Huntsville, Eden, and Liberty.

The Ogden Valley was prehistorically occupied by an arm of Lake Bonneville, a Pleistocene age, fresh water lake that covered most of northwestern Utah and parts of northeastern Nevada. Sediment deposited by the lake are still present within portions of the valley and at places within the foothills surrounding the valley below the elevation of the high stand of the lake which was between approximately 5,170 and 5,200 feet above sea level. The Great Salt Lake of northwestern Utah is a remnant of ancient Lake Bonneville.

The subject lot has a north facing slope of approximately 30% across the site, in an area mapped by Coogan and King 20161 to be Norwood Formation (lower Oligocene and upper Eocene) – Typically light-gray to light-brown altered tuff (claystone), altered tuffaceous siltstone and sandstone, and conglomerate; locally colored light shades of red and green; variable calcareous cement and zeolitization; involved in numerous landslides of various sizes.

5.0 SUBSURFACE EXPLORATION

5.1 Soil Exploration

Under the direction of a qualified member of our geotechnical staff, subsurface explorations were conducted at the site on November 1, 2017 by the excavation of two (2) test pits to depths of 9 to 12 feet below the existing ground surface using a a rubber-tire backhoe. The approximate locations of the test pits are shown on Figure No. 2, *Aerial Photograph Showing Location of Test Pits and Slope Stability Cross-section*. Graphical representations and detailed descriptions of the soils encountered are shown on Figure Nos. 3 through 4, *Test Pit Log* at the end of this report. The stratification lines shown on the logs represent the approximate boundary between soil units; the actual transition may be gradual. Due to potential natural

¹ Utah Geological Survey OFR 653: Interim geologic map of the Ogden 30' x 60' quadrangle, Weber, Box Elder, Cache, Davis, Morgan, Rich, and Summit Counties, Utah, and Uinta County, Wyoming by by James C. Coogan and Jon K. King 2016.



Project No.: 177075

variations inherent in soil deposits, care should be taken in interpolating between and extrapolating beyond exploration points. A key to the symbols and terms on the logs is presented on Figure No. 5, *Legend*.

Disturbed bag samples and relatively undisturbed block samples were collected at various depths in each test pit.

The soil samples collected were classified by visual examination in the field following the guidelines of the Unified Soil Classification System (USCS). The samples were transported to our Ogden, Utah laboratory where they will be retained for 30 days following the date of this report and then discarded, unless a written request for additional holding time is received prior to the 30-day limit.

6.0 LABORATORY TESTING

Representative soil samples collected during our field exploration were tested in the laboratory to assess pertinent engineering properties and to aid in refining field classifications, if needed. Tests performed included natural moisture content, dry density test, liquid and plastic limits determinations, mechanical (partial) gradation analyses, and one-dimensional consolidation test. The table below summarizes the laboratory test results, which are also included on the attached *Test Pit Logs* at the respective sample depths, on Figure Nos. 3 and 4, and *Consolidation-Swell Test*, on Figure No. 6.

Table 1: Laboratory Test Results

		2200	Natural	Atterb	erg Limits	Grain S			
Test Pit No.	Depth (ft.)	Natural Moisture (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	Gravel (+ #4)	Sand	Silt/Clay (- #200)	Soil Type
1	4	14				8	21	71	ML
1	6	13	ansassan Sistema	58	26	1	54	45	SM
2	8	18	104	47	22	6	38	56	CL
2	10	14	102	41	8	4	50	46	SM

NP* = Non-Plastic

As part of the consolidation test procedure, water was added to a sample to assess moisture sensitivity when the sample was loaded to an equivalent pressure of approximately 1,000 psf. The native clay and silt soils have a slight potential for expansion (heave) and a slight potential for compressibility under increased moisture contents and anticipated load conditions.

7.0 SUBSURFACE CONDITIONS

7.1 Soil Types

On the surface of the site, we encountered topsoil which is estimated to extend about one foot



Project No.: 177075

in depth at the test pit locations. Below the topsoil we encountered layers of clay, silt, and sand extending to depths of 9 to 12 feet below the existing ground surface. Graphical representations and detailed descriptions of the soils encountered are shown on Figure Nos. 3 through 4, *Test Pit Log* at the end of this report. Based on our experience and observations during field exploration, the clay and silt soils visually ranged from stiff to very stiff in consistency and the sand soils visually had a relative density varying from dense to very dense.

7.2 Groundwater Conditions

Groundwater was not encountered within the excavations at the depths explored. Note that groundwater levels will fluctuate in response to the season, precipitation, snow melt, irrigation, and other on and off-site influences. Quantifying these fluctuations would require long term monitoring, which is beyond the scope of this study. The contractor should be prepared to dewater excavations as needed.

8.0 SITE GRADING

8.1 General Site Grading

All surface vegetation and unsuitable soils (such as topsoil, organic soils, undocumented fill, soft, loose, or disturbed native soils, and any other inapt materials) should be removed from below foundations, floor slabs, exterior concrete flatwork, and pavement areas. We encountered topsoil on the surface of the site. The topsoil (including soil with roots larger than about ¼ inch in diameter) should be completely removed, even if found to extend deeper, along with any other unsuitable soils that may be encountered. Over-excavations below footings and slabs also may be needed, as discussed in Section 10.0.

Fill placed over large areas, even if only a few feet in depth, can cause consolidation in the underlying native soils resulting in settlement of the fill. Because there is more than 14 feet of relief from north to south in the building area, we anticipate that more than 3 feet of fill may be placed in some areas of the site during grading. If more than 3 feet of grading fill will be placed above the existing surface (to raise site grades), Earthtec should be notified so that we may provide additional recommendations, if required. Such recommendations will likely include placing the fill several weeks (or possibly more) prior to construction to allow settlement to occur.

8.2 <u>Temporary Excavations</u>

Temporary excavations that are less than 4 feet in depth and above groundwater should have side slopes no steeper than ½H:1V (Horizontal:Vertical). Temporary excavations where water is encountered in the upper 4 feet or that extend deeper than 4 feet below site grades should be sloped or braced in accordance with OSHA² requirements for Type B soils.

² OSHA Health And Safety Standards, Final Rule, CFR 29, part 1926.



Project No.: 177075

8.3 <u>Fill Material Composition</u>

The native soils within the upper 10 feet are not suitable for use as placed and compacted structural fill. Excavated soils, including clay and silt, may be stockpiled for use as fill in landscape areas.

Structural fill is defined as fill material that will ultimately be subjected to any kind of structural loading, such as those imposed by footings, floor slabs, pavements, etc. We recommend that a professional engineer or geologist verify that the structural fill to be used on this project meets the requirements, stated below. We recommend that structural fill consist of imported sandy/gravelly soils meeting the following requirements in the table below:

Table 2: Structural Fill Recommendations

Sieve Size/Other	Percent Passing (by weight					
4 inches	100					
3/4 inches	70 – 100					
No. 4	40 – 80					
No. 40	15 – 50					
No. 200	0 – 20					
Liquid Limit	35 maximum					
Plasticity Index	15 maximum					

In some situations, particles larger than 4 inches and/or more than 30 percent coarse gravel may be acceptable, but would likely make compaction more difficult and/or significantly reduce the possibility of successful compaction testing. Consequently, stricter quality control measures than normally used may be required, such as using thinner lifts and increased or full-time observation of fill placement.

We recommend that utility trenches below any structural load be backfilled using structural fill. Note that most local governments and utility companies require Type A-1-a or A-1-b (AASHTO classification) soils (which overall is stricter than our recommendations for structural fill) be used as backfill above utilities in certain areas. In other areas or situations, utility trenches may be backfilled with the native soil, but the contractor should be aware that native clay and silt soils (as observed in the explorations) may be time consuming to compact due to potential difficulties in controlling the moisture content needed to obtain optimum compaction. All backfill soil should have a maximum particle size of 4 inches, a maximum Liquid Limit of 35 and a maximum Plasticity Index of 15.

If required (i.e. fill in submerged areas), we recommend that free draining granular material (clean sand and/or gravel) meet the following requirements in the table below:



Project No.: 177075

Table 3: Free-Draining Fill Recommendations

Sieve Size/Other	Percent Passing (by weight)
3 inches	100
No. 10	0 – 25
No. 40	0 – 15
No. 200	0 – 5
Plasticity Index	Non-plastic

Three-inch minus washed rock (sometimes called river rock or drain rock) and pea gravel materials usually meet these requirements and may be used as free draining fill. If free draining fill will be placed adjacent to soil containing a significant amount of sand or silt/clay, precautions should be taken to prevent the migration of fine soil into the free draining fill. Such precautions should include either placing a filter fabric between the free draining fill and the adjacent soil material, or using a well-graded, clean filtering material approved by the geotechnical engineer.

8.4 Fill Placement and Compaction

Fill should be placed on level, horizontal surfaces. Where fill will be placed on existing slopes steeper than 5H:1V, the existing ground should be benched prior to placing fill. We recommend bench heights of 1 to 4 feet, with the lowest bench being a minimum 3 feet below adjacent grade and at least 10 feet wide.

The thickness of each lift should be appropriate for the compaction equipment that is used. We recommend a maximum lift thickness prior to compaction of 4 inches for hand operated equipment, 6 inches for most "trench compactors" and 8 inches for larger rollers, unless it can be demonstrated by in-place density tests that the required compaction can be obtained throughout a thicker lift. The full thickness of each lift of structural fill placed should be compacted to at least the following percentages of the maximum dry density, as determined by ASTM D-1557:

In landscape and other areas not below structurally loaded areas:
Less than 5 feet of fill below structurally loaded areas:
Greater than 5 feet of fill below structurally loaded areas:
98%

Generally, placing and compacting fill at moisture contents within ± 2 percent of the optimum moisture content, as determined by ASTM D-1557, will facilitate compaction. Typically, the further the moisture content deviates from optimum the more difficult it will be to achieve the required compaction.

Fill should be tested frequently during placement and we recommend early testing to demonstrate that placement and compaction methods are achieving the required compaction. The contractor is responsible to ensure that fill materials and compaction efforts are consistent so that tested areas are representative of the entire fill.



Project No.: 177075

8.5 Stabilization Recommendations

Near surface layers of clay, silt, and silty sand soils may rut and pump during grading and construction. The likelihood of rutting and/or pumping, and the depth of disturbance, is proportional to the moisture content in the soil, the load applied to the ground surface, and the frequency of the load. Consequently, rutting and pumping can be minimized by avoiding concentrated traffic, minimizing the load applied to the ground surface by using lighter equipment, partially loaded equipment, tracked equipment, by working in dry times of the year, and/or by providing a working surface for equipment.

During grading the soil in any obvious soft spots should be removed and replaced with granular material. If rutting or pumping occurs traffic should be stopped in the area of concern. The soil in rutted areas should be removed and replaced with granular material. In areas where pumping occurs the soil should either be allowed to sit until pore pressures dissipate (several hours to several days) and the soil firms up, or be removed and replaced with granular material. Typically, we recommend removal to a minimum depth of 24 inches.

For granular material, we recommend using angular well-graded gravel, such as pit run, or crushed rock with a maximum particle size of four inches. We suggest that the initial lift be approximately 12 inches thick and be compacted with a static roller-type compactor. A finer granular material such as sand, gravelly sand, sandy gravel or road base may also be used. Materials which are more angular and coarse may require thinner lifts in order to achieve compaction. We recommend that the fines content (percent passing the No. 200 sieve) be less than 15%, the liquid limit be less than 35, and the plasticity index be less than 15.

Using a geosynthetic fabric, such as Mirafi 600X or equivalent, may also reduce the amount of material required and avoid mixing of the granular material and the subgrade. If a fabric is used, following removal of disturbed soils and water, the fabric should be placed over the bottom and up the sides of the excavation a minimum of 24 inches. The fabric should be placed in accordance with the manufacturer's recommendations, including proper overlaps. The granular material should then be placed over the fabric in compacted lifts. Again, we suggest that the initial lift be approximately 12 inches thick and be compacted with a static roller-type compactor.

9.0 SEISMIC AND GEOLOGIC CONSIDERATIONS

9.1 Seismic Design

The residential structures should be designed in accordance with the 2015 International Residential Code (IRC). The IRC designates this area as a seismic design class D₁.

The site is located at approximately 41.310 degrees latitude and -111.851 degrees longitude from the approximate center of the site. The IRC site value for this property is 0.725g. The design spectral response acceleration parameters are given below.



Project No.: 177075

Table 4: Design Acceleration for Short Period

Ss	Fa	Site Value (S _{DS})
		2/3 S _S *F _a
0.982 g	1.107	0.725g

Ss = Mapped spectral acceleration for short periods Fa = Site coefficient from Table 1613.3.3(1)

 $S_{DS} = \frac{2}{3}S_{MS} = \frac{2}{3}(F_a \cdot S_s) = 5\%$ damped design spectral response acceleration for short periods

9.2 Faulting

The subject property is located within the Intermountain Seismic Belt where the potential for active faulting and related earthquakes is present. Based upon published geologic maps³, no active faults traverse through or immediately adjacent to the site and the site is not located within local fault study zones. The nearest mapped fault trace is the North Fork Fault about ½ mile east of the site.

9.3 <u>Liquefaction Potential</u>

Loose, saturated sands are most susceptible to liquefaction, but some loose, saturated gravels and relatively sensitive silt to low-plasticity silty clay soils can also liquefy during a seismic event. Subsurface soils were composed of clay, silt and sand soils. The soils encountered at this project do not appear liquefiable, but the liquefaction susceptibility of underlying soils (deeper than our explorations) is not known and would require deeper explorations to quantify.

10.0 FOUNDATIONS

10.1 General

The foundation recommendations presented in this report are based on the soil conditions encountered during our field exploration, the results of laboratory testing of samples of the native soils, the site grading recommendations presented in this report, and the foundation loading conditions presented in Section 3.0, *Proposed Construction*, of this report. If loading conditions and assumptions related to foundations are significantly different, Earthtec should be notified so that we can re-evaluate our design parameters and estimates (higher loads may cause more settlement), and to provide additional recommendations if necessary.

Conventional strip and spread footings may be used to support the proposed structures after appropriate removals as outlined in Section 8.1. Foundations should not be installed on topsoil, undocumented fill, debris, combination soils, organic soils, frozen soil, or in ponded water. If foundation soils become disturbed during construction, they should be removed or compacted.

³ U.S. Geological Survey, Quaternary Fault and Fold Database of the United States, November 3, 2010



Bill Rules Residence 4033 East Nordic Valley Drive Liberty, Utah

Project No.: 177075

10.2 Strip/Spread Footings

We recommend that conventional strip and spread foundations be constructed entirely on a minimum 18 inches of properly placed, compacted, and tested structural fill extending to undisturbed native soils. For foundation design we recommend the following:

- Footings founded on a minimum 18 inches of structural fill may be designed using a maximum allowable bearing capacity of 1,500 pounds per square foot. The values for vertical foundation pressure can be increased by one-third for wind and seismic conditions per Section 1806.1 when used with the Alternative Basic Load Combinations found in Section 1605.3.2 of the 2015 International Building Code.
- Continuous and spot footings should be uniformly loaded and should have a minimum width of 20 and 30 inches, respectively.
- Exterior footings should be placed below frost depth which is determined by local building codes. In general, 30 inches of cover is adequate for most sites; however local code should be verified by the end design professional. Interior footings, not subject to frost (heated structures), should extend at least 18 inches below the lowest adjacent grade.
- Foundation walls and footings should be properly reinforced to resist all vertical and lateral loads and differential settlement.
- The bottom of footing excavations should be compacted with at least 4 passes of an approved non-vibratory roller prior to erection of forms or placement of structural fill to densify soils that may have been loosened during excavation and to identify soft spots. If soft areas are encountered, they should be stabilized as recommended in Section 8.5.
- Footing excavations should be observed by the geotechnical engineer prior to beginning footing construction to evaluate whether suitable bearing soils have been exposed and whether excavation bottoms are free of loose or disturbed soils.
- Structural fill used below foundations should extend laterally a minimum of 6 inches for every 12 vertical inches of structural fill placed. For example, if 18 inches of structural fill is required to bring the excavation to footing grade, the structural fill should extend laterally a minimum of 9 inches beyond the edge of the footings on both sides.

10.3 <u>Estimated Settlements</u>

If the proposed foundations are properly designed and constructed using the parameters provided above, we estimate that total settlements should not exceed one inch and differential settlements should be one-half of the total settlement over a 25-foot length of continuous foundation, for non-earthquake conditions. Additional settlement could occur during a seismic event due to ground shaking, if more than 3 feet of grading fill is placed above the existing ground surface, if loading conditions are greater than anticipated in Section 3, and/or if foundation soils are allowed to become wetted.



Project No.: 177075

10.4 Lateral Earth Pressures

Below grade walls act as soil retaining structures and should be designed to resist pressures induced by the backfill soils. The lateral pressures imposed on a retaining structure are dependent on the rigidity of the structure and its ability to resist rotation. Most retaining walls that can rotate or move slightly will develop an active lateral earth pressure condition. Structures that are not allowed to rotate or move laterally, such as subgrade basement walls, will develop an at-rest lateral earth pressure condition. Lateral pressures applied to structures may be computed by multiplying the vertical depth of backfill material by the appropriate equivalent fluid density. Any surcharge loads in excess of the soil weight applied to the backfill should be multiplied by the appropriate lateral pressure coefficient and added to the soil pressure. For static conditions the resultant forces are applied at about one-third the wall height (measured from bottom of wall). For seismic conditions, the resultant forces are applied at about two-third times the height of the wall both measured from the bottom of the wall. The lateral pressures presented in the table below are based on drained, horizontally placed structural fill as backfill material using a 33° friction angle and a dry unit weight of 115 pcf.

Table 5: Lateral Earth Pressures (Static and Dynamic)

Condition	Condition Case La		Equivalent Flui Pressure (pcf		
Active	Static	0.29	34		
Active	Seismic	0.40	46		
At-Rest	Static	0.46	52		
Al-Nesi	Seismic	0.65	75		
Passive	Static	3.39	390		
rassive	Seismic	5.25	604		

^{*}Seismic values combine the static and dynamic values

These pressure values do not include any surcharge, and are based on a relatively level ground surface at the top of the wall and drained conditions behind the wall. It is important that water is not allowed to build up (hydrostatic pressures) behind retaining structures. Retaining walls should incorporate drainage behind the walls as appropriate, and surface water should be directed away from the top and bottom of the walls.

Lateral loads are typically resisted by friction between the underlying soil and footing bottoms. Resistance to sliding may incorporate the friction acting along the base of foundations, which may be computed using a coefficient of friction of soils against concrete of 0.55 for structural fill meeting the recommendations presented herein. Concrete or masonry walls shall be selected and constructed in accordance to the provision of Section R404 of the 2015 International Residential Code or sections referenced therein. Retaining wall lateral resistance design should further reference Section R404.4 for reference of Safety Factors.

The pressure and coefficient values presented above are ultimate; therefore, an appropriate factor of safety may need to be applied to these values for design purposes. The appropriate factor of safety will depend on the design condition and should be determined by the project



Liberty, Utah Project No.: 177075

structural engineer.

11.0 FLOOR SLABS AND FLATWORK

Concrete floor slabs and exterior flatwork may be supported on 8 inches of properly placed and compacted structural fill after appropriate removals and grading as outlined in Section 8.1 are completed. We recommend placing a minimum 4 inches of free-draining fill material (see Section 8.3) beneath floor slabs to facilitate construction, act as a capillary break, and aid in distributing floor loads. For exterior flatwork, we recommend placing a minimum 4 inches of road-base material. Prior to placing the free-draining fill or road-base materials, the native subgrade should be proof-rolled to identify soft spots, which should be stabilized as discussed above in Section 8.5.

For slab design, we recommend using a modulus of sub-grade reaction of 130 pounds per cubic inch. The thickness of slabs supported directly on the ground shall not be less than 3½ inches. A 6-mil polyethylene vapor retarder with joints lapped not less than 6 inches shall be placed between the ground surface and the concrete, as per Section R506 of the 2015 International Residential Code.

To help control normal shrinkage and stress cracking, we recommend that floor slabs have adequate reinforcement for the anticipated floor loads with the reinforcement continuous through interior floor joints, frequent crack control joints, and non-rigid attachment of the slabs to foundation and bearing walls. Special precautions should be taken during placement and curing of all concrete slabs and flatwork. Excessive slump (high water-cement ratios) of the concrete and/or improper finishing and curing procedures used during hot or cold weather conditions may lead to excessive shrinkage, cracking, spalling, or curling of slabs. We recommend all concrete placement and curing operations be performed in accordance with American Concrete Institute (ACI) codes and practices.

12.0 DRAINAGE

12.1 Surface Drainage

As part of good construction practice, precautions should be taken during and after construction to reduce the potential for water to collect near foundation walls. Accordingly, we recommend the following:

• The contractor should take precautions to prevent significant wetting of the soil at the base of the excavation. Such precautions may include: grading to prevent runoff from entering the excavation, excavating during normally dry times of the year, covering the base of the excavation if significant rain or snow is forecast, backfill at the earliest possible date, frame floors and/or the roof at the earliest possible date, other precautions that might become



Project No.: 177075

evident during construction.

- Adequate compaction of foundation wall backfill should be provided i.e. a minimum of 90% of ASTM D-1557. Water consolidation methods should not be used.
- The ground surface should be graded to drain away from the building in all directions. We recommend a minimum fall of 8 inches in the first 10 feet.
- Roof runoff should be collected in rain gutters with down spouts designed to discharge well
 outside of the backfill limits, or at least 10 feet from foundations, whichever is greater.
- Sprinkler nozzles should be aimed away, and all sprinkler components kept at least 5 feet, from foundation walls. A drip irrigation system may be utilized in landscaping areas within 10 feet of foundation walls. Also, sprinklers should not be placed at the top or on the face of slopes. Sprinkler systems should be designed with proper drainage and well maintained. Over-watering should be avoided.
- Any broken or leaking pipes should be fixed immediately.
- Watering of landscape areas should be limited to reduce the amount of water introduced into the slope.
- Any additional precautions which may become evident during construction.

12.2 Subsurface Drainage

Section R405.1 of the 2015 International Residential Code states, "Drains shall be provided around all concrete and masonry foundations that retain earth and enclose habitable or usable spaces located below grade." Section R310.2.3.2 of the 2015 International Residential Code states, "Window wells shall be designed for proper drainage by connecting to the building's foundation drainage system." An exception is allowed when the foundation is installed on well drained ground consisting of Group 1 soils, which include those defined by the Unified Soil Classification System as GW, GP, SW, SP, GM, and SM. The soils observed in the explorations at the depth of foundation consisted primarily of silt (ML) and clay (CL) which are not Group 1 soils. The recommendations presented below should be followed during design and construction of the foundation drains:

- A perforated 4-inch minimum diameter pipe should be enveloped in at least 12 inches of free-draining gravel and placed adjacent to the perimeter footings. The perforations should be oriented such that they are not located on the bottom side of the pipe, as much as possible. The free-draining gravel should consist of primarily ¾- to 2-inch size gravel having less than 5 percent passing the No. 4 sieve, and should be wrapped with a separation fabric such as Mirafi 140N or equivalent.
- The highest point of the perforated pipe bottom should be equal to the bottom elevation of the footings. The pipe should be uniformly graded to drain to an appropriate outlet (storm drain, land drain, other gravity outlet, etc.) or to one or more sumps where water can be



Bill Rules Residence 4033 East Nordic Valley Drive Liberty, Utah

Project No.: 177075

removed by pumping.

- A perforated 4-inch minimum diameter pipe should be installed in all window wells and connected to the foundation drain.
- To facilitate drainage beneath basement floor slabs we recommend that the minimum thickness of free-draining fill beneath the slabs be increased to at least 10 inches (approximately equal to the bottom of footing elevations). A separation fabric such as Mirafi 140N or equivalent should be placed beneath the free-draining gravel. Connections should be made to allow any water beneath the slabs to reach the perimeter foundation drain.
- The drain system should be periodically inspected and clean-outs should be installed for the foundation drain to allow occasional cleaning/purging, as needed. Proper drain operation depends on proper construction and maintenance.

13.0 SLOPE STABILITY

We evaluated the overall stability of the proposed slope at the subject property. The properties of the native soils at the site were estimated using laboratory testing on samples recovered during our field investigations and our experience with similar soils. Our direct shear testing on the native Lean Clay (CL) the soils encountered during our field investigation indicated the soils have an internal friction angle of about 33 degrees and cohesion of about 100 psf (See Figure No. 7, *Direct Shear Test*). We used an internal friction angle of 33 degrees, an apparent cohesion of 100 psf, a saturated unit weight of 127 pcf, and a moist unit weight of 118 pcf for our analyses.

For the seismic (pseudostatic) analysis, a peak horizontal ground acceleration of 0.392g for the 2% probability of exceedance in 50 years was obtained for site (grid) locations of 41.310 degrees north latitude and -111.851 degrees west longitude. Typically, one-third to one-half this value is utilized in analysis. Accordingly, a value of 0.196 was used as the pseudostatic coefficient for the stability analysis.

We evaluated the stability of the proposed site using the computer program XSTABLE. This program uses a limit equilibrium (Bishop's modified) method for calculating factors of safety against sliding on an assumed failure surface and evaluates numerous potential failure surfaces, with the most critical failure surface identified as the one yielding the lowest factor of safety of those evaluated. The configuration analyzed was based on our observations during the field investigation, provided site plan with the foundation and topography map. The site plan was provided by Mr. Bill Rules.

The configuration of the proposed slope was analyzed at Cross-Section A-A' and starts at the roadway of Nordic Valley Drive. The lot then slopes uphill to the proposed residence an approximately 20 to 25 percent grade. The residence location is model with a 1,500 psf load. The slope above the residence is graded at approximately 50 to 60 percent grade to the natural



Project No.: 177075

grade of 14 to 35 percent grades. A water table was conservatively placed at approximately 10 feet below the ground surface, although groundwater was not encountered during our field exploration. Typically, the required minimum factors of safety are 1.5 for static conditions and 1.0 for seismic (pseudostatic) conditions. The results of our analyses indicate that the slope configuration described above meets both these requirements. The slope stability data are attached as Figure Nos. 8 and 9, Stability Results. Any modifications to the slope, including the construction of retaining walls, should be properly designed and engineered.

It should be clearly understood that slope movements or even failure can occur if the slope is undermined, the slope soils become saturated, or the lot is underlain by a formation that is prone to landslides, such as the Norwood Tuff formation. Further investigation including a deeper boring may be required: to determine if a landslide is present at the site and if it is currently moving, to quantify the amount of movement, and to characterize the deposits within the affected area. The property owner and the owner's representatives should be made aware of the risks should these or other conditions occur that could saturate or erode/undermine the soils. Surface water should be directed away from the top and bottom of the slope, the slope should be vegetated with drought resistant plants, and sprinklers should not be placed on the face of the slope. Watering of landscape areas should be limited to reduce the amount of water introduced into the slope. Overwatering should be avoided. Any broken or leaking pipes should be fixed immediately.

14.0 **GENERAL CONDITIONS**

The exploratory data presented in this report was collected to provide geotechnical design recommendations for this project. The explorations may not be indicative of subsurface conditions outside the study area or between points explored and thus have a limited value in depicting subsurface conditions for contractor bidding. Variations from the conditions portrayed in the explorations may occur and which may be sufficient to require modifications in the design. If during construction, conditions are different than presented in this report, Earthtec should be advised immediately so that the appropriate modifications can be made.

The findings and recommendations presented in this geotechnical report were prepared in accordance with generally accepted geotechnical engineering principles and practice in this area of Utah at this time. No warranty or representation is intended in our proposals, contracts, letters, or reports.

This geotechnical report is based on relatively limited subsurface explorations and laboratory testing. Subsurface conditions may differ in some locations of the site from those described herein, which may require additional analyses and possibly modified recommendations. Thus, we strongly recommend consulting with Earthtec regarding any changes made during design and construction of the project from those discussed herein. Failure to consult with Earthtec regarding any such changes relieves Earthtec from any liability arising from changed conditions at the site.



To maintain continuity, Earthtec should also perform materials testing and special inspections for this project. The recommendations presented herein are based on the assumption that an adequate program of tests and observations will be followed during construction to verify compliance with our recommendations. We also assume that we will review the project plans and specifications to verify that our conclusions and recommendations are incorporated and remain appropriate (based on the actual design). Earthtec should be retained to review the final design plans and specifications so comments can be made regarding interpretation and implementation of our geotechnical recommendations in the design and specifications. Earthtec also should be retained to provide observation and testing services during grading, excavation, foundation construction, and other earth-related construction phases of the project.

We appreciate the opportunity of providing our services on this project. If we can answer questions or be of further service, please contact Earthtee at your convenience.

Respectfully;

EARTHTEC ENGINEERING

Frank F. h

Frank Namdar, P.G., E.I.T. Project Engineer

MITCHELL

MITCHELL

MITCHELL


Timothy A. Mitchell, P.E.

Timothy A. Mitchell, P.E. Senior Geotechnical Engineer



VICINITY MAP

4033 East Nordic Valley Drive Liberty, Utah





PROJECT NO.: 177075



AERIAL PHOTOGRAPH SHOWING LOCATION OF TEST PITS AND SLOPE STABILITY CROSS-**SECTION**

4033 East Nordic Valley Drive Liberty, Utah



Approximate Test Pit Location **►** Approximate Cross-Section Location



Not to Scale

PROJECT NO.: 177075



TEST PIT LOG

NO.: TP-1

PROJECT:

Bill Rules Residence

CLIENT:

Mr. Bill Rules

LOCATION:

See Figure 2

OPERATOR:

R. E. Bailey Construction

EQUIPMENT: Rubber-tire Backhoe

DEPTH TO WATER; INITIAL \square :

PROJECT NO.: 177075

DATE:

11/01/17

ELEVATION: Not Determined

LOGGED BY: F. Namdar

AT COMPLETION ▼:

	DEP	IHIC	WATER; INITIAL ⊻:	41 (COMP	LETIC						
	<u>.0</u>	(0)		U	3		TES	TRI	ESULT	S		
Depth (Ft.) 0		nscs	Description	Salumes	Water Cont. (%)	Dry Dens. (pcf)	LL	PI	Grave (%)	Sand (%)	Fines (%)	Other Tests
1	1/ 1/1/ 1/		TOPSOIL, clay with sand, gravel and cobble, moist, dark brown									
			SILT with sand, stiff to very stiff (estimated), slightly moist, brown									
2				þ								
3		ML										
4					14				8	21	71	
. 5			Silty SAND, dense to very dense, slighlty moist, light brown									
6					13		58	26	1	54	45	
7		SM			13		30	20		34	40	
8												
9				×	-							
10			REFUSAL, MAXIMUM DEPTH EXPLORED APPROXIMATELY 9 FEET									
.11												
.12												
13												
.14												
15	N1		dustar anagustarad	T	nata W-							
Not	es: N	o groun	dwater encountered.	1	CBR = 0	y California Consolida	a Bea	ring F	Ratio			

R = Resistivity

DS = Direct Shear SS = Soluble Sulfates

B = Burnoff

PROJECT NO.: 177075



TEST PIT LOG

NO.: TP-2

PROJECT:

Bill Rules Residence

CLIENT:

Mr. Bill Rules

LOCATION:

See Figure 2

OPERATOR:

R. E. Bailey Construction

EQUIPMENT: Rubber-tire Backhoe

DEPTH TO WATED. INITIAL T.

PROJECT NO.: 177075

DATE:

11/01/17

ELEVATION: Not Determined

LOGGED BY: F. Namdar

AT COMPLETION W

		DEF	PTH TO	WATER; INITIAI	. ∑:	\mathbf{A}	ГС	COMPI	ETIC	N J	▼:				
_		ic	S				es			TES	TRI	ESULT	S		
	epth (Ft.) 0	Gra			Description		Samples	. Water Cont. (%)	Dry Dens. (pcf)	LL	PI	Gravel (%)	Sand (%)	Fines (%)	Other Tests
	1	711/2		TOPSOIL, clay with sa brown	nd, gravel and cobble, moist, da	ark									
				Sandy Lean CLAY, stif some pinholes at 2'-3'	f to very stiff (estimated), moist,	brown,									
10.0	.3														
	.4														
	.5		CL												
	.6 7						X								
	. 8														
12/2	9							18	104	47	22	6	38	56	DS
	10			Silty SAND, dense to v brown	ery dense (estimated), slightly n	noist,									
	11		SM					14	102	41	8	4	50	46	С
	12			MAXIMUM DEPTH EX	PLORED APPROXIMATELY 12	2 FEET	-								
11/29/17	13														
1000	14														
ARTHTE	15 Not	es: N	lo groun	dwater encountered.				sts Ke							
LOG OF TESTPIT 177075.GPJ EARTHTEC.GDT								CBR = C C = C R = R DS = D SS = S	Californi Consolid Cesistivit	ation ty near		Ratio			
LOG OF TEST	PRO	DJEC	T NO.:	177075	ST.	A Land		<u> </u>		FIGI	URE	NO.:	4		



LEGEND

PROJECT:

Bill Rules Residence

CLIENT:

Mr. Bill Rules

DATE:

11/01/17

LOGGED BY:

F. Namdar

UNIFIED SOIL CLASSIFICATION SYSTEM

USCS

MAJOR SOIL DIVISIONS SYMBOL TYPICAL SOIL DESCRIPTIONS

171710	OR SOIL DIVIS	10115		IMD	OL TITICAL SOIL DESCRIPTIONS		
	GRAVELS	CLEAN GRAVELS	300	GW	Well Graded Gravel, May Contain Sand, Very Little Fines		
	(More than 50% of coarse fraction	(Less than 5% fines)	5.0	GP	Poorly Graded Gravel, May Contain Sand, Very Little Fines		
COARSE GRAINED	retained on No. 4 Sieve)	GRAVELS WITH FINES		GM	Silty Gravel, May Contain Sand		
SOILS		(More than 12% fines)		GC	Clayey Gravel, May Contain Sand		
(More than 50% retaining on No.	SANDS	CLEAN SANDS (Less than 5%		SW	Well Graded Sand, May Contain Gravel, Very Little Fines		
200 Sieve)	(50% or more of coarse fraction passes No. 4	fines)		SP	Poorly Graded Sand, May Contain Gravel, Very Little Fines		
		SANDS WITH FINES		SM	Silty Sand, May Contain Gravel		
	Sieve)	(More than 12% fines)		SC	Clayey Sand, May Contain Gravel		
	SII TS AN	D CLAYS		CL	Lean Clay, Inorganic, May Contain Gravel and/or Sand		
FINE GRAINED	(Liquid Limit		ML	Silt, Inorganic, May Contain Gravel and/or Sand			
SOILS	(1			OL	Organic Silt or Clay, May Contain Gravel and/or Sand		
(More than 50% passing No. 200	SILTS AN	SILTS AND CLAYS		СН	Fat Clay, Inorganic, May Contain Gravel and/or Sand		
Sieve)			ieve)		Ш	MH	Elastic Silt, Inorganic, May Contain Gravel and/or Sand
				ОН	Organic Clay or Silt, May Contain Gravel and/or Sand		
HIGI	HIGHLY ORGANIC SOILS				Peat, Primarily Organic Matter		

SAMPLER DESCRIPTIONS

SPLIT SPOON SAMPLER (1 3/8 inch inside diameter)



MODIFIED CALIFORNIA SAMPLER (2 inch outside diameter)



SHELBY TUBE (3 inch outside diameter)



BLOCK SAMPLE



LEGEND 177075.GPJ EARTHTEC.GDT 11/29/17

BAG/BULK SAMPLE

WATER SYMBOLS

Water level encountered during field exploration

Water level encountered at completion of field exploration

NOTES: 1. The logs are subject to the limitations, conclusions, and recommendations in this report.

2. Results of tests conducted on samples recovered are reported on the logs and any applicable graphs.


3. Strata lines on the logs represent approximate boundaries only. Actual transitions may be gradual.

4. In general, USCS symbols shown on the logs are based on visual methods only: actual designations (based on laboratory tests) may vary.

PROJECT NO.: 177075







Pressure (ksf)

Project: 4033 East Nordic Valley Drive

Location: TP-2

Sample Depth, ft: 10

Description: Block
Soil Type: Silty SAND (SN

Soil Type: Silty SAND (SM)
Natural Moisture, %: 14

Dry Density, pcf: 102

Liquid Limit: 41

Plasticity Index: 8

Water Added at: 1 ksf


Percent Swell: 0.2


PROJECT NO.: 177075



FIGURE NO .:

6





Source: TP-2	Depth:	8.0 ft						
Type of Test: Consolidated Drained/Saturate								
Test No. (Symbol)	1 (*)	2 (1)	3 (▲)					
Sample Type	J	Jndisturbe	d					
Initial Height, in.	1	1	1					
Diameter, in.	2.4	2.4	2.4					
Dry Density Before, pcf	105.2	103.8	103.3					
Dry Density After, pcf	104.2	103.1	101.9					
Moisture % Before	13.2	13.2	13.2					
Moisture % After	21.5	21.5	21.5					
Normal Load, ksf	1.0	2.0	4.0					
Shear Stress, ksf	0.69	1.41	2.73					
Strain Rate	.000	005573 IN/SEC						
Sample	Properties	B						
Cohesion, psf		10	00					
Friction Angle, 6		33						
Liquid Limit, %		47						
Plasticity Index, %		22						
Percent Gravel		6						
Percent Sand		3	8					
Percent Passing No. 200 sid	56							
Classification		C	L					

PROJECT:

4033 E. Nordic Valley Drive

PROJECT NO.: 177075



FIGURE NO.:

7

