

SPECIAL INSPECTION SCHEDULE

SOILS (IBC 1705.6)				
REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
X	VERIFY ADEQUATE MATERIALS BELOW FOOTINGS		◆	PRIOR TO PLACEMENT OF CONCRETE.
X	EXCAVATION EXTEND TO PROPER DEPTH AND MATERIALS		◆	PRIOR TO PLACEMENT OF COMPACTED FILL OR CONCRETE.
X	CLASSIFICATION AND TESTING OF FILL MATERIALS		◆	CHECK CLASSIFICATION AND GRADATIONS AT EACH LIFT, BUT NOT LESS THAN ONCE FOR EACH 10,000 FT ² OF SURFACE AREA.
X	VERIFY PROPER FILL MATERIALS, LIFT THICKNESSES AND IN-PLACE DENSITIES	◆		
X	VERIFY PROPERLY PREPARED SITE AND SUBGRADE		◆	PRIOR TO PLACEMENT OF CONCRETE.

CONCRETE CONSTRUCTION (IBC 1705.3)				
REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
X	REINFORCING STEEL PLACEMENT		◆	VERIFY SIZE, CLEARANCES, SPLICES AND PROPER TIES.
X	REINFORCING BAR WELDING a. WELDABILITY OF NON ASTM A706 BARS b. SINGLE PASS FILLED WELDS < 3/16" c. ALL OTHER WELDS	◆		
X	CAST IN ANCHORS		◆	VERIFY MIX DESIGN MEETS STRENGTH AND EXPOSURE REQUIREMENTS LISTED ON APPROVED PLANS.
X	POST-INSTALLED ANCHORS a. ADHESIVE ANCHORS INSTALLED HORIZONTALLY OR UPWARDLY INCLINED RESISTING SUSTAINED TENSION LOADS b. POST INSTALLED ANCHORS NOT DEFINED IN a.	◆		IN ACCORDANCE WITH APPROVED ICC-ES REPORT. PERIODIC INSPECTIONS ALLOWED IF STATED IN ES REPORT.
X	VERIFY REQUIRED DESIGN MIX		◆	VERIFY MIX DESIGN MEETS STRENGTH AND EXPOSURE REQUIREMENTS LISTED ON APPROVED PLANS.
X	SLUMP, AIR + TEMPERATURE TESTS. PREPARE STRENGTH TEST SAMPLES	◆		
X	CONCRETE PLACEMENT	◆		INCLUDES SAMPLING FOR AIR, SLUMP, STRENGTH AND TEMPERATURE TECHNIQUES.
X	CURING TEMPERATURE MAINTENANCE		◆	
	PRESTRESSED CONCRETE a. PRESTRESSING FORCES b. GROUTING OF BONDED TENDONS	◆		
	ERECTION OF PRECAST MEMBERS		◆	
	POST-TENSIONED CONCRETE STRENGTH		◆	
X	INSPECT FORMWORK		◆	

COLD-FORMED STEEL CONSTRUCTION (IBC 1705.11.2 & 1705.12.3)				
REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
	COMPONENTS OF WIND AND SEISMIC-FORCE RESISTING SYSTEMS		◆	VERIFY PROPER SCREW ATTACHMENT, BOLTING AND ANCHORING OF SHEAR WALLS, BRACES AND HOLDOWNS HAVING A FASTENER SPACING ≤ 4" O.C.
	FIELD WELDING OF ELEMENTS OF MAIN LATERAL FORCE RESISTING SYSTEM.		◆	

OTHER THAN STRUCTURAL STEEL (IBC 1705.2.2)				
REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
	STEEL ROOF & FLOOR DECK:			
	MATERIAL VERIFICATION OF STEEL DECK		◆	IDENTIFICATION MARKINGS PER APPLICABLE ASTM STANDARD
	ROOF AND DECK WELDS		◆	VERIFY THAT WELDS CONFORM TO AWS D1.3.
	WELDING OF REINFORCING STEEL:			
	VERIFICATION OF WELDABILITY (EXCEPT A706 BAR)		◆	VERIFY MATERIAL IS ABLE TO CONFORM TO AWS D1.4.

INSTALLATION OF OPEN-WEB STEEL JOISTS AND GIRDERS (IBC 1705.2.3)				
REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
	END CONNECTIONS		◆	SJI 2207.1
	BRIDGING - HORIZONTAL OR DIAGONAL a. STANDARD BRIDGING b. NON-STANDARD BRIDGING		◆	SJI 2207.1

MASONRY CONSTRUCTION (IBC 1705.4)

REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
	MINIMUM TESTING (TABLE 1.19.2, TMS - 402/ACI 530-11):			
	VERIFICATION OF SLUMP FLOW AND VISUAL STABILITY INDEX (VSI) FOR SELF-CONSOLIDATING GROUT.		◆	COMPRESSIVE STRENGTH TESTS PER ASTM C 1019 FOR SLUMP FLOW AND ASTM C 1611 FOR VSI.
	VERIFICATION OF F _u		◆	DETERMINE COMPRESSIVE STRENGTH PER "UNIT STRENGTH" OR "PRISM TEST" AS SPECIFIED IN ARTICLE 1.4.B OF ACI 530.1 PRIOR TO CONSTRUCTION.
	PRIOR TO CONSTRUCTION (ARTICLE 1.15, TMS-602/ACI 530.1-11):			
	REVIEW MATERIAL CERTIFICATES, MIX DESIGNS, TEST RESULTS AND CONSTRUCTION PROCEDURES		◆	VERIFY MATERIALS CONFORM TO APPROVED CONSTRUCTION DOCUMENTS. MIX DESIGN, TEST RESULTS, MATERIAL CERTIFICATES, AND CONSTRUCTION PROCEDURES SHOULD BE SUBMITTED FOR REVIEW. MORTAR MIX DESIGNS SHALL CONFORM TO ASTM C 270 WHILE GROUT SHALL CONFORM TO ASTM C 478. MATERIAL CERTIFICATES SHALL BE PROVIDED FOR THE FOLLOWING: REINFORCEMENT; ANCHORS, TIES, FASTENERS, AND METAL ACCESSORIES; MASONRY UNITS; MORTAR AND GROUT MATERIALS. REVIEW COLD-WEATHER OR HOT-WEATHER CONSTRUCTION PROCEDURES.
	AS CONSTRUCTION BEGINS (TABLE 1.19.2, TMS-402/ACI 530-11):			
	PROPORTIONS OF SITE-PREPARED MORTAR		◆	VERIFY THAT MORTAR IS TYPE AND COLOR SPECIFIED ON APPROVED PLANS, IT CONFORMS TO ASTM C 270, AND IS MIXED PER ARTICLE 2.6.A OF ACI 530.1.
	CONSTRUCTION OF MORTAR JOINTS		◆	VERIFY MORTAR JOINTS MEET ARTICLE 3.3.B OF ACI 530.1.1
	GRADE AND SIZE OF PRE-STRESSING TENDONS AND ANCHORAGES		◆	VERIFY THAT PRE-STRESSING TENDONS CONFORM TO REQUIREMENTS OF ARTICLE 2.4.B AND 2.4.H OF ACI 530.1
	LOCATION OF REINFORCEMENT, CONNECTORS AND ANCHORAGES.		◆	VERIFY REINFORCEMENT IS PLACED IN ACCORDANCE WITH ARTICLE 3.4 OF 530.1.
	PRE-STRESSING TECHNIQUE		◆	VERIFY PRE-STRESSING TECHNIQUE CONFORMS TO ARTICLE 3.6.B OR ACI 530.1
	PROPERTIES OF THIN BED MORTAR FOR AAC MASONRY	◆	◆	VERIFY REINFORCEMENT IS PLACED IN ACCORDANCE WITH ARTICLE 3.4 OF 530.1.
	PRIOR TO GROUTING (TABLE 1.19.2, TMS-402/ACI 530-11):			
	GROUT SPACE		◆	VERIFY GROUT SPACE IS FREE OF MORTAR DROPPINGS, DEBRIS, LOOSE AGGREGATE, AND OTHER DELETERIOUS MATERIALS AND THAT CLEANOUTS ARE PROVIDED PER ARTICLE 3.2.D AND 3.2.F OF ACI 530.1
	GRADE, TYPE AND SIZE OF REINFORCEMENT, ANCHOR BOLTS AND ANCHORAGES.		◆	VERIFY REINFORCEMENT, JOINT REINFORCEMENT, ANCHOR BOLTS AND VENEER ANCHORS COMPLY WITH APPROVED PLANS AND SECTIONS 1.6 OF ACI 530.
	PLACEMENT OF REINFORCEMENT, CONNECTORS AND ANCHORAGES.		◆	VERIFY REINFORCEMENT, JOINT REINFORCEMENT, ANCHOR BOLTS AND VENEER ANCHORS ARE INSTALLED PER APPROVED PLANS AND ARTICLES 3.2.E, 3.4, AND 3.6.A OF ACI 530.1.
	PROPORTIONS OF SITE-PREPARED GROUT.		◆	VERIFY GROUT PROPORTIONS MEET ASTM C 478 AND A SLUMP BETWEEN 8-11 INCHES. SELF-CONSOLIDATED GROUT SHALL NOT BE PROPORTIONED ONSITE.
	CONSTRUCTION OF MORTAR JOINTS		◆	VERIFY MORTAR JOINTS PLACED IN ACCORDANCE WITH ARTICLE 3.3.B OF ACI 530.1.
	DURING CONSTRUCTION (TABLE 1.19.2, TMS-402/ACI 530-11):			
	SIZE AND LOCATION OF STRUCTURAL ELEMENTS		◆	VERIFY LOCATIONS OF STRUCTURAL ELEMENTS PER APPROVED PLANS AND CONFIRM TOLERANCES MEET ARTICLE 3.3.F OF ACI 530.1.
	TYPE, SIZE AND LOCATION OF ANCHORS, FRAMES, ETC.		◆	VERIFY CORRECT ANCHORAGES AND CONNECTIONS ARE PROVIDED PER APPROVED PLANS AND SECTIONS 1.16.4.3 AND 1.17.1 OF ACI 530.
	WELDING OF REINFORCEMENT		◆	VERIFY CONFORMANCE WITH SECTIONS 2.1.7.7.2, 3.3.3.4 (c) AND 8.3.3.4 (b) OF ACI 530
	APPLICATION AND MEASUREMENT OF PRE-STRESSING FORCE		◆	VERIFY CONFORMANCE WITH ARTICLE 3.6.B OF ACI 530.1
	PLACEMENT OF GROUT		◆	
	PREPARATION, CONSTRUCTION AND PROTECTION OF MASONRY DURING COLD WEATHER (<40°F) OR HOT WEATHER (>90°F).		◆	VERIFY COLD-WEATHER CONSTRUCTION COMPLIES WITH ARTICLE 1.8.C OF ACI 530.1 AND HOT WEATHER CONSTRUCTION PER ARTICLE 1.8.D OF ACI 530.1.
	PLACEMENT OF GROUT AND PRE-STRESSING GROUT FOR BONDED TENDONS		◆	VERIFY COMPLIANCE WITH ARTICLE 3.5, 3.6C OF ACI 530.1
	OBSERVATION OF GROUT SPECIMENS, MORTAR SPECIMENS, AND / OR PRISMS.		◆	CONFIRM SPECIMENS/ PRISMS ARE PERFORMED AS REQUIRED BY ARTICLE 1.4 OF ACI 530.1.

WOOD CONSTRUCTION (IBC 1705.11.2)


REQD	TASK	INSPECTION FREQUENCY		COMMENTS:
		CONT.	PERIODIC	
X	COMPONENTS OF WIND AND SEISMIC-FORCE RESISTING SYSTEMS		◆	VERIFY PROPER SCREW ATTACHMENT, BOLTING AND ANCHORING OF SHEAR WALLS, BRACES AND HOLDOWNS HAVING A FASTENER SPACING ≤ 4" O.C.
	FIELD GLUING OF MAIN LATERAL FORCE RESISTING SYSTEM		◆	

STATEMENT OF SPECIAL INSPECTIONS

- THE PROJECT OWNER SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED BELOW. THE SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE COMPETENCE TO THE SATISFACTION OF THE BUILDING OFFICIAL. FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION, THESE INSPECTIONS ARE IN ADDITION TO THE INSPECTIONS REQUIRED BY THE BUILDING DEPARTMENT OF THE LOCAL JURISDICTION.
 - SPECIAL INSPECTORS SHALL KEEP RECORDS OF INSPECTIONS. THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. REPORTS SHALL INDICATE THAT WORK INSPECTED WAS DONE IN CONFORMANCE WITH APPROVED CONSTRUCTION DOCUMENTS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION. IF THE DISCREPANCIES ARE NOT CORRECTED, THE DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE PRIOR TO THE COMPLETION OF THAT PHASE OF THE WORK. A FINAL REPORT DOCUMENTING REQUIRED SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED IN THE INSPECTIONS SHALL BE SUBMITTED AT A POINT IN TIME AGREED UPON BY THE PERMIT APPLICANT AND THE BUILDING OFFICIAL PRIOR TO THE START OF WORK.
 - SPECIAL INSPECTIONS FOR EACH TASK SHALL BE CARRIED OUT IN COMPLIANCE WITH REQUIREMENTS PER THE CURRENT IBC AND OTHER MATERIAL STANDARDS.
- FABRICATION SHOP REQUIREMENTS
- WHERE FABRICATION OF STRUCTURAL LOAD BEARING MEMBERS AND ASSEMBLIES IS BEING PERFORMED ON THE PREMISES OF A FABRICATORS SHOP, SPECIAL INSPECTIONS REQUIRED BELOW SHALL BE PROVIDED IN THE SHOP DURING THE FABRICATION PROCESS. THIS REQUIREMENT MAY BE EXCEPTED IF THE WORK IS DONE ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION. A CERTIFICATE SHALL BE REQUIRED TO VERIFY SUCH APPROVAL. AT COMPLETION OF THE FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO THE BUILDING OFFICIAL STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DRAWINGS.



Structural Plans for:
POWDER MOUNTAIN CABIN 1500+



DESIGNED BY: J.D.A.
CHECKED BY: J.D.A.
SCALE:
DATE: JULY 28, 2017
JOB No. 17-089

SPECIAL
INSPECTION
SHEET

SHEET No.
S0.2

PLAN REVIEW-09/05/2017
PLAN REVIEW-09/22/2017


STRUCTURAL STEEL CONSTRUCTION (IBC 1705.2, 1705.11, 1705.12)				
REQD	TASK	INSPECTION TYPE		COMMENTS:
		Q.C.	Q.A.	
PRIOR TO WELDING (TABLE N5.4-1, AISC 360-10):				
X	VERIFY WELDING PROCEDURES	P	P	
X	MANUFACTURER CERTIFICATIONS	P	P	
X	MATERIAL IDENTIFICATION	O	O	VERIFY TYPE AND GRADE OF MATERIAL.
X	WELDER IDENTIFICATION	O	O	VERIFY THERE IS A SYSTEM IN PLACE TO IDENTIFY THE WELDER WHO HAS WELDED A JOINT OR MEMBER.
	FIT-UP GROOVE WELDS	O	O	VERIFY JOINT PREPARATION, DIMENSIONS, CLEANLINESS, TACKING AND BACKING.
	ACCESS HOLES	O	O	VERIFY CONFIGURATION AND FINISH.
	FIT-UP FILLET WELDS	O	O	VERIFY ALIGNMENT, GAPS AT ROOT, CLEANLINESS OF STEEL SURFACES, TACK WELD QUALITY AND LOCATION.
X	CHECK WELDING EQUIPMENT	O	O	
DURING WELDING (TABLE N5.4-2, AISC 360-10):				
X	USE OF QUALIFIED WELDERS	O	O	VERIFY THAT WELDERS ARE APPROPRIATELY QUALIFIED.
X	CONTROL AND HANDLING OF WELDING CONSUMABLES	O	O	VERIFY PACKAGING AND EXPOSURE CONTROL.
X	CRACKED TACK WELDS	O	O	VERIFY WELDING IS NOT OVER A CRACKED TACK WELD.
X	ENVIRONMENTAL CONDITIONS	O	O	VERIFY WIND SPEED IS WITHIN LIMITS AS WELL AS PRECIPITATION AND TEMPERATURE.
X	WPS FOLLOWED	O	O	VERIFY ITEMS SUCH AS WELDING EQUIPMENT SETTINGS, TRAVEL SPEED, WELDING MATERIALS, SHIELDING GAS TYPE/FLOW RATE, PREHEAT APPLIED, INTERPASS TEMPERATURE MAINTAINED, AND PROPER POSITION.
X	WELDING TECHNIQUES	O	O	VERIFY INTERPASS AND FINAL CLEANING. EACH PASS IS WITHIN PROFILE LIMITATIONS, AND QUALITY OF EACH PASS.
AFTER WELDING (TABLE N5.4-3, AISC 360-10):				
X	WELDS CLEANED	O	O	VERIFY THAT WELDS HAVE BEEN PROPERLY CLEANED.
X	SIZE, LENGTH AND LOCATION OF WELDS	P	P	
X	WELDS MEET VISUAL ACCEPTANCE CRITERIA	P	P	
	ARC STRIKES	P	P	
PRIOR TO BOLTING (TABLE N5.6-1 AISC 360-10):				
X	MANUFACTURERS CERTIFICATIONS FOR FASTENERS	O	P	
X	FASTENERS MARKED w/ ASTM REQUIREMENTS	O	O	
X	PROPER FASTENERS SELECTED FOR DETAIL	O	O	
X	PROPER PROCEDURE FOR DETAIL	O	O	
X	CONNECTING ELEMENTS	O	O	
X	PRE-INSTALLATION VERIFICATION TESTING	P	O	
X	PROPER STORAGE OF FASTENERS	O	O	
DURING BOLTING (TABLE N5.6-2 AISC 360-10):				
X	FASTENER ASSEMBLIES	O	O	
X	JOINTS SNUG TIGHT PRIOR TO PRETENSIONING	O	O	
X	PROPER WRENCH USAGE	O	O	
X	FASTENERS PRETENSIONED	O	O	
AFTER BOLTING (TABLE N5.6-3, AISC 360-10):				
X	STRUCTURAL STEEL DETAILS	P	P	

O- OBSERVE THESE ITEMS ON A RANDOM BASIS.

P- PERFORM THESE TASKS FOR EACH WELDED / BOLTED JOINT OR MEMBER (AISC 360-10 N5.4)



Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY: J.D.A.
CHECKED BY: J.D.A.
SCALE:
DATE: JULY 28, 2017
JOB No. 17-089


SPECIAL
INSPECTION
SHEET

SHEET No.


S0.3




5 CONSTRUCTION DETAIL
S1.2 NO SCALE




3 CONSTRUCTION DETAIL
S1.2 NO SCALE



1 CONSTRUCTION DETAIL
S1.2 NO SCALE




4 CONSTRUCTION DETAIL
S1.2 NO SCALE



2 CONSTRUCTION DETAIL
S1.2 NO SCALE


Structural Plans for:
POWDER MOUNTAIN CABIN 1500+



DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089

CONSTRUCTION DETAILS


SHEET No.
S1.2



FLOOR FRAMING NOTES

- ① FRAME FLOOR w/ 9/8" TJI/210 AT 16" O.C.
PROVIDE 3" CONCRETE TOPPING ON FLOOR WHERE INDICATED IN ARCH. PLANS
- ② SEE FRAMING NOTES ON S0.1 FOR FLOOR SHEATHING SPECIFICATIONS
- ③ REPRESENTS 1/2" ROD CROSS BRACING BETWEEN FOUNDATION AND MAIN LEVEL FRAMING

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	1/4" = 1'-0"
DATE:	JULY 28, 2017
JOB No.	17-089

MAIN FLOOR
 FRAMING PLAN

SHEET No.
S2.1

PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017




DEAD LOAD = 50 PSF
LIVE LOAD = 40 PSF

FLOOR FRAMING NOTES

- ① FRAME FLOOR w/ 9/2 TJI/210 AT 16" O.C. PROVIDE 3" CONCRETE TOPPING ON FLOOR WHERE INDICATED IN ARCH. PLANS
- ② SEE FRAMING NOTES ON S0.1 FOR FLOOR SHEATHING SPECIFICATIONS
- ③ INDICATES INTERIOR BEARING WALL
- ④ FRAME EXTERIOR WALLS AND BEARING WALLS w/ 2 x 6 AT 16" O.C.
- ⑤ FRAME ENTRY FLOOR w/ 2 x 8 AT 16" O.C.


Structural Plans for:
POWDER MOUNTAIN CABIN 1500+



DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	1/4" = 1'-0"
DATE:	JULY 28, 2017
JOB No.	17-089

UPPER FLOOR FRAMING PLAN

SHEET No.
S2.2




ROOF FRAMING PLAN
SCALE: 1/4" = 1'-0"

DEAD LOAD = 15 PSF
SNOW LOAD = 192 PSF

ROOF FRAMING NOTES

- ① FRAME ROOF w/ PRE-ENGINEERED ROOF TRUSSES AT 16" O.C.
- ② SEE FRAMING NOTES ON S0.1 FOR ROOF SHEATHING SPECIFICATIONS
- ③ FRAME EXTERIOR WALLS w/ 2 x 6 AT 16" O.C.

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	1/4" = 1'-0"
DATE:	JULY 28, 2017
JOB No.	17-089

ROOF FRAMING PLAN
SHEET No.
S2.3

PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




SHEARWALL SCHEDULE							
MARK	PANEL GRADE	PANEL THICKNESS	PANEL EDGE NAILING	PANEL FIELD NAILING	STUDS AT ADJOINING PANEL EDGES	ANCHOR BOLTS AT FOUNDATION LEVEL	SILL PLATE AT FOUNDATION
(A)	APA EXP. 1	3/8"	8d AT 6" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.	2x TREATED
(B)	APA EXP. 1	3/8"	8d AT 4" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.	2x TREATED
(C)	APA EXP. 1	3/8"	8d AT 3" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.	2x TREATED
(D)	APA EXP. 1	3/8"	8d AT 2" O.C.	8d AT 12" O.C.	3x	3/8" dia. x 10" AT 16" O.C.	2x TREATED

HOLD DOWN SCHEDULE					
MARK	HOLD DOWN	ATTACHMENT TO STUDS	FOUNDATION ANCHORS	MINIMUM STUDS	REMARKS
AA	SIMPSON MST48	(34) 16d SINKERS	N. A.	(2) 2x	SEE DETAILS ON S3.3
BB	SIMPSON MST72	(62) 16d SINKERS	N. A.	(2) 2x	SEE DETAILS ON S3.3

- SEE GENERAL NOTES FOR ADDITIONAL INFORMATION
- PLYWOOD, ORIENTED STRAND BOARD AND COMPOSITE BOARD (BUT NOT STRUCTURAL PARTICLE BOARD) ARE ACCEPTED AS EQUALS
- ALL PANEL EDGES AT SHEAR WALLS SHALL BE BACKED WITH 2" NOMINAL FRAMING, EXCEPT WHERE INDICATED TO BE 3" NOMINAL ON SCHEDULE. 3x MATERIAL MAY BE REPLACED WITH 4x MATERIAL. MULTIPLE LAYERS OF 2x FRAMING SHALL NOT BE USED WHERE 3x FRAMING IS INDICATED.
- ALL ANCHOR BOLTS TO HAVE A 3" x 3" x 1/2" PLATE WASHER (SEE SEE SCHEDULE ABOVE FOR SPACING)
- ALL STUDS IN SHEAR WALLS SHALL BE DOUGLAS FIR-LARCH
- SHEAR WALL PANELS INDICATED ON SCHEDULE ARE TO BE SHEATHED FOR FULL HEIGHT OF THE WALL.
- SEE SPECIAL INSPECTION PAGE FOR ADDITIONAL REQUIREMENTS
- WHERE PANELS ARE APPLIED ON BOTH FACES OF A SHEAR WALL AND NAIL SPACING IS LESS THAN 6" ON CENTER ON EITHER SIDE, PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS. ALTERNATIVELY, THE WIDTH OF THE NAILED FACE OF FRAMING MEMBERS SHALL BE 3" NOMINAL OR GREATER AT ADJOINING PANEL EDGES AND NAILS AT ALL PANEL EDGES SHALL BE STAGGERED.


- ALL ANCHORS ARE SIMPSON STRONG-TIE. (OR EQUAL)
- INSTALLATION OF ALL HOLDDOWN ANCHORS AND STRAPS SHALL BE PER MANUFACTURES RECOMMENDATIONS AND SPECIFICATIONS
- PROVIDE EDGE NAILING ALONG STUDS CONNECTED TO HOLDDOWN ANCHORS AND STRAPS
- SEE SPECIAL INSPECTION PAGE FOR ADDITIONAL REQUIREMENTS



DESIGNED BY: J.D.A.
 CHECKED BY: J.D.A.
 SCALE: 1/4" = 1'-0"
 DATE: JULY 28, 2017
 JOB No. 17-089

MAIN FLOOR SHEARWALL PLAN
 SHEET No.
S3.1

PLAN REVIEW-09/22/2017
 PLAN REVIEW-09/05/2017




SHEARWALL SCHEDULE						
MARK	PANEL GRADE	PANEL THICKNESS	PANEL EDGE NAILING	PANEL FIELD NAILING	STUDS AT ADJOINING PANEL EDGES	ANCHOR BOLTS AT FOUNDATION LEVEL
A	APA EXP. 1	3/8"	8d AT 6" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.
B	APA EXP. 1	3/8"	8d AT 4" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.
C	APA EXP. 1	3/8"	8d AT 3" O.C.	8d AT 12" O.C.	2x	3/8" dia. x 10" AT 32" O.C.
D	APA EXP. 1	3/8"	8d AT 2" O.C.	8d AT 12" O.C.	3x	3/8" dia. x 10" AT 16" O.C.

- SEE GENERAL NOTES FOR ADDITIONAL INFORMATION
- PLYWOOD, ORIENTED STRAND BOARD AND COMPOSITE BOARD (BUT NOT STRUCTURAL PARTICLE BOARD) ARE ACCEPTED AS EQUALS
- ALL PANEL EDGES AT SHEAR WALLS SHALL BE BACKED WITH 2" NOMINAL FRAMING, EXCEPT WHERE INDICATED TO BE 3" NOMINAL ON SCHEDULE. 3x MATERIAL MAY BE REPLACED WITH 4x MATERIAL. MULTIPLE LAYERS OF 2x FRAMING SHALL NOT BE USED WHERE 3x FRAMING IS INDICATED.
- ALL ANCHOR BOLTS TO HAVE A 3" x 3" x 1/2" PLATE WASHER (SEE SEE SCHEDULE ABOVE FOR SPACING)
- ALL STUDS IN SHEAR WALLS SHALL BE DOUGLAS FIR-LARCH
- SHEAR WALL PANELS INDICATED ON SCHEDULE ARE TO BE SHEATHED FOR FULL HEIGHT OF THE WALL.
- SEE SPECIAL INSPECTION PAGE FOR ADDITIONAL REQUIREMENTS
- WHERE PANELS ARE APPLIED ON BOTH FACES OF A SHEAR WALL AND NAIL SPACING IS LESS THAN 6" ON CENTER ON EITHER SIDE, PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS. ALTERNATIVELY, THE WIDTH OF THE NAILED FACE OF FRAMING MEMBERS SHALL BE 3" NOMINAL OR GREATER AT ADJOINING PANEL EDGES AND NAILS AT ALL PANEL EDGES SHALL BE STAGGERED.

HOLD DOWN SCHEDULE					
MARK	HOLD DOWN	ATTACHMENT TO STUDS	FOUNDATION ANCHORS	MINIMUM STUDS	REMARKS
AA	SIMPSON MST48	(34) 16d SINKERS	N. A.	(2) 2x	SEE DETAILS ON S3.3
BB	SIMPSON MST72	(62) 16d SINKERS	N. A.	(2) 2x	SEE DETAILS ON S3.3

- ALL ANCHORS ARE SIMPSON STRONG-TIE. (OR EQUAL)
- INSTALLATION OF ALL HOLD DOWN ANCHORS AND STRAPS SHALL BE PER MANUFACTURES RECOMMENDATIONS AND SPECIFICATIONS
- PROVIDE EDGE NAILING ALONG STUDS CONNECTED TO HOLD DOWN ANCHORS AND STRAPS
- SEE SPECIAL INSPECTION PAGE FOR ADDITIONAL REQUIREMENTS

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY: J.D.A.
 CHECKED BY: J.D.A.
 SCALE: 1/4" = 1'-0"
 DATE: JULY 28, 2017
 JOB No. 17-089


UPPER FLOOR
 SHEARWALL
 PLAN

SHEET No.
S3.2


PLAN REVIEW-09/22/2017 PLAN REVIEW-09/05/2017



1 CONSTRUCTION DETAIL
S3.3 NO SCALE



2 CONSTRUCTION DETAIL
S3.3 NO SCALE




3 CONSTRUCTION DETAIL
S3.3 NO SCALE

NOT USED

3 CONSTRUCTION DETAIL
S3.3 NO SCALE

DYNAMIC STRUCTURES
1887 NORTH 1120 WEST PROVO, UTAH 84604
PH: (801) 356-1140 FAX: (801) 356-0001

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+



DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089


CONSTRUCTION DETAILS

SHEET No.
S3.3


PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017

NOT USED


10 CONSTRUCTION DETAIL
S4.1 NO SCALE



7 CONSTRUCTION DETAIL
S4.1 NO SCALE




4 CONSTRUCTION DETAIL
S4.1 NO SCALE




1 CONSTRUCTION DETAIL
S4.1 NO SCALE

NOT USED


11 CONSTRUCTION DETAIL
S4.1 NO SCALE




8 CONSTRUCTION DETAIL
S4.1 NO SCALE




5 CONSTRUCTION DETAIL
S4.1 NO SCALE




2 CONSTRUCTION DETAIL
S4.1 NO SCALE




12 CONSTRUCTION DETAIL
S4.1 NO SCALE



9 CONSTRUCTION DETAIL
S4.1 NO SCALE



6 CONSTRUCTION DETAIL
S4.1 NO SCALE




3 CONSTRUCTION DETAIL
S4.1 NO SCALE

DYNAMIC STRUCTURES

1887 NORTH 1120 WEST PROVO, UTAH 84604
PH: (801) 356-1140 FAX: (801) 356-0001

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089


CONSTRUCTION DETAILS

SHEET No.
S4.1


PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017




10 CONSTRUCTION DETAIL
S4.2 NO SCALE



7 CONSTRUCTION DETAIL
S4.2 NO SCALE



4 CONSTRUCTION DETAIL
S4.2 NO SCALE




1 CONSTRUCTION DETAIL
S4.2 NO SCALE

NOT USED


11 CONSTRUCTION DETAIL
S4.2 NO SCALE

NOT USED

8 CONSTRUCTION DETAIL
S4.2 NO SCALE




5 CONSTRUCTION DETAIL
S4.2 NO SCALE




2 CONSTRUCTION DETAIL
S4.2 NO SCALE

NOT USED


12 CONSTRUCTION DETAIL
S4.2 NO SCALE



9 CONSTRUCTION DETAIL
S4.2 NO SCALE



6 CONSTRUCTION DETAIL
S4.2 NO SCALE



3 CONSTRUCTION DETAIL
S4.2 NO SCALE

DYNAMIC STRUCTURES

1887 NORTH 1120 WEST PROVO, UTAH 84604
PH: (801) 356-1140 FAX: (801) 356-0001

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+


PROFESSIONAL STRUCTURAL ENGINEER
NO. 190917
JAY D. ADAMS
STATE OF UTAH
9/22/17

DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089


CONSTRUCTION DETAILS

SHEET No.
S4.2


PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017




7 CONSTRUCTION DETAIL
S4.3 NO SCALE




4 CONSTRUCTION DETAIL
S4.3 NO SCALE




1 CONSTRUCTION DETAIL
S4.3 NO SCALE




5 CONSTRUCTION DETAIL
S4.3 NO SCALE



2 CONSTRUCTION DETAIL
S4.3 NO SCALE



6 CONSTRUCTION DETAIL
S4.3 NO SCALE



3 CONSTRUCTION DETAIL
S4.3 NO SCALE

① = DIAPHRAGM EDGE NAILING
SEE FRAMING NOTES
② = SHEAR WALL EDGE NAILING
SEE SHEAR WALL PLAN

DYNAMIC STRUCTURES
1887 NORTH 1120 WEST PROVO, UTAH 84604
PH: (801) 356-1140 FAX: (801) 356-0001

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+

PROFESSIONAL STRUCTURAL ENGINEER
NO. 190917
JAY D. ADAMS
STATE OF UTAH
9/22/17

DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089


CONSTRUCTION DETAILS

SHEET No.
S4.3

PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017

NOT USED


10 CONSTRUCTION DETAIL
S5.1 NO SCALE




7 CONSTRUCTION DETAIL
S5.1 NO SCALE

NOT USED


4 CONSTRUCTION DETAIL
S5.1 NO SCALE




1 CONSTRUCTION DETAIL
S5.1 NO SCALE




11 CONSTRUCTION DETAIL
S5.1 NO SCALE




8 CONSTRUCTION DETAIL
S5.1 NO SCALE



5 CONSTRUCTION DETAIL
S5.1 NO SCALE




2 CONSTRUCTION DETAIL
S5.1 NO SCALE



9 CONSTRUCTION DETAIL
S5.1 NO SCALE

NOT USED


6 CONSTRUCTION DETAIL
S5.1 NO SCALE



3 CONSTRUCTION DETAIL
S5.1 NO SCALE

DYNAMIC STRUCTURES
1887 NORTH 1120 WEST PROVO, UTAH 84604
PH: (801) 356-1140 FAX: (801) 356-0001


Structural Plans for:
POWDER MOUNTAIN CABIN 1500+




DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089

CONSTRUCTION DETAILS
SHEET No.
S5.1


PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017




7 CONSTRUCTION DETAIL
S5.2 NO SCALE




4 CONSTRUCTION DETAIL
S5.2 NO SCALE




1 CONSTRUCTION DETAIL
S5.2 NO SCALE




8 CONSTRUCTION DETAIL
S5.2 NO SCALE




5 CONSTRUCTION DETAIL
S5.2 NO SCALE




2 CONSTRUCTION DETAIL
S5.2 NO SCALE




9 CONSTRUCTION DETAIL
S5.2 NO SCALE



6 CONSTRUCTION DETAIL
S5.2 NO SCALE




3 CONSTRUCTION DETAIL
S5.2 NO SCALE




DESIGNED BY: J.D.A.
CHECKED BY: J.D.A.
SCALE: AS SHOWN
DATE: JULY 28, 2017
JOB No. 17-089

CONSTRUCTION DETAILS


SHEET No.
S5.2



3 CONSTRUCTION DETAIL
S6.1 NO SCALE




3 CONSTRUCTION DETAIL
S6.1 NO SCALE




NOTE:
CONSTRUCT LENGTH OF BRIDGE TO PROVIDE NEAREST COMPLETE EQUAL NUMBER OF 4'-0" SEGMENTS EACH SIDE OF CENTERLINE NOT TO EXCEED 48'-0" OVERALL LENGTH

NOTE:
ALL CONTACT POINTS TO BE WELDED ALL AROUND WITH 3/8" FILLET WELDS. PROVIDE SHOP DRAWINGS OF ASSEMBLIES FOR REVIEW AND APPROVAL

4 SIDE ELEVATION
S6.1 NO SCALE




PLAN VIEW



NOTE:
ALL CONTACT POINTS TO BE WELDED ALL AROUND WITH 3/8" FILLET WELDS. PROVIDE SHOP DRAWINGS OF ASSEMBLIES FOR REVIEW AND APPROVAL


5 PLAN VIEW
S6.1 NO SCALE



SECTION VIEW

2 CONSTRUCTION DETAIL
S6.1 NO SCALE

Structural Plans for:
POWDER MOUNTAIN CABIN 1500+



DESIGNED BY:	J.D.A.
CHECKED BY:	J.D.A.
SCALE:	AS SHOWN
DATE:	JULY 28, 2017
JOB No.	17-089

CONSTRUCTION DETAILS

PLAN REVIEW-09/05/2017 PLAN REVIEW-09/22/2017