


Project Narrative/Notes/Revisions

1. 07/17/17 CK - COMPLETED DESIGN FOR CLIENT & CITY REVIEW.
2. 08/03/17 TP - REVISED PER INTERNAL REVIEW.
3. 10/17/17 CK - REVISED PER FINAL INTERNAL REVIEW.
4. 12/12/17 CK - UPDATED PER IRRIGATION COMMENTS DATED NOVEMBER 22 2017.
5. 04/03/18 CK - UPDATED PER COUNTY REVIEW COMMENTS.
6. 06/05/18 CK - UPDATED STREET NAMES.
7. 07/30/18 CK - REMOVED CATCH BASIN #4.
8. 02/06/19 CK - UPDATED STORM DRAIN & DETENTION BASIN.
9. 02/11/19 CK - CHANGED C-BASIN#4 TO A COMBO BOX.
10. 02/28/19 CK - REVISED DETENTION BASIN & DRAINAGE OUTFALL.
11. 03/14/19 CK - UPDATED CONTROL BOX DETAIL.


Cameron Cove Cluster Subdivision

Improvement Plans

WEBER COUNTY, UTAH
JUNE 2017




Vicinity Map
NOT TO SCALE



Sheet Index Key Map
NOT TO SCALE

Sheet Index

- Sheet 1 - Cover/Index Sheet
- Sheet 2 - Notes/Legend/Street Cross-Section
- Sheet 3 - 4000 West Street - 4+00.00 - 8+00.00
- Sheet 4 - 4065 West Street - 9+00.00 - 11+50.00
- Sheet 5 - 2375 South Street - 11+50.00 - 17+00.00
- Sheet 6 - 2375 South Street - 17+00.00 - 20+50.00
- Sheet 7 - 3925 West Street - 20+50.00 - 26+00.00
- Sheet 8 - 2275 South Street - 31+00.00 - 36+50.00
- Sheet 9 - 3900 West Street 36+00.00 - 40+00.00
- Sheet 10 - 3900 West Street 40+00.00 - 42+00.00
2200 South Street - 42+00.00 - 44+00.00
- Sheet 11 - Grading & Drainage Plan
- Sheet 12 - Utility Plan
- Sheet 13 - Storm Water Pollution Prevention Plan Exhibit
- Sheet 14 - Storm Water Pollution Prevention Plan Details
- Sheet L1 - Landscape Plan
- Sheet L2 - Landscape Details



Reeve
& Associates, Inc.

5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-8866 www.reeve-assoc.com
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CB#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Reeve & Associates, Inc. - Solutions You Can Build On

Cameron Cove Cluster Subdivision

WEBER COUNTY, UTAH

Cover/Index Sheet

PROFESSIONAL ENGINEER

THOMAS I. HUNT
03/22/2019
STATE OF UTAH

Project Info.

Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Sheet **16**

1

Sheets

Engineer's Notice To Contractors

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM AVAILABLE INFORMATION PROVIDED BY OTHERS. THE LOCATIONS SHOWN ARE APPROXIMATE AND SHALL BE CONFIRMED IN THE FIELD BY THE CONTRACTOR, SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO CONTACT THE UTILITY COMPANIES AND TAKE DUE PRECAUTIONARY MEASURE TO PROTECT ANY UTILITY LINES SHOWN, AND ANY OTHER LINES OBTAINED BY THE CONTRACTOR'S RESEARCH, AND OTHERS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.

Developer Contact:
 Doug Hamblin
 Hamblin Investments
 P.O. Box 625
 Roy, UT. 84067
 PH: (801) 725-3782

Blue Stakes Location Center
**Call: Toll Free
 1-800-662-4111**
 Two Working Days Before You Dig

1/4/2016 11:58:11 AM | n:\skinn | c:\3442\A48 - Cameron Village Cluster, West Weber\Improvements\Cameron Cove imp. 3-21-19.dwg

General Notes:

- 1. ALL CONSTRUCTION MUST STRICTLY FOLLOW THE STANDARDS AND SPECIFICATIONS SET FORTH BY: GOVERNING UTILITY MUNICIPALITY, GOVERNING COUNTY OR COUNTY INCORPORATED... 2. CONTRACTOR TO STRICTLY FOLLOW COMMENTS FOR THIS PROJECT... 3. TRAFFIC CONTROL, STRIPING & SIGNAGE TO CURRENT GOVERNING AGENCIES... 4. ANY AREA OUTSIDE THE LIMIT OF WORK THAT IS DISTURBED SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT NO COST TO OWNER... 5. CONSULT ALL OF THE DRAWINGS AND SPECIFICATIONS FOR COORDINATION REQUIREMENTS BEFORE COMMENCING CONSTRUCTION... 6. AT ALL LOCATIONS WHERE EXISTING PAVEMENT ABUTS NEW CONSTRUCTION, THE EDGE OF THE EXISTING PAVEMENT SHALL BE SAWCUT TO A CLEAN, SMOOTH EDGE... 7. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE MOST RECENT, ADOPTED EDITION OF ADA ACCESSIBILITY GUIDELINES... 8. PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING SURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED... 9. CONTRACTOR IS RESPONSIBLE FOR SCHEDULING AND NOTIFYING ENGINEER OR INSPECTING AUTHORITY 48 HOURS IN ADVANCE OF COVERING UP ANY PHASE OF CONSTRUCTION REQUIRING OBSERVATION... 10. ANY WORK IN THE PUBLIC RIGHT-OF-WAY WILL REQUIRE PERMITS FROM THE APPROPRIATE CITY, COUNTY OR STATE AGENCY... 11. ALL DIMENSIONS SHOWN ON THE PLANS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION... 12. CONTRACTOR MUST VERIFY ALL EXISTING CONDITIONS BEFORE BIDDING AND BRING UP ANY QUESTIONS BEFOREHAND... 13. SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH BY THE GEOTECHNICAL ENGINEER... 14. CATCH BASINS SHALL BE CONSTRUCTED AS SHOWN ON THESE PLANS... 15. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL FLAGGING, CAUTION SIGNS, LIGHTS, BARRICADES, FLAGMEN, AND ALL OTHER DEVICES NECESSARY FOR PUBLIC SAFETY... 16. CONTRACTOR SHALL AT THE TIME OF BIDDING AND THROUGHOUT THE PERIOD OF THE CONTRACT, BE LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED AND SHALL BE BONDABLE FOR AN AMOUNT EQUAL TO OR GREATER THAN THE AMOUNT BID AND TO DO THE TYPE OF WORK CONTEMPLATED IN THE PLANS AND SPECIFICATIONS... 17. CONTRACTOR SHALL INSPECT THE SITE OF THE WORK PRIOR TO BIDDING TO SATISFY HIMSELF BY PERSONAL EXAMINATION OR BY SUCH OTHER MEANS AS HE MAY PREFER OF THE LOCATIONS OF THE PROPOSED WORK AND OF THE ACTUAL CONDITIONS OF THE WORK... 18. CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE ALL WATER, POWER, SANITARY FACILITIES AND TELEPHONE SERVICES AS REQUIRED FOR THE CONTRACTOR'S USE DURING CONSTRUCTION... 19. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT PRIOR WRITTEN AUTHORIZATION FROM THE OWNER, ENGINEER, AND/OR GOVERNING AGENCIES... 20. CONTRACTOR SHALL EXERCISE DUE CAUTION AND SHALL CAREFULLY PRESERVE BENCH MARKS, CONTROL POINTS, REFERENCE POINTS AND ALL SURVEY STAKES... 21. CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF THIS PROJECT... 22. CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATELY SCHEDULING INSPECTION AND TESTING OF ALL FACILITIES COVERED UNDER THIS CONTRACT... 23. IF EXISTING IMPROVEMENTS NEED TO BE DISTURBED AND/OR REMOVED FOR THE PROPER PLACEMENT OF IMPROVEMENTS TO BE CONSTRUCTED BY THESE PLANS... 24. WHENEVER EXISTING FACILITIES ARE REMOVED, DAMAGED, BROKEN, OR CUT IN THE INSTALLATION OF THE WORK COVERED BY THESE PLANS... 25. CONTRACTOR SHALL MAINTAIN A NEATLY MARKED SET OF FULL-SIZE AS-BUILT RECORD DRAWINGS SHOWING THE FINAL LOCATION AND LAYOUT OF ALL STRUCTURES AND OTHER FACILITIES... 26. WHERE THE PLANS OR SPECIFICATIONS DESCRIBE PORTIONS OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL... 27. CONTRACTOR SHALL BE SKILLED AND REGULARLY ENGAGED IN THE GENERAL CLASS AND TYPE OF WORK CALLED FOR IN THE PROJECT PLANS AND SPECIFICATIONS... 28. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL STRIPING AND/OR PAVEMENT MARKINGS NECESSARY TO THE EXISTING STRIPING INTO FUTURE STRIPING... 29. CONTRACTOR SHALL PROVIDE ALL SHORING, BRACING, SLOPING OR OTHER PROVISIONS NECESSARY TO PROTECT WORKMEN FOR ALL AREAS TO BE EXCAVATED TO A DEPTH OF 4 FEET OR MORE... 30. ALL EXISTING GATES AND FENCES TO REMAIN UNLESS OTHERWISE NOTED ON PLANS...

Utility Notes:

- 1. CONTRACTOR SHALL COORDINATE LOCATION OF NEW "DRY UTILITIES" WITH THE APPROPRIATE UTILITY COMPANY, INCLUDING BUT NOT LIMITED TO: TELEPHONE SERVICE, GAS SERVICE, CABLE, POWER, INTERNET... 2. EXISTING UTILITIES HAVE BEEN SHOWN ON THE PLANS USING A COMBINATION OF ON-SITE SURVEYS (BY OTHERS), PRIOR TO COMMENCING ANY WORK... 3. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY CONFLICTS EXISTING PRIOR TO BEGINNING ANY EXCAVATION... 4. CARE SHOULD BE TAKEN IN ALL EXCAVATIONS DUE TO POSSIBLE EXISTENCE OF UNRECORDED UTILITY LINES... 5. ALL VALVES AND MANHOLE COVERS SHALL BE RAISED OR LOWERED TO MEET FINISHED GRADE... 6. CONTRACTOR SHALL CUT PIPES OFF FLUSH WITH THE INSIDE WALL OF THE BOX OR MANHOLE... 7. CONTRACTOR SHALL GROUT AT CONNECTION OF PIPE TO BOX WITH NON-SHRINKING GROUT... 8. CONTRACTOR SHALL GROUT WITH NON-SHRINK GROUT BETWEEN GRADE RINGS AND BETWEEN BOTTOM OF INLET LID FRAME AND TOP OF CONCRETE BOX... 9. SILT AND DEBRIS IS TO BE CLEANED OUT OF ALL STORM DRAIN BOXES... 10. CONTRACTOR SHALL CLEAN ASPHALT, TAR OR OTHER ADHESIVES OFF OF ALL MANHOLE LIDS AND INLET GRATES TO ALLOW ACCESS... 11. EACH TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND GRADE AS REQUIRED... 12. CONTRACTOR SHALL PROVIDE AND MAINTAIN AT ALL TIMES AMPLE MEANS AND DEVICES WITH WHICH TO REMOVE PROMPTLY AND TO PROPERLY DISPOSE OF ALL WATER ENTERING THE TRENCH EXCAVATION... 13. MAINTAIN A MINIMUM 18" VERTICAL SEPARATION DISTANCE BETWEEN ALL UTILITY CROSSINGS... 14. CONTRACTOR SHALL START INSTALLATION AT LOW POINT OF ALL NEW GRAVITY UTILITY LINES... 15. ALL BOLTED FITTINGS MUST BE GREASED AND WRAPPED... 16. UNLESS SPECIFICALLY NOTED OTHERWISE, MAINTAIN AT LEAST 2 FEET OF COVER OVER ALL STORM DRAIN LINES AT ALL TIMES... 17. ALL WATER LINES SHALL BE INSTALLED A MINIMUM OF 60" BELOW FINISHED GRADE... 18. ALL SEWER LINES AND SEWER SERVICES SHALL HAVE A MINIMUM SEPARATION OF 10 FEET... 19. CONTRACTOR SHALL INSTALL THRU-ROCKING AT ALL WATERLINE ANGLE POINTS AND TEES... 20. ALL UNDERGROUND UTILITIES SHALL BE IN PLACE PRIOR TO INSTALLATION OF CURB, GUTTER, SIDEWALK AND STREET PAVING... 21. CONTRACTOR SHALL INSTALL MAGNETIC LOCATING TAPE CONTINUOUSLY OVER ALL NONMETALLIC PIPE.

Erosion Control General Notes:

THE CONTRACTOR TO USE BEST MANAGEMENT PRACTICES FOR PROVIDING EROSION CONTROL FOR CONSTRUCTION OF THIS PROJECT. ALL MATERIAL AND WORKMANSHIP SHALL CONFORM TO GOVERNING AGENCIES ORDINANCES AND ALL WORK SHALL BE SUBJECT TO INSPECTION BY THE COUNTIES. ALSO, INSPECTORS WILL HAVE THE RIGHT TO CHANGE THE FACILITIES AS NEEDED.

CONTRACTOR SHALL KEEP THE SITE WATERED TO CONTROL DUST. CONTRACTOR TO LOCATE A NEARBY HYDRANT FOR USE AND TO INSTALL TEMPORARY METER. CONSTRUCTION WATER COST TO BE INCLUDED IN BID.

WHEN GRADING OPERATIONS ARE COMPLETED AND THE DISTURBED GROUND IS LEFT OPEN FOR 14 DAYS OR MORE, THE AREA SHALL BE FURROWED PARALLEL TO THE CONTOURS.

THE CONTRACTOR SHALL MODIFY EROSION CONTROL MEASURES TO ACCOMMODATE PROJECT PLANNING.

ALL ACCESS TO PROPERTY WILL BE FROM PUBLIC RIGHT-OF-WAYS. THE CONTRACTOR IS REQUIRED BY STATE AND FEDERAL REGULATIONS TO PREPARE A STORM WATER POLLUTION PREVENTION PLAN AND FILE A "NOTICE OF INTENT" WITH THE GOVERNING AGENCIES.

Maintenance:

ALL BEST MANAGEMENT PRACTICES (BMP'S) SHOWN ON THIS PLAN MUST BE MAINTAINED AT ALL TIMES UNTIL PROJECT CLOSE-OUT.

THE CONTRACTOR'S RESPONSIBILITY SHALL INCLUDE MAKING BI-WEEKLY CHECKS ON ALL EROSION CONTROL MEASURES TO DETERMINE IF REPAIR OR SEDIMENT REMOVAL IS NECESSARY. CHECKS SHALL BE DOCUMENTED AND COPIES OF THE INSPECTIONS KEPT ON SITE.

SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL. THEY MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF BARRIER.

SEDIMENT TRACKED ON PAVED ROADS MUST BE CLEANED UP AS SOON AS PRACTICAL, BUT IN NO CASE LATER THAN THE END OF THE NORMAL WORK DAY. THE CLEAN UP WILL INCLUDE SWEEPING OF THE TRACKED MATERIAL, PICKING IT UP, AND DEPOSITING IT TO A CONTAINED AREA.

EXPOSED SLOPES:

- ANY EXPOSED SLOPE THAT WILL REMAIN UNTOUCHED FOR LONGER THAN 14 DAYS MUST BE STABILIZED BY ONE OR MORE OF THE FOLLOWING METHODS: A) SPRAYING DISTURBED AREAS WITH A TACKIFIER VIA HYDROSEED B) TRACKING STRAW PERPENDICULAR TO SLOPES C) INSTALLING A LIGHT-WEIGHT, TEMPORARY EROSION CONTROL BLANKET

Master Legend

Table with 3 columns: Symbol, Description, and Additional Info. Includes items like PROPOSED CULINARY WATER LINE, EXISTING CATCH BASIN, LINEAR FEET, NATURAL GRADE, ON CENTER, POINT OF CURVE, POINT OF REVERSE CURVE, POINT OF TANGENT, POWER/UTILITY POLE, REBAR & CAP, REINFORCED CONCRETE BOX, REINFORCED CONCRETE PIPE, RIM OF MANHOLE, RIGHT-OF-WAY, STORM DRAIN, SANITARY SEWER, STOP SIGN, SECONDARY WATER, TOP BACK OF CURB, TOE OF SLOPE, TOP OF SLOPE, TOP OF WALL, TOP OF SIDEWALK, VERTICAL POINT OF INTERSECT, CULINARY WATER, WATER METER, PROPOSED PAVEMENT, PROPOSED CONCRETE, SEWER EASEMENT.

General Project Notes:

- 1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE DEVELOPMENT STANDARDS OF WEBER COUNTY AND THE STANDARD DRAWINGS CONTROLLED BY THE ENGINEER, WEBER COUNTY PUBLIC WORKS REQUIREMENTS SHALL BE MET... 2. THE LOCATION OF EXISTING UTILITIES SHOWN ARE APPROXIMATE ONLY AND THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UTILITIES SHOWN OR NOT SHOWN ON THESE PLANS... 3. THE STREET STRUCTURAL CROSS SECTION IS PER WEBER COUNTY DETAILS CONTAINED WITHIN THESE PLANS, MODIFIED AS INSTRUCTED BY COUNTY REVIEW... 4. WATER LINE PIPE SHALL BE PVC C-900 CLASS 200. WASHOUT ASSEMBLIES SHALL CONSIST OF A KUPFERLE FOUNDRY CO. 2" BLOW-OFF HYDRANT (OR COUNTY-APPROVED EQUIV.)... 5. SECONDARY WATER LINE SHALL BE PVC C-900 CLASS 200. ALL SECONDARY WATER VALVE LIDS SHALL BE STAMPED "IRRIGATION".

Secondary Water Notes:


- 1. ALL SECONDARY WATER SHALL BE IN CONFORMANCE WITH HOOPER IRRIGATION WATER STANDARDS... 2. ALL SECONDARY WATER MAINS TO HAVE A MINIMUM OF 2.5' OF COVER... 3. A LOCATION RIBBON MUST BE INSTALLED ABOVE THE WATER MAIN IN ACCORDANCE WITH HOOPER IRRIGATION STANDARDS... 4. CONTRACTOR MUST FILE FOR A LICENSE AGREEMENT FOR EVERY UTILITY CROSSING OF HOOPER IRRIGATION CANALS. THIS AGREEMENT MUST BE ACCOMPANIED WITH A COPY OF THE PLANS FOR THE CROSSING ALONG WITH THE FEES TO BE PAID. THERE NEEDS TO BE AT LEAST 2' VERTICAL SEPARATION FROM THE BOTTOM OF THE CANAL. THIS APPLIES TO BOTH THE CANAL ON 2200 SOUTH AND THE CANAL ON THE SOUTH END OF THE DEVELOPMENT.

Reeve & Associates, Inc. logo and contact information: 5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405. TEL: (801) 641-1000 FAX: (801) 641-8666 www.reeve-assoc.com

REVISIONS table with columns: DATE, DESCRIPTION, and a list of revision dates from 12-12-17 to 03-14-19.

Survey Control Note:

THE CONTRACTOR OR SURVEYOR SHALL BE RESPONSIBLE FOR FOLLOWING THE NATIONAL SOCIETY OF PROFESSIONAL SURVEYORS (NSPS) MODEL STANDARDS FOR ANY SURVEYING OR CONSTRUCTION LAYOUT TO BE COMPLETED USING REEVE & ASSOCIATES, INC. SURVEY DATA OR CONSTRUCTION IMPROVEMENT PLANS. PRIOR TO PROCEEDING WITH CONSTRUCTION STAKING, THE SURVEYOR SHALL BE RESPONSIBLE FOR VERIFYING HORIZONTAL CONTROL FROM THE SURVEY MONUMENTS AND FOR VERIFYING ANY ADDITIONAL CONTROL POINTS SHOWN ON AN ALTA SURVEY, IMPROVEMENT PLAN, OR ANY ELECTRONIC DATA PROVIDED.




ADA Ramp Detail SCALE: NONE

Flood Information Data:


FLOOD ZONE DESIGNATION "X" PER F.E.M.A. FLOOD INSURANCE RATE MAPS, COMMUNITY PANEL NUMBERS 49057C0425E DATED DECEMBER 16, 2005.

AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN.


(THE ABOVE STATEMENT IS FOR INFORMATION ONLY AND THE SURVEYOR ASSUMES NO LIABILITY FOR THE CORRECTNESS OF THE CITED MAP OR THE LOCATION OF THE FLOOD ZONE BOUNDARY. IN ADDITION, THE ABOVE STATEMENT DOES NOT REPRESENT THE SURVEYOR'S OPINION OF THE PROBABILITY OF FLOODING.)




Sidewalk Section SCALE: NONE



4' Concrete Waterway SCALE: NONE



On-Site 'L' Type Curb & Gutter SCALE: NONE



Street Section (66'/60' R.O.W.) SCALE: NONE *VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.



NOTE: THESE PAVEMENT THICKNESS SHALL BE CONSIDERED AS MINIMUMS AND MAY BE INCREASED BY THE COUNTY ENGINEER WHEN THE SUBGRADE C.B.R. IS LESS THAN 10 OR WHEN A GREATER DEPTH IS NECESSARY TO PROVIDE SUFFICIENT STABILITY. DEVELOPER MAY SUBMIT AN ALTERNATIVE PAVEMENT DESIGN BASED ON A SOILS ANALYSIS FOR APPROVAL BY THE COUNTY ENGINEER. COMPACTION TESTS ON BOTH SUB-BASE AND BASE COURSES WILL BE REQUIRED.

Cameron Cove Cluster Subdivision Notes/Legend/Street Cross-Section. WEBER COUNTY, UTAH

PROFESSIONAL ENGINEER THOMAS J. RUBY 03/22/2019 STATE OF UTAH


Project Info. Engineer: J. NATE REEVE, P.E. Drafter: C. KINGSLEY. Begin Date: JUNE 2017. Name: CAMERON COVE CLUSTER SUBDIVISION. Number: 3442-A48

Sheet 2 of 16 Sheets



#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	89°54'36"	20.00'	31.38'	19.97'	N44°14'27"W	28.26'
C14	90°05'24"	20.00'	31.45'	20.03'	S45°45'33"W	28.31'

NOTE:
 ADA RAMP PER MODIFIED APWA
 235 EXAMPLE A WITH FLARED
 TRANSITION PER APWA 238.
 SEE DETAIL SHEET 2




- Construction Notes:**
- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
 W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
 SD/12 - 12" RCP STORM DRAIN
 SD/15 - 15" RCP STORM DRAIN
 SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
 SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE
 SW - 2" PVC C-900 SECONDARY WATER LATERAL

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-2666 www.reeve-assoc.com
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

TRA



DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
 WEBER COUNTY, UTAH
4000 West Street
4+00.00 - 8+00.00



Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
 Two Working Days Before You Dig





TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C2	32°38'13"	39.50'	22.50'	11.56'	S74°29'09"W	22.20'
C3	155°22'29"	55.50'	150.50'	254.28'	S44°08'43"E	108.45'
C4	32°45'45"	39.50'	22.59'	11.61'	N17°09'39"E	22.28'
C5	89°58'31"	39.50'	62.03'	39.48'	S44°12'29"E	55.85'


Centerline Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	89°58'31"	60.00'	94.22'	59.97'	S44°12'29"E	84.83'



- Construction Notes:**
- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
SD/12 - 12" RCP STORM DRAIN
SD/15 - 15" RCP STORM DRAIN
SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE
SW - 2" PVC C-900 SECONDARY WATER LATERAL


Reeve & Associates, Inc.
5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
TEL: (801) 621-1000 FAX: (801) 621-1866 www.reeve-assoc.com
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • LANDSCAPE ARCHITECTS



REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH
4065 West Street
9+00.00 - 11+50.00




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafted: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig



NOTE:
 ADA RAMP PER MODIFIED APWA
 235 EXAMPLE A WITH FLARED
 TRANSITION PER APWA 238.
 SEE DETAIL SHEET 2

Key Map NOT TO SCALE




Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
 W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
 SD/12 - 12" RCP STORM DRAIN
 SD/15 - 15" RCP STORM DRAIN
 SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
 SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE
 SW - 2" PVC C-900 SECONDARY WATER LATERAL



TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C1	89°54'36"	20.00'	31.38'	19.97'	N44°14'27"W	28.26'
C14	90°05'24"	20.00'	31.45'	20.03'	S45°45'33"W	28.31'



Blue Stakes Location Center
Call: Toll Free
1-800-662-4111
 Two Working Days Before You Dig

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-2666 WWW.REEVE-ASSOCIATES.COM
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

TRA

REVISIONS




DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Structure
02-11-19	CK Swapped Basin
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
 WEBER COUNTY, UTAH
2375 South Street
11+50.00 - 17+00.00

PROFESSIONAL ENGINEER
 THOMAS J. BUNT
 03/22/2019
 STATE OF UTAH

Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Sheet **5** of **16** Sheets



- Construction Notes:**
- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
SD/12 - 12" RCP STORM DRAIN
SD/15 - 15" RCP STORM DRAIN
SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE
SW - 2" PVC C-900 SECONDARY WATER LATERAL

Reeve & Associates, Inc.
5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
TEL: (801) 621-1000 FAX: (801) 621-2666 www.reeve-assoc.com
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


TRA

REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail


Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH

2375 South Street
17+00.00 - 20+50.00




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig



Key Map NOT TO SCALE



Construction Notes:

1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.

CULINARY WATER
W/10 - 10" PVC C-900 CLASS 200 WATER

STORM DRAIN
SD/12 - 12" RCP STORM DRAIN
SD/15 - 15" RCP STORM DRAIN
SD/18 - 18" RCP STORM DRAIN



SANITARY SEWER
SS/8 - 8" PVC C-900 SEWER LINE

SECONDARY WATER
SW/8 - 8" PVC C-900 SECONDARY WATER LINE
SW - 2" PVC C-900 SECONDARY WATER LATERAL

TBC Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C7	89°56'11"	20.00'	31.39'	19.98'	N44°15'09"W	28.27'
C10	90°03'49"	20.00'	31.44'	20.02'	S45°44'51"W	28.30'

NOTE:
ADA RAMP PER MODIFIED APWA
235 EXAMPLE A WITH FLARED
TRANSITION PER APWA 238.
SEE DETAIL SHEET 2




Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Reeve & Associates, Inc.
5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405
TEL: (801) 621-1000 FAX: (801) 621-2666 www.reeve-assoc.com
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH
3925 West Street
20+50.00 - 26+00.00





Project Info.
Engineer: J. NATE REEVE, P.E.
Drafted: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48




NOTE:
 ADA RAMPS PER MODIFIED APWA
 235 EXAMPLE A WITH FLARED
 TRANSITION PER APWA 238.
 SEE DETAIL SHEET 2

#	Delta	Radius	Length	Tangent	Chord	CH Length
C7	89°56'11"	20.00'	31.39'	19.98'	N44°15'09"W	28.27'
C10	90°03'49"	20.00'	31.44'	20.02'	S45°44'51"W	28.30'



- Construction Notes:**
- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
 W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
 SD/12 - 12" RCP STORM DRAIN
 SD/15 - 15" RCP STORM DRAIN
 SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
 SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE
 SW - 2" PVC C-900 SECONDARY WATER LATERAL




Blue Stakes Location Center
Call: Toll Free
1-800-662-4111
 Two Working Days Before You Dig

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-1666 WWW.REEVE-ASSOCIATES.COM
 LAND SURVEYORS • CIVIL ENGINEERS • LAND SURVEYORS
 WATER ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISONS


DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
 WEBER COUNTY, UTAH
2275 South Street
31+00.00 - 36+50.00




Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Sheet **16**
8 Sheets



NOTE: INSTALL STREET SECTION TO CROWN @ CL




TBC Curve Data


#	Delta	Radius	Length	Tangent	Chord	CH Length
C8	90°03'49"	20.00'	31.44'	20.02'	N45°44'51"E	28.30'

Centerline Curve Data

#	Delta	Radius	Length	Tangent	Chord	CH Length
C3	90°03'53"	40.50'	63.66'	40.55'	N45°44'49"E	57.31'



Key Map NOT TO SCALE



Construction Notes:

1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.

CULINARY WATER
W/10 - 10" PVC C-900 CLASS 200 WATER

STORM DRAIN
SD/12 - 12" RCP STORM DRAIN
SD/15 - 15" RCP STORM DRAIN
SD/18 - 18" RCP STORM DRAIN

SANITARY SEWER
SS/8 - 8" PVC C-900 SEWER LINE


SECONDARY WATER
SW/8 - 8" PVC C-900 SECONDARY WATER LINE
SW - 2" PVC C-900 SECONDARY WATER LATERAL

Reeve & Associates, Inc.
5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-1000 FAX: (801) 621-2666 www.reeve-assoc.com
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Structure
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail


Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH
3900 West Street
36+00.00 - 40+00.00





Project Info.
Engineer: J. NATE REEVE, P.E.
Draftsman: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig





1/4/2016 | rfskln | G:\3442\448 - Cameron Village Cluster - West Weber\Improvements\Cameron Cove Imp 3-21-19.dwg



NOTE:
 ADA RAMP PER MODIFIED APWA
 235 EXAMPLE A WITH FLARED
 TRANSITION PER APWA 238.
 SEE DETAIL SHEET 2



TBC Curve Data						
#	Delta	Radius	Length	Tangent	Chord	CH Length
C9	89°56'28"	20.00'	31.40'	19.98'	N44°15'17"W	28.27'



- Construction Notes:**
- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CULINARY WATER**
 W/10 - 10" PVC C-900 CLASS 200 WATER
- STORM DRAIN**
 SD/12 - 12" RCP STORM DRAIN
 SD/15 - 15" RCP STORM DRAIN
 SD/18 - 18" RCP STORM DRAIN
- SANITARY SEWER**
 SS/8 - 8" PVC C-900 SEWER LINE
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE
 SW - 2" PVC C-900 SECONDARY WATER LATERAL

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-2666 WWW.REEVE-ASSOC.COM

PROFESSIONAL ENGINEER
 THOMAS J. BUNT
 03/22/2019
 STATE OF UTAH

Revisions:

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed Basin
02-06-19	CK Updated Structure
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
 WEBER COUNTY, UTAH

3900 West Street
2200 South Street
40+00 - 42+00
42+00 - 44+00

Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
 Two Working Days Before You Dig

Sheet **10** of **16** Sheets

Existing Detention Basin

Combined Storm Runoff Calculations Cameron Crossing, Cameron Cove & Mallard Springs Subdivisions 4/6/2017 rhh

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken from data compiled by NOAA Atlas14, using a 100-year storm event.

Runoff storm water has been calculated for two different sets of conditions, one being the existing undeveloped land and the other with land fully improved. The difference between the two quantities will be retained in a holding pond and discharged at its historical rate of 0.1 cfs/acre.

In case of a storm even greater than the 100-year storm, an emergency spillway has been designed for the storm water to overtop the baffle wall in the control box and follow its historical path.

The calculations are as follows:

1. Project Site Drainage Area:

Runoff Coefficients		
Paved Area	441,213	C = 0.95
Landscaped Area	1,663,351	C = 0.20
Roof	190,136	C = 0.95
Weighted Runoff Coefficient		
		C = 0.41

2. Time of Concentration:

Tc from Project Site = 60 minutes

3. Rainfall Intensities:

Rainfall Intensities were obtained from the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken and compiled by NOAA Atlas 14 for the 100-year storm event.

Rainfall Intensity for a 60 minute Time of Concentration 1.74 in/hr

4. Peak Run-off:

Runoff Coefficient	C = 0.41
Rainfall Intensity	i = 1.74 IN./HR.
Acres	A = 52.68 ACRES
Runoff Quantity	Q = CIA
Q (total)	Q = 37.25 cfs

5. Allowable Discharge:

Allowable Discharge of Storm Water Volume (pre-development) is 0.1 cfs per acre.
Allowable Discharge Q = (0.1 x acres)

Allowable Discharge =	Q = 5.91 cfs	(total allowable discharge)
Limit Basin to =	Q = 1.05 cfs	(total - peak flow from cameron crossing)

SEE SHEET 12 FOR DETENTION BASIN #2 CALCULATIONS

6. Volume of Run-off for 100-year Storm Event

C = 0.41
A = 52.68
Q(out) = 1.05 (based on combined allowed outflow)

time (min)	time (sec)	i (in./hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0	0	0
5	300	6.64	142.14	42641	316	42325
10	600	5.05	108.10	64861	632	64229
15	900	4.17	89.26	80337	948	79389
30	1800	2.91	60.15	108272	1896	106377
60	3600	1.74	37.25	134088	3791	130297
180	10800	0.65	13.91	150271	11374	138898
360	21600	0.36	7.71	166454	22747	143707
720	43200	0.22	4.71	203444	45495	157950
1440	86400	0.13	2.78	240434	90989	149445



7. Orifice Sizing

Given: Q = 1.05 cfs (0.1 cfs/acre)
2g = 64.4 ft/s²
H = 3.50 ft
Cd = 0.7 for circular openings
D = SQRT(Q/(0.7*(64.4*H)^(0.5)))
D = 0.32 feet
D = 3.80 inches


SUMMARY:

The required volume of the detention basin is **138,898 cubic feet**
Orifice Diameter at Outlet is **3.80 inches**

USE A 4" Ø ORIFICE FOR CONSTRUCTABILITY




Section




Plan

Detention Basin #2 Control Box

SCALE: 1" = 2'



Section A-A
SCALE: NO SCALE



Reeve & Associates, Inc.
1810 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-1100 FAX: (801) 621-1866 www.reeve-assoc.com
LAND SURVEYORS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

TRA

REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
08-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH

Grading & Drainage Plan

PROFESSIONAL ENGINEER
THOMAS J. RUBY
03/22/2019
STATE OF UTAH

Project Info.
Engineer: J. NATE REEVE, P.E.
Drafted: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48

Sheet **11** of **16** Sheets

1/4/2016 | rfrickin | G:\3442\A48 - Cameron Village Cluster - West Weber\Improvements\Cameron Cove Imp 3-21-19.dwg

Detention Basin#2

Storm Runoff Calculations Cameron Cove Subdivision- Secondary Basin

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken from data compiled by NOAA Atlas14, using a 100-year storm event.

Runoff storm water has been calculated for two different sets of conditions, one being the existing undeveloped land and the other with land fully improved. The difference between the two quantities will be retained in a holding pond and discharged at its historical rate of 0.2 cfs/acre.

In case of a storm even greater than the 100-year storm, an emergency spillway has been designed for the storm water to overtop the baffle wall in the control box and follow its historical path.

The calculations are as follows:

1. Project Site Drainage Area:

Runoff Coefficients			
Paved Area	258,660	C = 0.95	
Landscaped Area	867,219	C = 0.20	
Roof	95,000	C = 0.95	
Weighted Runoff Coefficient		C = 0.42	

2. Time of Concentration:

Tc from Project Site =	60	minutes
------------------------	----	---------

3. Rainfall Intensities:
Rainfall Intensities were obtained from the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT are taken and compiled by NOAA Atlas 14 for the 100-year storm event.
Rainfall Intensity for a 60 minute Time of Concentration = 1.74 in/hr

4. Peak Run-off:

Runoff Coefficient	C = 0.42
Rainfall Intensity	i = 1.74 IN./HR.
Acreage	A = 1.69 ACRES
Runoff Quantity	Q = CIA
Q (total)	Q = 1.22 cfs

5. Allowable Discharge:
Allowable Discharge of Storm Water Volume (pre-development) is 0.1cfs per acre.
Allowable Discharge Q = (0.1 x acres)
Allowable Discharge = Q = 0.17 cfs

SEE SHEET 11 FOR EXISTING
DETENTION BASIN CALCULATIONS

6. Volume of Run-off for 100-year Storm Event

C =	0.42					
A =	1.69					
Q(out) =	0.17 (based on 0.1 cfs/acre)					
time (min)	time (sec)	i (in./hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0	0	0
5	300	6.64	4.87	1401	51	1351
10	600	5.05	3.55	2132	101	2031
15	900	4.17	2.93	2640	152	2489
30	1800	2.81	1.98	3559	304	3255
60	3600	1.74	1.22	4407	607	3800
180	10800	0.65	0.46	4939	1821	3118
360	21600	0.36	0.25	5471	3642	1829
720	43200	0.22	0.15	6886	7284	-598
1440	86400	0.13	0.09	7902	14568	-6666

Required Detention Volume **3800 c.f.**



7. Orifice Sizing

Given:

Q =	0.34	cfs	(0.1 cfs/acre)
2g =	64.4	ft/s ²	
H =	3.50	ft	
Cd =	0.7		for circular openings
D =	SQRT(Q/(0.7*(64.4*H)^0.5))		
D =	0.18	feet	
D =	2.15	inches	

SUMMARY:

The required volume of the detention basin is **2.15** **3,800** cubic feet
Orifice Diameter at Outlet is **2.15** **inches**
USE A 3"Ø ORIFICE FOR CONSTRUCTABILITY



Reeve & Associates, Inc.
1800 SOUTH 1500 WEST RIVERDALE, UTAH 84405
TEL: (801) 621-1000 FAX: (801) 621-1066 www.reeve-assoc.com
LAND SURVEYORS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-06-19	CK Updated Basin
02-11-19	CK Swapped Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail



Cameron Cove Cluster Subdivision
WEBER COUNTY, UTAH

Utility Plan

Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: C. KINGSLEY
Begin Date: JUNE 2017
Name: CAMERON COVE CLUSTER SUBDIVISION
Number: 3442-A48

Cameron Cove Cluster Subdivision Improvement Plans


WEBER COUNTY, UTAH
MARCH 2018



STREETS TO BE SWEEPED WITHIN 1000 FEET OF CONSTRUCTION ENTRANCE DAILY IF NECESSARY.

ALL VEHICLES EXITING SITE TO PROCEED THROUGH CONSTRUCTION ENTRANCE TO REDUCE AMOUNTS OF SEDIMENT TRACKED ONTO ROADWAYS.

50'x20' CONSTRUCTION ENTRANCE W/8" CLEAN GRAVEL



Reeve & Associates, Inc. - Solutions You Can Build On

1/4/2016 | nficklin | G:\3442\A48 - Cameron Village Cluster, West Weber\Improvements\Cameron Cove Imp 3--21--19.dwg

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF REEVE & ASSOCIATES, INC., 5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405, AND SHALL NOT BE PHOTOCOPIED, RE-DRAWN, OR USED ON ANY PROJECT OTHER THAN THE PROJECT SPECIFICALLY DESIGNED FOR, WITHOUT THEIR WRITTEN PERMISSION. THE OWNERS AND ENGINEERS OF REEVE & ASSOCIATES, INC. DISCLAIM ANY LIABILITY FOR ANY CHANGES OR MODIFICATIONS MADE TO THESE PLANS OR THE DESIGN THEREON WITHOUT THEIR CONSENT.




REVISIONS	DATE	DESCRIPTION
	12-12-17	CK Irrigation Comments
	04-03-18	CK County Review
	06-05-18	CK Street Names
	07-30-18	CK Removed CH#4
	02-08-19	CK Updated Basin
	02-11-19	CK Swapped Structure
	02-28-19	CK Updated Basin
	03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision

WEBER COUNTY, UTAH

Storm Water Pollution Prevention Plan Exhibit




Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Construction Activity Schedule

- PROJECT LOCATION.....WEST HAVEN CITY, WEBER COUNTY, UTAH
- PROJECT BEGINNING DATE.....MARCH 2018
- BMP'S DEPLOYMENT DATE.....MARCH 2018
- STORM WATER MANAGEMENT CONTACT / INSPECTOR.....DOUG HAMBLIN (801) 725-3782
- SPECIFIC CONSTRUCTION SCHEDULE INCLUDING BMP CONSTRUCTION SCHEDULE TO BE INCLUDED WITH SWPPP BY OWNER/DEVELOPER


Notes:

- Describe all BMP's to protect storm water inlets:
All storm water inlets to be protected by straw wattle barriers, or gravel bags (see detail).
- Describe BMP's to eliminate/reduce contamination of storm water from:
 - Equipment / building / concrete wash areas:
To be performed in designated areas only and surrounded with silt fence barriers.
 - Soil contaminated by soil amendments:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Areas of contaminated soil:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Fueling area:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle maintenance areas:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle parking areas:
To be performed in designated areas only and surrounded with silt fence.
 - Equipment storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Materials storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Waste containment areas:
To be performed in designated areas only and surrounded with silt fence.
 - Service areas:
To be performed in designated areas only and surrounded with silt fence.
- BMP's for wind erosion:
Stockpiles and site as needed to be watered regularly to eliminate / control wind erosion
- Construction Vehicles and Equipment:
 - Maintenance
 - Maintain all construction equipment to prevent oil or other fluid leaks.
 - Keep vehicles and equipment clean, prevent excessive build-up of oil and grease.
 - Regularly inspect on-site vehicles and equipment for leaks, and repair immediately.
 - Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment on-site.
 - Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic, and transmission fluids.
 - Fueling
 - If fueling must occur on-site, use designated areas away from drainage.
 - Locate on-site fuel storage tanks within a bermed area designed to hold the tank volume.
 - Cover retention area with an impervious material and install in a manner to ensure that any spills will be contained in the retention area. To catch spills or leaks when removing or changing fluids.
 - Use drip pans for any oil or fluid changes.
 - Washing
 - Use as little water as possible to avoid installing erosion and sediment controls for the wash area.
 - If washing must occur on-site, use designated, bermed wash areas to prevent waste water discharge into storm water, creeks, rivers, and other water bodies.
 - Use phosphate-free, biodegradable soaps.
 - Do not permit steam cleaning on-site.
- Spill Prevention and Control
 - Minor Spills:
Minor spills are those which are likely to be controlled by on-site personnel. After contacting local emergency response agencies, the following actions should occur upon discovery of a minor spill:
 - Contain the spread of the spill.
 - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (i.e. absorbent materials, cat litter, and / or rags).
 - If the spill occurs in dirt areas, immediately contain the spill by constructing an earth dike. Dig up and properly dispose of contaminated soil.
 - If the spill occurs during rain, cover the impacted area to avoid runoff.
 - Record all steps taken to report and contain spill.
 - Major Spills:
On-site personnel should not attempt to control major spills until the appropriate and qualified emergency response staff have arrived at the site. For spills of federal reportable quantities, also notify the National Response Center at (800) 424-8802. A written report should be sent to all notified authorities. Failure to report major spills can result in significant fines and penalties.
- Post Roadway / Utility Construction
 - Maintain good housekeeping practices.
 - Enclose or cover building material storage areas.
 - Properly store materials such as paints and solvents.
 - Store dry and wet materials under cover, away from drainage areas.
 - Avoid mixing excess amounts of fresh concrete or cement on-site.
 - Perform washout of concrete trucks offsite or in designated areas only.
 - Do not wash out concrete trucks into storm drains, open ditches, streets or streams.
 - Do not place material or debris into streams, gutters or catch basins that stop or reduce the flow of runoff water.
 - All public streets and storm drain facilities shall be maintained free of building materials, mud and debris caused by grading or construction operations. Roads will be swept within 1000' of construction entrance daily, if necessary.
 - Install straw wattle around all inlets contained within the development and all others that receive runoff from the development.
- Erosion Control Plan Notes
 - The contractor will designate an emergency contact that can be reached 24 hours a day 7 days a week.
 - A stand-by crew for emergency work shall be available at all times during potential rain or snow runoff events. Necessary materials shall be available on site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain or runoff is eminent.
 - Erosion control devices shown on the plans and approved for the project may not be removed without approval of the engineer of record. If devices are removed, no work may continue that have the potential of erosion without consulting the engineer of record. If deemed necessary erosion control should be reestablished before this work begins.
 - Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of the slope at the conclusion of each working day. This should be confirmed by survey or other means acceptable to the engineer of record.
 - All silt and debris shall be removed from all devices within 24 hours after each rain or runoff event.
 - Except as otherwise approved by the inspector, all removable protective devices shown shall be in place at the end of each working day and through weekends until removal of the system is approved.
 - All loose soil and debris, which may create a potential hazard to offsite property, shall be removed from the site as directed by the engineer of record of the governing agency.
 - The placement of additional devices to reduce erosion damage within the site is left to the discretion of the engineer of record.
 - Desilting basins may not be removed or made inoperable without the approval of the engineer of record and the governing agency.
 - Erosion control devices will be modified as need as the project progresses and plans of these changes submitted for approval by the engineer of record and the governing agency.
- Conduct a minimum of one inspection of the erosion and sediment controls every two weeks. Maintain documentation on site.
 - Part III.D.4 of general permit UTR300000 identifies the minimum inspection requirements.
 - Part II.D.4.C identifies the minimum inspection report requirements.
 - Failure to complete and/or document storm water inspections is a violation of part III.D.4 of Utah General Permit UTR 300000.



Perspective View

Figure 2



Section

INSTALLATION

The silt fence should be installed prior to major soil disturbances in the drainage area. The fence should be placed across the slope along a line of uniform elevation wherever flow of sediment is anticipated. Table 1 shows generally-recommended maximum slope lengths (slope spacing between fences) at various site grades for most silt fence applications.


Slope Steepness (%)	Max. Slope Length (m)	Max. Slope Length (ft)
<2%	30.5m	(100ft)
2-5%	22.9m	(75ft)
5-10%	15.2m	(50ft)
10-20%	7.6m	(25ft)
>20%	4.5m	(15ft)

PREFABRICATED SILT FENCE ROLLS
 *Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location.
 *Unroll the silt fence, positioning the post against the downstream wall of the trench.
 *Adjacent rolls of silt fence should be joined by nesting the end post of one fence into the other. Before nesting the end posts, rotate each post until the geotextile is wrapped completely around the post, then about the end posts to create a tight seal as shown in Figure 1.
 *Drive posts into the ground until the required fence height and/or anchorage depth is obtained.
 *Bury the loose geotextile at the bottom of the fence in the upstream trench and backfill with natural soil, tamping the backfill to provide good compaction and anchorage. Figure 2 illustrates a typical silt fence installation and anchor trench placement.

should generally be less than three (3) times the height of the fence.
 *If a steel or plastic mesh is required to reinforce the geotextile, it shall have a minimum mesh opening of 15.2cm (6").
 *Fasten the mesh to the upslope side of the posts using heavy duty wire staples, tie wires or hog strings. Extend the mesh into the bottom of the trench.
 *The geotextile shall then be stapled or wired to the posts. An extra 20-50cm (8-20") of geotextile shall extend into the trench.


INSPECTION
 *Inspect the silt fence daily during periods of rainfall, immediately after significant rainfall event and weekly during periods of no rainfall. Make any repairs immediately.
 *When sediment deposits behind the silt fence are one-third of the fence height, remove and properly dispose of the silt accumulations. Avoid damage to the fabric during cleanout.

REMOVAL
 *Silt fence should not be removed until construction ceases and the upslope area has been properly stabilized and/or revegetated.




Silt Fence Detail

SCALE: NONE




Concrete Washout Area w/ 10 mil Plastic Liner


SCALE: NONE




Inlet Box Protection




Plan View



Drop Inlet Protection



Stake Detail



Cross Section 50' x 20' Construction Entrance

Reeve & Associates, Inc.
IRA
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-1000 FAX: (801) 621-1866 www.reeve-assoc.com
 LAND OWNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

DATE	DESCRIPTION
12-12-17	CK Irrigation Comments
04-03-18	CK County Review
06-05-18	CK Street Names
07-30-18	CK Removed CH#4
02-11-19	CK Updated Structure
02-28-19	CK Updated Basin
03-14-19	CK CTRL Box Detail

Cameron Cove Cluster Subdivision
 WEBER COUNTY, UTAH
Storm Water Pollution Prevention Plan Details

PROFESSIONAL ENGINEER
 THOMAS J. HUNT
 03/22/2019
 STATE OF UTAH

Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: C. KINGSLEY
 Begin Date: JUNE 2017
 Name: CAMERON COVE CLUSTER SUBDIVISION
 Number: 3442-A48

Sheet **16**
14 Sheets