

## West Warren and Warren Water Improvement District

1561 S. 7500 W.  
Ogden, UT 84404  
801-259-7614

February 15, 2019

To Whom It May Concern:


This letter is in reference to the development Fenster Farms. Mr. Kenny Palmer has supplied requested materials (except for connection and impact fees) to warrant approval of phase 2. The West Warren and Warren WID will supply the culinary water and there is adequate water to supply phase 2 of the subdivision. Please note, this is only approval for phase 2. Over the last 24 hours, questions have risen regarding the irrigation ditch involved in phase 3. These concerns must be addressed prior to said water district approving phase 3.

Randy Giordano is satisfied with the drawings Mr. Kenny Palmer has provided, if the following conditions are met:

1. C900 PVC class 150 10' pipe.
2. Trace wire buried with pipe.
3. All valve fittings and fire hydrant fitting wrapped in plastic prior, and to be blocked properly.
4. All meter boxes will be installed 18 x 36 with yolks 5/8s x 3/4 yolks with backflow preventers, and 1'cts from main line to meter boxes poly class 200.
5. After installation prior to connecting to existing waterline, a 150lb pressure test verified by Randy Giordano. The duration of the test must be 2 hours.
6. After hookup 2 bacteria tests must be performed by contractor.
7. Randy Giordano must be notified before and during construction for inspection.

If you have questions or concerns, please contact Randy Giordano 801-791-7368.

Sincerely,



Melissa Murray, Clerk