

CIVIL

C000	General Notes & Legend
C200	Site & Utility Plan
C201	Horizontal Control Plan
C300	Grading & Drainage Plan
C600	Erosion Control Plan
C700	Details
C701	Details

ARCHITECTURAL

A001	Rm Finish Schedule, Abbreviations, Int Partitions	A500	Detail Wall Sections
A002	Assembly Types	A501	Detail Wall Sections
A100	Site Plan	A502	Detail Wall Sections
A200	Basement Floor Plan	A503	Detail Wall Sections
A201	Main Floor Plan	A504	Detail Wall Sections
A202	Second Floor Plan	A5XX	Plan Details
A203	Roof Plan	A5XX	Section Details
A204	Foundation Plan	A600	Millwork
A205	Reflected Ceiling Plan Basement Level	A601	Millwork
A206	Reflected Ceiling Plan Main Level	A602	Millwork
A207	Reflected Ceiling Plan Second Level	A603	Millwork
A300	Exterior Elevation	A604	Millwork
A301	Exterior Elevation	A605	Millwork
A302	Exterior Elevation	A606	Millwork
A303	Exterior Elevation	A607	Millwork
A304	Exterior Elevation	A610	Stair Details
A305	Exterior Elevations	A611	Stair Details
A306	Exterior Elevations	A612	Stair Details
A400	Building Sections	A613	Stair Details
A401	Building Sections	A614	Stair Details
A402	Building Sections	A800	Electrical Plan Basement Level
A403	Building Sections	A801	Electrical Plan Main Level
		A802	Electrical Plan Second Level
		A900	Window/Door Schedule

STRUCTURAL

S0.1	Structural Notes
S0.2	Structural Notes
S0.3	Structural Details
S0.4	Structural Details
S0.5	Structural Details
S1.1	Footing & Foundation Plan
S1.2	Foundation Details
S2.1	Main Floor Framing Plan
S2.2	Upper Floor Framing Plan
S2.3	Roof Framing Plan
S3.1	Main Level Shear Wall Plan
S3.2	Second Level Shear Wall Plan
S4.1	Floor Framing Details
S4.2	Floor Framing Details
S5.1	Framing Details

September 12, 2019

Revised for Construction

Mackay-Lyons Sweetapple
Architects Limited

2188 Gottingen Street
Halifax, Nova Scotia Canada B3K 3B4
ph: (902) 429-1867

AE Urbia
Structural Engineers

909 W. South Jordan Parkway
SouthJordan, Utah, United States 84095
ph: (801) 746-0456

Talisman
Civil Engineers

1588 South Main Street, Suite 200
Salt Lake City, Utah, United States 84115
ph: (801) 743-1300

Michael Boucher
Landscape Architects


457 US Route 1, Suite 2
Freeport, Maine, United States 04032
ph: (207) 865-1080

Edge Builders LLC.
Construction Management

P.O. Box 17404, Salt Lake City, Utah, United States 84117
ph: (801) 381-9003



Klinefelter Residence




GENERAL NOTES:
 THE CONTRACTOR TO USE BEST MANAGEMENT PRACTICES FOR PROVIDING EROSION CONTROL FOR CONSTRUCTION OF THIS PROJECT. ALL MATERIAL AND WORKMANSHIP SHALL CONFORM TO WEBER COUNTY ORDINANCES AND ALL WORK SHALL BE SUBJECT TO INSPECTION BY WEBER COUNTY. ALSO, INSPECTORS WILL HAVE THE RIGHT TO REQUEST CHANGES TO THE FACILITIES AS NEEDED.
 DUST MUST BE KEPT TO A MINIMUM. CONTRACTOR SHALL KEEP THE SITE WATERED TO CONTROL DUST. CONTACT POWDER MOUNTAIN WATER & SEWER IMPROVEMENT DISTRICT TO LOCATE A NEARBY HYDRANT FOR USE AND TO INSTALL TEMPORARY METER.
 THE CONTRACTOR SHALL MODIFY EROSION CONTROL MEASURES TO ACCOMMODATE PROJECT PLANNING.
 ALL ACCESS TO PROPERTY WILL BE FROM PUBLIC RIGHT-OF-WAYS.
 THE CONTRACTOR IS REQUIRED BY STATE AND FEDERAL REGULATIONS TO PREPARE A STORM WATER POLLUTION PREVENTION PLAN AND FILE A "NOTICE OF INTENT" WITH THE UTAH DEPARTMENT OF ENVIRONMENTAL QUALITY DIVISION OF WATER QUALITY.
 ENSURE ALL GRADING SLOPES AWAY FROM STRUCTURE PER IRC R401.3

- SITE KEY NOTES:**
- 1 BUILDING FOOTPRINT. REFER TO ARCHITECTURAL PLANS.
 - 2 BUILDING OVERHANG. REFER TO ARCHITECTURAL PLANS.
 - 3 PROTECT IN PLACE EXISTING IMPROVEMENTS. IF DAMAGED, REPLACE AT CONTRACTOR'S EXPENSE.
 - 4 DRAINAGE SWALE FLOWLINE. SEE GRADING PLAN FOR DETAIL.
 - 5 INSTALL CONCRETE DRIVEWAY PER DETAIL A/SHEET C700.
 - 6 PROPOSED STAIRS. REFER TO ARCHITECTURAL AND STRUCTURAL PLANS.
 - 7 PROPOSED HAND RAIL. REFER TO ARCHITECTURAL PLANS.
 - 8 PROPOSED TERRACE. REFER TO ARCHITECTURAL PLANS.
 - 9 PROPOSED CONCRETE WALL. REFER TO ARCHITECTURAL AND STRUCTURAL PLANS. SEE GRADING PLAN FOR ELEVATIONS.
 - 10 PROPOSED GRADE BREAK. SEE GRADING PLAN FOR DETAIL.

UTILITIES:
 NOTE: UTILITIES SHOWN IN THESE PLANS ARE FOR INFORMATION PURPOSES ONLY. FULL DESIGN-BUILD DOCUMENTS ARE TO BE PRODUCED BY THE CONTRACTOR IN COORDINATION WITH THE ARCHITECT.
 CONTRACTOR TO ENSURE MINIMUM BURY DEPTH IS ACHIEVED PER BUILDING CODE FOR ALL BURIED UTILITIES.
 IMPROVEMENTS, INCLUDING LANDSCAPING, SHALL NOT INTERFERE WITH ANY DRAINAGE CULVERT, RIP RAP, DRAINAGE SWALE, AND/OR DRAINAGE PATTERN ASSOCIATED WITH ANY DRAINAGE EASEMENT.


- UTILITY KEY NOTES:**
- 1 INSTALL 4" SEWER LATERAL WITH CLEANOUT PER APWA PLAN NO. 381, 382 AND 431. SEE SHEET C700.
 - 2 INSTALL 15" DR-11 IPS PRESSURE SEWER PIPE, MINIMUM COVER OF 72".
 - 3 INSTALL E/ONE GRINDER PUMP STATION MODEL DHO71 WITH E/ONE SANITARY ALARM PANEL INCLUDING GENERATOR RECEPTACLE WITH AUTO TRANSFER AND GFCI RECEPTACLE. ALARM PANELS SHALL BE INSTALLED WITHIN LINE OF SIGHT OF ENTRY TO UNIT. SEE DETAIL B/SHEET C701.
 - 4 CONNECT TO EXISTING SANITARY SEWER LATERAL PER DETAIL A/SHEET C701.
 - 5 INSTALL CULINARY WATER AND FIRE LINES PER DETAIL C/SHEET C700.
 - 6 INSTALL ELECTRICAL LINE FROM SERVICE BOX TO BUILDING.
 - 7 INSTALL TELECOMMUNICATIONS LINE FROM SERVICE BOX TO BUILDING.
 - 8 INSTALL PROPANE TANK PER DETAIL D/SHEET C700. SERVICE LINE TO BUILDING TO BE INSTALLED BY OTHERS.
 - 9 INSTALL TRENCH DRAIN PER DETAIL B/SHEET C700.
 - 10 INSTALL 4" HDPE OUTLET PIPE.
 - 11 EXISTING SEWER LATERAL.
 - 12 EXISTING WATER LATERAL.
 - 13 EXISTING TELECOMMUNICATIONS PULL BOX.
 - 14 EXISTING ELECTRICAL PULL BOX.

Kirelefer Residence
 2188 College St.
 Heber, Utah 84304
 Canada B3K 3B4
 Tel: (403) 429-1867
 Fax: (403) 429-6276




No.	Description	Date

NOTES:
 COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
 The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.
ARCHITECT'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify Mackay Lyons Sewerage Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.
ENGINEER'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify Mackay Lyons Sewerage Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.
AUTHORITY'S REQUIREMENTS AND APPROVALS:
 All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.
DIMENSIONS:
 All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, all dimensions exist. Consult Architect. All minimum dimensions are to comply with the International Building Code, 2009 Edition.
SHOP DRAWINGS:
 Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




Site & Utility Plan
 Title: 16-11-2019
 Date: 06-11-2019
 Drawn: JB
 Check: JP
C200




No.	Description	Date

NOTES:
 COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
 The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.
ARCHITECT'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify MacKay Lyon Sweattoppe Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.
ENGINEER'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify MacKay Lyon Sweattoppe Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.
AUTHORITY'S REQUIREMENTS AND APPROVALS:
 All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.
DIMENSIONS:
 All dimensions must be verified on site. Do not scale off drawings. Plans take precedence over elevations. In the absence of dimensions, all dimensions must be verified on site. All dimensions are to comply with the International Building Code, 2009 Edition.
SHOP DRAWINGS:
 Submit shop drawings to the Architect and Engineer for approval prior to installation of prefabricated elements of the building.




DRIVEWAY PLAN VIEW





DRIVEWAY PROFILE

- ABBREVIATIONS:**
- BG - BUILDING
 - BS - BOTTOM OF STEP
 - BW - BOTTOM OF WALL
 - EX - EXISTING
 - FFE - FINISHED FLOOR ELEVATION (REFERENCE)
 - FG - FINISHED GRADE
 - FL - FLOWLINE
 - GR - GRAVEL
 - MA - MATCH
 - TC - TOP OF CONCRETE
 - TG - TOP OF GRATE
 - TS - TOP OF STEP



OVERALL GRADING PLAN





EROSION CONTROL GENERAL NOTES:

THE CONTRACTOR TO USE BEST MANAGEMENT PRACTICES FOR PROVIDING EROSION CONTROL FOR CONSTRUCTION OF THIS PROJECT. ALL MATERIAL AND WORKMANSHIP SHALL CONFORM TO WEBER COUNTY ORDINANCES AND ALL WORK SHALL BE SUBJECT TO INSPECTION BY THE COUNTY. ALSO, INSPECTORS WILL HAVE THE RIGHT TO CHANGE THE FACILITIES AS NEEDED.

CONTRACTOR SHALL KEEP THE SITE WATERED TO CONTROL DUST. CONTRACTOR TO LOCATE A NEARBY HYDRANT FOR USE AND TO INSTALL TEMPORARY METER. CONSTRUCTION WATER COST TO BE INCLUDED IN BID.

WHEN GRADING OPERATIONS ARE COMPLETED AND THE DISTURBED GROUND IS LEFT "OPEN" FOR 14 DAYS OR MORE, THE AREA SHALL BE FURROWED PARALLEL TO THE CONTOURS.

THE CONTRACTOR SHALL MODIFY EROSION CONTROL MEASURES TO ACCOMMODATE PROJECT PLANNING.

ALL ACCESS TO PROPERTY WILL BE FROM PUBLIC RIGHT-OF-WAYS.

THE CONTRACTOR IS REQUIRED BY STATE AND FEDERAL REGULATIONS TO PREPARE A STORM WATER POLLUTION PREVENTION PLAN AND FILE A "NOTICE OF INTENT" WITH THE UTAH DIVISION OF WATER QUALITY.

MAINTENANCE:
ALL BEST MANAGEMENT PRACTICES (BMP'S) SHOWN ON THIS PLAN MUST BE MAINTAINED AT ALL TIMES UNTIL VEGETATION IS RE-ESTABLISHED.

THE CONTRACTOR'S RESPONSIBILITY SHALL INCLUDE MAKING BI-WEEKLY CHECKS ON ALL EROSION CONTROL MEASURES TO DETERMINE IF REPAIR OR SEDIMENT REMOVAL IS NECESSARY. CHECKS SHALL BE DOCUMENTED AND COPIES OF THE INSPECTIONS KEPT ON SITE.







SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL. THEY MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF BARRIER.

SEDIMENT TRACKED ONTO PAVED ROADS MUST BE CLEANED UP AS SOON AS PRACTICAL, BUT IN NO CASE LATER THAN THE END OF THE NORMAL WORK DAY. THE CLEAN UP WILL INCLUDE SWEEPING OF THE TRACKED MATERIAL, PICKING IT UP, AND DEPOSITING IT TO A CONTAINED AREA.

EXPOSED SLOPES:
ANY EXPOSED SLOPE THAT WILL REMAIN UNTOUCHED FOR LONGER THAN 14 DAYS MUST BE STABILIZED BY ONE OR MORE OF THE FOLLOWING METHODS:

- SPRAYING DISTURBED AREAS WITH A TACKIFIER VIA HYDROSEED
- TRACKING STRAW PERPENDICULAR TO SLOPES
- INSTALLING A LIGHT-WEIGHT, TEMPORARY EROSION CONTROL BLANKET

SCOPE OF WORK:
PROVIDE, INSTALL AND/OR CONSTRUCT THE FOLLOWING PER THE SPECIFICATIONS GIVEN OR REFERENCED, THE DETAILS NOTED, AND/OR AS SHOWN ON THE CONSTRUCTION DRAWINGS:


-  HATCHING INDICATES AREAS TO RECEIVE 4" TOPSOIL AND TO BE SEEDED FOR NATURAL VEGETATION. AREAS RECEIVING SEEDING FOR NATURAL VEGETATION ON SLOPES OF 3:1 OR STEEPER MUST BE COVERED WITH AN EROSION CONTROL BLANKET AFTER THE FINAL GRADING AND SEEDING ARE FINISHED. INSTALL NORTH AMERICAN GREEN SC-150 BLANKET OR APPROVED EQUAL. FOLLOW MANUFACTURER'S SPECIFICATIONS.
-  HATCHING INDICATES AREAS TO RECEIVE 3" WASHED ROCK OR RECYCLED COBBLE.
-  INSTALL INLET PROTECTION IN FORM OF CONCRETE BLOCKS / FILTER CLOTH / GRAVEL OR SILT SACK AT EXISTING AND PROPOSED CATCH BASINS AS SHOWN ON PLAN.
-  INSTALL SILT FENCE ALONG DOWN GRADIENT LIMITS OF DISTURBANCE AS SHOWN ON PLAN. SEE DETAIL ON THIS SHEET.
-  INSTALL ORANGE SAFETY FENCING AROUND OUTER LIMITS OF PROJECT PRIOR TO GRADING.
-  STABILIZED CONSTRUCTION ENTRANCE FOR SITE INGRESS/EGRESS. IF ALTERNATE ACCESS POINTS ARE APPROVED BY OWNER, ADDITIONAL STABILIZED CONSTRUCTION ENTRANCES WILL BE REQUIRED. SEE DETAIL ON THIS SHEET.
- SEED MIXTURE FOR REVEGETATION
40% MOUNTAIN BROME (BROMUS MARGINATUS)
25% SLENDER WHEATGRASS (ELYMUS TRACHYCAULUS SPP. TRACHYCAULUS)
5% SHEEP FESCUE (FESTUCA OVINA SPP. DURISCUCLA)
5% ALPINE BLUEGRASS (POA ALPINE)
25% THICKSPIKE WHEATGRASS (ELYMUS LANCEOLATUS SPP. LANCEOLATUS)
- SEEDING RATE IS 40 POUNDS PER ACRE.

- Silt fence**
- GENERAL**
 - Description. A temporary sediment barrier consisting of a filter fabric stretched across and attached to supporting posts and entrenched.
 - Application. To intercept sediment from disturbed areas of limited extent.
 - Perimeter Control. Place barrier at down gradient limits of disturbance.
 - Sediment Barrier. Place barrier at toe of slope or soil stockpile.
 - Protection of Existing Waterways: Place barrier at top of stream bank.
 - Inlet Protection.
 - PRODUCTS**
 - Fabric. Synthetic filter fabric shall be a pervious sheet of propylene, nylon, polyester, or polyethylene yarn. Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of 6 months of expected usable construction life at a temperature range of 0 deg F to 120 deg F.
 - Burlap. 10 ounces per square yard of fabric.
 - Posts. Either 2" x 4" diameter wood, or 1.33 pounds per linear foot steel with a minimum length of 5 feet, or steel posts with projections for fastening wire to them.
 - EXECUTION**
 - Call the fabric on site to desired width, unroll, and drape over the barrier. Secure the fabric toe with rocks or dirt and secure the fabric to the mesh with twin, staples or similar devices.
 - When attaching two silt fences together, place the end post of the second fence inside the end post of the first fence. Rotate both posts at least 180 degrees on a clockwise direction to create a tight seal with the filter fabric. Drive both posts into the ground and bury the flap.
 - When used to control sediments from a steep slope, place silt fences away from the toe of the slope for increased holding capacity.
 - Maintenance.
 - Inspect immediately after each rainfall and at least daily during prolonged rainfall.
 - Should the fabric on a silt fence or filter barrier decompose or become ineffective before the end of the expected usable life and the barrier still be necessary, replace the fabric promptly.
 - Remove sediment deposits after each storm event. They must be removed when deposits reach approximately one-half the height of the barrier.
 - Re-anchor fence as necessary to prevent shortcutting.
 - Inspect for runoff bypassing ends of barriers or undercutting barriers.


- Stabilized roadway entrance**
- GENERAL**
 - Description. A temporary stabilized pad of gravel for controlling equipment and construction vehicle access to the site.
 - Application. At any site where vehicles and equipment enter the public right of way.
 - PRODUCT** (Not used)
 - EXECUTION**
 - Clear and grub area and grade to provide maximum slope of 1 percent away from paved roadway.
 - Compact subgrade.
 - Place filter fabric under stone if desired (recommended for entrance area that remains more than 3 months).
 - Maintenance.
 - Prevent tracking or flow of mud into the public right-of-way.
 - Periodic top dressing with 2-inch stone may be required, as conditions demand, and repair any structures used to trap sediments.
 - Inspect daily for loss of gravel or sediment buildup.
 - Inspect adjacent area for sediment deposit and install additional controls as necessary.
 - Expand stabilized area as required to accommodate activities.

122

NARRATIVE: THIS PLAN MAY BE USED FOR THE CONSTRUCTION OF A STORM WATER BEST MANAGEMENT PRACTICE (BMP). IT IS NOT INCLUSIVE OF ALL PRACTICES AVAILABLE AND IS ONLY SPECIFIC TO THE CONSTRUCTION OF THIS TYPE. MAINTENANCE OF THIS TYPE OF INSTALLATION IS IMPORTANT AND SHOULD BE CONTINUOUSLY MONITORED BY THE CONTRACTOR AND ENGINEER. DETAILS SHOWN HERE HIGHLIGHT IMPORTANT PARTS OF CONSTRUCTION AND SHOULD BE MODIFIED AS NEEDED.



INSTALLATION SEQUENCE




Silt fence



Plan 122
February 2006

126

NARRATIVE: THIS PLAN MAY BE USED FOR THE CONSTRUCTION OF A STORM WATER BEST MANAGEMENT PRACTICE (BMP). IT IS NOT INCLUSIVE OF ALL PRACTICES AVAILABLE AND IS ONLY SPECIFIC TO THE CONSTRUCTION OF THIS TYPE. MAINTENANCE OF THIS TYPE OF INSTALLATION IS IMPORTANT AND SHOULD BE CONTINUOUSLY MONITORED BY THE CONTRACTOR AND ENGINEER. DETAILS SHOWN HERE HIGHLIGHT IMPORTANT PARTS OF CONSTRUCTION AND SHOULD BE MODIFIED AS NEEDED.



Stabilized roadway entrance



Plan 126
February 2006

Kirelefer Residence
 MidCity Lyon
 Swetapine
 Architects
 Limited
 2180 Colquhoun Dr.
 Heber, Utah 84304
 Canada 83K 3B4
 ph: (435) 429-1867
 fax: (435) 429-6276

TALISMAN
 1588 SOUTH MAIN STREET
 SUITE 200
 SALT LAKE CITY, UT 84115
 801.743.1100



No.	Description	Date

NOTES:
 COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
 The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify MidCity Lyon Swetapine Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
 It is the Builder's responsibility to notify MidCity Lyon Swetapine Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITY'S REQUIREMENTS AND APPROVALS:
 All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.





DIMENSIONS:
 All dimensions must be verified on site. Do not scale off drawings. Plans take precedence over elevations. In the absence of dimensions, all dimensions shall conform to the International Building Code, 2009 Edition.

SHOP DRAWINGS:
 Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Erosion Control Plan


Scale: 1" = 10'
 Date: 06-17-2019
 Drawn: JS
 Check: JP

C600



B] GRINDER PUMP STATION DETAIL
SCALE: N.T.S.

A] SEWER LATERAL CONNECTION
SCALE: N.T.S.



No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay Lynn Sewerage Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay Lynn Sewerage Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITY'S REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, all dimensions must consult Architect. All minimum dimensions are to comply with the International Building Code, 2009 Edition.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

MECHANICAL AND PLUMBING NOTES:

- All work shall be performed in accordance with, 2015 International Residential Code.
- For plumbing fixtures that are located below the elevation level of the nearest upstream man hole cover a backwater valve is required. Fixtures that are above the elevation level of the manhole cover shall not discharge through the backwater valve.
- Closely coordinate new mechanical and plumbing construction with all mechanical, electrical, architectural, and structural members. Provide alternate routing, offsets, and transitions as required for coordination of all work without additional cost.
- Do not shut-off / put out service any systems / services without first coordinating all downtime with the owner's personnel.
- Submit all equipment, air devices, valves, fittings, pipe materials, insulation, and accessories to be used in this project. Submit electronic submittal to architect for review and approval. Do not place order until reviewed and approved.

- Contractor shall provide 1 year standard warranty. Submit all all equipment, air devices, valves, fittings, pipe materials, insulation, and accessories to be used in project electronically to architect for review and approval.
- Install all equipment in accordance with manufacturer's installation instructions.
- Project Elevation is 8533 ft for equipment selection.
- Provide all duct in accordance with SMACNA standards for 2" WC pressure class. Seal all transverse and longitudinal seams and joints except for welded or locking-type longitudinal joints.
- Disinfect new domestic water piping.
- Dryers located in closets shall be provided with make-up air, per IRC G2439.5
- All outlets to be tamper resistant, in accordance with IRC E4002.14.
- Mechanical rooms to have solid, weather stripped doors equipped with an approved self-closing device, in accordance with IRC G2406.2.5.
- Provide outdoor combustion air for all gas-fired appliances, in accordance with IRC G2407.

Finish Types

- Paint
- PTC1 - Benjamin Moore Decorators White - Egg Shell Finish
 - PTC2 - Benjamin Moore Decorators White - Semi Gloss Finish
 - PTC3 - Benjamin Moore Decorators White - Flat Finish (Ceiling Only)
- Tile
- TILE1 - white tile type - # x #
 - TILE2 - white tile type - # x #
 - TILE3 - white tile type - # x #
- Wood Cladding
- WD1 - 1x4 red cedar shiplap, clear sealant, satin (cladding profile 2)
 - WD2 - 1x6 engineered white ash hardwood flooring on conc. topping pre-finished.
 - WD3 - finished plywood, clear sealant
 - WD4 - black ebonized wood (oak)
 - WD5 - white ash hardwood, clear sealant
- Concrete
- SEALED - sealed concrete
 - ANTISLIP - sealed concrete
- Steel
- STL1 - steel truss; PTD black

Legend

- N/A not applicable
- GWB gypsum wall board per spec.
- GWB-W waterproofer sheathing as per spec.
- CONC concrete
- TILE ceramic tile
- WD wood
- GLZ glazing
- STL steel

	North		South		East		West		Floors		Ceiling		Trim		Remarks
	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	
Basement Level															
Bedroom 5 (001)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Ensuite (002)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Mechanical (003)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Hallway (004)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Hallway (005)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	CONC	SEALED	GWB	PTC3	##	##	
Stair (006)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	
Ski Room (007)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	ANTISLIP	GWB	PTC3	##	##	
Storage/Mech (008)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Stair (009)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	
Storage/Mech (010)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Stair (011)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	

	North		South		East		West		Floors		Ceiling		Trim		Remarks
	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	
Main Level															
Great Room (101)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	WD	WD1	##	##	##
Dining (102)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	WD	WD1	##	##	
Kitchen (103)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	WD	WD1	##	##	
Pantry (104)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Entry (105)	GLZ	N/A	GLZ	N/A	WD	WD3	WD	WD3	CONC	SEALED	GWB	PTC3	##	##	
Coat Closet (106)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Hallway (107)	GLZ	N/A	GLZ	N/A	WD	WD3	WD	WD3	CONC	SEALED	GWB	PTC3	##	##	
1/2 Bath (108)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
1/2 Bath (109)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Bedroom 4 (110)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Ensuite (111)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Closet (112)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Garage (113)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	CONC	SEALED	GWB	PTC3	##	##	
Laundry (114)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	TILE	TILE2	GWB	PTC3	##	##	
Family Room (115)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Hallway (116)	WD	WD3	WD	WD3	N/A	N/A	N/A	N/A	CONC	SEALED	GWB	PTC3	##	##	
Stair (117)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	WD	WD1	##	##	
Stair (118)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	
Stair (119)	WD	WD4	WD	WD4	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	
Stair (120)	N/A	N/A	N/A	N/A	WD	WD4	WD	WD4	WD	WD5	GWB	PTC3	##	##	
Stair (121)	WD	WD3	WD	WD3	WD	WD3	N/A	N/A	WD	WD5	GWB	PTC3	##	##	

	North		South		East		West		Floors		Ceiling		Trim		Remarks
	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Finish	
Second Level															
Loft (201)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	WD	WD1	##	##	##
Bathroom (202)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Mech/Storage (203)	N/A	UNFINISH	N/A	UNFINISH	N/A	UNFINISH	N/A	UNFINISH	WD	WD2	N/A	UNFINISH	##	##	
Bedroom 1 (204)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Ensuite (205)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Bedroom 2 (206)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Ensuite (207)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Bunk Room (208)	WD	WD1	WD	WD1	WD	WD1	WD	WD1	WD	WD2	WD	WD1	##	##	
Ensuite (209)	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE1	TILE	TILE2	GWB	PTC3	##	##	
Stair (210)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Hallway (211)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	WD	WD1	##	##	
Hallway (212)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	
Hallway (213)	GWB	PTC1	GWB	PTC1	GWB	PTC1	GWB	PTC1	WD	WD2	GWB	PTC3	##	##	

3 Room Finish Schedule
A001 NTS

TYPE	WOOD CLADDING PROFILE	
1		+ 1X6 vertical tongue & groove wood cladding; clear western red cedar as per specification (Exterior Wall Finish)
2		+ 1X4 square edge shiplap wood cladding; clear western red cedar as per specification (great room + kitchen ceiling finish)

4 Cladding Profiles
A001 NTS

AD	AREA DRAIN	MO	MASONRY OPENING
ADJ	ADJACENT	MECH	MECHANICAL
AFF	ABOVE FINISHED FLOOR	MEMBR	MEMBRANE
ALUM	ALUMINUM	MIN	MINIMUM
ANOD	ANODIZED		
BSMT	BASEMENT	MRGWB	MOISTURE-RESISTANT GYPSUM WALL BOARD
BYOND	BEYOND		
BOT	BOTTOM	MTL	METAL
B/W	BETWEEN	NIC	NOT IN CONTRACT
CHNL	CHANNEL	NOM	NOMINAL
CJ	CONTROL JOINT	OC	ON CENTER
CLG	CEILING	OH	OPPOSITE HAND
CLR	CLEAR	OZ	OUNCE
CMU	CONCRETE MASONRY UNIT	PCC	PRE-CAST CONCRETE
COF	CENTERLINE OF WOOD FRAMING	PLYD	PLYWOOD
COL	COLUMN	PT	PRESSURE TREATED
CONC	CONCRETE	PTD	PAINTED
CONT	CONTINUOUS	PVC	POLYVINYL CHLORIDE
CPT	CARPET	RCP	REFLECTED CEILING PLAN
CT	CERAMIC TILE	RD	ROOF DRAIN
DBL	DOUBLE	REQD	REQUIRED
DIA	DIAMETER	REV	REVERSE
DIMS	DIMENSIONS	RM	ROOM
DN	DOWN	SIM	SIMILAR
DR	DOOR	SPEC	SPECIFIED OR SPECIFICATION
DWG	DRAWING	SPK	SPRINKLER
EA	EACH	ST STL	STAINLESS STEEL
EL	ELEVATION	STC	SOUND TRANSMISSION COEFFICIENT
ELEC	ELECTRICAL	STL	STEEL
ELEV	ELEVATOR / ELEVATION	STRUCT	STRUCTURAL
EQ	EQUAL	TELE	TELEPHONE
FOC	FACE OF CONCRETE	TLT	TOILET
FOF	FACE OF WOOD FRAMING	TO	TOP OF
FDN	FOUNDATION	TOC	TOP OF CONCRETE
GA	GAUGE	TOS	TOP OF STEEL
GALV	GALVANIZED	TP	TOILET PAPER DISPENSER
GWB	GYPSUM WALL BOARD	T/D	TELEPHONE/DATA
HC	HOLLOW CORE	TYP	TYPICAL
HI	HIGH	UON	UNLESS OTHERWISE NOTED
HM	HOLLOW METAL	U/S	UNDERSIDE
HP	HIGH POINT	VIF	VERIFY IN FIELD
HVAC	HEATING, VENTILATING, AND AIR CONDITIONING	VP	VISION PANEL
		TYP	TYPICAL
		VIF	VERIFY IN FIELD
ILO	INSULATED	W/	WITH
INT	INTERIOR	WD	WOOD
LO	LOW	FOC	FACE OF CONCRETE
MAX	MAXIMUM	FOF	FACE OF FRAME

2 Abbreviations
A001 NTS

TYPE	INTERIOR WALL TYPE DESCRIPTION
P1	 + 1/2" GWB, PTD + 2x4 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P1A	 + 1/2" GWB, PTD + 2x4 studs @ 16" o.c. + thermal acoustic batt insulation to fill cavity + 1/2" GWB, PTD
P2	 + 1/2" GWB, PTD + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P3	 + tile; see finish schedule + 5/8" tile backer board+ 2x4 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P3A	 + tile; see finish schedule + 5/8" tile backer board+ 2x4 studs @ 16" o.c. + thermal acoustic batt insulation to fill cavity + 1/2" GWB, PTD
P4	 + tile; see finish schedule + 5/8" tile backer board + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P5	 + tile; see finish schedule + 2x4 studs @ 16" o.c. + acoustic batt to fill cavity + tile; see finish schedule
P6	 + 3/4" plywood paneling + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P7	 + 3/4" plywood paneling + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P8	 + tile; see finish schedule + 2x4 studs @ 16" o.c. + acoustic batt to fill cavity + 3/4" plywood paneling
P9	 + tile; see finish schedule + 5/8" tile backer board + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 3/4" plywood paneling
P10	 + 3/4" plywood paneling + 6 mil poly air barrier (sealed) + 5 1/2" 2lb. closed-cell spray foam insulation (R27) + 2x6 studs @ 16" o.c. + 2x4 studs @ 16" o.c. infill cavity + 1/2" GWB, PTD
P11	 + 1/2" GWB, PTD + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 1/2" GWB, PTD
P12	 + 3/4" plywood paneling + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + 2x4 studs @ 16" o.c. infill cavity + 1/2" GWB, PTD
P13	 + 3/4" ebonized wood paneling + 2x4 studs @ 16" o.c. + 1/2" GWB, PTD
P14	 + tile; see finish schedule + 2x6 studs @ 16" o.c. + acoustic batt to fill cavity + tile; see finish schedule
P15	 + 1/2" GWB, PTD + 3/4" sheathing as per structural + 2x6 studs @ 16" o.c. + 5 1/2" 2lb. closed-cell spray foam insulation (27) + 1/2" GWB, PTD

1 Interior Partition Types
A001 NTS

Kinefeller Residence

Summit Powder Mountain
Elev. 9000'

MackKay-Lyons
Sweetapple
Architects
Limited

2188 Gorington St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429 1867
fax: (902) 429 6276

north

STATE OF UTAH


Brian MackKay-Lyons

No. 9

ROOF TYPE DESCRIPTION


Roof Assembly Type 1 (RA1)

- System Components:**
- snow retention system, refer to spec. & roof plan for locations
 - standing-seam metal roofing system (Class A roof covering), refer to specification
 - 2 layers of alternating 1x4 strapping
 - 2" vapor-open mineral wool rigid insulation board (R8), refer to specification
 - vapor open roof membrane, refer to spec
 - 3/4" exterior grade sheathing as per structural
 - wood l-joists, refer to structural
 - 6" 2lb. closed-cell spray foam insulation (R36)
 - interior sprinkler system
 - 1/2" OSB sheathing
 - 1x4 shiplap wood cladding, refer to finish schedule




Roof Assembly Type 2 (RA2)

- System Components:**
- snow retention system, refer to spec. & roof plan for locations
 - standing-seam metal roofing system (Class A roof covering), refer to specification
 - 2 layers of alternating 1x4 strapping
 - 2" vapor-open mineral wool rigid insulation board (R8), refer to specification
 - vapor open roof membrane, refer to spec
 - 3/4" exterior grade sheathing as per structural
 - wood l-joists, refer to structural
 - 6" 2lb. closed-cell spray foam insulation (R36)
 - interior sprinkler system
 - 5/8" gypsum board, refer to finish schedule



Roof Assembly Type 3 (RA3)

- System Components:**
- Class A EPDM low slope roof membrane
 - sloped continuous XPS rigid insulation (minimum 1") - minimum 2% slope to drain
 - self-adhered air / vapor barrier
 - 3/4" exterior grade sheathing as per structural
 - wood joists as per structural
 - 6" 2lb. closed-cell spray foam insulation (R36)
 - interior sprinkler system
 - 5/8" gypsum board, refer to finish schedule




4 Roof Types
Scale 1-1/2" = 1'-0"

SOFFIT TYPE DESCRIPTION

Soffit Assembly Type 1 (SA1)

- System Components:**
- typical floor assembly as noted
 - wood l-joists, refer to structural
 - infill 2x4 framing as required
 - 6" 2lb. closed-cell spray foam insulation (R36)
 - 1/2" OSB sheathing
 - 1x6 tongue and groove wood cladding to match facade (refer to finish schedule, cladding profile 1)




3 Soffit Types
Scale 1-1/2" = 1'-0"

FLOOR TYPE DESCRIPTION

Floor Assembly Type 1 (FA1)


- System Components:**
- 3" min. polished concrete topping (class A aggregate exposure) w/ hydronic in-floor heating system, refer to schedule for finish
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - resilient channel
 - 2x6 framing as required
 - acoustic insulation, refer to specification
 - interior sprinkler system
 - 5/8" gypsum board, refer to finish schedule



STC


Floor Assembly Type 2 (FA2)

- System Components:**
- 3" min. polished concrete topping (class A aggregate exposure) w/ hydronic in-floor heating system, refer to schedule for finish
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)



Floor Assembly Type 3 (FA3)


- System Components:**
- 3/4" engineered hardwood flooring
 - 2 1/4" gypcrete w/ hydronic in-floor heating system
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - acoustic insulation, refer to specification
 - ceiling suspension system
 - interior sprinkler system
 - resilient channel
 - 5/8" gypsum board, refer to finish schedule



STC

Floor Assembly Type 4 (FA4)


- System Components:**
- 3/4" engineered hardwood flooring
 - 1-1/2" gypcrete w/ hydronic in-floor heating system
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)



STC

Floor Assembly Type 5 (FA5)


- System Components:**
- 3/4" engineered hardwood flooring
 - 1 1/2" gypcrete w/ hydronic in-floor heating system
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - acoustic insulation, refer to specification
 - interior sprinkler system
 - resilient channel
 - 5/8" gypsum board, refer to finish schedule



STC

Floor Assembly Type 6 (FA6)


- System Components:**
- tile floor finish as per schedule
 - 3/16" GenieMAT RST Series
 - 1-1/2" concrete topping w/ radiant heat
 - 3/4" sheathing as per structural
 - wood l-joists, as per structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)



2 Floor Types
Scale 1-1/2" = 1'-0"

Floor Assembly Type 7 (FA7)


- System Components:**
- tile floor finish as per schedule
 - 3/16" GenieMAT RST Series
 - 1-1/2" concrete topping w/ radiant heat
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)
 - acoustic insulation, refer to specification
 - 5/8" gypsum board, refer to finish schedule



STC

Floor Assembly Type 8 (FA8)


- System Components:**
- tile floor finish as per schedule
 - 3/16" GenieMAT RST Series
 - 1-1/2" concrete topping w/ radiant heat
 - 3/4" sheathing as per structural
 - wood l-joists, refer to structural
 - acoustic insulation, refer to specification
 - interior sprinkler system
 - 5/8" gypsum board, refer to finish schedule



STC


Floor Assembly Type 9 (FA9)

- System Components:**
- 4" pea gravel
 - class I vapor retarder
 - 2" XPS rigid insulation (R10)
 - 6" compacted gravel base



Floor Assembly Type 10 (FA10)


- System Components:**
- 4" reinforced polished concrete slab on grade as per structural
 - class I vapor retarder
 - 2" XPS rigid insulation (R10)
 - 6" compacted gravel base



EXTERIOR WALL TYPE DESCRIPTION

Exterior Wall Assembly 1 (EWA1)

- System Components:**
- 1x6 tongue and groove wood cladding - profile 1
 - rainscreen grid
 - vapour permeable weather barrier
 - 1/2" sheathing
 - 2" continuous XPS rigid insulation (R10)
 - 1/2" plywood sheathing as per structural
 - 2" 2lb. closed cell sprayfoam insulation (R12 - vapour retarder Class 2)
 - 5 1/2" insulation batts (R24)
 - 2x6 wood studs as per structural
 - interior finish, refer to finish schedule




1 Exterior Wall Types
Scale 1-1/2" = 1'-0"

EXTERIOR WALL TYPE DESCRIPTION CONT.


Exterior Wall Assembly 1B (EWA1B)

- System Components:**
- 1x6 tongue and groove wood cladding - profile 1
 - rainscreen grid
 - vapour permeable weather barrier
 - 1/2" sheathing
 - 2" continuous XPS rigid insulation (R10)
 - 1/2" plywood sheathing as per structural
 - 2" 2lb. closed cell sprayfoam insulation (R12 - vapour retarder Class 2)
 - 5 1/2" insulation batts (R24)
 - 2x6 wood studs as per structural
 - furring as required
 - interior finish, refer to finish schedule




Exterior Wall Assembly 2 (EWA2)

- System Components:**
- waterproofing system below grade; as per spec
 - reinforced 8" thick architectural concrete wall as per structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)
 - 2x4 stud wall, hold stud wall 1" from conc. wall
 - interior finish, refer to finish schedule




Exterior Wall Assembly 3 (EWA3)

- System Components:**
- reinforced 8" thick concrete wall as per structural; board form finish, refer to specification
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)
 - 2x4 stud wall, hold stud wall 1" from concrete wall
 - interior finish, refer to room finish schedule




Exterior Wall Assembly 4 (EWA4)

- System Components:**
- waterproofing system below grade; as per spec
 - reinforced 8" thick architectural concrete wall as per structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)




Exterior Wall Assembly 5 (EWA5)

- System Components:**
- reinforced 8" thick architectural concrete wall as per structural; board form finish, refer to specification
 - 2" continuous XPS rigid insulation (R10)
 - 1/2" plywood sheathing as per structural
 - 4-1/2" 2lb. closed-cell spray foam insulation (R27)
 - 2x6 stud wall, hold stud wall 1" from concrete wall
 - hearth interior finish, refer to drawings



Exterior Wall Assembly 6 (EWA6)

- System Components:**
- 1/4" metal cladding
 - 3/4" horizontal strapping
 - 3/4" vertical strapping
 - vapour permeable weather barrier
 - 1/2" sheathing
 - 2" continuous XPS rigid insulation (R10)
 - 1/2" plywood sheathing as per structural
 - 2" 2lb. closed cell sprayfoam insulation (R12 - vapour retarder Class 2)
 - 5 1/2" insulation batts (R24)
 - 2x6 wood studs as per structural
 - interior finish, refer to finish schedule



Kinfeleter Residence

Submit Powder Mountain Elev. 200

MackKay-Lyons Sweetapple Architects Limited

2188 Gorington St. Halifax, Nova Scotia Canada B3K 3B4

ph: (902) 429-1867 fax: (902) 429-6276

STATE OF UTAH

Brian MackKay-Lyons

No. 9809836

LICENSED ARCHITECT

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


scale: NTS
date: 2019-06-03
drawn: TRL/M
chk'd: SA

Assembly Types
A002



Siteplan Notes:

- + See Civil Engineering drawings for information relating but not limited to:
 - site location.
 - site boundaries.
 - rights-of-way, easements.
 - geodetic elevations, site grading, earthwork.
 - all underground and aboveground services including fire hydrants, maintenance access covers, transformers, air condensers.
 - paved areas such as driveways, curbs, curb cutouts.
- + See Electrical drawings for site lighting.
- + See Structural Engineering drawings for reference to Geotechnical Report.
- + See Landscape Architect drawings for reference to landscape design.



2 Site Plan
Scale 1/16" = 1'-0"

1 Key Plan
Scale 1/128" = 1'-0"

Kinfeleter Residence

Summit Powder Mountain
Egan, Utah

MackKay-Lyons
Sweetapple
Architects
Limited

2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429 1867
fax: (902) 429 6276

north

STATE OF UTAH
Brian MackKay-Lyons
No. 9809836
LICENSED ARCHITECT

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Site Plan

scale: 1/16" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A100



LEGEND


	Center line		Partition type
	Door Schedule		Reinforced Concrete as per Structural
	Window Schedule		Stone Pavers; Paving Pattern to be determined

NOTE:

- + PROJECT DATUM OF 100'-0" IS 8533.2' GEODETIC ELEVATION. FOR INFORMATION RELATING TO CONTOURS, GRADING AND SERVICES SEE CIVIL ENGINEERING DRAWINGS.
- + FOR WINDOW TAGS REFER TO EXTERIOR ELEVATIONS
- + FOR WINDOW SIZES REFER TO A900 - WINDOW DOOR SCHEDULE
- + FOR DOOR SIZES REFER TO A900 - WINDOW DOOR SCHEDULE

AREA CALCS:

BASEMENT LEVEL FLOOR AREA:	787 SF ANSI Z675-2003
MAIN LEVEL FLOOR AREA:	2397 SF ANSI Z675-2003
SECOND LEVEL FLOOR AREA:	2262 SF ANSI Z675-2003
TOTAL AREA:	5446 SF ANSI Z675-2003



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

1 Basement Floor Plan
Scale 1/4" = 1'-0"

**Basement
Floor Plan**

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A200



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.


ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Main Floor Plan



LEGEND


	Center line		Partition type
	Door Schedule		Reinforced Concrete as per Structural
	Window Schedule		Stone Pavers; Paving Pattern to be determined

NOTE:

- + PROJECT DATUM OF 100'-0" IS 8533.2' GEODETIC ELEVATION. FOR INFORMATION RELATING TO CONTOURS, GRADING AND SERVICES SEE CIVIL ENGINEERING DRAWINGS.
- + FOR WINDOW TAGS REFER TO EXTERIOR ELEVATIONS
- + FOR WINDOW SIZES REFER TO A900 - WINDOW DOOR SCHEDULE
- + FOR DOOR SIZES REFER TO A900 - WINDOW DOOR SCHEDULE

AREA CALCS:

BASEMENT LEVEL FLOOR AREA:	787 SF ANSI Z675-2003
MAIN LEVEL FLOOR AREA:	2397 SF ANSI Z675-2003
SECOND LEVEL FLOOR AREA:	2262 SF ANSI Z675-2003
TOTAL AREA:	5446 SF ANSI Z675-2003



1
A202
Second Floor Plan
Scale 1/4" = 1'-0"

LEGEND


	Center line		Partition type
	Door Schedule		Reinforced Concrete as per Structural
	Window Schedule		Stone Pavers; Paving Pattern to be determined

NOTE:

- + PROJECT DATUM OF 100'-0" IS 8533.2' GEODETIC ELEVATION. FOR INFORMATION RELATING TO CONTOURS, GRADING AND SERVICES SEE CIVIL ENGINEERING DRAWINGS.
- + FOR WINDOW TAGS REFER TO EXTERIOR ELEVATIONS
- + FOR WINDOW SIZES REFER TO A900 - WINDOW DOOR SCHEDULE
- + FOR DOOR SIZES REFER TO A900 - WINDOW DOOR SCHEDULE

AREA CALCS:

BASEMENT LEVEL FLOOR AREA:	787 SF ANSI Z675-2003
MAIN LEVEL FLOOR AREA:	2397 SF ANSI Z675-2003
SECOND LEVEL FLOOR AREA:	2262 SF ANSI Z675-2003
TOTAL AREA:	5446 SF ANSI Z675-2003



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.



DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Second
Floor Plan

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A202



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Roof Plan

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A203



LEGEND

	Center line		Partition type
	Door Schedule		Reinforced Concrete as per Structural
	Window Schedule		Stone Pavers; Paving Pattern to be determined


NOTE:

- + PROJECT DATUM OF 100'-0" IS 8533.2' GEODETIC ELEVATION. FOR INFORMATION RELATING TO CONTOURS, GRADING AND SERVICES SEE CIVIL ENGINEERING DRAWINGS.
- + FOR WINDOW TAGS REFER TO EXTERIOR ELEVATIONS
- + FOR WINDOW SIZES REFER TO A900 - WINDOW DOOR SCHEDULE
- + FOR DOOR SIZES REFER TO A900 - WINDOW DOOR SCHEDULE

AREA CALCS:

BASEMENT LEVEL FLOOR AREA:	787 SF ANSI Z675-2003
MAIN LEVEL FLOOR AREA:	2397 SF ANSI Z675-2003
SECOND LEVEL FLOOR AREA:	2262 SF ANSI Z675-2003
TOTAL AREA:	5446 SF ANSI Z675-2003


1
A203
Roof Plan
Scale 1/4" = 1'-0"



Note:

- + Project Datum of 100'-0" is 8533.2' geodetic elevation. For information relating to to contours, grading and services see Civil Engineering Drawings.
- + See structural drawings for concrete footing and foundation wall layout and specifications.
- + The Contractor shall examine all drawings, check all dimensions, and report any discrepancies prior to proceeding with the work.
- + The Contractor shall verify that all top of concrete levels are at the appropriate height in relation to the existing topography prior to proceeding with the work.
- + Step footings (locations by contractor) as required to meet variation in underside of footing elevations. Refer to structural for maximum step requirements
- + All crawl spaces are to be designed and built in accordance with IRC R408.3 to meet requirements of R408.3.1 and R408.3.2.2.1 or R408.3.2.2.2

REPORT ANY DISCREPANCIES BETWEEN ARCHITECTURAL DRAWINGS AND STRUCTURAL DRAWINGS PRIOR TO PROCEEDING WITH THE WORK. VERIFY ALL DIMENSIONS IN FIELD.



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.



ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

**Foundation
Plan**



- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

MackKay-Lyons
Sweetapple
Architects
Limited


2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429.1867
fax: (902) 429.6276

north



- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.



2 Elevation 2
A301 Scale 1/4" = 1'-0"

Elevation 2


scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A301


MackKay-Lyons
Sweetapple
Architects
Limited

2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429.1867
fax: (902) 429.6276



- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Elevation 3

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA

A302




1 Elevation 3
Scale 1/4" = 1'-0"

MackKay-Lyons
Sweetapple
Architects
Limited


2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429.1867
fax: (902) 429.6276

north

- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

MackKay-Lyons
Sweetapple
Architects
Limited


2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429.1867
fax: (902) 429.6276

north



- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.



SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

MackKay-Lyons
Sweetapple
Architects
Limited

2188 Cottingham St.
Halifax, Nova Scotia
Canada B3K 3B4


ph: (902) 429.1867
fax: (902) 429.6276

north

2 Elevation 7
Scale 1/4" = 1'-0"

- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.


ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




1 Elevation 6
Scale 1/4" = 1'-0"


Elevation
6 + 7

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA


A305



2
A306 Elevation 9
Scale 1/4" = 1'-0"




3
A306 Elevation 10
Scale 1/4" = 1'-0"



1
A306 Elevation 8
Scale 1/4" = 1'-0"

- 1 1x6 vertical wood cladding, refer to specification, see A001 for profile
- 2 black standing seam metal roofing, refer to specification
- 3 metal flashing - to match roofing, refer to specification
- 4 horizontal board-formed concrete, refer to specification
- 5 black steel panel TBD, refer to specification
- 6 glazing system, see window/door schedule
- 7 metal flashing - to match glazing system, refer to specification
- 8 skylight glazing system, see window/door schedule
- 9 stainless steel chimney, refer to specification
- 10 1x6 vertical shiplap shou sugi ban clad sliding barn doors, see window/door schedule
- 11 bi-fold garage door clad w/ 1x6 vertical shou sugi ban; align w/ exterior siding, see window/door schedule
- 12 reserved
- 13 snow cleat system, refer to specification
- 14 sliding door track, refer to specification



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.



ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




2 Building Section
Scale 1/4" = 1'-0"




3 Building Section
Scale 1/4" = 1'-0"



4 Building Section
Scale 1/4" = 1'-0"



1 Building Section
Scale 1/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.



DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


Building Sections

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA


A400



2 Building Section
Scale 1/4" = 1'-0"



1 Building Section
Scale 1/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.


ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


Building Sections





3 Building Section
Scale 1/4" = 1'-0"



2 Building Section
Scale 1/4" = 1'-0"



1 Building Section
Scale 1/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.



ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.



2 Building Section
Scale 1/4" = 1'-0"



1 Building Section
Scale 1/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


Building Sections

scale: 1/4" = 1'-0"
date: 2019-06-03
drawn: TRLM
chk'd: SA


A403




5 Wall Section @ Great Rm Hearth
Scale 1/2" = 1'-0"




4 Wall Section @ Great Room
Scale 1/2" = 1'-0"




3 Wall Section @ Kitchen/Loft
Scale 1/2" = 1'-0"



2 Wall Section @ Great Room Cantilever
Scale 1/2" = 1'-0"



1 Wall Section @ Entry
Scale 1/2" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Wall Sections


scale: 1/2" = 1'-0"

date: 2019-06-03


drawn: TR

chk'd: SA


A500




4
A501
Wall Section @ Center Gable/Entry
Scale 1/2" = 1'-0"



3
A501
Wall Section @ Center Gable
Scale 1/2" = 1'-0"



2
A501
Wall Section @ Garage Connection
Scale 1/2" = 1'-0"



1
A501
Wall Section @ Garage/Bunk Room
Scale 1/2" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.


ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




4
A502
Wall Section @ Day Bed
Scale 1/2" = 1'-0"



3
A502
Wall Section @ Center Gable/Entry
Scale 1/2" = 1'-0"



2
A502
Wall Section @ Hall Connection
Scale 1/2" = 1'-0"



1
A502
Wall Section @ Laundry Rm
Scale 1/2" = 1'-0"

STATE OF UTAH
Brian MackKay-Lyons
No. 9809836
LICENSED ARCHITECT

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.


ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




4
A503
Wall Section @ Family Rm Cantilever
Scale 1/2" = 1'-0"



3
A503
Wall Section @ Garage
Scale 1/2" = 1'-0"



2
A503
Wall Section @ Family Rm
Scale 1/2" = 1'-0"



1
A503
Wall Section @ Family Rm Hearth
Scale 1/2" = 1'-0"

Kinefelter Residence


Summit Powder Mountain
Elev. 9000'

MackKay-Lyons
Sweetapple
Architects
Limited

2188 Gorington St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429 1867
fax: (902) 429 6276

north



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.



DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


Wall Sections

scale: 1/2" = 1'-0"
date: 2019-06-03
drawn: TR
chk'd: SA


A503




5
A504 Wall Section @ Terrace Door
Scale 1/2" = 1'-0"




4
A504 Wall Section @ Entry
Scale 1/2" = 1'-0"




3
A504 Wall Section @ Hallway
Scale 1/2" = 1'-0"



2
A504 Wall Section @ Hallway Stair
Scale 1/2" = 1'-0"



1
A504 Wall Section @ Hallway
Scale 1/2" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.



DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


Wall Sections

scale: 1/2" = 1'-0"
date: 2019-06-03
drawn: TR
chk'd: SA


A504




4
A610 Stair 006 Section
Scale 3/4" = 1'-0"




3
A610 Partial Plan @ Stair 006 to Ski Room
Scale 3/4" = 1'-0"



2
A610 Stair 117 Section
Scale 3/4" = 1'-0"



1
A610 Partial Plan @ Stair 117 to Kitchen
Scale 3/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


STAIR DETAILS

scale: 3/4" = 1'-0"
date: 2019-08-27
drawn: KC
chk'd:


A610



3
A611 Stair 011 and 118 Section
Scale 3/4" = 1'-0"



2
A611 Partial Plan @ Stair 118 2nd Floor to Main Floor Center Building
Scale 3/4" = 1'-0"



1
A611 Partial Plan @ Stair 011 and 118 to Center Building 2nd Floor / Basement
Scale 3/4" = 1'-0"

STATE OF UTAH
Brian MacKay-Lyons
No. 9809836
LICENSED ARCHITECT

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.



ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MacKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.


AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.




4
A612 Stair 121 Section
Scale 3/4" = 1'-0"




2
A612 Stair 120 Section
Scale 3/4" = 1'-0"



3
A612 Partial Plan @ Stair 121 to Day Bed
Scale 3/4" = 1'-0"



1
A612 Partial Plan @ Stair 120 to Garage
Scale 3/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.



AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.


SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

**STAIR
DETAILS**


scale: 3/4" = 1'-0"
date: 2019-08-27
drawn: KC
chk'd: A612



2 Stair 119 and 009 Section
Scale 3/4" = 1'-0"



1 Partial Plan @ Stair 119 to East Building 2nd Floor and Stair 009 to Basement
Scale 3/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date
Revision:		

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.


DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.


**STAIR
DETAILS**

scale: 3/4" = 1'-0"
date: 2019-08-27
drawn: KC
chk'd:


A613




5 Section at Stair Tread
Scale 3" = 1'-0"




4 Elevation - Wood Rail
Scale 3" = 1'-0"




3 Section at Wood Rail and Guard
Scale 3" = 1'-0"



6 Section at Stair Rise to Run
Scale 3" = 1'-0"



2 Stair 210 Section
Scale 3/4" = 1'-0"



1 Partial Plan @ Stair 210 to East Building Bunk Room
Scale 3/4" = 1'-0"

Kinefeller Residence

Summit Powder Mountain
Eden, Utah

MackKay-Lyons
Sweetapple
Architects
Limited

2188 Göttingen St.
Halifax, Nova Scotia
Canada B3K 3B4

ph: (902) 429-1867
fax: (902) 429-6276

north

STATE OF UTAH
Brian MackKay-Lyons
No. 9809836
LICENSED ARCHITECT

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

Revision:

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.



DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

STAIR
DETAILS

scale: 3/4" = 1'-0"
date: 2019-08-27
drawn: KC
chk'd:

A614



ELECTRICAL LEGEND

- ⊕ 120v duplex
- ⊕ duplex with USB charger - Type A and Type C
- ⊕ gfci duplex
- ⊕ 240v duplex
- ⊕ floor duplex
- exterior duplex
- ⊕ wall mounted luminaire
- shower luminaire
- ⊕ ceiling mounted luminaire
- ⊕ ceiling mounted pendant
- exterior wall mounted light
- ⊕ adjustable recessed luminaire
- ceiling mounted
- puck light
- ⊕ wall switch
- ⊕ multi way switch
- ⊕ timer switch
- ⊕ exhaust fan
- ⊕ HRV supply/return
- ⊕ telephone jack
- ⊕ cable tv jack

- ⊕ internet jack
- ⊕ ceiling mounted smoke alarm / CO detector
- ⊕ wall mounted smoke alarm / CO detector
- ⊕ thermostat
- ⊕ electric wall heater
- ⊕ alarm control pad
- ⊕ recessed linear lighting
- ⊕ recessed footlights
- ⊕ track light
- ⊕ LED tape light
- ⊕ square trim LED potlight

APPLIANCE LEGEND

- ① dishwasher
 - ② grill
 - ③ cooktop
 - ④ refrigerator
 - ⑤ freezer
 - ⑥ washer
 - ⑦ dryer
 - ⑧ ventilation hood
 - ⑨ undercounter microwave
 - ⑩ undercounter fridge/freezer
 - ⑪ built-in coffee
 - ⑫ built-in oven
- (refer to appliance specs for electrical requirements)

1 A800 Electrical Plan - Basement Level
Scale 1/4" = 1'-0"

02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:


COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.



ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

**Electrical Plan
Bsmt Level**






ELECTRICAL LEGEND

- ⊕ 120v duplex
- ⊕ duplex with USB charger - Type A and Type C
- ⊕ gfi duplex
- ⊕ 240v duplex
- ⊕ floor duplex
- exterior duplex
- ⊕ wall mounted luminaire
- shower luminaire
- ⊕ ceiling mounted luminaire
- ⊕ ceiling mounted pendant
- exterior wall mounted light
- adjustable recessed luminaire
- ceiling mounted
- puck light
- ⊕ wall switch
- ⊕ multi way switch
- ⊕ timer switch
- ⊕ exhaust fan
- ⊕ HRV supply/return
- ⊕ telephone jack
- ⊕ cable tv jack

- ⊕ internet jack
- ⊕ ceiling mounted smoke alarm / CO detector
- ⊕ wall mounted smoke alarm / CO detector
- ⊕ thermostat
- ⊕ electric wall heater
- ⊕ alarm control pad
- ⊕ recessed linear lighting
- ⊕ recessed footlights
- ⊕ track light
- ⊕ LED tape light
- ⊕ square trim LED potlight

APPLIANCE LEGEND

- ① dishwasher
 - ② grill
 - ③ cooktop
 - ④ refrigerator
 - ⑤ freezer
 - ⑥ washer
 - ⑦ dryer
 - ⑧ ventilation hood
 - ⑨ undercounter microwave
 - ⑩ undercounter fridge/freezer
 - ⑪ built-in coffee
 - ⑫ built-in oven
- (refer to appliance specs for electrical requirements)



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.



ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify Mackay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify Mackay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.



ELECTRICAL LEGEND


- ⊕ 120v duplex
- ⊕ duplex with USB charger - Type A and Type C
- ⊕ gfi duplex
- ⊕ 240v duplex
- ⊕ floor duplex
- exterior duplex
- ⊕ wall mounted luminaire
- shower luminaire
- ⊕ ceiling mounted luminaire
- ⊕ ceiling mounted pendant
- exterior wall mounted light
- adjustable recessed luminaire
- ceiling mounted
- puck light
- ⊕ wall switch
- ⊕ multi way switch
- ⊕ timer switch \$T
- ⊕ exhaust fan
- ⊕ HRV supply/return
- ⊕ telephone jack
- ⊕ cable tv jack

- ⊕ internet jack
- ⊕ ceiling mounted smoke alarm / CO detector
- ⊕ wall mounted smoke alarm / CO detector
- ⊕ thermostat
- ⊕ electric wall heater
- ⊕ alarm control pad
- ⊕ recessed linear lighting
- ⊕ recessed footlights
- ⊕ track light
- ⊕ LED tape light
- ⊕ square trim LED potlight

APPLIANCE LEGEND

- ① dishwasher
 - ② grill
 - ③ cooktop
 - ④ refrigerator
 - ⑤ freezer
 - ⑥ washer
 - ⑦ dryer
 - ⑧ ventilation hood
 - ⑨ undercounter microwave
 - ⑩ undercounter fridge/freezer
 - ⑪ built-in coffee
 - ⑫ built-in oven
- (refer to appliance specs for electrical requirements)

1 A802 Electrical Plan - Second Level
Scale 1/4" = 1'-0"



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.



ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

**Electrical Plan
Second Level**



DOOR SCHEDULE				
MARK	TYPE	SIZE	FIRE RATING	STC
0001	A		Unrated	--
0002	A		Unrated	--
0003	B		Unrated	--
0004	B		Unrated	--
0005	M		Unrated	--
0006	G		Unrated	--
0007	N		Unrated	--
0008	O		Unrated	--
0009	L		Unrated	--
0010	L		Unrated	--
0011	H		Unrated	--
0012	L		Unrated	--
0013	H		Unrated	--
0014	O		Unrated	--
0015	H		Unrated	--
0016	H		Unrated	--
0017	H		Unrated	--
0018	H		Unrated	--
0019	D		Unrated	--
0020	D		Unrated	--
0021	K		Unrated	--
0022	H		Unrated	--
0023	H		Unrated	--
0024	H		Unrated	--
0025	K		Unrated	--
0026	C		Unrated	--
0027	H		Unrated	--
0028	K		Unrated	--
0029	H		Unrated	--
0030	H		Unrated	--
0031	H		Unrated	--
0032	F		Unrated	--
0033	H		Unrated	--
0034	O		Unrated	--
0035	O		Unrated	--
0036	L		Unrated	--
0037	L		Unrated	--

WINDOW SCHEDULE				
MARK	TYPE	SIZE	FIRE RATING	STC
w001	5		Unrated	--
w002	7		Unrated	--
w003	7		Unrated	--
w004	7		Unrated	--
w005	7		Unrated	--
w006	12		Unrated	--
w007	14		Unrated	--
w008	26		Unrated	--
w009	18		Unrated	--
w010	18		Unrated	--
w011	20		Unrated	--
w012	27		Unrated	--
w013	23		Unrated	--
w014	23		Unrated	--
w015	16		Unrated	--
w016	15		Unrated	--
w017	15		Unrated	--
w018	10		Unrated	--
w019	17		Unrated	--
w020	2		Unrated	--
w021	7		Unrated	--
w022	3		Unrated	--
w023	3		Unrated	--
w024	3		Unrated	--
w025	3		Unrated	--
w026	8		Unrated	--
w027	8		Unrated	--
w028	13		Unrated	--
w029	17		Unrated	--
w030	19		Unrated	--
w031	24		Unrated	--
w032	24		Unrated	--
w033	15		Unrated	--
w034	15		Unrated	--
w035	8		Unrated	--
w036	4		Unrated	--
w037	6		Unrated	--
w038	23		Unrated	--
w039	27		Unrated	--
w040	27		Unrated	--
w041	27		Unrated	--
w042	28		Unrated	--
w043	22		Unrated	--


GLAZING LEGEND

GL1 - Double Glazed Vision Glass
GL2 - Double Glazed Vision Glass w/ Category II Safety Glass

NOTES

+ Door type O is to be solid weather stripped door equipped with approved self-closing mechanism, in accordance with IRC G2406.2.5 and N1102.4.4

+ All skylights are to have fully tempered panes, require screens and shall be tested by an approved independent laboratory and bear a label identifying manufacturer, performance grade rating and approved inspection agency in compliance with the requirements of AAMA/WDMA/CSA 101/I.S.2/A440, in accordance with IRC R308.6.9.



02	Revised for Construction	12 Sept 2019
01	Revised for Construction	27 August 2019
No.	Description	Date

NOTES:

COPYRIGHT RELATED TO THE USE OF THIS DRAWING:
The use of this drawing shall be governed by standard copyright law as generally accepted in architectural practice.

ARCHITECT'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Architect.

ENGINEER'S REQUIREMENTS AND APPROVALS:
It is the Builder's responsibility to notify MackKay-Lyons Sweetapple Architects Ltd. and to seek prior written approval for materials and workmanship which deviates from instructions provided by the Engineer.

AUTHORITIES' REQUIREMENTS AND APPROVALS:
All materials and workmanship must comply with the requirements of all authorities having jurisdiction over the work. It is the Builder's responsibility to gain necessary approval from all relevant Authorities.

DIMENSIONS:
All dimensions must be verified on site. Do not scale off drawings. Plans take precedent over elevations. In the absence of dimensions, or if discrepancies exist, consult Architect. All minimum dimensions are to comply with the National Building Code of Canada.

SHOP DRAWINGS:
Submit shop drawings to the Architect and Engineer for approval prior to manufacture of prefabricated elements of the building.

Window +
Door
Schedule

DESIGN CODE:

2015 INTERNATIONAL BUILDING CODE (IBC)

DESIGN CRITERIA:

GROUND SNOW LOAD,	= 260 PSF
ROOF SNOW LOAD	= 170 PSF
UNBALANCED SNOW LOAD	= 221 PSF
FLAT ROOF SNOW LOAD, Pf	= 117 PSF
SNOW EXPOSURE FACTOR, Ce	= 1.0
SNOW IMPORTANCE FACTOR, Is	= 1.0
THERMAL FACTOR, Ct	= 1.0
3 SECOND GUST WIND SPEED	= 115 MPH

WIND EXPOSURE	= C
INTERNAL PRESSURE COEFFICIENT	= ± 0.18
COMPONENT & CLADDING DESIGN PRESSURE	= 20 PSF

SEISMIC USE GROUP	= 11
SDS, SDI	= 0.582g, 0.275g
SOIL SITE CLASS	= C
BASIC SEISMIC-FORCE RESISTING SYSTEM	= LIGHT FRAME WALLS WITH SHEAR PANELS
R (RESPONSE MODIFICATION)	= 6.5K
ANALYSIS PROCEDURE	= EQUIVALENT LATERAL FORCE
SEISMIC DESIGN COT	= D

DESIGN LOADS:

ROOF LIVE LOAD	= 117 PSF + DRIFTING (221 PSF UNBALANCED)
ROOF DEAD LOAD	= 20 PSF
FLOOR LIVE LOAD	= 40 PSF
FLOOR DEAD LOAD	= 34 PSF (40 PSF @ 3" TOPPING)

GENERAL STRUCTURAL NOTES:

- GENERAL STRUCTURAL NOTES ARE CONSTRUCTION DOCUMENTS THAT SHALL BE INCLUDED WITH THE STRUCTURAL PLANS AND PROJECT SPECIFICATIONS.
- TYPICAL DETAILS AND SCHEDULES SHALL APPLY WHERE SPECIFIC DETAILS ARE NOT SHOWN.
- "CONTRACTOR" REFERS TO THE CONTRACTOR OR SUB-CONTRACTOR RESPONSIBLE FOR THE PARTICULAR TRADE REFERRED TO IN THE NOTES. THE "CONTRACTOR" SHALL MEET ALL NOTE REQUIREMENTS AND SHALL INCLUDE THE ASSOCIATED COSTS IN HIS/HER BID.
- JMWA REFERS TO J.M. WILLIAMS AND ASSOCIATES, INC.
- THE GENERAL CONTRACTOR, PROJECT MANAGER, OR SUPERINTENDENT SHALL COORDINATE THE WORK PERFORMED BY ALL TRADES, AND IS ULTIMATELY RESPONSIBLE FOR COMPLIANCE WITH ALL NOTE REQUIREMENTS.
- THE CONTRACTOR SHALL PERFORM HIS/HER TRADE AND DUTIES IN A MANNER CONFORMING TO THE PROCEDURES AND REQUIREMENTS AS STATED IN THE 2015 INTERNATIONAL BUILDING CODE (IBC), AND/OR THE LATEST CODE AND ORDINANCES ADOPTED BY THE LOCAL BUILDING OFFICIAL.
- CONTRACTOR SHALL BE RESPONSIBLE FOR SAFETY AND PROTECTION WITHIN AND ADJACENT TO THE JOB SITE.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND / OR ARCHITECT OF ANY DISCREPANCIES, OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS, SPECIFICATIONS, AND / OR THE NOTES BEFORE PROCEEDING WITH THE FABRICATION OR CONSTRUCTION OF ANY EFFECTED ELEMENTS. ANY WORK DONE BY THE CONTRACTOR BEFORE RECEIVING THE ENGINEERS WRITTEN APPROVAL WILL BE AT THE CONTRACTOR'S RISK/EXPENSE. IN CASE OF CONFLICT, THE MOST STRINGENT REQUIREMENTS SHALL GOVERN AND BE PERFORMED AT NO ADDITIONAL COST TO THE OWNER.
- FAILURE TO FOLLOW PLANS AND CONSTRUCTION DOCUMENTS CONSTITUTES CHANGE IN PROJECT SCOPE. THE ENGINEER RESERVES THE RIGHT TO REQUEST REPLACEMENT OF ANY PORTION OF THE STRUCTURE DEVIATING FROM THE PLANS WHERE WRITTEN APPROVAL HAS NOT BEEN OBTAINED. DEVIATION FROM CONSTRUCTION DOCUMENTS WITHOUT WRITTEN APPROVAL RELIEVES ENGINEER OF ALL LIABILITY, AND CONTRACTOR ASSUMES FULL LIABILITY.
- THE CONTRACTOR SHALL VERIFY ALL CONDITIONS, DIMENSIONS, SLOPES AND ELEVATIONS, ETC... (BOTH PLANS AND AT THE JOB SITE PRIOR TO DOING WORK), AND SHALL COORDINATE THESE WITH THE ARCHITECT AND ALL TRADES. CONSTRUCTION DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR, PROVIDE AND INSTALL ALL TEMPORARY SHORING (BRACING) AS NECESSARY. SHORING SHALL SUPPORT ALL LOADS TO WHICH THE STRUCTURE MAY BE SUBJECTED [i.e. WIND, CONSTRUCTION LOADING, ETC.]. SHORING SHALL REMAIN IN PLACE AS LONG AS SAFETY REQUIRES AND/OR UNTIL ALL THE STRUCTURAL ELEMENTS ARE COMPLETED.
- DURING AND AFTER CONSTRUCTION, THE LOADS IMPOSED ON THE STRUCTURE BY THE CONTRACTOR AND OWNER SHALL BE WITHIN THE LIMITS OF THE OCCUPANCY DESIGN LOADS. SEE STRUCTURAL PLANS AND CALCULATIONS FOR THE OCCUPANCY DESIGN LOADINGS AND CRITERIA.
- VISITS TO THE JOB SITE BY REPRESENTATIVES OF J.M. WILLIAMS AND ASSOCIATES DO NOT CONSTITUTE APPROVAL OR SPECIAL INSPECTION OF THE WORK PERFORMED BY THE CONTRACTOR OR HIS SUBCONTRACTORS.
- STRUCTURAL SHOP DRAWINGS SHALL BE APPROVED BY THE ENGINEER AND ARCHITECT OF RECORD PRIOR TO FABRICATION AND ERECTION. SHOP DRAWINGS SHALL BE STAMPED BY A PROFESSIONAL ENGINEER REGISTERED IN THE SAME STATE AS THE PROJECT.
- SEE STRUCTURAL PLANS AND PROJECT SPECIFICATIONS FOR ADDITIONAL STRUCTURAL NOTES AND REQUIREMENTS.
- ALL COMPONENTS AND SYSTEMS NOT SPECIFICALLY ENGINEERED BY THE ENGINEER OF RECORD SHALL BE "DESIGN-BUILD" BY THE CONTRACTOR. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SHOP DRAWINGS OR AS-BUILT DRAWINGS STAMPED BY A PROFESSIONAL ENGINEER IF REQUIRED BY THE CITY. IF PRE-ENGINEERED SYSTEM IMPACTS THE ORIGINAL DESIGN FOR INTENT OF THE PROJECT IN ANY WAY, CONTRACTOR SHALL COORDINATE WITH ENGINEER OF RECORD.
- PRE-ENGINEERED SYSTEMS SUCH AS TRUSSES, GREENHOUSES, POOLS, DECKS, ETC. SHALL BE ENGINEERED AND DETAILED BY OTHERS UNLESS SPECIFICALLY CONTRACTED OTHERWISE. THE ENGINEER OF RECORD IS NOT RESPONSIBLE FOR, NOR HAS ANY LIABILITY REGARDING PRE-ENGINEERED SYSTEMS. THE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS AS REQUIRED.
- THE ENGINEER OF RECORD IS ONLY RESPONSIBLE FOR ITEMS SPECIFICALLY ENGINEERED BY HIM OR UNDER HIS DIRECT SUPERVISION. THE ENGINEER OF RECORD IS NOT LIABLE FOR ANY NON-STRUCTURAL ISSUES UNLESS SPECIFICALLY CONTRACTED OTHERWISE.
- CHECKING OF SHOP DRAWINGS IS ONLY FOR GENERAL CONFORMATION WITH THE DESIGN CONCEPT OF THE PROJECT AND GENERAL COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. ANY ACTION SHOWN IS SUBJECT TO THE REQUIREMENTS OF THE PLANS AND SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR: DIMENSIONS WHICH SHALL BE CONFIRMED AND CORRELATED AT THE JOB SITE; FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION; COORDINATION OF HIS WORK WITH THAT OF ALL OTHER TRADES AND THE SATISFACTORY PERFORMANCE OF HIS WORK.
- JMWA IS NOT RESPONSIBLE FOR THE COST OF CONSTRUCTION NOR PROJECT BUDGETS, U.N.O. ANY STRUCTURAL CHANGES REQUIRED BY THE CONTRACTOR, OWNER, ARCHITECT, ETC., SHALL BE INVOICED BY JMWA AND TREATED AS ADDITIONAL SERVICES. JMWA SHALL BE COMPENSATED FOR ADDITIONAL ENGINEERING REQUIRED AS A RESULT OF ANY THIRD PARTY OR CITY REVIEW, PROVIDED ORIGINAL DESIGN IS IN ACCORDANCE WITH THE CURRENT BUILDING CODE.

EARTHWORK:

DESIGN CRITERIA

- SOILS REPORT: IGES NO. 02904-001
- SOIL BEARING PRESSURE: 2900 PSF, USE 2500 PSF
- LATERAL SOIL PRESSURE:
 - ACTIVE = 40 PCF
 - AT REST = 60 PCF (RIGID FOUNDATION WALLS)
 - PASSIVE = 350 PCF
- FROST DEPTH = 42 in.
- COEFFICIENT OF FRICTION = 0.45
- ENGINEERED FILL = 2'-0" MIN.

REQUIREMENTS

- CONTRACTOR SHALL REMOVE EXISTING FOOTINGS, FOUNDATIONS, SLABS, SITE PAVING, STRUCTURES AS REQUIRED.
- CONTRACTOR SHALL STRIP THE BUILDING AREA FROM ALL VEGETATION, DEBRIS AND TOPSOIL. CONTRACTOR SHALL EXCAVATE ANY REMAINING LOOSE NATURAL OR FILL SOILS TO EXPOSE COMPETENT NATURAL SOILS.
- CONTRACTOR SHALL CHECK FOR SOFT SPOTS OR OTHER UNSUITABLE SOILS BY PROOF ROLLING THE ENTIRE BUILDING PAD AREA WITH SUITABLE COMPACTION EQUIPMENT. REMOVE UNSUITABLE MATERIALS AND REPLACE WITH COMPACTED ENGINEERED OR STRUCTURAL FILL OR 2,000 PSI LEAN CONCRETE (FLOWABLE FILL).
- ENGINEERED OR STRUCTURAL FILL MATERIAL SHALL BE WELL-GRADED, GRANULAR, WITH A MAXIMUM SIZE LESS THAN 4 INCHES, AND NOT MORE THAN 20 PERCENT PASSING A NO. 200 SEIVE. PLACE STRUCTURAL FILL IN MAXIMUM LIFTS OF 8 INCHES. COMPACT STRUCTURAL FILL TO 95 PERCENT OF THE MAXIMUM LABORATORY DENSITY AS DETERMINED BY ASTM D 1557. TEST ALL STRUCTURAL FILL. FILL MATERIAL AND PLACEMENT OF ALL FILL MATERIAL MUST MEET THE APPROVAL OF THE SOILS ENGINEER.
- SEE PLANS FOR THICKNESS OF ALL FLOOR SLABS. UNDERLAY ALL SLABS WITH AT LEAST A 4 INCH THICK LAYER OF FREE-DRAINING GRANULAR MATERIAL. GRANULAR MATERIAL SHALL HAVE A MAXIMUM SIZE LESS THAN 1 INCH, WITH NOT MORE THAN 5 PERCENT PASSING A NO. 200 SIEVE. COMPACT GRANULAR MATERIAL TO AT LEAST 90 PERCENT OF THE MAXIMUM LABORATORY DENSITY PER ASTM D 1557, U.N.O.
- REFER TO THE PROJECT SPECIFICATIONS AND SOILS REPORT FOR FURTHER EARTHWORK REQUIREMENTS.
- ANY UNFORSEEN CONDITIONS ENCOUNTERED DURING SITE PREPARATION SHALL BE BROUGHT TO THE ATTENTION OF THE SOILS ENGINEER.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL SITE SOILS CONDITIONS FIELD VERIFIED.
- EXPANSIVE SOILS, COLLAPSIVE SOILS SOILS WITH A HIGH LIQUIFICATION POTENTIAL, HIGH WATER TABLES, STEEP SLOPES, ETC. ALL REQUIRE ADDITIONAL ENGINEERING. CONTRACTOR TO COORDINATE WITH PROJECT ENGINEER AND SOILS ENGINEER.
- PROVIDE SUBSURFACE DRAINAGE AS RECOMMENDED BY SOILS ENGINEER SHOULD LOWEST FLOOR LEVEL OF A STRUCTURE EXTEND BELOW ORIGINAL GRADE AND WITHIN 4 FEET OF THE WATER LEVEL.

DRAINAGE NOTES:

- THE GROUND SURFACE SURROUNDING THE PROPOSED RESIDENCES SHOULD BE SLOPED AWAY FROM THE BUILDING IN ALL DIRECTIONS. ROOF DOWNSPOUTS AND DRAINS SHOULD DISCHARGE BEYOND THE LIMITS OF BACKFILL.
- SLOPE GARAGE FLOOR TO FRONT W/ 2% SLOPE FOR DRAINAGE - TYP.

SUB SURFACE DRAIN NOTES:

- IF THE LOWEST FLOOR LEVEL OF A STRUCTURE EXTENDS BELOW ORIGINAL GRADE AND BELOW OR WITHIN 4 FEET OF THE WATER LEVEL, THE SUBGRADE FLOOR PORTION OF THE PROPOSED STRUCTURE SHOULD BE PROTECTED WITH A PERIMETER DRAIN SYSTEM. THE PERIMETER DRAIN SYSTEM SHOULD CONSIST OF AT LEAST THE FOLLOWING ITEMS:
 - THE UNDERDRAIN SYSTEM SHOULD CONSIST OF A PERFORATED PIPE INSTALLED IN A GRAVEL FILLED TRENCH AROUND THE PERIMETER OF THE SUBGRADE FLOOR PORTION OF THE BUILDING.
 - THE FLOW LINE OF THE PIPES SHOULD BE PLACED AT LEAST 18 INCHES BELOW THE FINISHED FLOOR LEVEL AND SHOULD SLOPE TO A SUMP OR OUTLET WHERE WATER CAN BE REMOVED BY PUMPING OR BY GRAVITY FLOW.
 - IF PLACING THE GRAVEL AND DRAINPIPE REQUIRES EXCAVATION BELOW THE BEARING LEVEL OF THE FOOTING, THE EXCAVATION FOR THE DRAINPIPE AND GRAVEL SHOULD HAVE A SLOPE NO STEEPER THAN 1 HORIZONTAL TO 1 VERTICAL SO AS NOT TO DISTURB THE SOIL BELOW THE FOOTING.
 - A FILTER FABRIC SHOULD BE PLACED BETWEEN THE NATURAL SOIL AND THE DRAIN GRAVEL. THIS WILL HELP REDUCE THE POTENTIAL FOR FINE GRAIN MATERIAL FILLING IN THE VOID SPACES OF THE GRAVEL.
 - THE SUBGRADE FLOOR SLAB SHOULD HAVE AT LEAST 6 INCHES OF FREE DRAINING GRAVEL PLACED BELOW IT AND THE UNDERSLAB GRAVEL SHOULD CONNECT TO THE PERIMETER DRAIN.
 - CONSIDERATION SHOULD BE GIVEN TO INSTALLING CLEAN OUTS TO ALLOW ACCESS INTO THE PERIMETER DRAIN SHOULD CLEANING OF THE PIPES BE REQUIRED IN THE FUTURE.

CONCRETE NOTES

- ALL WORK SHALL BE IN STRICT ACCORDANCE WITH THE 2015 IBC, ACI 318, AND LOCAL ORDINANCES.
- CONTRACTOR SHALL COORDINATE WITH MECHANICAL, ELECTRICAL, AND ARCHITECTURAL PRIOR TO PLACING CONCRETE. PROVIDE SLEEVES, BLOCK OUTS, ETC... AS REQUIRED.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER PLACEMENT OF ALL ANCHOR BOLTS, SEISMIC ANCHORS OR STRAPS, ETC... INSTALL PER MANUFACTURER'S SPECIFICATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, DETAILING, CARE, PLACEMENT AND REMOVAL OF ALL FORMWORK AND SHORES.
- DO NOT REMOVE FORMS AND SHORING UNTIL STRUCTURAL MEMBERS ACQUIRE SUFFICIENT STRENGTH TO SUPPORT THEIR OWN WEIGHT PLUS CONSTRUCTION LOADS.

CONCRETE AND REINFORCING MATERIAL

- REQUIRED MIN. 28 DAY COMPRESSIVE STRENGTH OF CONCRETE: 4000 PSI USED FOR DESIGN (USE 4000 PSI FOR DURABILITY NO TESTING REQUIRED TYP.)
- FOOTINGS AND FOUNDATIONS: 4000 PSI
- INTERIOR SLABS ON GRADE: 3000 PSI U.N.O.
- WALLS: 4000 PSI
- SITE CONCRETE: 4000 PSI

- PROVIDE NORMAL WEIGHT AGGREGATES PER ASTM C-33, U.N.O.
- PROVIDE TYPE II CEMENT PER ASTM C-150 FOR ALL CONCRETE, U.N.O.
- MAXIMUM WATER TO CEMENT RATIO IS EQUAL TO 0.50 FOR ALL CONCRETE.
- MAXIMUM SLUMP OF CONCRETE IS EQUAL TO 4 INCHES PLUS OR MINUS 1 INCH.
- PROVIDE AIR ENTRAINING AS RECOMMENDED BY ACI 318 AND ASTM C-260.
- DO NOT ADD CALCIUM CHLORIDE TO CONCRETE MIX.
- THE MAX. CHLORIDE ION CONTENT FOR CORROSION PROTECTION OF REINFORCEMENT IS 0.15% BY WEIGHT OF CEMENT.
- SEE PROJECT SPECIFICATIONS FOR ADDITIONAL CONCRETE DESIGN REQUIREMENTS.

REINFORCEMENT

- ALL REINFORCING STEEL SHALL BE GRADE 60 BARS PER ASTM A615. FIELD BENT DOWELS MAY BE GRADE 40.
- ALL DEFORMED BAR ANCHORS SHALL CONFORM TO ASTM A496.
- ALL HEADED STUD ANCHORS SHALL CONFORM TO ASTM A108.
- ALL WELDED WIRE FABRIC SHALL CONFORM TO ASTM 185. LAP ONE MESH TIE.
- ALL REINFORCING STEEL SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH THE CI DETAILING MANUAL AND ACI STANDARDS (LATEST ADDITION).
- REINFORCING STEEL AND EMBEDS SHALL BE PROPERLY TIED INTO PLACE PRIOR TO PLACING CONCRETE.
- ALL SPLICES IN REINFORCING BARS SHALL LAP A MINIMUM OF 40 BAR DIAMETERS (U.N.O.). ALL SPLICES SHALL OCCUR IN A COMPRESSION ZONE UNLESS NOTED OTHERWISE. TERMINATE ALL REINFORCING BARS WITH A 90 DEG. BEND OR WITH SEPARATE CORNER BARS.
- MECHANICAL SPLICES SHALL BE POSITIVE CONNECTING COUPLERS AND SHALL MEET ALL APPLICABLE CODE REQUIREMENTS. ADJACENT MECHANICAL SPLICES SHALL BE STAGGERED A MINIMUM OF 24 INCHES ALONG THE REINFORCING BARS. TENSILE CAPACITY OF MECHANICAL % OF THE SPLICED BAR. SPLICES SHALL BE 12S.
- HORIZONTAL REINFORCEMENT SHALL BE CONTINUOUS THROUGH CONSTRUCTION AND CONTROL JOINTS. 10.DD NOT SPLICE STIRRUPS AND TIES.
- DO NOT WELD REINFORCING BARS. DO NOT SUBSTITUTE REINFORCING BARS FOR DEFORMED ANCHOR BARS OR HEADED ANCHOR STUDS.
- REINFORCEMENT SHALL HAVE THE FOLLOWING CLEAR COVER:
 - CAST-IN-PLACE CONCRETE:
 - CAST AGAINST/PERMANENTLY EXPOSED TO EARTH 3"
 - FORMED CONCRETE EXPOSED TO EARTH/WEATHER:
 - #6 THRU #18 BARS 2"
 - #5 AND SMALLER BARS 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH/WEATHER:
 - SLABS, WALLS, JOISTS (#11 AND SMALLER) 3/4"
 - BEAMS, COLUMNS, TIES, STIRRUPS 1-1/2"
 - TILT-UP PANELS (PLANT-CONTROLLED CONDITIONS):
 - #9 THRU #18 BARS 2"
 - #8 BARS AND SMALLER 1"

FOUNDATION AND RETAINING WALLS

- BRACE WALLS AS REQUIRED UNTIL FLOOR SLABS AND/OR FLOOR FRAMING ARE IN PLACE, AND UNTIL WALLS HAVE PROPERLY CURED.
- BACKFILL ADJACENT TO FOUNDATION WALLS OR IN LANDSCAPED AREAS SHALL BE PLACED IN 8% OF OPTIMUM AND INCH MAXIMUM LOOSE LIFTS. FILL SHALL HAVE MOISTURE CONTENT WITHIN 2% MAXIMUM DENSITY (ASTM D 1557). HEAVY EQUIPMENT SHALL BE CHAIRED IN THE SLAB. WWF SHALL BE CONTINUOUSLY SUPPORTED AT 36" ON CENTER PRIOR TO PLACING CONCRETE.
- SEE ARCHITECTURAL DRAWINGS FOR DRAINAGE METHOD BEHIND FOUNDATION AND RETAINING WALLS.
- CONSTRUCTION JOINTS (COLD JOINTS) IN WALLS SHALL BE WATERPROOFED TO PREVENT LEAKS.
- DO NOT SPICE VERTICAL BARS IN RETAINING WALLS UNLESS SPECIFICALLY SHOWN.
- CONTRACTOR SHALL COORDINATE STEPS IN WALLS WITH THE ARCHITECT, AND SHALL VERIFY WITH JMWA.
- PROVIDE CORNER BARS AT INTERSECTING WALL CORNERS USING THE SAME BAR SIZE AND SPACING AS THE HORIZONTAL WALL REINFORCING.
- PROVIDE VERTICAL DOWELS INTO FOOTINGS AND FOUNDATIONS THAT MATCH THE SIZE AND SPACING OF THE VERTICAL REINFORCEMENT IN THE ABOVE MEMBER.
- DO NOT SURCHARGE FDN. AND RETAINING WALLS WITH EQUIPMENT NOR STAGING.
- PROVIDE (2) #5 BARS MIN. AROUND ALL DOOR AND WINDOW OPENINGS, U.N.O.
- PENETRATIONS THROUGH WALLS SHALL BE REINFORCED BY PROVIDING ONE ADDITIONAL BAR AT THE EDGE OF OPENING FOR EACH BAR INTERRUPTED BY THE PENETRATION. PROVIDE UNIFORM NUMBER OF BARS EACH SIDE. PROVIDE (2) #4 DIAGONAL BARS ON 4 SIDES TYP. U.N.O.
- SEE SCHEDULES, TABLES, AND DETAILS FOR ADDITIONAL REINFORCING AND INFORMATION.

SLABS

- REINFORCE ALL SLABS ON GRADE W/ #4 @ 18" O.C. EACH WAY, TOPPING SLABS, #3 @ 18" O.C. EACH WAY OR WITH 6 x 6 - W2.9xW2.9 WELDED WIRE FABRIC (WWF) UNLESS NOTED OTHERWISE ON THE PLAN.
- ALL REINFORCING BARS SHALL BE CHAIRED IN THE SLAB. WWF SHALL BE CONTINUOUSLY SUPPORTED AT 36" ON CENTER PRIOR TO PLACING CONCRETE.
- BEGIN POUR OF COMPOSITE STEEL DECK AND CONCRETE FLOORS AT OR NEAR A SUPPORT OR BEARING WALL TO AVOID EXCESSIVE DEFLECTION AND/OR STRESSING OF THE FLOOR STRUCTURE. SEE SUSPENDED SLAB CONSTRUCTION NOTES FOR ADDITIONAL REQUIREMENTS.
- RECESS FOUNDATION AND POUR SLABS THROUGH, TYPICAL AT ALL EXTERIOR DOORS AND STORE FRONT TYPE WINDOWS.
- DEPRESS SLABS AS REQUIRED IN AREAS OF CERAMIC TILE, SPECIAL ENTRY MATS, HARDWOOD FLOORS, ETC. COORDINATE LOCATION AND DEPTH WITH THE ARCHITECT.
- PROVIDE ISOLATION JOINTS AROUND COLUMNS/SPREAD FOOTINGS, AND CONTROL JOINTS AS REQUIRED (I.E., WHERE SLABS TRANSITION IN SIZE).
- THE CONTRACTOR SHALL ENSURE THAT HEAVY EQUIPMENT AND STAGING AREAS DO NOT CRACK AND DAMAGE SLABS. DAMAGED SLABS SHALL BE REPAIRED OR REPLACED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- PROVIDE 2 - #4 BARS X 48 INCHES AT ALL DISCONTINUOUS CONTROL OR CONSTRUCTION JOINTS IN SLAB-ON-GRADE.
- SPACING BETWEEN CONSTRUCTION OR CONTROL JOINTS IN SLABS-ON-GRADE SHALL NOT EXCEED 15'-0" FOR 4" THICK SLABS AND 20'-0" FOR 5" AND 6" THICK SLABS.
- THE LENGTH TO WIDTH RATIO OF CONTROL JOINTS SHALL NOT EXCEED 1.25:1. CONSTRUCTION AND CONTROL JOINTS SHALL BE INSTALLED AS DETAILED IN THE DRAWINGS.
- SAWCUT JOINTS SHALL BE MADE WITHIN 12 HOURS AT PLACING CONCRETE.
- PROVIDE (1) DIAGONAL #4 BAR X 48" OF ALL INSIDE CORNERS.
- ALL SLABS SHALL BE PROPERLY CURED.
- REFER TO THE ARCHITECTURAL PLANS FOR SPECIFICATION OF ALL FLAT WORK.
- PROVIDE 4" MIN. OF FREE-DRAINING GRANULAR MATERIAL, "PEA" GRAVEL OR 3/4" TO 1" MINUS CLEAN GAP-GRADED GRAVEL UNDER ALL SLABS-ON-GRADE.
- PROPERLY CURE ALL CONCRETE. ALL CONCRETE (OTHER THAN HIGH-EARLY-STRENGTH) SHALL BE MAINTAINED ABOVE 50°F AND A MOIST CONDITION FOR AT LEAST THE FIRST 7 DAYS AFTER PLACEMENT. (HIGH-EARLY-STRENGTH CONCRETE TO REMAIN IN A MOIST CONDITION FOR THE FIRST 3 DAYS) EXCEPT WHEN CURED IN ACCORDANCE WITH ACI 318-"ACCELERATED CURING".

FOOTINGS

- ALL FOOTINGS SHALL BE 10" THICK & PROPERLY FORMED. INTERLOCKING SHALL BE MAINTAINED WITH SLAB.
- ALL EXTERIOR FOOTINGS SHALL BEAR BELOW FROST DEPTH (42 INCHES, PER GEOTECHNICAL REPORT)
- FOOTINGS SHALL BEAR ON UNDISTURBED NATURAL MATERIALS OR SHORING PLACED ENGINEERED FILL. SEE EARTHWORK NOTES FOR ADDITIONAL REQUIREMENTS, AND SOILS REPORT.
- CONTRACTOR SHALL STEP FOOTINGS & FOUNDATION AS REQUIRED.
- NO FOOTING SHALL BE PLACED IN WATER OR ON FROZEN GROUND.

WOOD FRAMING NOTES:

- ALL WORK TO BE IN STRICT ACCORDANCE WITH THE 2015 IBC, NDS, AND LOCAL ORDINANCES.

DIMENSIONAL LUMBER

- DIMENSIONAL LUMBER USED AS STRUCTURAL FRAMING (I.E. JOISTS, RAFTERS, AND HEADERS) SHALL BE DOUGLAS FIR-LARCH NO. 2 OR EQUAL.
- DIMENSIONAL LUMBER USED FOR STUD WALLS SHALL BE STUD GRADE 2x4 UNLESS NOTED OTHERWISE. SPACE AT 16" O.C. MINIMUM, WITH A DOUBLE TOP PLATE. SPLICES IN THE DOUBLE TOP PLATE SHALL ALTERNATE TOP AND BOTTOM.
- ALL SILL PLATES ARE TO BE BOLTED TO FOUNDATION W/ 5/8" DIA X 12" J-BOLTS @ 48" O.C. MINIMUM, UNLESS NOTED OTHERWISE ON THE STRUCTURAL DRAWINGS AND SHEARWALL SCHEDULE.
- IN NO CASE SHALL 2 X 4" BEARING WALLS SUPPORT MORE THAN TWO FLOORS OF FRAMING IN ADDITION TO ROOF AND CEILING.
- REFER TO CONSTRUCTION DOCUMENTS FOR ROUGH CUT TIMBER USED AS STRUCTURAL FRAMING.
- ALL NAILS SPECIFIED ON THE DETAILS AND SCHEDULES SHALL BE COMMON NAILS UNLESS NOTE OTHERWISE.

ENGINEERED LUMBER

- GLU-LAMINATED BEAMS FOR SIMPLE SPANS SHALL BE 24F-V4 DF/DF. GLU-LAMINATED BEAMS FOR CONTINUOUS SPANS AND CANTILEVERS SHALL BE 24F-V8 DF/DF. DO NOT INSTALL GLU-LAMINATED BEAMS UPSIDE DOWN.
- LAMINATED VENEER LUMBER AND THE LIKE SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS.
- I-JOISTS SHALL BE TJI OR EQUIVALENT, AND SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS.
- ENGINEERED LUMBER, WITH THE EXCEPTION OF GLU-LAMINATED LUMBER, SHALL NOT BE USED IN EXTERIOR APPLICATIONS.
- USE REDWOOD OR PRESSURE TREATED LUMBER FOR ALL WOOD IN CONTACT WITH CONCRETE, MASONRY, OR EARTH (I.E. MUD SILL).

COLUMNS

- ALL COLUMNS SHALL EXTEND DOWN THROUGH THE STRUCTURE TO THE FOUNDATION.
- COLUMNS SHALL BE BRACED AT EACH FLOOR LEVEL.
- POSTS SHALL BE DOUGLAS FIR-LARCH NO. 1 OR EQUAL.
- BEARING POINTS OF COLUMNS ARE TO BE SUPPORTED BY ADDITIONAL BUILT-UP BLOCKING AT JOISTS AND RAFTERS EQUAL TO THE NUMBER OF PLYS IN POST OR EQUAL TO WIDTH OF POST. BLOCKING SHALL BE CONSTRUCTED USING RIM BOARD MATERIAL OR SOLID SAWN LUMBER.

FLOOR, ROOF AND WALL SHEATHING

- ALL ROOF SHEATHING SHALL BE A MINIMUM OF 5/8" 48/24 APA EXP. 1 RATED SHEATHING OR EQUAL WITH 10x COMMON NAILS AT 6" O.C. PERIMETER, 6" O.C. PANEL EDGES, AND AT 12" O.C. IN THE FIELD UNLESS NOTED OTHERWISE ON SHEATHING SCHEDULE.
- PROVIDE 2 X SHAPED BLOCKING AT RIDGES UNLESS A CONTINUOUS MEMBER EXISTS. PANEL EDGES ARE UNBLOCKED UNLESS NOTED OTHERWISE ON THE STRUCTURAL PLANS.
- ALL FLOOR SHEATHING SHALL BE A MINIMUM OF 3/4" THICK T&G SHEATHING GLUED AND NAILED WITH 10d COMMON NAILS OR EQUAL AT 6" O.C. PERIMETER, 6" O.C. PANEL EDGES, AND AT 10" O.C. IN THE FIELD UNLESS NOTED OTHERWISE ON SHEATHING SCHEDULE. PANEL EDGES ARE UNBLOCKED UNLESS NOTED OTHERWISE ON THE STRUCTURAL PLANS.
- ALL EXTERIOR WALLS SHALL BE SHEATHED WITH 7/16" APA EXP. 1 RATED SHEATHING OR EQUAL WITH 8d COMMON NAILS AT 6" O.C. EDGES AND AT 12" O.C. IN THE FIELD - FLAT BLOCKED AT ALL PANEL EDGES, UNLESS NOTED OTHERWISE IN THE STRUCTURAL PLANS AND SHEAR WALL SCHEDULE.
- AT ROOF AND FLOOR DIAPHRAGMS, PANEL EDGE NAILING IS TO INCLUDE DRAG STRUTS, TENSION CHORDS, BLOCKING OVER BEARING WALLS AND SHEAR WALLS, AND ANY OTHER SPECIAL DIAPHRAGM MEMBERS NOTED ON PLANS.
- AT SHEAR WALLS, PANEL EDGE NAILING IS TO INCLUDE TOP AND BOTTOM PLATES, END POSTS, ALL VERTICLE ELEMENTS @ HOLDOWN ANCHORS, AND HORIZONTAL BLOCKING. ALL PANEL EDGES MUST BE BLOCKED.
- INTERIOR SHEAR WALLS MUST EXTEND DOWN THROUGH THE CRAWL SPACE TO A FOUNDATION. SHEATHING, NAILING AND HOLDOWNS TO MATCH THROUGH ABOVE U.N.O.
- INTERIOR SHEAR WALLS MUST EXTEND UP TO THE ROOF SHEATHING AND OR FLOOR SHEATHING ABOVE. WHEN PERPENDICULAR TO TRUSSES OR JOISTS PROVIDE TRUSSED BLOCKING OR SHEAR PANELS.

STRUCTURAL CONNECTIONS

- THE CONTRACTOR IS ULTIMATELY RESPONSIBLE TO PROVIDE ADEQUATE STRUCTURAL CONNECTIONS. CONNECTIONS MUST CARRY THE BEARING CAPACITY OF THE MEMBER AND ANY UPLIFT OR SEISMIC FORCES GENERATED IN THE MEMBER. SPECIAL CONSIDERATION SHALL BE GIVEN TO PREVENT CRUSHING OF THE MEMBER AT BEARING, SPLITTING AND / OR CRACKING OF THE WOOD, ETC.
- WRITTEN PRIOR APPROVAL FROM JMWA IS REQUIRED FOR ANY DEVIATION FROM THE CONSTRUCTION DOCUMENTS. JMWA IS NOT RESPONSIBLE FOR CONNECTIONS NOT APPROVED PRIOR TO CONSTRUCTION OR INSTALLATION.
- PROVIDE SIMPSON CONNECTIONS OR EQUAL IF CONNECTION DETAILS ARE NOT PROVIDED IN THE CONSTRUCTION DOCUMENTS. INSTALL PER MANUFACTURERS' RECOMMENDATIONS. REQUEST ADDITIONAL ASSISTANCE FROM JMWA IF NON-STANDARD CONNECTIONS ARE REQUIRED.
- ALL STRUCTURAL MEMBERS SHALL HAVE 1 3/4" BEARING (MINIMUM).
- SEE SCHEDULES IN THE 2015 IBC FOR ADDITIONAL NAILING PATTERNS.

BLOCKING, BRIDGING, MISCELLANEOUS.

- ALL JOISTS AND RAFTERS SHALL HAVE FULL-HEIGHT SOLID BLOCKING AT THEIR BEARING POINTS. CONNECT EACH BLOCK TO THE TOP OF EXTERIOR WALLS WITH SIMPSON A34 CLIPS (U.N.O.). EACH RAFTER AND/OR ROOF TRUSS SHALL BE ANCHORED WITH SIMPSON H1 ANCHORS AT EACH END.
- I-JOIST JOISTS USED AS JOISTS AND RAFTERS SHALL HAVE FULL-HEIGHT SOLID BLOCKING AT THEIR BEARING POINTS. CONNECT EACH BLOCK TO THE TOP OF EXTERIOR WALLS WITH SIMPSON A34 CLIPS (U.N.O.). EVERY OTHER I-JOIST RAFTER SHALL BE ANCHORED WITH A SIMPSON H3 CLIP.
- INSTALL BRIDGING AT THE MID-SPAN OF ALL FLOOR JOISTS AND/OR AT 8'-0" O.C. (WHICH EVER IS SMALLER). INSTALLATION SHALL BE PER MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS TO AVOID EXCESSIVE FLOOR VIBRATION AND/OR SQUEAKING.
- STANDARD PENETRATIONS THROUGH STRUCTURAL MEMBERS FOR MECHANICAL, PLUMBING, ELECTRICAL SYSTEMS, ETC. SHALL BE PROVIDED ON THE CENTER LINE OF THE MEMBER'S DEPTH AND WITHIN THE MIDDLE ONE-THIRD OF THE SPAN. LARGER THAN STANDARD PENETRATIONS ARE NOT PERMITTED WITHOUT PRIOR APPROVAL.
- BIRDS MOUTHS AND/OR NOTCHING OF STRUCTURAL MEMBERS NOT SPECIFICALLY DETAILED ON THE STRUCTURAL PLANS IS NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL.

FABRICATED FRAMING

- FABRICATED (PRE-ENGINEERED) TRUSSES MAY BE USED FOR ROOF AND/OR FLOOR FRAMING. INSTALL PER MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS. TRUSS MANUFACTURER SHALL DESIGN TRUSSES FOR ALL LOADS PER IBC, INCLUDING UNBALANCED SNOW LOADS, SNOW DRIFTING, SNOW BUILD UP IN VALLEYS AND ON EAVES, ETC. TRUSS MANUFACTURER SHALL RECOMMEND AND PROVIDE ALL REQUIRED TRUSS BRACING, BLOCKING, TRUSS TO TRUSS AND TRUSS TO BEAM CONNECTIONS, ETC. SEE GENERAL TRUSS NOTES.
- SHOP DRAWINGS FOR ALL FABRICATED FRAMING SHALL BE SUBMITTED FOR REVIEW AND APPROVAL PRIOR TO FABRICATION AND INSTALLATION.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
Ph. 801.576.6455 Fax. 801.576.6456 Web. WWW.JMWA.COM



6/8/2019

STRUCTURAL NOTES

KLINFELTER RESIDENCE

EDEN, UTAH

REVISIONS:

▲	AUG 20, 2019
▲	SEP 11, 2019

SCALE: AS NOTED

DATE: JAN. 1, 2000

DRAWN BY: SM

JOB NO. 2019.002

FILE: 2019.002

SHEET NO.

S0.1

STEEL NOTES:

- ALL WORK TO BE IN STRICT ACCORDANCE WITH THE 2015 IBC, LOCAL ORDINANCES, AWS STRUCTURAL WELDING CODE, AND THE FOLLOWING AISC PUBLICATIONS: "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS" WITH "COMMENTARY", "CODE OF STANDARD PRACTICE", SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS", AND "SEISMIC PROVISION FOR STRUCTURAL BUILDINGS".
- ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO FABRICATION AND ERECTION.
- SEE ARCHITECTURAL SHEETS FOR DIMENSIONS AND DECK BEARING ELEVATIONS.
- SEE ARCHITECTURAL FOR ACCESS HATCHES, DRAFT STOPS, ETC.
- SEE ARCHITECTURAL, MECHANICAL AND ELECTRICAL FOR ADDITIONAL STEEL MEMBERS (BRACKETS, ANGLES, ETC...) REQUIRED.
- SUBMIT SHOP DRAWINGS OF ALL STRUCTURAL STEEL, STEEL JOISTS, STEEL DECKING AND MISCELLANEOUS STEEL TO JMWA FOR APPROVAL PRIOR TO FABRICATION.
- ALL STEEL SHALL BE PROPERLY PRIMED EXCEPT AREAS THAT REQUIRE FIELD WELDING.
- PROVIDE A STANDARD AISC FRAMED CONNECTION FOR ONE HALF THE BEAM'S TOTAL UNIFORM LOAD CAPACITY WHERE A CONNECTION IS NOT SHOWN.
- ANY CONNECTION NOT DETAILED SHALL BE THE RESPONSIBILITY OF THE STEEL FABRICATOR. CONNECTIONS MUST BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER. CONNECTIONS MUST ACCOUNT FOR ALL LOADS & STRESSES INCLUDING BUT NOT LIMITED TO : GRAVITY, SEISMIC, WIND, THERMAL STRESSES, EXPANSION / CONTRACTION ETC...
- ALL EXPOSED STEEL SHALL HAVE WELDS GROUND SMOOTH

MATERIALS

- WIDE FLANGE SECTIONS: ASTM A992 (50 KSI).
- OTHER SHAPES AND PLATES: ASTM A36.
- TUBULAR COLUMNS: ASTM A500 GRADE B (46 KSI).
- PIPE COLUMNS: ASTM A501 (36 KSI) OR A53 GRADE B.
- DEFORMED BAR ANCHORS: ASTM A496
- HEADED STUD ANCHORS: ASTM A108
- ANCHOR BOLTS: ASTM A307 WITH ASTM A563 HEAVY HEX NUTS WITH HARDENED WASHERS GRADE A (U.N.O.)
- BOLTED CONNECTIONS: ASTM A325-N (3/4" DIAMETER MIN.)
- WELDS: E70 XX AT ALL JOISTS E60 XX AT ALL DECKS E70 XX AT ALL OTHER LOCATIONS

CONSTRUCTION

- ALL WELDS AND BOLTING TO MEET APPROVAL OF SPECIAL INSPECTOR AS REQUIRED BY BUILDING OFFICIAL.
- ALL WELDING AND CUTTING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS.
- ALL INTERSECTING STEEL SHAPES WHICH ARE NOT BOLTED SHALL BE CONNECTED BY A FILLET WELD ALL AROUND, UNLESS NOTED OTHERWISE.
- FOR THICKNESSES 1/4" AND LARGER, WELD SIZES SHALL BE 1/16" LESS THAN THE THINNEST CONNECTED PART, UNLESS NOTED OTHERWISE. FOR THICKNESSES LESS THAN 1/4", WELD SIZE SHALL BE THE SAME SIZE AS THE THINNEST CONNECTED PART, UNLESS NOTED OTHERWISE.
- DO NOT WELD REBAR OR ANCHOR BOLTS, INCLUDING "TACK" WELDS.
- WELD HEADED STUD ANCHORS AND DEFORMED BAR ANCHORS PER MANUFACTURER'S SPECIFICATIONS.
- TIGHTEN BOLTS BY THE TURN OF THE NUT, CALIBRATED WRENCH, OR DIRECT TENSION INDICATOR METHOD.
- USE HARDENED WASHERS BENEATH THE TURNED ELEMENT OF ALL BOLTS OR NUTS. ALSO USE HARDENED BEVELED WASHERS TO COMPENSATE FOR THE LACK OF PARALLELISM.

- PROVIDE HARDENED WASHERS BENEATH THE HEAD AND NUT WHERE A490 BOLTS ARE SPECIFIED PER AISC REQUIREMENTS.
- HARDENED WASHERS AND PLATES AT OVERSIZED HOLES SHALL CONFORM TO ASTM F-436 AND SHALL COMPLETELY COVER THE SLOT AFTER INSTALLATION.
- DO NOT REUSE BOLTS, NUTS OR WASHERS.
- PROVIDE FULL-DEPTH STIFFENER PLATES AT EACH SIDE OF ALL BEAMS AT ALL BEARING POINTS. STIFFENER PLATE THICKNESS EQUALS THE BEAM WEB THICKNESS (1/4" MIN.), FILLET WELD BOTH SIDES OF STIFFENER, ALL AROUND.
- STANDARD PENETRATIONS THROUGH STRUCTURAL MEMBERS FOR MECHANICAL, PLUMBING, ELECTRICAL SYSTEMS, ETC. SHALL BE PROVIDED ON THE CENTER LINE OF THE MEMBER'S DEPTH AND WITHIN THE MIDDLE ONE-THIRD OF THE SPAN. PENETRATIONS LARGER THAN STANDARD (OR GREATER THAN 1/3 THE BEAM DEPTH) ARE NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL FROM JMWA.

SPECIAL INSPECTION NOTES:

SPECIAL INSPECTION SHALL BE PROVIDED BY OWNER ACCORDING TO CHAPTER 17 OF THE IBC. THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS. THE SPECIAL INSPECTOR SHALL SEND REPORTS TO THE OWNER, BUILDING OFFICIAL, ARCHITECT, ENGINEER AND CONTRACTOR. ALL DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE CONTRACTOR FOR CORRECTION. THE SPECIAL INSPECTOR SHALL SUBMIT A FINAL SIGNED REPORT STATING THAT THE SPECIAL INSPECTION WORK WAS, TO THE BEST OF HIS/HER KNOWLEDGE, IN CONFORMANCE WITH THE PLANS, SPECIFICATIONS AND APPLICABLE WORKMANSHIP PROVISIONS OF THE IBC. SPECIAL INSPECTION IS REQUIRED FOR THE FOLLOWING WORK:

- ALL FIELD WELDING
- BOLTED CONNECTIONS
- ENGINEERED FILL (PER SOILS ENGINEER)
- REINFORCED CONCRETE (POURED IN PLACE, ABOVE GRADE)

POST INSTALLED ANCHOR OR DOWEL:

CONCRETE

- EPOXY ANCHORS AND DOWELS
 - USE HILTI HIT-RE 500-SD (ESR-2322) OR SIMPSON SET-XP (ESR-2508) FOR ALL EPOXIED IN ANCHORS AND DOWELS. NO SUBSTITUTIONS PERMITTED WITHOUT APPROVAL FROM THE ENGINEER OF RECORD.
 - INSTALL EPOXY/ADHESIVE AND ANCHORS OR DOWELS PER MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS.
 - ALL DRILLED HOLES SHALL BE 1/8" LARGER THAN THE BAR OR ANCHOR BOLT BEING INSTALLED.
 - CLEAN THE WALL AND HOLE WITH A NYLON BRUSH AND FREE COMPRESSED AIR. THE HOLE MUST BE FREE OF DUST, DEBRIS AND STANDING WATER.
 - REFER TO STANDARD DETAIL FOR ADDITIONAL REQUIREMENTS.
- EXPANSION ANCHORS
 - USE HILTI HDA UNDERCUT ANCHOR (ESR-1546) OR HILTI HSL-3 EXPANSION ANCHOR (ESR-1545) OR HILTI KB-TZ EXPANSION ANCHOR (ESR-1917) OR SIMPSON STRONG BOLT (ESR-1771) OR REDHEAD TRUBOLT+ EXPANSION ANCHOR (ESR-2427) FOR ALL EXPANSION ANCHORS. NO SUBSTITUTIONS PERMITTED WITHOUT APPROVAL FROM THE ENGINEER OF RECORD.
 - INSTALL EXPANSION ANCHORS PER MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS.
 - ALL DRILLED HOLES SHALL BE THE SAME DIAMETER AS THE NOMINAL DIAMETER OF THE EXPANSION BOLT BEING INSTALLED.
 - CLEAN THE HOLE WITH COMPRESSED AIR.
 - REFER TO STANDARD DETAIL FOR ADDITIONAL REQUIREMENTS.

MASONRY


- EPOXY ANCHORS AND DOWELS
 - USE HILTI HIT-HY 150 (ESR-5193) OR SIMPSON SET (ESR-1772) FOR ALL EPOXIED IN ANCHORS AND DOWELS IN SOLID GROUTED CELLS. NO SUBSTITUTIONS PERMITTED WITHOUT APPROVAL FROM THE ENGINEER OF RECORD.
 - USE HILTI HIT-HY 20 (ESR-4815) OR SIMPSON SET (ESR-1772) WITH SCREEN TUBE FOR ALL EPOXIED IN ANCHORS AND DOWELS IN HOLLOW CELLS. NO SUBSTITUTIONS PERMITTED WITHOUT APPROVAL FROM THE ENGINEER OF RECORD.
 - INSTALL EPOXY/ADHESIVE AND ANCHORS OR DOWELS PER MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS.
 - ALL DRILLED HOLES SHALL BE 1/8" LARGER THAN THE BAR OR ANCHOR BOLT BEING INSTALLED.
 - CLEAN THE WALL AND HOLE WITH A NYLON BRUSH AND FREE COMPRESSED AIR. THE HOLE MUST BE FREE OF DUST, DEBRIS AND STANDING WATER.
 - REFER TO STANDARD DETAIL FOR ADDITIONAL REQUIREMENTS.

LEGEND OF ABBREVIATIONS:


AB	ANCHOR BOLT(S)	JT	JOINT
ABV	ABOVE	JST	JOIST
APPROX	APPROXIMATE		
ARCH	ARCHITECTURAL	K	KIPS
		KLF	KIP PER FOOT
		KSF	KIP PER SQUARE FOOT
BLDG	BUILDING	LBS	POUNDS
BLK	BLOCKING	LF	LINEAL FOOT
BLW	BELOW		
BM-X	BEAM	MAX	MAXIMUM
B.N.	BOUNDARY NAILING	MECH	MECHANICAL
BOT	BOTTOM	MFR	MANUFACTURER
BRG	BEARING	MIN	MINIMUM
BTWN	BETWEEN	MISC	MISCELLANEOUS
		ML	METAL
C.J.	CONST/CONTROL JOINT	NTS	NOT TO SCALE
CLR	CLEAR	O.C.	ON CENTER
COL	COLUMN	O.F.	OUTSIDE FACE
CONC	CONCRETE	OPP	OPPOSITE
CONT	CONTINUOUS		
CTR	CENTER	PCF	POUNDS PER CUBIC FT
CW-X	CONCRETE WALL	PERP	PERPENDICULAR
		PLF	POUNDS PER LINEAL FT
DBL	DOUBLE	PSF	POUNDS PER SQ FOOT
DIA	DIAMETER	PSI	POUNDS PER SQ INCH
DIM	DIMENSION		
DN	DOWN	EA	EACH
DWG	DRAWING	E.F.	EACH FACE
		E.J.	EXPANSION JOINT
EA	EACH	ELEC	ELECTRICAL
E.F.	EACH FACE	ELEV	ELEVATION
E.J.	EXPANSION JOINT	EQ	EQUAL
ELEC	ELECTRICAL	E.W.	EACH WAY
ELEV	ELEVATION	EXST	EXISTING
EQ	EQUAL	EXP	EXPANSION
SCP-X	STEEL CAP PLATE	EXT	EXTERIOR
SI	SPECIAL INSPECTION		
SI	SPECIAL INSPECTION	FC-X	CONTINUOUS FOOTING
SIM	SIMILAR	FDN	FOUNDATION
SOG	SLAB ON GRADE	FIN	FINISH(ED)
SQ	SQUARE	FLR	FLOOR
SW-X	SHEAR WALL	FR-X	RECTANGULAR FOOTING
		FS-X	SQUARE FOOTING
		FT	FEET
		FIG	FOOTING
		HORIZ	HORIZONTAL
		HT	HEIGHT
		UNO	UNLESS NOTED OTHERWISE
		VERT	VERTICAL
		INT	INTERIOR
		IF.	INTERIOR FACE
		IN.	INCHES
		INT	INTERIOR
		w/	WITH
		WF	WIDE FLANGE
		WWF	WELDED WIRE FABRIC
		WWM	WELDED WIRE MESH

SYMBOLS LEGEND

SECTION		DRAWING-DETAIL NUMBER SHEET NUMBER
DETAIL		DRAWING-DETAIL NUMBER SHEET NUMBER
ELEVATION		LOCATION ELEVATION
ELEVATION		DRAWING-DETAIL NUMBER SHEET NUMBER



JM WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
 Ph. 801.576.6455 Fax. 801.576.6456 Web. WWW.JMWA.COM



STRUCTURAL NOTES
KLINFELTER RESIDENCE
 EDEN, UTAH

REVISIONS:


	AUG 20, 2019
	SEP 11, 2019

SCALE:	AS NOTED
DATE:	JAN. 1, 2000
DRAWN BY:	SM
JOB NO.	2019.002
FILE:	2019.002

SHEET NO.
S0.2

THIS DRAWING IS THE PROPERTY OF J.M. WILLIAMS AND ASSOCIATES. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED OR IN ANY MANNER WITHOUT WRITTEN CONSENT OF J.M. WILLIAMS AND ASSOCIATES.

NOTE: FOR LARGER PENETRATIONS - SEE PROJECT ENGINEER - TYP.




NOTE: ALL PENETRATIONS IN BEAMS TO BE AT MID-HEIGHT OF BEAMS AND AT QUARTER POINTS OF SPANS. SEE DETAIL 5/S0.3


#4 DIAGONAL BARS EACH SIDE AS SHOWN

(2) #4 x 3/6\"/>

10 WALL PENETRATION DETAIL-TYP. SCALE: N.T.S.



BAR SIZE	FINISHED BEND DIAMETER D, IN.	180-DEG HOOKS		90-DEG HOOKS
		A OR G	J	A OR G
#3	2 1/4	5"	3"	6"
#4	3	6"	4"	8"
#5	3 3/4	7"	5"	10"
#6	4 1/2	8"	6"	11-0"
#7	5 1/4	10"	7"	11-2"
#8	6	11"	8"	11-4"
#9	9 1/2	11-3"	11 3/4"	11-7"
#10	10 3/4	11-5"	11-1 1/4"	11-10"
#11	12	11-7"	11-2 3/4"	11-12"
#14	18 1/4	23"	11-9 3/4"	21-7"
#18	24	31-0"	21-4 1/2"	31-5"




BAR SIZE	D, IN.	STIRRUP AND TIE HOOKS, ALL GRADES				
		GENERAL USE		SEISMIC USE		
		90-DEG HOOK	135-DEG HOOK	135-DEG HOOK	135-DEG HOOK	
		A OR G	A OR G	H, APPROX.	A OR G	H, APPROX.
#3	1 1/2	4"	4"	2 1/2"	5"	3 1/2"
#4	2	4 1/2"	4 1/2"	3"	6 1/2"	4 1/2"
#5	2 1/2	6"	5 1/2"	3 3/4"	8"	5 1/2"
#6	4 1/2	11-0"	8"	4 1/2"	11"	6 1/2"
#7	5 1/4	11-2"	9"	5 1/4"	11-0 1/2"	7 3/4"
#8	6	11-4"	10 1/2"	6"	11-2 1/2"	9"

12 STD. HOOKS / STIRRUPS - TYP. BENDS SCALE: N.T.S.


REINFORCING LAP SPICE SCHEDULE																
BAR SIZE	f _c = 3000 PSI				f _c = 4000 PSI				f _c = 5000 PSI				f _c = 6000 PSI			
	REGULAR		TOP		REGULAR		TOP		REGULAR		TOP		REGULAR		TOP	
	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS	CLASS
#3	13"	17"	17"	21"	12"	16"	16"	21"	12"	16"	16"	21"	12"	16"	16"	21"
#4	17"	22"	22"	28"	15"	19"	19"	25"	13"	17"	17"	22"	12"	16"	16"	21"
#5	21"	27"	27"	35"	18"	24"	24"	31"	16"	21"	21"	27"	15"	19"	19"	25"
#6	27"	36"	36"	46"	24"	31"	31"	40"	21"	28"	28"	36"	20"	25"	25"	33"
#7	37"	48"	48"	63"	32"	42"	42"	54"	29"	38"	38"	49"	27"	34"	34"	44"
#8	49"	64"	64"	82"	42"	55"	55"	71"	38"	49"	49"	64"	35"	45"	45"	58"
#9	62"	80"	80"	104"	54"	70"	70"	90"	48"	62"	62"	81"	44"	57"	57"	74"
#10	78"	102"	102"	132"	68"	88"	88"	115"	61"	79"	79"	102"	56"	72"	72"	94"
#11	96"	125"	125"	162"	83"	108"	108"	141"	76"	97"	97"	126"	68"	88"	88"	115"

NOTE:


- THESE NOTES SHALL BE USED FOR ALL SPLICES, UNLESS NOTED OTHERWISE.
- CLASS 'A' SPLICES MAY BE USED ONLY IN CASES WHERE 50% OR LESS OF THE BARS ARE SPLICED WITHIN THE LAP SPICE LENGTH.
- CLASS 'B' SPLICES SHALL BE USED FOR ALL SPLICES UNLESS THE REQUIREMENTS OF NOTE #2 ABOVE ARE MET.
- TIES AND STIRRUPS SHALL NOT BE SPLICED.
- a. FOR BUNDLED BARS OF THREE OR LESS, LAP SPICE LENGTHS SHALL BE MULTIPLIED BY 1.2.
b. FOR BUNDLED BARS OF FOUR OR MORE, LAP SPICE LENGTHS SHALL BE MULTIPLIED BY 1.33.
c. INDIVIDUAL BAR SPLICES WITHIN A BUNDLE SHALL NOT OVERLAP.
d. ENTIRE BUNDLES SHALL NOT BE LAP SPLICED.
- FOR ALL LIGHTWEIGHT CONCRETE, LAP LENGTHS SHALL BE MULTIPLIED BY 1.3.
- FOR ALL EPOXY COATED BARS, LAP LENGTHS SHALL BE MULTIPLIED BY 1.3 FOR TOP BARS AND 1.5 FOR REGULAR BARS.
- TOP BARS ARE CLASSIFIED AS HORIZONTAL BARS WHERE 12" OR MORE OF FRESH CONCRETE IS CAST BELOW THE REINFORCING BAR.




8 REINFORCING LAP SPICE SCHEDULE & BAR BENDING DIAGRAMS SCALE: N.T.S.




9 PIPE THROUGH FOOTING AND TRENCH SCALE: N.T.S.




4 TYP. FOOTING STEP DETAIL @ CONCRETE FOUNDATION WALL SCALE: N.T.S.




5 MAX SLOPE BETWEEN ADJACENT FOOTINGS SCALE: N.T.S.




3 TYP. CORNER WALL REINF. DETAIL SCALE: N.T.S.




1 TYPICAL KEY IN CONCRETE SCALE: N.T.S.




2 SLEEVE FOR PIPE AT SLAB SCALE: N.T.S.



3 TYP. CORNER WALL REINF. DETAIL SCALE: N.T.S.



JM WILLIAMS and Associates
2815 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



STRUCTURAL DETAILS
KLINFELTER RESIDENCE
EDEN, UTAH


REVISIONS:

▲	AUG 20, 2019
▲	SEP 11, 2019


SCALE: AS NOTED
DATE: JAN. 1, 2000
DRAWN BY: SM
JOB NO. 2019.002
FILE: 2019.002

SHEET NO.
S0.3


THIS PLAN, SPECIFICATION, AND CONTRACT SHALL BE CONSIDERED COMPLETE AND CORRECT. NO OTHER CONDITIONS SHALL APPLY UNLESS SPECIFICALLY NOTED OTHERWISE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.




7 TYPICAL TRUSS BLOCKING
S0.4 SCALE: N.T.S.




8 TJI BLOCKING DETAIL
S0.4 SCALE: N.T.S.



9 SOLID BLOCKING DETAIL
S0.4 SCALE: N.T.S.




6 TYPICAL SHEARWALL w/ STRAPS DETAIL
S0.4 SCALE: N.T.S.




NOTE: STUDS SHALL BE BUILT-UP AS REQ'D FOR SOLID BEARING w/ KING STUD EA SIDE TYP U.N.O.

1 TYPICAL BUILT-UP POST
S0.4 SCALE: N.T.S.




2 TYPICAL TOP PLATE SPLICE
S0.4 SCALE: N.T.S.




NOTE: TRUSS MFR. SHALL PROVIDE VERTICAL WEB TO MATCH LOCATION OF SHEAR PANEL

NOTE: FOR CONSTRUCTION BELOW PANEL, SEE PLAN

3 TYPICAL SHEAR PANEL
S0.4 SCALE: N.T.S.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



6/8/2019

STRUCTURAL DETAILS
KLINEFELTER RESIDENCE
EDEN, UTAH

REVISIONS:	
1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED

DATE: JAN. 1, 2000

DRAWN BY: SM

JOB NO. 2019.002

FILE: 2019.002

SHEET NO.


S0.4

NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM J.M. WILLIAMS AND ASSOCIATES.

NOTE: SEE PLAN FOR COLUMN SIZES

STEEL COLUMN NOTES:

- UNLESS NOTED OTHERWISE, ALL COLUMNS SHALL BE INSTALLED WITH (4) 3/4" DIA. ANCHOR BOLTS WITH 3" MINIMUM HOOKS. PROJECT ANCHOR BOLTS 3" MINIMUM ABOVE THE TOP OF THE BASE PLATE. EMBEDMENT SHALL BE 9" MINIMUM. ALL BOLTS SHALL BE INSTALLED WITH HARDENED WASHERS BENEATH THE NUT. ANY BOLT HOLES LARGER THAN THE BOLT DIAMETER PLUS 5/16" SHALL HAVE 5/16" PLATE WASHERS INSTALLED BENEATH THE HARDENED WASHERS.
- ALL CAP PLATE BOLTS SHALL BE 3/4" DIA. A325N BOLTS, TYPICAL UNLESS NOTED OTHERWISE.
- ANCHOR BOLTS SHALL NOT BE WELDED (INCLUDING TACK WELDS).
- SEE GENERAL STRUCTURAL NOTES FOR ALL OTHER REQUIREMENTS.




8 STEEL COLUMN CONNECTION SCHEDULE - TYP.
 30.5 SCALE: N.T.S.

A-325 BOLT SCHEDULE

MAXIMUM BEAM SIZE IN EACH BEAM DEPTH GROUP	A-325N BOLTS	
	No. PER BEAM	SIZE
W8	2	3/4" DIA.
W10	2	3/4" DIA.
W12	3	3/4" DIA.
W14	3	3/4" DIA.
W16	4	3/4" DIA.
W18	4	3/4" DIA.
W21	5	3/4" DIA.
W24	5	3/4" DIA.
W27	6	3/4" DIA.
W30	7	3/4" DIA.

- CLIP ANGLES: (2) L 4x3 1/2. THICKNESS SHALL BE EQUAL TO ONE HALF THE BEAM WEB THICKNESS PLUS 1/16" (1/4" MIN.). FOR TWO ROWS OF BOLTS OR SKEWED CONNECTIONS, USE BENT PLATES. WHERE COLUMN WIDTH IS SMALLER THAN THE CONNECTING CLIP ANGLES, ANGLE LEGS MAY BE REDUCED TO MATCH WIDTH OF COLUMN. USE L 4x4 ANGLES AT BEAM TO CONCRETE WALL OR COLUMN CONNECTIONS.
- FILLET WELDS SHALL BE ANGLE THICKNESS MINUS 1/16" (1/4" MIN.).
- CONTRACTOR HAS OPTION TO BOLT CLIP ANGLES IN EITHER BEAM WEB IN BEAM TO BEAM CONNECTIONS AND IN COLUMN WEB AND FLANGE.
- BOLT EDGE DISTANCE SHALL BE 1 1/2" MIN. AT ALL BEAM AND CLIP ANGLE EDGES. BOLT SPACING SHALL BE 3" O.C. MIN.




5 TYP. BOLTED CLIP ANGLE CONNECTIONS W/ BOLT SCHEDULE (DOUBLE SHEAR)
 30.5 SCALE: N.T.S.


A-325 BOLT SCHEDULE

MAXIMUM BEAM SIZE IN EACH BEAM DEPTH GROUP	A-325N BOLTS	
	No. PER BEAM	SIZE
W8	2	3/4" DIA.
W10	2	3/4" DIA.
W12	3	3/4" DIA.
W14	3	3/4" DIA.
W16	4	3/4" DIA.
W18	5	3/4" DIA.
W21	6	3/4" DIA.
W24	7	3/4" DIA.
W27	8	3/4" DIA.
W30	9	3/4" DIA.

- BEAM WEB CONNECTION PLATES. THICKNESS EQUALS THE BEAM WEB THICKNESS PLUS 1/8" (3/8" MIN.)
- FILLET WELDS SHALL BE AS FOLLOWS:
 ONE SIDE: PLATE THICKNESS MINUS 1/16" (1/4" MIN.)
 TWO SIDES: 1/2 PLATE THICKNESS PLUS 1/16" (1/4" MIN.) EACH SIDE
- THICKNESS EQUALS BEAM FLANGE THICKNESS OF BEAM FRAMING INTO COLUMN WEB (3/8" MIN.)
- BOLT EDGE DISTANCE SHALL BE 1 1/2" MIN. AT ALL EDGES. BOLT SPACING SHALL BE 3" MIN.



2 TYP. BOLTED WEB PLATE CONNECTIONS W/ BOLT SCHEDULE (SINGLE SHEAR)
 30.5 SCALE: N.T.S.



J.M. WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
 Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



6/8/2019

STRUCTURAL DETAILS
 KLINEFELTER RESIDENCE
 EDEN, UTAH


REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
 DATE: JAN. 1, 2000
 DRAWN BY: SM
 JOB NO. 2019.002
 FILE: 2019.002

SHEET NO.
 S0.5

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN ARE THE PROPERTY OF J.M. WILLIAMS AND ASSOCIATES, INC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM J.M. WILLIAMS AND ASSOCIATES, INC.



J.M. WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
 Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



FOOTING AND FOUNDATION PLAN
KLINFELTER RESIDENCE
 EDEN, UTAH

REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
 DATE: JAN. 1, 2000
 DRAWN BY: SM
 JOB NO. 2019.002
 FILE: 2019.002

SHEET NO.
S1.1

IMPORTANT HOLDOWN NOTES:

- SEE SHEETS S3.1 AND 3.2 FOR LOCATIONS OF HOLDOWNS.
- ALL HOLDOWN ANCHORS TO BE CAST IN CONCRETE.
- SEE SHEETS S3.1 AND S3.2 FOR ANCHOR BOLT REQUIREMENTS AT SHEARWALLS AND DETAILS ON SHEETS S4.1 AND S4.2.
- THE BACKGROUND LAYERS THAT CONTAINED WALL HEIGHTS ETC. TURNED OFF FOR CLARITY.
- REMOVED ARCHITECTURAL SECTION AND ELEVATION CALLOUTS FOR CLARITY.

CONCRETE WALL SCHEDULE

MARK	THICKNESS	REINFORCING			WALL TYPE	NOTES
		VERTICAL	HORIZONTAL	TOP AND BTM.		
CW-1	8"	#5 @ 12" O.C.	#4 @ 12" O.C.	(2) #4	"A"	BRACE @ FLOOR LEVELS
CW-2	8"	#4 @ 12" O.C.	#4 @ 12" O.C.	(2) #4	"A"	

WALL REINFORCEMENT PLACEMENT TYPES:


FOOTING SCHEDULE

MARK	WIDTH	LENGTH	DEPTH	REINFORCING CROSSWISE		REINFORCING LENGTHWISE		NOTES		
				NO	SIZE	NO	SIZE			
FC1.5	1'-6"	CONT	12"			2	#4	CONT	EQUAL	
FC2.0	2'-0"	CONT	12"			3	#4	CONT	EQUAL	
FS2.0	2'-0"	2'-0"	12"	4	#5	2'-6"	EQUAL	4	#5	1'-6"
FS3.0	3'-0"	3'-0"	12"	4	#5	2'-6"	EQUAL	4	#5	2'-6"
FS4.0	4'-0"	4'-0"	12"	4	#5	3'-6"	EQUAL	4	#5	3'-6"
FS5.0	5'-0"	5'-0"	12"	6	#5	4'-6"	EQUAL	6	#5	4'-6"
FS5.5	5'-6"	5'-6"	12"	6	#5	5'-0"	EQUAL	6	#5	5'-0"


- ALLOWABLE SOIL BEARING PRESSURE = 2500 PSF (ASSUMED CODE MINIMUM - CONTRACTOR TO VERIFY)
- MINIMUM COMPRESSIVE CONCRETE STRENGTH $f_c = 4000$ PSI
- ALL REINFORCING STEEL SHALL BE GRADE 60 AND BE PROPERLY TIED INTO PLACE PRIOR TO POUR
- ALL CONCRETE WORK MUST MEET THE REQUIREMENTS OF THE 2015 IBC, ACI 318 AND LOCAL ORDINANCES
- ALL BARS MUST BE 3" CLEAR FROM GRADE

NOTE:


- FOUNDATION AND FOOTING STEP LOCATIONS SHALL BE DETERMINED ON SITE BY THE CONTRACTOR. IF WALL STEPS MOVE FROM WHERE THEY ARE SHOWN, ENGINEER SHALL BE CONTACTED TO VERIFY SHEARWALL DESIGN.




1 FOOTING AND FOUNDATION PLAN
 SCALE (24x36): 1/4"=1'-0"




10 THICKENED SLAB
S1.2 SCALE: N.T.S.




7 WOOD STRINGER AT SLAB
S1.2 SCALE: N.T.S.




4 FOUNDATION WALL AT BASEMENT
S1.2 SCALE: N.T.S.




1 CONTROL JOINT AT SLAB ON GRADE
S1.2 SCALE: N.T.S.




11 INTERIOR STEEL COLUMN FOOTING
S1.2 SCALE: N.T.S.




8 WOOD STUD WALL FOUNDATION
S1.2 SCALE: N.T.S.




5 INTERIOR SLAB FOOTING
S1.2 SCALE: N.T.S.




2 FOUNDATION DETAIL AT OPENING
S1.2 SCALE: N.T.S.




12 FOUNDATION DETAIL
S1.2 SCALE: N.T.S.



9 STAIR ON GRADE
S1.2 SCALE: N.T.S.



6 FOUNDATION DETAIL
S1.2 SCALE: N.T.S.



3 INTERIOR CONCRETE WALL FOOTING
S1.2 SCALE: N.T.S.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
Ph: 801.575.6453 Fax: 801.575.6456 Web: WWW.JMW.COM



6/8/2019

FOUNDATION DETAILS
KLINFELTER RESIDENCE
EDEN, UTAH



REVISIONS:	
1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
DATE: JAN. 1, 2000
DRAWN BY: SM
JOB NO. 2019.002
FILE: 2019.002

SHEET NO.
S1.2

SEE PLAN, FRAMING, FINISHING AND THE EXISTING PROPERTY FOR ALL DETAILS AND CONDITIONS. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND CONDITIONS BEFORE CONSTRUCTION.

NOTES:
 SEE ARCHITECTURAL FLOOR PLANS AND ELEVATIONS FOR FINISHED FLOOR ELEVATIONS - STEP OVERBUILD FRAMING AS NEEDED - TYPICAL.
 SEE ARCHITECTURAL PLANS FOR FOR FLOOR TYPES AND WALL TYPES.
 SEE S0.1 AND S0.2 FOR ADDITIONAL NOTES AND REQUIREMENTS
 SEE SHEETS S3.1 AND S3.2 FOR SHEARWALL LOCATIONS AND REQUIREMENTS



NOTES:
SEE ARCHITECTURAL FLOOR PLANS AND ELEVATIONS FOR FINISHED FLOOR ELEVATIONS - STEP OVERBUILD FRAMING AS NEEDED - TYPICAL.

SEE ARCHITECTURAL PLANS FOR FLOOR TYPES AND WALL TYPES.

SEE S0.1 AND S0.2 FOR ADDITIONAL NOTES AND REQUIREMENTS

SEE SHEETS S3.1 AND S3.2 FOR SHEARWALL LOCATIONS AND REQUIREMENTS

NOTE:
FRAME BEAM INTO SIDE OF COLUMN WITH SINGLE PLATE SHEAR TAB 3-1/2"x8"x3/8" w/ 5/16" FILLET WELDS EACH SIDE


NOTE:
CONTINUOUS BEAM WITH CANTILEVERED END

NOTE:
HANG FROM BEAM

LEGEND

- POLISHED CONCRETE SLAB OVER FLOOR JOISTS - COORDINATE FINISH AND THICKNESS W/ ARCHITECTURAL
- BEARING WALL (INTERIOR)
- BEAM
- JOIST
- OPEN TO BELOW
- JOIST BRIDGING @ 8'-0" O.C. TYP


REMOVED ARCHITECTURAL SECTION AND ELEVATION CALLOUTS FOR CLARITY



1 SECOND FLOOR/LOW ROOF FRAMING PLAN
S2.2 SCALE () 24x36 1/4"=1'-0"
SCALE () 11x17 1/8"=1'-0"

FLOOR NOTES:
VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS. SCHEDULED MARK DESIGNATION ARE TYPICAL TO THE PROJECT AND MAY NOT NECESSARILY BE FOUND ON THIS PLAN.
FOR CLARITY, ALL FLOOR OPENINGS MAY NOT BE SHOWN ON PLANS. FOR EXACT SIZE, NUMBER AND LOCATION OF OPENINGS, SEE ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS.
IDENOTES AN AXIAL FORCE DUE TO WIND/SEISMIC THAT THE TRUSS MANUFACTURER SHALL DESIGN THE TRUSS FOR. TRUSS MFR TO DESIGN TRUSSES FOR ADDITION LOADS ON PLANS AND IN DETAILS.
FOR CLARITY, DETAILS MAY SHOW ONLY ONE SIDE OF FRAMING CONDITION.
PROVIDE JOIST BLOCKING PER DETAIL 5/S4.1 FOR ALL JOISTS AT EXTERIOR WALLS

NOTE:
MINIMUM MEMBER SIZES ARE SHOWN AND MAY BE INCREASED TO FACILITATE CONNECTION ETC. - TYP.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
Ph. 801.575.6456 Fax. 801.575.6456 Web. WWW.JMWA.COM



6/8/2019

UPPER FLOOR FRAMING PLAN
KLINFELTER RESIDENCE
EDEN, UTAH

REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE:	AS NOTED
DATE:	JAN. 1, 2000
DRAWN BY:	SM
JOB NO.	2019.002
FILE:	2019.002

SHEET NO.
S2.2

NOT TO SCALE UNLESS SPECIFICALLY NOTED. ALL DIMENSIONS ARE TO FACE UNLESS SPECIFICALLY NOTED. THE USER ASSUMES ALL RISKS AND LIABILITIES FOR ANY AND ALL DAMAGES, INCLUDING BUT NOT LIMITED TO, PERSONAL INJURY, PROPERTY DAMAGE, AND ECONOMIC LOSS, ARISING FROM THE USE OF THIS DOCUMENT.

NOTES:

SEE ARCHITECTURAL FLOOR PLANS AND ELEVATIONS FOR FINISHED FLOOR ELEVATIONS - STEP OVERBUILD FRAMING AS NEEDED - TYPICAL.

SEE ARCHITECTURAL PLANS FOR FLOOR TYPES AND WALL TYPES.


SEE S0.1 AND S0.2 FOR ADDITIONAL NOTES AND REQUIREMENTS.

SEE SHEETS S3.1 AND S3.2 FOR SHEARWALL LOCATIONS AND REQUIREMENTS.

OPTION:
FOR REDUNDANCY W12x72 RIDGE BEAM MAY BE CONTINUOUS 53'-0" +/- AND ACT AS RIDGE FOR TRUSS AREA OVER GREAT ROOM - HANG TOP CHORDS FROM RIDGE BEAM.

NOTE:
SKYLIGHTS TO BE DESIGNED FOR UNBALANCED SNOW LOAD - TYP.

REMOVED ARCHITECTURAL SECTION AND ELEVATION CALLOUTS FOR CLARITY



1 UPPER ROOF FRAMING PLAN
 SCALE | 1/24=3/8 1/4"=1'-0"
 SCALE | 1/16=1/8 1/8"=1'-0"

ROOF NOTES:

VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS. SCHEDULED MARK DESIGNATION ARE TYPICAL TO THE PROJECT AND MAY NOT NECESSARILY BE FOUND ON THIS PLAN.


FOR CLARITY, ALL FLOOR AND ROOF OPENINGS MAY NOT BE SHOWN ON PLANS. FOR EXACT SIZE, NUMBER AND LOCATION OF OPENINGS, SEE ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS.

FOR CLARITY, DETAILS MAY SHOW ONLY ONE SIDE OF FRAMING CONDITION.

PROVIDE SOLID BLOCKING PER STANDARD DETAILS.

NOTE:

ALL ROOF JOISTS ARE:
 14" TJI 210 @ 12" O.C. OR EQUAL
 OR
 1-3/4" x 9-1/2" LVL @ 16" O.C.



J.M. WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
 Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



6/8/2019

ROOF FRAMING PLAN
KLINFELTER RESIDENCE
 EDEN, UTAH


REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
 DATE: JAN. 1, 2000
 DRAWN BY: SM
 JOB NO. 2019.002
 FILE: 2019.002

SHEET NO.
S2.3

THIS DRAWING IS THE PROPERTY OF J.M. WILLIAMS AND ASSOCIATES. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF J.M. WILLIAMS AND ASSOCIATES.



REMOVED ARCHITECTURAL SECTION AND ELEVATION CALLOUTS FOR CLARITY


NOTE:
 AT STEEL COLUMNS, BOLT (2) NAILERS/STUDS W/ 1/2" DIA. AB @ 24" O.C. - NAIL SHEATHING TO NAILERS - TYPICAL

MARK	SHEATHING	NAIL SIZE	EDGE NAIL	FIELD NAIL	SILL BOLTING TO CONCRETE	NOTES
SW-1	7/16" APA	8d	6" O.C.	12" O.C.	5/8" Ø x 12" @ 32" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.
SW-2	7/16" APA	8d	4" O.C.	12" O.C.	5/8" Ø x 12" @ 32" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.
SW-3	7/16" APA	8d	3" O.C.	12" O.C.	5/8" Ø x 10" LONG @ 12" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.


- MIN. NAIL PENETRATION INTO FRAMING, 8d-1 1/2", 10d-1 5/8".
- ALL NAILS TO BE COMMON NAILS
- (2) 2x MEMBERS SHALL NOT BE USED TO REPLACE 3x MEMBER. 3x MEMBERS MAY BE REPLACED W/ 4x MEMBERS.
- PLYWOOD, ORIENTED STAND BOARD AND COMPOSITE BOARD (BUT NOT STRUCTURAL PARTICLE BOARD) ARE ACCEPTED AS EQUAL.
- ALL ANCHOR BOLTS TO HAVE A 3"x3"x1/4" PLATE WASHER.
- SHEAR WALL PANELS INDICATED ON SCHEDULE ARE TO BE SHEATHED FOR FULL HEIGHT OF WALL.
- ALL FRAMING SHALL BE SPACED @ 16" O.C.
- SEE HOLDOWN SCHEDULE AND PLAN FOR LOCATION AND SIZE OF HOLDOWNS REQUIRED.
- ALL PANEL EDGE MEMBERS TO BE 2x MEMBERS U.N.O.
- FASTENERS USED BELOW GRADE IN PONY WALLS, CRIPPLE WALLS OR KNEE WALLS AND FASTENERS USED TO ATTACH SHEATHING TO THE EXTERIOR BASEMENT OR CRAWLSPACE WALL STUDS SHALL BE TYPE 304 OR 316 STAINLESS STEEL.
- FASTENERS USED ABOVE GRADE TO ATTACH SHEATHING TO PRESSURE TREATED SILL PLATES SHALL BE OF TYPE 304 OR 316 STAINLESS STEEL, SILICON BRONZE, COPPER, HOT DIPPED GALVANIZED (ZINC COATED) STEEL NAILS OR HOT-TUMBLER GALVANIZED (ZINC COATED) STEEL NAILS, ELECTRO-GALVANIZED STEEL NAILS AND GALVANIZED (ZINC COATED) STEEL STAPLES SHALL NOT BE PERMITTED.

HOLDOWN	EDGE MEMBER	FOUNDATION ANCHOR	EDGE MEMBER ATTACHMENT	NOTES
HDU2	(2) STUDS	5/8" DIA. A.B.	(6) 1/4x2-1/2 SDS	
MST37	(2) STUDS	N/A	(24) 16d SINKERS	
HDU4	(2) STUDS	5/8" DIA. AB	(10) 1/4x2-1/2 SDS	
HDU5	(2) STUDS	5/8" DIA. AB	(14) 1/4x2-1/2 SDS	
HDU8	(2) STUDS	7/8" DIA. AB	(20) 1/4x2-1/2 SDS	

- ALL ANCHORS ARE SIMPSON STRONG-TIE OR EQUAL.
- INSTALLATION OF HOLDOWN ANCHORS AND STRAPS SHALL BE PER MFRS RECOMMENDATIONS & SPECIFICATIONS.
- WHEN 4x MEMBER IS REQUIRED FOR PANEL EDGES IN SHEAR WALL SCHEDULE USE 6x FOR HOLDOWN MEMBER. SSB ANCHOR BOLTS MAY BE SUBSTITUTED FOR THE SCHEDULED ANCHOR BOLTS.
- INCREASE FOOTING DEPTH WHERE EMBEDMENT LENGTH PLUS 3" IS GREATER THAN FOOTING DEPTH SPECIFIED.
- PROVIDE EDGE NAILING ALONG STUDS CONNECTED TO HOLDOWN ANCHORS AND STRAPS.



J.M. WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
 Ph. 801.575.6453 Fax. 801.575.6456 Web. WWW.JMWA.COM



MAIN LEVEL SHEARWALL PLAN
KLINFELTER RESIDENCE
 EDEN, UTAH


REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
 DATE: JAN. 1, 2000
 DRAWN BY: SM
 JOB NO. 2019.002
 FILE: 2019.002

SHEET NO.
S3.1

ALL DIMENSIONS UNLESS OTHERWISE NOTED TO BE IN FEET AND INCHES. DIMENSIONS SHALL BE TO FACE UNLESS OTHERWISE NOTED. ALL DIMENSIONS SHALL BE TO FACE UNLESS OTHERWISE NOTED. ALL DIMENSIONS SHALL BE TO FACE UNLESS OTHERWISE NOTED.




SHEARWALL SCHEDULE						
MARK	SHEATHING	NAIL SIZE	EDGE NAIL	FIELD NAIL	SILL BOLTING TO CONCRETE	NOTES
SW-1	7/16" APA	8d	6" O.C.	12" O.C.	5/8" Ø x 12" @ 32" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.
SW-2	7/16" APA	8d	4" O.C.	12" O.C.	5/8" Ø x 12" @ 32" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.
SW-3	7/16" APA	8d	3" O.C.	12" O.C.	5/8" Ø x 12" LONG @ 12" O.C.	USE 18" LONG ANCHOR BOLTS WHERE FOUNDATION WALL STEPS TO A 4" WIDE STEM WALL - SEE DETAILS ON S4.1 AND S4.2 - TYP.

- MIN. NAIL PENETRATION INTO FRAMING, 8d-1 1/2", 10d-1 5/8".
- ALL NAILS TO BE COMMON NAILS
- (2) 2x MEMBERS SHALL NOT BE USED TO REPLACE 3x MEMBER. 3x MEMBERS MAY BE REPLACED W/ 4x MEMBERS.
- PLYWOOD, ORIENTED STRAND BOARD AND COMPOSITE BOARD (BUT NOT STRUCTURAL PARTICLE BOARD) ARE ACCEPTED AS EQUAL.
- ALL ANCHOR BOLTS TO HAVE A 3"x3"x1/4" PLATE WASHER.
- SHEAR WALL PANELS INDICATED ON SCHEDULE ARE TO BE SHEATHED FOR FULL HEIGHT OF WALL.
- ALL FRAMING SHALL BE SPACED @ 16" O.C.
- SEE HOLDOWN SCHEDULE AND PLAN FOR LOCATION AND SIZE OF HOLDOWNS REQUIRED.
- ALL PANEL EDGE MEMBERS TO BE 2x MEMBERS U.N.O.
- FASTENERS USED BELOW GRADE IN PONY WALLS, CRIPPLE WALLS OR KNEE WALLS AND FASTENERS USED TO ATTACH SHEATHING TO THE EXTERIOR BASEMENT OR CRAWLSPACE WALL STUDS SHALL BE TYPE 304 OR 316 STAINLESS STEEL.
- FASTENERS USED ABOVE GRADE TO ATTACH SHEATHING TO PRESSURE TREATED SILL PLATES SHALL BE OF TYPE 304 OR 316 STAINLESS STEEL, SILICON BRONZE, COPPER, HOT DIPPED GALVANIZED (ZINC COATED) STEEL NAILS OR HOT-TUMBLER GALVANIZED (ZINC COATED) STEEL NAILS, ELECTRO-GALVANIZED STEEL NAILS AND GALVANIZED (ZINC COATED) STEEL STAPLES SHALL NOT BE PERMITTED.


HOLDOWN SCHEDULE				
HOLDOWN	EDGE MEMBER	FOUNDATION ANCHOR	EDGE MEMBER ATTACHMENT	NOTES
HD12	(2) STUDS	5/8" DIA. A.B.	(6) 1/4x2-1/2 SDS	
MST37	(2) STUDS	N/A	(2) 1/4x SINKERS	
HD14	(2) STUDS	5/8" DIA. AB	(10) 1/4x2-1/2 SDS	
HD15	(2) STUDS	5/8" DIA. AB	(14) 1/4x2-1/2 SDS	
HD18	(2) STUDS	7/8" DIA. AB	(20) 1/4x2-1/2 SDS	

- ALL ANCHORS ARE SIMPSON STRONG-TIE OR EQUAL.
- INSTALLATION OF HOLDOWN ANCHORS AND STRAPS SHALL BE PER MFRS RECOMMENDATIONS & SPECIFICATIONS.
- WHEN 4x MEMBER IS REQUIRED FOR PANEL EDGES IN SHEAR WALL SCHEDULE USE 6x FOR HOLDOWN MEMBER. SSB ANCHOR BOLTS MAY BE SUBSTITUTED FOR THE SCHEDULED ANCHOR BOLTS.
- INCREASE FOOTING DEPTH WHERE EMBEDMENT LENGTH PLUS 3" IS GREATER THAN FOOTING DEPTH SPECIFIED.
- PROVIDE EDGE NAILING ALONG STUDS CONNECTED TO HOLDOWN ANCHORS AND STRAPS.

REMOVED ARCHITECTURAL SECTION AND ELEVATION CALLOUTS FOR CLARITY



J.M. WILLIAMS and Associates
 2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
 Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM




2ND LEVEL SHEARWALL PLAN
KLINEFELTER RESIDENCE
 EDEN, UTAH

REVISIONS:	
1	AUG 20, 2019
2	SEP 11, 2019


SCALE: AS NOTED
 DATE: JAN. 1, 2000
 DRAWN BY: SM
 JOB NO. 2019.002
 FILE: 2019.002

SHEET NO.
S3.2


ALL DIMENSIONS UNLESS OTHERWISE NOTED TO THE CONTRARY. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED.




10 WOOD LEDGER AT CONC. WALL
SCALE: N.T.S.




7 WOOD LEDGER AT CONC. WALL
SCALE: N.T.S.




4 WOOD FLOOR AT WOOD LEDGER
SCALE: N.T.S.




1 FLOOR AT FRAMED EXTERIOR WALL
SCALE: N.T.S.




11 WOOD JOISTS AT CONC WALL
SCALE: N.T.S.




8 WOOD LEDGER AT CONC. WALL
SCALE: N.T.S.




5 WOOD FLOOR AT WOOD LEDGER
SCALE: N.T.S.




2 FLOOR AT FRAMED EXTERIOR WALL
SCALE: N.T.S.




12 ROOF BETWEEN BEARING WALLS
SCALE: N.T.S.




9 WOOD LEDGER AT CONC. WALL
SCALE: N.T.S.



6 WOOD LEDGER AT CONC. WALL
SCALE: N.T.S.



3 FLOOR AT INTERIOR BEARING WALL
SCALE: N.T.S.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
Ph: 801.575.6455 Fax: 801.575.6456 Web: WWW.JMW.COM



6/8/2019

FLOOR FRAMING DETAILS
KLINEFELTER RESIDENCE
EDEN, UTAH


REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019


SCALE: AS NOTED
DATE: JAN. 1, 2000
DRAWN BY: SM
JOB NO. 2019.002
FILE: 2019.002

SHEET NO.
S4.1


NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE WRITTEN PERMISSION OF J.M. WILLIAMS AND ASSOCIATES




7 OPTIONAL DETAIL
FLUSH-MOUNT WOOD BEAM AT JOISTS
SCALE: N.T.S.




4 JOIST HANGER DETAIL
SCALE: N.T.S.




1 FLOOR JOISTS AT NON-FLUSH BEAM
SCALE: N.T.S.




5 BEAM TO POST DETAIL
SCALE: N.T.S.




2 FLOOR JOISTS AT WOOD BEAM
SCALE: N.T.S.



6 OPTIONAL DETAIL
FLUSH-MOUNT WOOD BEAM AT JOISTS
SCALE: N.T.S.



3 FLUSH-MOUNT WOOD BEAM AT JOISTS
SCALE: N.T.S.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 275, Salt Lake City, Utah 84119
Ph: 801.575.6455 Fax: 801.575.6456 Web: WWW.JMW.COM



FLOOR FRAMING DETAILS
KLINEFELTER RESIDENCE
EDEN, UTAH


REVISIONS:

▲	AUG 20, 2019
▲	SEP 11, 2019


SCALE: AS NOTED
DATE: JAN. 1, 2000
DRAWN BY: SM
JOB NO. 2019.002
FILE: 2019.002

SHEET NO.
S4.2


THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF J.M. WILLIAMS AND ASSOCIATES. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED IN ANY FORM WITHOUT WRITTEN CONSENT OF J.M. WILLIAMS AND ASSOCIATES.




10 TRUSS/BEARING DETAIL
SS.1 SCALE: N.T.S.




7 TOP PLATE CHORD SPLICE
SS.1 SCALE: N.T.S.




4 I-JOIST AT STEEL BEAM
SS.1 SCALE: N.T.S.



1 I-JOIST AT WOOD STUD WALL
SS.1 SCALE: N.T.S.




11 TYP. BEAM TO COLUMN CONNECTION
SS.1 SCALE: N.T.S.




NOTE: STUDS SHALL BE BUILT-UP AS REQ'D FOR SOLID BEARING w/ KING STUD EA SIDE TYP U.N.O.


8 BUILT-UP POST DETAIL
SS.1 SCALE: N.T.S.




5 STEEL BEAM AT WOOD POST
SS.1 SCALE: N.T.S.




2 I-JOIST AT WOOD RIDGE BEAM
SS.1 SCALE: N.T.S.




9 RIDGE DETAIL
SS.1 SCALE: N.T.S.




6 STEEL BEAM AT STEEL COLUMN
SS.1 SCALE: N.T.S.



4 RAFTER BLOCKING DETAIL
SS.1 SCALE: N.T.S.



J.M. WILLIAMS and Associates
2875 South Decker Lake Drive, Suite 276, Salt Lake City, Utah 84119
Ph. 801.575.6455 Fax. 801.575.6456 Web. WWW.JMWA.COM



6/8/2019

FRAMING DETAILS
KLINFELTER RESIDENCE
EDEN, UTAH

REVISIONS:

1	AUG 20, 2019
2	SEP 11, 2019

SCALE: AS NOTED
DATE: JAN. 1, 2000
DRAWN BY: SM
JOB NO. 2019.002
FILE: 2019.002

SHEET NO.
S5.1

NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM J.M. WILLIAMS AND ASSOCIATES.