I, the undersigned owner of the herein described tract of land, do hereby set apart and subdivide the same into lots and private street as shown on this plat, and name said tract Dixie Subdivision and do hereby: dedicate and reserve unto themselves, their heirs, their grantees and assigns, a right of way to be used in common with all others within said subdivision (and those adjoining subdivisions that may be subdivided by the undersigned owners, their successors, or assigns) on, over and across all those portions or parts of said tract of land designated on said plat as Private Street (Private Right of Way) as access to the individual lots, to be maintained by The Summit at Ski Lake Owners Association whose membership consists of said owners, their grantees, successors, or assigns, and also grant and dedicate a perpetual right and easement over, upon and under Private Streets and the lands designated hereof as sanitary sewer easements, slope and public utility/drainage easements, the same to be used for the installation, maintenance and operation of public utility service lines, storm drainage/detention facilities, sanitary sewer facilities, grading, or for the perpetual preservation of water drainage channels in their natural state whichever is applicable as may be authorized by the governing authority with no buildings or structures being erected within such easements, and hereby grant a temporary turn around easement as shown hereon to be used by the public until such time that the road is extended. The temporary turn around easement shall be revoked and nullified at the event of the extension of the road without further written document and the encumbered land within the affected lots shall be released for the full and exclusive use and benefit of the lot owners. Is a temporary turn-around easement applicable for this proposal?

Signed this day of , 2020.

~ John & Lara Schlaf Family Trust ~

State of County of

Commission Expires:

-S 89°36'57" E 2660.93' Measured, Bearing Base

(2660.82' W.C.S.)

(S 89°36'46" E W.C.S.)

Northwest Corner of Section 24,

T6S, R1E, SLB&M, U.S. Survey, Found Weber County 3 1/2" Brass

Cap Monument, Good Condition, 15" Below Ground, Dated 2006.

The foregoing instrument was acknowledged before me this ___ day of _____

A Notary Public commissioned in Utah Commission Number:

A part of the Northeast Quarter of Section 24, Township 6 North, Range 1 East, Salt Lake Base and Meridian, U.S. Survey: Beginning at a point which is 1336.37 feet South 89°45'09" East along the section line and 487.40 feet North 00°23'03" East from the Center of said Section 24; and running thence North 2°29'07" East 70.05 feet to the Southwest corner of The Summit at Ski Lake No. 11, a subdivision in Weber County, Utah, said point being on the Northeasterly line of The Summit at Ski Lake No. 12, a subdivision in Weber County, Utah; thence North 51°53'52" West 292.11 feet along said Northeasterly line to the Easterly line of Via Monaco, a Private Street; thence along said Easterly line the following three (3) courses: Northerly along the arc of a 144.52 foot radius curve to the left 48.08 feet (Central Angle is 19°03'48" and Long Chord bears North 22°11'25" East 47.86 feet), North 12°39'42" East 69.67 feet, and Northerly along the arc of a 225.00 foot radius curve to the left 43.35 feet (Central Angle is 11°02'16" and Long Chord bears North 07°08'34" East 43.28 feet) to the Southwest corner of Lot 32, Valley Lake Estates No. 3, Weber County, Utah; thence South 88°52'40" East 192.62 feet along the South line of said Lot 32; thence South 00°23'03" West 331.72 feet to the Point of Beginning.

BOUNDARY DESCRIPTION

Print Name

North Corner of Section 24, T6S, R1E,

SLB&M, U.S. Survey, Found Weber County Brass Cap, Good Condition, at

Road Surface, Dated 1991.

_1/4 Section Line

─ S 89°45'09" E

Developer:

John Schlaf

6874 East 1100 South

Huntsville, Utah 84317

Contains 52,895 square feet Or 1.21 acres

Dixie Subdivision

A part of the Northeast Quarter of Section 24, T6N, R1E, SLB & M., U.S. Survey Weber County, Utah March 2020

is sufficient for the installation of these improvements.

OGDEN VALLEY TOWNSHIP PLANNING COMMISSION

This is to certify that this subdivision plat was duly

approved by the Ogden Valley Township Planning Commission on the day of , 2020.

Chair, Ogden Valley Township Planning Commission

Signed this day of

my opinion they conform with the County Ordinance

applicable thereto and now in force and affect. Signed this day of , 2020.

SURVEYOR'S CERTIFICATE
I, Mark E. Babbitt, do hereby certify that I am a Registered Professional Land Surveyor in the State of Utah, and that I hold Certificate No. 166484 in accordance with Title 58 Chapter 22, Professional Engineers and Land Surveyors Licensing Act. I also do hereby certify this plat of Dixie Subdivision in Weber County, Utah has been correctly drawn to the designated scale and is a true and correct representation of the following description of lands included in said subdivision based on data compiled from records in the Weber County Recorder's Office, and of a survey made on the ground in accordance with Section 17–23–17. Monuments have been set as depicted on this drawing. I also certify that all the lots within this plat of Dixie Subdivision meet the frontage and area requirements of the Weber County Zoning Ordinance.

WEBER

___FILED FOR RECORD AND

___ IN BOOK______ OF OFFICIAL

COUNTY RECORDER

RECORDS, PAGE_____. RECORDER


WEBER COUNTY RECORDER

DEPUTY

RECORDED___

Signed this day of , 2020.

166484	
licence number	Mark E Pabbitt



Study by CMT Engineering Laboratories, dated

for review at the Weber County Planning Office.

Chair, Weber County Commission

WEBER COUNTY SURVEYOR

corner data, and for harmony with the lines and monuments on record in the county offices. The approval of this plat by

the Weber County Surveyor does not relieve the Licensed Land Surveyor who executed this plat from the responsibilities

Signature

and/or liabilities associated therewith. Signed this day of

I hereby certify that the Weber County Surveyor's Office has reviewed this plat for mathematical correctness, section

January 5, 2019, Project Number 13838, is available

W:\19N239 - John Schlaf Subd\Drawings\19N239 - S2.dwg, 3/12/2020 3:08:58 PM, mark, 1:1

GREAT BASIN OF ENGINEERING 2

Center of Section 24, T6S, R1E, SLB&M,-U.S. Survey, Found Weber County

Monument, Good Condition, Dated 2005.