



NOTES:

- THE CONTRACTOR WILL BE RESPONSIBLE FOR RUNNING (1) RUN OF 8x8 HYBRIFLEX CABLE FROM THE DISTRIBUTION BOX LOCATED WITHIN THE EQUIPMENT ROOM TO THE DISTRIBUTION BOX LOCATED AT THE VZW ANTENNA CENTERLINE, THEN (1) RUN OF 1x1 HYBRIFLEX CABLE FROM THE DISTRIBUTION BOX AT THE ANTENNA CENTERLINE TO EACH RRH. THE NEW HYBRIFLEX CABLE(S) IS TO BE RUN ALONG SIDE VZW'S EXISTING COAX AND IS TO BE INSTALLED PER VZW REQUIREMENTS, THE CONTRACTOR WILL BE REQUIRED TO FURNISH AND INSTALL ANY ADDITIONAL MATERIALS THAT ARE REQUIRED IN ORDER TO INSTALL THE NEW CABLE(S).

HYBRIFLEX LENGTHS:

- FROM THE EQUIPMENT ROOM DISTRIBUTION BOX TO THE ANTENNA CENTERLINE DISTRIBUTION BOX WILL REQUIRE THAT (1) RUN OF 8x8 HYBRIFLEX BE INSTALLED, LENGTH = 135'.
- FROM THE ANTENNA CENTERLINE DISTRIBUTION BOX TO EACH RRH WILL REQUIRE THAT (1) RUN OF 1x1 HYBRIFLEX BE INSTALLED, LENGTH = 15'.



VERIZON WIRELESS
9656 SOUTH PROSPERITY ROAD
WEST JORDAN, UTAH 84088

TAEC
Technology Associates Engineering Corporation Inc.
TECHNOLOGY ASSOCIATES

UTAH MARKET OFFICE
9847 SOUTH 500 WEST
SANDY, UTAH 84070

CORPORATE OFFICE
5473 KEARNY VILLA ROAD, SUITE 300
SAN DIEGO, CALIFORNIA 92123

DRAWN BY: JAY C
CHECKED BY: CHAD B

REV	DATE	DESCRIPTION
0	04.15.2013	SITE MODIFICATION

SAL - PINEVIEW
SW SEC 7, T6N, R2E
7100 EAST 700 NORTH
HUNTSVILLE, UTAH
-- SITE MODIFICATION --

SHEET TITLE
SITE ELEVATIONS

SHEET NUMBER
C200

