

INDEX OF DRAWINGS

DWG #	SHEET #	SHEET NAME
C-0.1	-	INDEX, LEGEND, AND ABBREVIATIONS
C-0.2	-	GENERAL NOTES
C-1.1	-	TOPOGRAPHIC SURVEY
C-1.2	-	SITE PLAN
C-1.3	-	UTILITY PLAN
C-1.4	-	GRADING & DRAINAGE PLAN
C-1.5	-	PLAN & PROFILE ACCESS & SANITARY
C-1.6	-	PLAN & PROFILE
C-1.7	-	EROSION CONTROL PLAN (SWPPP)
C-5.1	-	CIVIL DETAILS - SHEET 1
C-5.2	-	CIVIL DETAILS - SHEET 2
C-5.3	-	CIVIL DETAILS - SHEET 3
C-5.4	-	CIVIL DETAILS - SHEET 4


LEGEND

EXISTING	PROPOSED
= MONUMENT	= MONUMENT
= SECTION CORNER	= SECTION CORNER
= BENCHMARK	= BENCHMARK
= RIVET	= RIVET
= ROD & CAP	= ROD & CAP
= SPOT ELEVATION	= SPOT ELEVATION
= FINISH FLOOR ELEVATION	= FINISH FLOOR ELEVATION
= FINAL GRADE	= FINAL GRADE
FH = FIRE HYDRANT	FH = FIRE HYDRANT
SSMH = SEWER MANHOLE	SSMH = SEWER MANHOLE
SSCO = SEWER CLEANOUT	SSCO = SEWER CLEANOUT
SDMH = STORM DRAIN MANHOLE	SDMH = STORM DRAIN MANHOLE
BP = BOLLARD POLE	BP = BOLLARD POLE
CB = CATCH BASIN	CB = CATCH BASIN
= INLET GRATE	= INLET GRATE
EMH = ELECTRIC MANHOLE	EMH = ELECTRIC MANHOLE
EB = ELECTRIC BOX	EB = ELECTRIC BOX
EM = ELECTRIC METER	EM = ELECTRIC METER
GM = GAS METER	GM = GAS METER
PPO = POWER POLE	PPO = POWER POLE
LP = LIGHT POLE	LP = LIGHT POLE
TRANS = TRANSFORMER PAD	TRANS = TRANSFORMER PAD
TMH = TELEPHONE MANHOLE	TMH = TELEPHONE MANHOLE
TP = TELEPHONE PEDESTAL	TP = TELEPHONE PEDESTAL
FO = FIBER OPTIC MARKER	GP = GUY WIRE
GP = GUY WIRE	WMH = WATER MANHOLE
WMH = WATER MANHOLE	WV = WATER VALVE
WV = WATER VALVE	WM = WATER METER
WM = WATER METER	MW = MONITOR WELL
MW = MONITOR WELL	SPB = SPRINKLER BOX
SPB = SPRINKLER BOX	RD = ROOF DRAIN
RD = ROOF DRAIN	RVO = ROOF VENT
RVO = ROOF VENT	= VINYL FENCE
= VINYL FENCE	= CHAIN LINK FENCE
= CHAIN LINK FENCE	= MISCELLANEOUS FENCE
= MISCELLANEOUS FENCE	— 4230 — = CONTOUR MAJOR
— 4230 — = CONTOUR MAJOR	— 4231 — = CONTOUR MINOR
— 4231 — = CONTOUR MINOR	— SS — = SEWER LINE
— SS — = SEWER LINE	— SD — = STORM DRAIN LINE
— SD — = STORM DRAIN LINE	— G — = GAS LINE
— G — = GAS LINE	— OP — = OVERHEAD POWER LINE
— OP — = OVERHEAD POWER LINE	— EL — = BURIED ELECTRIC CABLE
— EL — = BURIED ELECTRIC CABLE	— COM — = COMMUNICATION LINE
— COM — = COMMUNICATION LINE	— T — = TELEPHONE LINE
— T — = TELEPHONE LINE	— W — = CULINARY WATER LINE
— W — = CULINARY WATER LINE	— NPW — = IRRIGATION WATER LINE
— NPW — = IRRIGATION WATER LINE	— FL — = FIRE LINE
— FL — = FIRE LINE	= SILT FENCE


ABBREVIATIONS

ABUT	ABUTMENT	FEN COR	FENCE CORNER	PRC	POINT OF REVERSE CURVE
ASPH	ASPHALT	FD	FLOOR DRAIN	PROJ	PROJECT
ADT	AVERAGE DAILY TRAFFIC	FDN	FOUNDATION	PROP	PROPERTY
APPROX	APPROXIMATELY	FF	FINISH FLOOR	PSI	POUNDS PER SQUARE INCH
AZ	AZIMUTH	FIN	FINISH	PT	POINT OF TANGENCY
		E	FLOW LINE	POB	POINT OF BEGINNING
BAL	BALANCE	FLR	FLOOR	PVC	POLYVINYL CHLORIDE
BEG	BEGINNING / BEGIN	FL	FLANGE		
BDRY	BOUNDARY	FT	FEET	QTY	QUANTITY
BK	BACK	FTG	FOOTING		
BKFL	BACKFILL	FW	FLAT WASHER	R	RANGE / RADIUS
BLD FLG	BLIND FLANGE	FE	FIRE EXTINGUISHER	RCP	REINFORCED CONCRETE PIPE
BLDG	BUILDING	FP	FLOOR PENETRATION	RCCP	
BLM	BUREAU OF LAND MANAGEMENT				
BM	BENCH MARK	G	GAS	RD	ROAD
BLK	BLOCK	GA	GAGE OR GAUGE	REF	REFERENCE
BOT/BTM	BOTTOM	GALV	GALVANIZED	REINF	REINFORCED
BRG	BEARING	GEN	GENERAL	REQ'D	REQUIRED
BSMT	BASEMENT	GM	GAS METER	REV	REVISION
BTWN	BETWEEN	GSP	GALVANIZED STEEL PIPE	RP	REFERENCE POINT
		GV	GATE VALVE	RR	RAILROAD
				RT	RIGHT / ROUTE
				R/W	RIGHT OF WAY
CALC	CALCULATED	HDWL	HEADWALL		
CB	CATCH BASIN	H&T	HUB & TACK	S	SOUTH / SLOPE
CCW	COUNTER CLOCKWISE	HOR/HORZ/HORIZ	HORIZONTAL	SAN	SANITARY
C-C	CENTER TO CENTER	HWL	HIGH WATER LEVEL	SCH	SCHEDULE
C&G	CURB AND GUTTER	HWY	HIGHWAY	SD	STORM SEWER
CEM	CEMETERY	HYD	HYDRANT	SEC COR	SECTION CORNER
CFS	CUBIC FEET PER SECOND	ID	INSIDE DIAMETER	SHT	SHEET
CL	CENTERLINE	IE	INVERT ELEVATION	SHT	SPECIFICATIONS
CIP	CAST IRON PIPE	IN	INCH	SO	SQUARE
CMP	CORRUGATED METAL PIPE	INFO	INFORMATION	SQ FT	SQUARE FEET
CMP-A	CORRUGATED METAL PIPE-ARCH	IRR	IRRIGATION	SQ YD	SQUARE YARD
		INV	INVERT	SS	STAINLESS STEEL
COB	CLEAN OUT BOX	JCT	JUNCTION	ST	STREET
COL	COLUMN			STL	STEEL
CONC	CONCRETE	L	LENGTH	STN STL	STAINLESS STEEL
CONST	CONSTRUCT	LB	POUND	STA	STATION
COR	CORNER	LG	LONG	STD	STANDARD
CTR	CENTER	LIC	LICENSE	STRUCT	STRUCTURE
CU FT	CUBIC FEET	LIN	LINEAR / LINEAL	T	TOWNSHIP / TELEPHONE
CU YD	CUBIC YARD	LPG	PROPANE GAS LINE	TA	TOP OF ASPHALT
CUL	CULINARY	LS	LAND SURVEYOR	TAN	TANGENT
CULV	CULVERT	LT	LEFT	TBC	TOP BACK CURB
CW	CLOCKWISE	LWL	LOW WATER LEVEL	TEMP	TEMPORARY
				TELE	TELEPHONE / TELEGRAM
D	DEGREE			TF	TOP OF FOOTING
DET	DETAIL	MAINT	MAINTENANCE	TP	TELEPHONE POLE
DIA	DIAMETER	MATL	MATERIAL	TW/TOW	TOP OF WALL
DIP	DUCTILE IRON PIPE	MAX	MAXIMUM	TOC	TOP OF CONCRETE
DIST	DISTANCE	MKR	MARKER	TYP	TYPICAL
DN	DOWN	MH	MANHOLE		
DWG	DRAWINGS	MI	MILE	UG	UNDERGROUND
DWV	DRAIN WASTE VENT	MIN	MINIMUM		
				VBI	VINYL BACK INSULATION
E	EAST	MISC	MISCELLANEOUS	VC	VERTICAL CURVE
EA	EACH	MON	MONUMENT	VERT	VERTICAL
ELEV/ELV	ELEVATION	NPH	MILES PER HOUR	VIC	VICTAULIC
ELEC	ELECTRIC			VOL	VOLUME
EMB	EMBANKMENT	NO OR #	NORTH	VPI	VERTICAL POINT OF INTERSECTION
ENGR	ENGINEER	NPW	NON-POTABLE WATER	VPC	VERTICAL POINT OF CURVE
ENT	ENTRANCE	NTS	NOT TO SCALE	VPT	VERTICAL POINT OF TANGENCY
EO	EDGE OF OIL EQUIPMENT				
EQUIP	EQUIPMENT	OC	ON CENTER	W	WEST / WATER
EST	ESTIMATE	OD	OUTSIDE DIAMETER	WM	WATER METER
EW	EACH WAY	O-O	OUTSIDE TO OUTSIDE	W/	WITH
EXC	EXCAVATION	OFF REV	OFFICE REVISION	W/O	WITHOUT
EXIST	EXISTING	ORIG	ORIGINAL		
ES	EXIT SIGN			XING	CROSSING
				X-SEC	CROSS SECTION
		PVMT	PAVEMENT		
		PC	POINT OF CURVATURE		
		PCC	POINT OF COMPOUND CURVATURE		
				PERF	PERFORATED
				PI	POINT OF INTERSECTION
				PL	PROPERTY LINE
				POC	POINT ON CURVE
				PP	POWER POLE

SECTION AND DETAIL IDENTIFICATION




NOTE: IF PLAN AND SECTION (OR DETAIL REFERENCE AND DETAIL) ARE SHOWN ON THE SAME DRAWING, THE DRAWING NUMBER IS REPLACED WITH A LINE.



DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reuse or modification without the written express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

COVER SHEET

C-0.1

PERMIT SET

CIVIL ENGINEER'S SITE & UTILITY NOTES

1. COMPLIANCE:
ALL CONSTRUCTION AND MATERIALS SHALL COMPLY WITH THE MOST RECENT EDITIONS OF THE FOLLOWING: THE INTERNATIONAL PLUMBING CODE, UTAH DRINKING WATER REGULATIONS, APWA STANDARDS & SPECIFICATIONS, CITY PUBLIC WORKS STANDARD PLANS AND CONSTRUCTION SPECIFICATIONS. THE CONTRACTOR IS REQUIRED TO ADHERE TO ALL OF THE ABOVE-MENTIONED DOCUMENTS UNLESS OTHERWISE NOTED AND APPROVED IN WRITING BY THE GOVERNING AUTHORITY.

2. CONTACT:
THE CONTRACTOR IS RESPONSIBLE TO NOTIFY ALL APPROPRIATE GOVERNMENT AND PRIVATE ENTITIES ASSOCIATED WITH THE PROJECT.

3. PERMITS, FEES AND AGREEMENTS
CONTRACTOR MUST OBTAIN ALL THE NECESSARY PERMITS AND AGREEMENTS, AND PAY ALL APPLICABLE FEES PRIOR TO ANY CONSTRUCTION ACTIVITIES. CONTACT CITY PUBLIC WORKS, STATE, AND COUNTY REGARDING PERMITS AND INSPECTIONS REQUIRED FOR WORK CONDUCTED WITHIN THE PUBLIC RIGHT-OF-WAY. APPLICABLE UTILITY PERMITS MAY INCLUDE MAINLINE EXTENSION AGREEMENTS AND SERVICE CONNECTION PERMITS. ALL UTILITY WORK MUST BE BONDED. ALL CONTRACTORS MUST BE LICENSED TO WORK ON CITY UTILITY MAINS.

4. STORM WATER POLLUTION PREVENTION PLAN (SWPPP) NOTES
CONSTRUCTION SITES MUST BE IN COMPLIANCE WITH THE UDEQ POLLUTION DISCHARGE ELIMINATION SYSTEM (NMPDES) STORM WATER PERMIT FOR CONSTRUCTION ACTIVITIES. A COPY OF THE PERMIT'S STORM WATER POLLUTION PREVENTION PLAN MUST BE KEPT ONSITE AT ALL TIMES. EROSION AND SEDIMENT CONTROL MEASURES WILL BE CONSTRUCTED AS SHOWN ON THE SWPPP. THE SWPPP IS CONSIDERED A DYNAMIC DOCUMENT AND MUST CHANGE AS CONDITIONS WARRANT. ADDITIONAL WATER QUALITY AND EROSION CONTROL MEASURES MAY BE REQUIRED DEPENDING ON SITE CONDITIONS.

5. SAFETY
THE CONTRACTOR IS RESPONSIBLE FOR ALL ASPECTS OF SAFETY OF THE PROJECT, AND SHALL MEET ALL OSHA, STATE, COUNTY AND OTHER GOVERNING ENTITY REQUIREMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFORMING TO LOCAL AND FEDERAL CODES GOVERNING SHORING AND BRACING OF EXCAVATIONS AND TRENCHES, AND FOR THE PROTECTION OF WORKERS.

6. TEMPORARY TRAFFIC CONTROL
TEMPORARY TRAFFIC CONTROL MUST CONFORM TO THE MOST CURRENT EDITION OF MUTCD PART 6 "TEMPORARY TRAFFIC CONTROL" AND CITY CONSTRUCTION SPECIFICATIONS. ALL TRAFFIC LANE CLOSURES AND PEDESTRIAN ROUTE CLOSURES MUST BE APPROVED BY CITY, COUNTY, OR STATE AGENCIES A MINIMUM OF 24 HOURS PRIOR TO BEGINNING WORK. THE CONTRACTOR MUST ALSO CONFORM TO CITY, NMDOT, COUNTY, OR OTHER APPLICABLE GOVERNING ENTITIES REQUIREMENTS FOR TRAFFIC CONTROL. MAINTAIN EMERGENCY ACCESS TO THE SITE AND ACCESS TO SURROUNDING FIRE HYDRANTS AT ALL TIMES.

7. SURVEY CONTROL
CONTRACTOR MUST PROVIDE A REGISTERED LAND SURVEYOR OR PERSONS UNDER SUPERVISION OF A REGISTERED LAND SURVEYOR TO SET STAKES FOR ALIGNMENT AND GRADE OF EACH UTILITY AND SITE IMPROVEMENT. THE CONTRACTOR WILL BE RESPONSIBLE FOR FURNISHING, MAINTAINING, OR RESTORING ALL MONUMENTS, REFERENCE MARKS, AND PROPERTY MARKERS WITHIN THE PROJECT SITE. CONTACT THE COUNTY SURVEYOR FOR MONUMENT LOCATIONS. ALL ELEVATIONS SHALL BE REFERENCED TO THE BENCHMARK ELEVATION AS PROVIDED ON THE APPROVED PLANS.

8. QUALITY CONTROL
WHERE TWO OR MORE STANDARDS ARE SPECIFIED AND THE STANDARDS ESTABLISH DIFFERENT OR CONFLICTING REQUIREMENTS FOR MINIMUM QUANTITIES OR QUALITY LEVELS, COMPLY WITH THE CITY PUBLIC WORKS SPECIFICATION FIRST AND THE MOST STRINGENT REQUIREMENT SECOND. REFER UNCERTAINTIES AND REQUIREMENTS TO THE PROJECT ENGINEER FOR CLARIFICATION.

9. DUST CONTROL
THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL ACCORDING TO THE GOVERNING ENTITY STANDARDS. USE OF HYDRANT WATER OR PUMPING FROM CITY-OWNED CANALS OR STORM DRAINAGE FACILITIES IS NOT ALLOWED FOR DUST CONTROL ACTIVITIES WITHOUT WRITTEN APPROVAL BY THE PUBLIC WORKS DIRECTOR.

10. DEWATERING
ALL ON-SITE DEWATERING ACTIVITIES MUST BE APPROVED IN WRITING BY PUBLIC UTILITIES. PROPOSED OUTFALL LOCATIONS AND ESTIMATED FLOW VOLUME CALCULATIONS MUST BE SUBMITTED TO PUBLIC UTILITIES FOR REVIEW AND APPROVAL. ADEQUATE MEASURES MUST BE TAKEN TO REMOVE ALL SEDIMENT PRIOR TO DISCHARGE. PUBLIC UTILITIES MAY REQUIRE ADDITIONAL MEASURES FOR SEDIMENT CONTROL AND REMOVAL.

THE CONTRACTOR MUST KEEP ALL EXCAVATIONS FREE FROM GROUNDWATER BY DEWATERING. THE CONTRACTOR MUST DISPOSE OF WATER SO AS NOT TO CAUSE A MENACE TO PUBLIC HEALTH, OR BECOME A NUISANCE. THE GROUNDWATER SHALL BE DRAWN DOWN TO 12" BELOW THE MINIMUM EXCAVATION. DEWATERING SHALL CONTINUE UNTIL FILL HAS BEEN PLACED AND COMPACTED A MINIMUM OF 24" ABOVE THE STATIC GROUNDWATER LEVEL. THE CONTRACTOR SHALL CONFORM TO BEST MANAGEMENT PRACTICES FOR REMOVING GROUNDWATER AS PER THE UPDES PERMIT.

11. PROJECT LIMITS
THE CONTRACTOR IS REQUIRED TO KEEP ALL CONSTRUCTION ACTIVITIES WITHIN THE APPROVED PROJECT LIMITS. THIS INCLUDES, BUT IS NOT LIMITED TO, VEHICLE AND EQUIPMENT STAGING, MATERIAL STORAGE AND LIMITS OF TRENCH EXCAVATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN PERMISSION AND/OR EASEMENTS FROM THE APPROPRIATE GOVERNING ENTITY AND/OR INDIVIDUAL PROPERTY OWNER(S) FOR WORK OR STAGING OUTSIDE OF THE PROJECT LIMITS.

12. DAMAGE TO EXISTING UTILITIES
THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE, CAUSED BY ANY CONDITION INCLUDING SETTLEMENT, TO EXISTING UTILITIES FROM WORK PERFORMED AT OR NEAR EXISTING UTILITIES. THE CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO PROTECT ALL EXISTING PUBLIC AND PRIVATE ROADWAYS AND UTILITY FACILITIES. DAMAGE TO EXISTING FACILITIES CAUSED BY THE CONTRACTOR, MUST BE REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE, TO THE SATISFACTION OF THE OWNER OF SAID FACILITIES.

13. UTILITY LOCATIONS
CONTRACTOR WILL BE RESPONSIBLE FOR LOCATING AND AVOIDING ALL UTILITIES AND SERVICE LATERALS, AND FOR REPAIRING ALL DAMAGE THAT OCCURS TO THE UTILITIES DUE TO THE CONTRACTOR'S ACTIVITIES. CONTRACTOR IS TO VERIFY LOCATION, DEPTH, SIZE, MATERIAL AND OUTSIDE DIAMETERS OF UTILITIES IN THE FIELD BY POTHOLING IN ORDER TO IDENTIFY POTENTIAL CONFLICTS, AND PROBLEMS WITH FUTURE CONSTRUCTION ACTIVITIES. EXISTING UTILITY INFORMATION SHOWN ON THE DRAWINGS WAS OBTAINED FROM PUBLIC UTILITIES' MAPS AND MUST BE ASSUMED AS APPROXIMATE; REQUIRING FIELD VERIFICATION. CONTACT BLUE STAKES OR APPROPRIATE OWNER FOR COMMUNICATION, GAS, TELEPHONE, FIBER OPTIC, CABLE, AND/OR PRIVATE UTILITY LOCATIONS.

14. UTILITY RELOCATIONS
FOR UTILITY CONFLICTS REQUIRING MAINLINE RELOCATIONS, THE CONTRACTOR MUST NOTIFY THE APPLICABLE UTILITY COMPANY, OR USER, A MINIMUM OF 2-WEEKS IN ADVANCE. A ONE-WEEK MINIMUM NOTIFICATION IS REQUIRED FOR CONFLICTS REQUIRING THE RELOCATION OF SERVICE LATERALS. ALL RELOCATIONS ARE SUBJECT TO APPROVAL FROM THE APPLICABLE UTILITY COMPANY AND/OR USER.

15. FIELD CHANGES
NO ROADWAY, UTILITY ALIGNMENT OR GRADE CHANGES ARE ALLOWED FROM THE APPROVED CONSTRUCTION PLANS/DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE PUBLIC WORKS DIRECTOR. CHANGES TO HYDRANT LOCATIONS AND/OR FIRE LINES MUST BE REVIEWED AND APPROVED BY THE FIRE DEPARTMENT (AS APPLICABLE TO THE PROJECT) AND PUBLIC WORKS.

16. PUBLIC NOTICE TO PROJECTS IN THE PUBLIC WAY
FOR APPROVED PROJECTS THE CONTRACTOR IS RESPONSIBLE TO PROVIDE AND DISTRIBUTE WRITTEN NOTICE TO ALL RESIDENTS LOCATED WITHIN THE PROJECT AREA AT LEAST 72-HOURS PRIOR TO CONSTRUCTION. WORK TO BE CONDUCTED WITHIN COMMERCIAL OR INDUSTRIAL AREAS MAY REQUIRE A LONGER NOTIFICATION PERIOD, AND ADDITIONAL CONTRACTOR COORDINATION WITH PROPERTY OWNERS. THE WRITTEN NOTICE IS TO BE APPROVED BY THE PUBLIC WORKS DIRECTOR OR CITY ENGINEER.

17. PUBLIC NOTICE FOR WATER MAIN SHUT DOWNS
THE PUBLIC WORKS DEPARTMENT AND CITY ENGINEER MUST APPROVE ALL WATER MAIN SHUTDOWNS. ONCE APPROVED, THE CONTRACTOR MUST NOTIFY ALL AFFECTED USERS BY WRITTEN NOTICE A MINIMUM OF 48-HOURS (RESIDENTIAL) AND 72-HOURS (COMMERCIAL/INDUSTRIAL) PRIOR TO THE WATER MAIN SHUT DOWN. PUBLIC WORKS MAY REQUIRE LONGER NOTICE PERIODS.

18. WATER AND SEWER SEPARATION
IN ACCORDANCE WITH UTAH'S DEPARTMENT OF HEALTH REGULATIONS, A MINIMUM TEN-FOOT HORIZONTAL AND 1.5-FOOT VERTICAL (WITH WATER ON TOP) SEPARATION IS REQUIRED. IF THESE CONDITIONS CANNOT BE MET, STATE AND PUBLIC WORKS APPROVAL IS REQUIRED. ADDITIONAL CONSTRUCTION MEASURES WILL BE REQUIRED FOR THESE CONDITIONS.

19. SEWER MAIN AND LATERAL CONSTRUCTION REQUIREMENTS
PUBLIC WORKS MUST INSPECT ALL SEWER CONNECTIONS. ALL SEWER LATERALS 6-INCHES AND SMALLER MUST WYE INTO THE MAINS PER PUBLIC WORKS REQUIREMENTS. A MINIMUM 4-FOOT BURY DEPTH IS REQUIRED ON ALL SEWER MAINS AND LATERALS.

THE CONTRACTOR MUST PROVIDE AIR PRESSURE TESTING OF SEWER MAINS IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATIONS AND PUBLIC WORKS REQUIREMENTS. THE CONTRACTOR SHALL PROVIDE SEWER LATERAL WATER TESTING AS REQUIRED BY THE PUBLIC WORKS DIRECTOR OR INSPECTOR. ALL PIPES SUBJECT TO WATER TESTING SHALL BE FULLY VISIBLE TO THE INSPECTOR DURING TESTING. TESTING MUST BE PERFORMED IN THE PRESENCE OF A PUBLIC WORKS REPRESENTATIVE. ALL VISIBLE LEAKAGE MUST BE REPAIRED TO THE SATISFACTION OF THE PUBLIC WORKS ENGINEER OR INSPECTOR.

20. WATER AND FIRE MAIN AND SERVICE CONSTRUCTION REQUIREMENTS
PUBLIC WORKS MUST INSPECT AND APPROVE ALL FIRE AND WATER SERVICE CONNECTIONS. A MINIMUM 3-FOOT SEPARATION IS REQUIRED BETWEEN ALL WATER AND FIRE SERVICE TAPS INTO THE MAIN. ALL CONNECTIONS MUST BE MADE MEETING PUBLIC WORKS REQUIREMENTS. A 7-FOOT MINIMUM BURY DEPTH (FINAL GRADE TO TOP OF PIPE) IS REQUIRED ON ALL WATER/FIRE LINES UNLESS OTHERWISE APPROVED BY PUBLIC UTILITIES. WATER LINE THRUST BLOCK AND RESTRAINTS ARE REQUIRED AS PER PUBLIC WORKS STANDARDS DRAWINGS AND CONSTRUCTION SPECIFICATIONS. ALL EXPOSED NUTS AND BOLTS WILL BE COATED WITH CHEVRON FM1 GREASE, PLUS A MINIMUM 8 MIL THICKNESS PLASTIC. PROVIDE STAINLESS STEEL NUTS, BOLTS, AND WASHERS FOR HIGH GROUNDWATER/ SATURATED CONDITIONS AT FLANGE FITTINGS, ETC.

ALL WATERLINE INSTALLATIONS AND TESTING TO BE ACCOMPLISHED IN ACCORDANCE WITH PUBLIC WORKS STANDARDS AND SPECIFICATIONS, INCLUDING UTAH STATE DRINKING WATER STANDARDS, AWWA SPECIFICATIONS, AND ALL OTHER APPLICABLE UPWS, ASTM, AND ANSI SPECIFICATIONS RELEVANT TO THE INSTALLATION AND COMPLETION OF THE PROJECT.

ALL NEW WATER MAINS OR APPURTENANCES SHALL BE DISINFECTED IN ACCORDANCE WITH AWWA STANDARD C651-99. THE SPECIFICATION SHALL INCLUDE DETAILED PROCEDURES FOR THE ADEQUATE FLUSHING, DISINFECTION, AND MICROBIOLOGICAL TESTING OF ALL WATER MAINS. ON ALL NEW AND EXTENSIVE DISTRIBUTION SYSTEM CONSTRUCTION, EVIDENCE OF SATISFACTORY DISINFECTION SHALL BE PROVIDED TO THE UTAH DIVISION OF DRINKING WATER. SAMPLES FOR COLIFORM ANALYSES SHALL BE COLLECTED AFTER DISINFECTION IS COMPLETE AND THE SYSTEM IS REFILLED WITH POTABLE WATER. A STANDARD HETEROTROPHIC PLATE COUNT IS ADVISABLE. THE USE OF WATER FOR CULINARY PURPOSES SHALL NOT COMMENCE UNTIL THE BACTERIOLOGIC TESTS INDICATE THE WATER TO BE FREE FROM CONTAMINATION.

CONTRACTOR IS TO INSTALL WATER SERVICE LINES, METER YOKES, AND/OR ASSEMBLIES AND METER BOXES WITH LIDS LOCATED AS APPROVED ON THE PLANS, AND PER APPLICABLE PUBLIC UTILITIES DETAIL DRAWINGS. METER BOXES ARE TO BE PLACED IN THE PARK STRIPS PERPENDICULAR TO THE WATERMAIN SERVICE TAP CONNECTION. ALL WATER METERS, CATCH BASINS, CLEANOUT BOXES, MANHOLES, DOUBLE CHECK VALVE DETECTOR ASSEMBLIES, REDUCED PRESSURE DETECTOR ASSEMBLIES, AND BACKFLOW PREVENTION DEVICES MUST BE LOCATED OUTSIDE OF ALL APPROACHES, DRIVEWAYS, PEDESTRIAN WALKWAYS, AND OTHER TRAVELED WAYS UNLESS OTHERWISE APPROVED ON PLANS.

BACKFLOW PREVENTERS ARE REQUIRED ON ALL IRRIGATION AND FIRE SPRINKLING TAPS PER PUBLIC UTILITIES AND FIRE DEPARTMENT REQUIREMENTS.

21. GENERAL WATER, SEWER AND STORM DRAIN REQUIREMENTS
NO CHANGE IN DESIGN OF UTILITY LOCATION OR GRADE WILL BE MADE BY THE CONTRACTOR WITHOUT THE WRITTEN APPROVAL OF CITY PUBLIC WORKS OR OTHER AUTHORITY HAVING JURISDICTION OVER THAT UTILITY.

NO SUBSTITUTES IN PIPE DIAMETER DIFFERENT FROM THOSE SHOWN ON THIS PLAN WILL BE PERMITTED UNLESS SUBMITTED TO AND APPROVED BY THE CITY PUBLIC WORKS, OR OTHER AUTHORITY HAVING JURISDICTION OVER THAT UTILITY.

ALL MANHOLES, HYDRANTS, VALVES, CLEAN-OUT BOXES, CATCH BASINS, METERS, ETC. MUST BE RAISED OR LOWERED TO FINAL GRADE PER PUBLIC WORKS STANDARDS, AND INSPECTOR REQUIREMENTS. CONCRETE COLLARS MUST BE CONSTRUCTED ON ALL MANHOLES, CLEANOUT BOXES, CATCH BASINS AND VALVES PER PUBLIC WORKS STANDARDS. ALL MANHOLE, CATCH BASIN, OR CLEANOUT BOX CONNECTIONS MUST BE MADE WITH THE PIPE CUT FLUSH WITH THE INSIDE OF THE BOX, AND GROUDED OR SEALED. ALL MANHOLE, CLEANOUT BOX OR CATCH BASIN DISCONNECTIONS MUST BE REPAIRED AND GROUDED WATERTIGHT.

CONTRACTOR SHALL NOT ALLOW ANY SURFACE WATER, GROUNDWATER OR DEBRIS TO ENTER THE NEW, OR EXISTING PIPE DURING CONSTRUCTION.

22. TRENCH BACKFILL
PIPE BEDDING AND TRENCH BACKFILL SHALL CONFORM TO PUBLIC WORKS STANDARDS. PLACE BACKFILL IN 8-INCH MAXIMUM LIFTS AND COMPACT TO 95% MAXIMUM DRY DENSITY AS PER ASTM D1557. THE PIPE SHALL BE LAID ON 6-INCH MINIMUM SAND BED. THE BACKFILL MATERIAL FOR THE PIPE ZONE SHALL BE A-1 SOILS, FREE FROM STONES, CLODS AND OTHER DELETERIOUS MATERIALS.

THE BOTTOM OF ALL UTILITY TRENCHES SHALL BE COMPACTED THOROUGHLY PRIOR TO PLACING PIPE. IF ROCK IS ENCOUNTERED AT DESIGN GRADE, OR A SOFT OR SOGGY BOTTOM IS ENCOUNTERED, THE TRENCH BOTTOM SHALL BE OVEREXCAVATED AND SUITABLE MATERIAL PLACED AND COMPACTED TO BOTTOM OF TRENCH GRADE.

COMPACTION REPORTS ON ALL TRENCHES SHALL BE SUBMITTED TO THE PROJECT ENGINEER, CITY ENGINEER, AND/OR OWNER'S REPRESENTATIVE BY THE MATERIALS TESTER, WHICH CERTIFIES THAT TRENCH BACKFILL WAS COMPACTED AS DIRECTED BY THE GEOTECHNICAL REPORT, IN ACCORDANCE WITH EARTHWORK SPECIFICATIONS AND PUBLIC WORKS SPECIFICATIONS.

23. SITE CONSTRUCTION
ALL EXISTING ASPHALT TO BE CUT SHALL BE SAW CUT IN NEAT STRAIGHT LINES BY THE CONTRACTOR PRIOR TO EXCAVATION.

GENERAL CONTRACTOR AND SUBCONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS ON SITE. CONTRACTORS SHALL HAVE VISITED AND BECOME FAMILIAR WITH THE PROJECT SITE.

GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE SITE CLEANUP INCLUDING DEBRIS, SCRAP, AND WASTE FROM SUBCONTRACTORS, AND INSTALLERS.

BEFORE BEGINNING ANY CUTTING OR DEMOLITION, THE CONTRACTOR SHALL HAVE REVIEWED THE SITE AND CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BEFORE CONTINUING.

CONTRACTOR SHALL PROVIDE PAVEMENT MARKINGS JUST PRIOR TO PROJECT COMPLETION. PAINT STRIPING SHALL CONSIST OF PAINTED LINES AND SYMBOLS IN ACCORDANCE WITH MUTCD STANDARDS & SPECIFICATIONS.

24. CONCRETE (CIVIL WORK ONLY)

ALL WORK SHALL CONFORM TO ACI AND ADA STANDARDS & SPECIFICATIONS. FINE BROOM FINISH REQUIRED ON EXTERIOR FLATWORK.

CONCRETE COVER	
CASE	COVER (IN)
COLUMNS GIRDS AND BEAMS	1 1/2
CONCRETE PLACED AGAINST EARTH	3
CONCRETE PLACED IN FORMS, EXPOSED TO WEATHER OR EARTH	2
SLABS OR WALLS NOT EXPOSED TO EARTH OR WEATHER	1

REINFORCING MATERIAL TABLE				
REINFORCING ELEMENT	ASTM	Fy (KSI)	Fu (KSI)	COMMENTS
TYPICAL REINFORCING	A706	60	80	**
WELDED & FIELD BENT	A706	60	80	-
WELDED WIRE, SMOOTH	A185	65	75	-
WELDED WIRE, DEFORMED	A497	70	80	-

** OR SEISMICALLY QUALIFIED ASTM A615 REBAR PER ACI 318-05 SECTION

CONCRETE MIX TABLE											
CONCRETE MIX TYPE	INTENDED USE	28 DAY STRENGTH, f c (KSI)	CONCRETE WEIGHT	MAX W/C RATIO, INCLUDING FLY ASH	MIN CEMENT MATERIAL (#/CY), INCLUDING FLY ASH	MAX AGGREGATE SIZE (IN)	SLUMP LIMITS (IN)	TOTAL AIR CONTENT (%) +/- 1 1/2%	CEMENT TYPE	REQUIRED ADMIXTURES	OTHER REQUIREMENTS
1	FOOTINGS	4	NWC	0.45	470	1	4	-	II/V	-	FLY ASH REQD
2	GRADE BEAMS, PILASTERS	4	NWC	0.45	517	1	4	6	II/V	AIR ENTRAINING	FLY ASH REQD
3	ALL CONCRETE EXPOSED TO WEATHER, OR DEICERS (SLABS AND WALLS)	5	NWC	0.4	564	1	4	6	II/V	AIR ENTRAINING, WATER REDUCING	FLY ASH REQD
4	INTERIOR SLABS ON GRADE	4	NWC	0.45	517	1	4	NOT PERMITTED	II/V	-	FLY ASH REQD
5	ALL CONCRETE OTHERWISE NOT SPECIFIED	4	NWC	0.45	517	1	4	6	II/V	AIR ENTRAINING	FLY ASH REQD

25. GRADING/EARTHWORK
THE GRADING CONTRACTOR SHALL OBTAIN A COPY OF THE SITE GEOTECHNICAL REPORT, AND FOLLOW ALL RECOMMENDATIONS PROVIDED BY THE GEOTECHNICAL ENGINEER.

NO GRADE CHANGES WILL BE PERMITTED FROM THAT SHOWN AND APPROVED ON THIS PLAN WITHOUT RESUBMITTING THE PROPOSED CHANGES TO THE OWNER AND/OR HIS REPRESENTATIVE.

COMPACTION OF MATERIALS PLACED AT THE SITE SHOULD EQUAL OR EXCEED THE FOLLOWING DENSITIES WHEN COMPARED TO THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-1557:

FOOTINGS = (SEE STRUCTURAL DRAWINGS)
PAVEMENT = 95%
LANDSCAPING = 90%


26. PAVEMENT
PAVEMENT STRUCTURAL SECTION FOR THE AUTOMOBILE PARKING, MANEUVERING AREAS AND LIGHT TO MEDIUM TRUCK AREAS SHALL CONSIST OF 4 INCHES OF ASPHALT SURFACE COURSE OVER 6 INCHES OF BASE COURSE OVER A PREPARED SUBGRADE, OR SELECT FILL. THE GRANULAR BASE SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D698. ALL CONCRETE SLABS SHALL CONSIST OF A 6" PORTLAND CEMENT CONCRETE SLAB OVER A PREPARED SUBGRADE OR SELECT FILL.

PAVEMENT MATERIALS SHOULD MEET THE UTAH DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR GRADATION & QUALITY. (1/2" AGGREGATE REQUIRED IN PARKING AREAS)


27. AS-BUILT DRAWINGS
THE CONTRACTOR MUST MAINTAIN A SET OF COMPLETE PLANS ON THE SITE AT ALL TIMES. THE CONTRACTOR MUST MARK IN RED INK DEVIATIONS FROM THE APPROVED SET OF DRAWINGS, INCLUDING:

ALIGNMENT OR GRADE CHANGES
DRAINAGE CHANGES SUCH AS LOCATION, FLOWLINE, STRUCTURE, SIZE, ETC.
SURFACE CHANGES SUCH AS DITCHES, PAVING, CURBS, SIDEWALKS, ETC.
UTILITY CHANGES, RELOCATIONS, OR CONFLICTS
ITEMS OR UTILITIES NOT SHOWN ON THE APPROVED SET OF PLANS
LIST ALTERNATE CONSTRUCTION METHODS
STRUCTURAL CONFLICTS OR RELOCATION OF EXISTING WALLS, UTILITY POLES, ETC.

THE CONTRACTOR MUST PROVIDE THE PROJECT ENGINEER OR OWNER'S REPRESENTATIVE WITH A COMPLETE SET OF AS-BUILT PLANS FOR CITY RECORDS.



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reuse or reproduction without the written express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6857



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN


Rev. # Rev. Date Rev. Desc.

PROJECT NO: 120138
DESIGN BY: JWS
DRAWN BY: AWF
CHECKED BY: JWS
DATE: 2/24/2021

CIVIL NOTES

C-0.2

PERMIT SE



LEGEND		
No.	ITEM	DESCRIPTION
(A)	FIRE HYDRANT	MUELLER SUPER CENTURION
(B)	VALVE BOX WITH LID	2-PIECE CAST IRON
(C)	GATE VALVE WITH 2"x2" NUT	AWWA C509
(D)	TEE WITH 125# FLANGE	AWWA C110

FURNISHED BY UTILITY AGENCY


SECTION

	FIRE HYDRANT WITH VALVE	PLAN NO.
		511S


FIRE HYDRANT WITH VALVE

- GENERAL**
 - BEFORE BACKFILLING, SECURE INSPECTION BY ENGINEER.
 - ADDITIONAL REQUIREMENTS ARE SPECIFIED IN APWA SECTION 33 11 00.
- PRODUCTS**
 - HYDRANT: DRY BARREL, AWWA C502.
 - THRUST BLOCK: CONCRETE CLASS 4000, APWA SECTION 03 30 04
 - REINFORCEMENT: DEFORMED, 60ksi YIELD GRADE STEEL, ASTM A 615.
 - BACKFILL: APWA SECTION 31 05 13. MAXIMUM PARTICLE SIZE 2-INCHES.
 - SEWER ROCK: ASTM SIZE No. 3 (2" TO 1") OR LARGER.
 - OTHER TYPE OF COMMON FILL: CONTRACTOR'S CHOICE.
 - GEOTEXTILE: STABILIZATION-SEPARATION FABRIC, APWA SECTION 31 05 19.
- EXECUTION**
 - INSTALLATION:**
 - PROVIDE AT LEAST 1 CUBIC YARD OF SEWER ROCK AROUND DRAIN HOLE AT BASE OF HYDRANT SPOOL. WRAP GEOTEXTILE AROUND SEWER ROCK AND TAPE GEOTEXTILE TO HYDRANT SPOOL TO PREVENT SILTING OF SEWER ROCK.
 - PAINT FIRE HYDRANT SPOOL TO PREVENT SILTING OF SEWER ROCK.
 - APPLY NON-OXIDE GREASE TO ALL BURIED METAL SURFACES. WRAP WITH POLYETHYLENE SHEET AND TAPE WRAP.
 - NOTIFY FIRE DEPARTMENT AS SOON AS HYDRANT IS PLACE IN SERVICE.
 - THRUST BLOCKS:**
 - BEFORE POURING CONCRETE, WRAP PIPE SYSTEM WITH POLYETHYLENE SHEET TO PREVENT BONDING OF CONCRETE TO PIPE SYSTEM.
 - REQUIRED FOR FLANGE OR WELDED PIPE SYSTEMS UNLESS APPROVED BY DISTRICT ENGINEER.
 - BACKFILL:**
 - MAXIMUM LIFT THICKNESS IS 8-INCHES BEFORE COMPACTION. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY, APWA SECTION 31 25 26.

	FIRE HYDRANT WITH VALVE	PLANNO.
		511S



	27" FRAME AND WATER COVER	PLAN NO.
		502S




- NOTES:**
- METER BOXES SHALL BE 18" DIA. BY 96" DEEP MUELLER-THERMAL-COIL PVC BOXES FOR 1" SINGLE METERS (MUELLER 330C51869FBSN)
 - POLYETHYLENE PIPE FOR WATER SERVICES SHALL BE PE 3408 TUBING, SDR-9, COPPER TUBING SIZE AND NSF APPROVED FOR POTABLE WATER.
 - METER SHALL BE INSTALLED IN HORIZONTAL ALIGNMENT, WITH METER FACING UP, ONLY.
 - ALL PIPE, FITTING, AND VALVES SHALL COMPLY WITH NSF STANDARD NO. 14 FOR USE WITH POTABLE WATER.
 - THE CUSTOMER IS RESPONSIBLE FOR PROPERLY SIZING THE SERVICE TO DELIVER FLOWS REQUIRED FOR FIRE SPRINKLER SYSTEMS. THE SERVICE FROM THE METER TO THE BUILDING CAN BE UPSIZED FROM 1" DIAMETER IF NECESSARY. CONNECTING FIRE SPRINKLER LINES TO THE 2" SERVICE BEFORE THE METER MAY BE APPROVED BY THE DISTRICT ENGINEER ONLY IF THE REQUIRED FIRE SPRINKLER CANNOT BE DELIVERED THROUGH THE METER.
 - THE DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE SERVICE FROM THE MAIN TO THE METER BOX, INCLUDING THE SERVICE SADDLE, CORP STOP, CURB STOP BOX, AND METER BOX.
 - BASED UPON OBSERVATIONS DURING WINTER CONDITIONS, THE DISTRICT HAS DETERMINED THAT 9" (MIN) OF COVER OVER WATER MAINS AND SERVICES IS REQUIRED TO PROTECT AGAINST FREEZING.

TYPICAL METER PIT DETAIL		
--------------------------	--	--

DRI

This design and any ideas portrayed here-in are the property of DRI. No part of this design may be reproduced or used in any form without the express written permission from an authorized DRI representative. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

COORDINATION SET - NOT FOR CONSTRUCTION

Rev. #	Rev. Date	Rev. Desc.
--------	-----------	------------

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021


CIVIL DETAILS

C-5.1

Direct bearing thrust block

1. GENERAL
 - A. Thrust design for pipe sizes or configurations not shown require special design.
 - B. Bearing areas, volumes, and special thrust blocking details shown on Drawings take precedence over this plan.
 - C. Restraint sizing is based upon a maximum operating pressure of 150 psi and a test pressure of 200 psi, and a minimum soil bearing strength of 2,000 psf. Operating pressures in excess of 150 psi or soils with less than 2,000 pound bearing strength will require special design.
 - D. Before backfilling around thrust block, secure inspection of installation by ENGINEER.
2. PRODUCTS
 - A. Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - B. Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - C. Thrust Blocks: Concrete Class 4000, APWA Section 03 30 04.
 - D. Grease: Non-oxide poly-FM.
3. EXECUTION
 - A. Pour concrete against undisturbed soil.
 - B. Pipe Joints: Do not cover with concrete. Leave completely accessible.
 - C. Grease: Apply grease to all buried metal surfaces. Wrap with polyethylene sheet and tape wrap.
 - D. Locking restraint devices may be used in conjunction with concrete thrust blocking (at discretion of ENGINEER).
 - E. Base Course and Backfill Placement: Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.

266



SIZE OF PIPE	MINIMUM BEARING AREA IN SQ. FT.				
	TEE VALVES 90° BENDS	90° BENDS	45° BENDS	22.5° BENDS	1/4" BENDS
4"	2	3	2	2	2
6"	4	5.5	3	1.5	1
8"	6.5	9.5	5	2.75	1.5
12"	14	20	11	5.5	3
14"	19	26.5	14.5	7.5	4
16"	24	34	18.5	8.5	6
20"	27	52	28.5	14.5	16
24"	53	74	41	21	63
30"	81	114	62	32	16

Direct bearing thrust block

Plan 561

August 2010

267

Direct bearing thrust block

1. GENERAL
 - A. Thrust design for pipe sizes or configurations not shown require special design.
 - B. Bearing areas, volumes, and special thrust blocking details shown on Drawings take precedence over this plan.
 - C. Restraint sizing is based upon a maximum operating pressure of 150 psi and a test pressure of 200 psi, and a minimum soil bearing strength of 2,000 psf. Operating pressures in excess of 150 psi or soils with less than 2,000 pound bearing strength will require special design.
 - D. Before backfilling around thrust block, secure inspection of installation by ENGINEER.
2. PRODUCTS
 - A. Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - B. Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - C. Thrust Blocks: Concrete Class 4000, APWA Section 03 30 04.
 - D. Grease: Non-oxide poly-FM.
3. EXECUTION
 - A. Pour concrete against undisturbed soil.
 - B. Pipe Joints: Do not cover with concrete. Leave completely accessible.
 - C. Grease: Apply grease to all buried metal surfaces. Wrap with polyethylene sheet and tape wrap.
 - D. Locking restraint devices may be used in conjunction with concrete thrust blocking (at discretion of ENGINEER).
 - E. Base Course and Backfill Placement: Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.

266

PIPE SIZE	FOUNDS @ 1' HORIZONTAL PER SQUARE INCH OF WATER PRESSURE*			
	TEES	90° BENDS	45° BENDS	22.5° BENDS
4"	18.5	26.1	14.2	7.2
6"	28	53.7	28.1	14.7
8"	55.8	93	50.4	25.5
10"	107.5	162	82.4	41.7
12"	153.1	216.4	117.2	59.4
14"	183.8	265.0	141.0	71.5
16"	237.8	356.3	182.8	92.7
18"	286.5	423.3	229.7	116.5

SOIL TYPE	SAFE BEARING LOAD (PSF)
SAND	1000
SAND & GRAVEL	1500
SAND & GRAVEL CEMENTED WITH CLAY	3000
SHALE	5000

SAFE BEARING LOAD FORMULA

THRUST ON FITTINGS = THRUST ON SAFE BEARING FITTING / LOAD OF SOIL (SQUARE FEET)

*MULTIPLY THRUST BY MAXIMUM WATER PRESSURE


CONCRETE THRUST BLOCK DETAILS

NOTES:

- WATER LINES 12 INCHES AND LARGER SHALL BE DUCTILE IRON CLASS-51.
- WATER LINES 10 INCHES AND SMALLER SHALL BE PVC AWWA C900 CLASS 2008.
- VALVES 12 INCHES AND LARGER SHALL BE BUTTERFLY VALVES.
- WHENEVER POSSIBLE "HOT TAP" CONNECTIONS REQUIRED. "HOT TAP" VALVE TO BE SUPPORTED DURING CONNECTION. CONTRACTOR TO NOTIFY CITY 24 HOURS IN ADVANCE OF MAKING CONNECTION.
- PIPE ZONE SHALL BE BACKFILLED WITH 3/4" GRAVEL MATERIAL.
- TRACING WIRE TO BE BROUGHT OUTSIDE OF BOTTOM PORTION OF VALVE BOX AND INSIDE TOP TO SURFACE.
- FURNISH AND INSTALL POLY-WRAP ON DUCTILE IRON PIPE. POLY-WRAP MAY BE DELETED WHERE DIRECTED BY CITY ENGINEER.
- WHERE COLLAPSIBLE SOILS ARE ENCOUNTERED, FURNISH, PLACE AND COMPACT IMPORTED BACKFILL MATERIALS AS REQUIRED AND AS DIRECTED.
- SEE WT-2 FOR PIPE BEDDING SPECIFICATIONS.

DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use or construction. Any reuse or reproduction of these drawings without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. # Rev. Date Rev. Desc.


PROJECT NO: 120138
DESIGN BY: JWS
DRAWN BY: AWF
CHECKED BY: JWS
DATE: 2/24/2021

CIVIL DETAILS


C-5.2

COORDINATION SET - NOT FOR CONSTRUCTION

STANDARD SET Owner ### 2/24/2021 1:29:21 PM/2/24/2021




POWDER MOUNTAIN WATER AND SEWER IMPROVEMENT DISTRICT
 27" FRAME AND SEWER COVER
 PLAN NO. 402S




Sanitary sewer manhole
 April 2011
 213

- Sanitary sewer manhole*
- GENERAL**
 - The drawing shows typical pipe connections. Refer to construction drawings for connection locations or refer to field location of existing piping when engineering pipe connection to the manhole.
 - Manhole size.
 - Diameter is 4 feet: For sewers under 12" diameter.
 - Diameter is 5 feet: For sewers 12" and larger, or when 3 or more pipes intersect the manhole.
 - PRODUCTS**
 - Base Course: Untreated base course, APWA Section 32 11 23. Do not use gravel as a base course without ENGINEER's permission.
 - Backfill: Common fill, APWA Section 31 05 13. Maximum particle size 2-inches.
 - Concrete: Class 4000, APWA Section 03 30 04.
 - Riser and Reducing Riser: ASTM C 478.
 - Reinforcement: Deformed, 60 ksi yield grade steel, ASTM A 615.
 - Grout: 2 parts sand to 1 part cement mortar, ASTM C 1329.
 - Stabilization-Separation Geotextile: Moderate or high at CONTRACTOR's choice, APWA Section 31 05 19.
 - EXECUTION**
 - Foundation Stabilization: Get ENGINEER's permission to use a sewer rock or a granular backfill borrow in a geotextile wrap to stabilize an unstable foundation.
 - Base Course Placement: APWA Section 32 11 23. Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a modified proctor density, APWA Section 31 23 26.
 - Invert Cover: During construction, place invert covers over the top of pipe in manholes that currently convey sewerage. See Plan 412.
 - Pipe Connections: Grout around all pipe openings.
 - Pipe Seal: Install rubber-based pipe seals on all plastic pipes when connecting plastic pipes to manholes. Hold water-stop in place with stainless steel bands.
 - Joints: Place flexible gasket-type sealant in all riser joints. Finish with grout.
 - Adjustment: If the required manhole adjustment is more than 1'-0", remove the cone and grade rings and adjust the manhole elevation with the appropriate manhole section, the cone section, and the grade rings or plastic form to make frame and lid match finish grade.
 - Finish: Provide smooth and neat finishes on interior of cones, shafts, and rings. Imperfect moldings or honeycombs will not be accepted.
 - Backfill: Provide backfill against the manhole shaft. Pea gravel and recycled RAP aggregate is NOT ALLOWED. Water jetting is NOT allowed. Maximum lift thickness is 8-inches before compaction. Compaction is 95 percent or greater relative to a standard proctor density, APWA Section 31 23 26.

212




POWDER MOUNTAIN WATER AND SEWER IMPROVEMENT DISTRICT
 SEWER LATERAL CONNECTION
 PLAN NO. 431S



1. AMCOR PRECAST 3'x3' CATCH BASIN - ISOMETRIC VIEW
 NO SCALE

NOTES:

- INLET BOX DETAILS SHOWN ON THESE PLANS WERE PROVIDED BY OLDCASTLE PRECAST (AMCOR) AS A COURTESY. CONTRACTOR MAY CHOOSE ANOTHER PRECAST MANUFACTURER. HOWEVER, ALL BOXES, GRATES OR LIDS MUST BE HS20 RATED AND INSTALLED AS PER APWA STANDARDS AND SPECIFICATIONS. THIS INCLUDES BACKFILL AND BEDDING OF THE CONCRETE BOXES, AND GROUTING ALL PIPE CONNECTIONS WATERTIGHT.




- NOTES:**
- CONCRETE PIPE INSTALLATION MUST CONFORM TO GEOTECHNICAL ENGINEER'S RECOMMENDATIONS, APWA STD'S & THE AMERICAN CONCRETE PIPE ASSOCIATION DESIGN MANUAL.
 - COMPACT BACKFILL AS SHOWN PROVIDE SUFFICIENT TRENCH WIDTH TO FIT COMPACTION EQUIPMENT.
 - FILL AND COMPACT HAUNCH AREAS UNDER PIPE ACCORDING TO SPECIFICATIONS. REMOVE ANY VOIDS WITHOUT DISTURBING THE PIPE FROM SPECIFIED LINE AND GRADE.
 - SEAL ALL CONNECTIONS TO JUNCTION BOXES, MANHOLES AND INLETS AS PER MANUFACTURER'S RECOMMENDATIONS.
 - PROTECT PIPE DURING CONSTRUCTION. REMOVE AND REPLACE DAMAGED PIPE.
 - REMOVE ALL UNSTABLE OR UNYIELDING SOILS AS DIRECTED BY THE GEOTECHNICAL ENGINEER.

2. CONCRETE PIPE TRENCH DETAIL (ONSITE PIPE/TYPE 1 INSTALLATION)
 NO SCALE

COORDINATION SET - NOT FOR CONSTRUCTION

JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN



Rev. #	Rev. Date	Rev. Desc.


PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

CIVIL DETAILS


C-5.3

DRI

This design and any ideas portrayed here-in are the property of DRI. Only the original client may use this design for any project. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



SILT FENCE ISOMETRIC VIEW



SILT FENCE TYPICAL SECTION

- NOTES:
- THE GEOTEXTILE FABRIC SHALL BE PLACED IN THE EXCAVATED TRENCH, BACKFILLED, AND COMPACTED TO THE EXISTING GROUND SURFACE.
 - WOODEN SUPPORT POSTS SHALL BE A MINIMUM DIMENSION OF 1-1/8" x 1-1/8" AIR OR KILN DRIED OF HICKORY OR OAK AND 4 FEET LONG. STEEL POSTS SHALL BE STUDDED "TEE" OR "U" TYPE WITH A MINIMUM WEIGHT OF 1.3 POUNDS PER LINEAL FOOT AND 5 FEET LONG. POST SPACING SHALL BE A MAXIMUM OF 8 FEET FOR WOVEN FABRIC AND 3 FEET FOR NON-WOVEN FABRIC.
 - THE GEOTEXTILE FABRIC SHALL BE ATTACHED DIRECTLY TO THE UPSLOPE SIDE OF WOODEN POSTS WITH 0.5 INCH STAPLES IN AT LEAST 3 PLACES, OR WITH WOODEN LATH AND NAILS. ATTACHMENT TO STEEL POSTS WILL BE BY WIRE FASTENERS OR 50 POUND PLASTIC TIE STRAPS ON THE UPSLOPE SIDE.
 - THE GEOTEXTILE FABRIC SHALL CONSIST OF EITHER WOVEN OR NON-WOVEN POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE, OR POLYVINYLIDENE CHLORIDE. NON-WOVEN FABRIC MAY BE NEEDLE PUNCHED, HEAT BONDED, RESIN BONDED, OR COMBINATIONS THEREOF. ALL FABRIC SHALL MEET THE FOLLOWING REQUIREMENTS:

TEST REQUIREMENT	METHOD	VALUE *
MINIMUM GRAB TENSILE STRENGTH IN THE MACHINE DIRECTION	ASTM D 4632	120 LBS.
MINIMUM GRAB TENSILE STRENGTH IN THE CROSS MACHINE DIRECTION	ASTM D 4632	100 LBS.
MAXIMUM APPARENT OPENING SIZE EQUIVALENT STANDARD SIEVE	ASTM D 4751	NO. 30
MINIMUM PERMITTIVITY	ASTM D 4491	0.05 SEC ⁻¹
MAXIMUM PERMITTIVITY	ASTM D 4491	0.135 SEC ⁻¹ OR 10 gpm/sq ft at 50 mm constant head.
MINIMUM ULTRAVIOLET STABILITY PERCENTAGE OF STRENGTH RETAINED AFTER 500 HOURS OF EXPOSURE	ASTM D 4355	70%

* ALL NUMERICAL VALUES REPRESENT MINIMUM/MAXIMUM AVERAGE ROLL VALUES. (FOR EXAMPLE, THE AVERAGE OF MINIMUM TEST RESULTS ON ANY ROLL IN A LOT SHOULD MEET OR EXCEED THE MINIMUM SPECIFIED VALUES.)

1 SILT FENCE DETAIL
C109 NO SCALE


NON-IRRIGATED EROSION CONTROL SEED MIX

COMMON NAME	LB/LIVE SEED/ACRE
SLENDER WHEATGRASS	3.00
INDIAN RICEGRASS-NEZPAR	3.00
BLUEBUNCH WHEATGRASS	3.00
SANDBERG BLUEGRASS	0.50
FOURWING SALTBRUSH	1.00
ANTELOPE BITTIERBRUSH	1.00
MOUNTAIN BIG SAGE	1.00
TOTAL	10.50 LB/ACRE


NON-IRRIGATED WILDFLOWER SEED MIX

COMMON NAME	LB/LIVE SEED/ACRE
GLOBEMALLOW-GOOSEBERRY LEAF	0.50
ROCKY MOUNTAIN BEEPLANT	2.00
SULFUR FLOWER	2.00
SCARLET GILIA	1.00
NORTHERN SWEETVETCH	0.50
MAPLE GROVE BLUE FLAX	0.50
WHITE EVENING PRIMROSE	0.50
PALMER PENSTEMON	0.50
WASATCH PENSTEMON	0.50
SCARLET GLOBEMALLOW	0.50
TOTAL	8.50 LB/ACRE

2 LONG TERM EROSION CONTROL SEED MIX
C109 NO SCALE




FIBER ROLL DROP INLET BARRIER PLAN



SECTION

- NOTES:
- KEY-IN FIBER ROLLS 2 INCH DEEP AROUND THE PERIMETER OF THE DROP INLET STRUCTURE AND STAKE AS SHOWN.
 - OVERLAP THE ENDS OF THE FIBER ROLL AT LEAST 18 INCHES.
 - CONSTRUCT ROLLS IN MEDIAN AREAS SO THAT THE TOPS OF THE ROLLS ARE NOT HIGHER THAN THE ADJACENT ROADWAY.
 - MAINTAIN A PROPERLY FUNCTIONING FIBER LOG BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
 - REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.


3 INLET PROTECTION DETAILS
C109 NTS




STABILIZED CONSTRUCTION ENTRANCE

4 STABILIZED CONSTRUCTION ENTRANCED - DETAIL
C109 NO SCALE

- NOTES FOR STABILIZED CONSTRUCTION ENTRANCE:
- PLACE STABILIZED CONSTRUCTION ENTRANCES AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
 - MAINTAIN A PROPERLY FUNCTIONING CONSTRUCTION ENTRANCE THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS HAVE BEEN PAVED.
 - DO NOT ALLOW VEHICLES LEAVING THE CONSTRUCTION SITE TO TRACK MUD ONTO PAVED ROADS.




SILT FENCE DROP INLET BARRIER PLAN




SECTION

- NOTES:
- ENTRENCH THE BOTTOM 18 INCH OF SILT FENCE SECURELY IN THE GROUND AROUND THE PERIMETER OF THE DROP INLET.
 - DRIVE POSTS AT EACH CORNER OF THE INLET STRUCTURE. PLACE ANOTHER POST(S) BETWEEN THEM IF THE DISTANCE BETWEEN CORNER POST(S) EXCEEDS 4 FT.
 - CROSS-BRACE THE TOPS OF ALL POSTS WITH A WOODEN FRAME MADE OF 2 x 4 STUDS. USE NAILS OR SCREWS FOR FASTENING.
 - CONSTRUCT SILT FENCE IN MEDIAN AREAS SO THAT THE TOPS OF THE SILT FENCE ARE NOT HIGHER THAN THE ADJACENT ROADWAY.
 - MAINTAIN A PROPERLY FUNCTIONING SILT FENCE BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
 - REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.




SECTION B-B




GUTTER INLET BARRIER PLAN

- NOTES FOR GUTTER INLET BARRIER:
- PLACE FIBER ROLL AND SAND BAGS AS SHOWN AROUND GUTTER INLETS AND AVOID PLACING THE BARRIER IN THE TRAVEL LANE.
 - USE GUTTER INLET BARRIERS ONLY WHERE THERE IS THE POTENTIAL OF SEDIMENT FROM NON-STABILIZED AREAS GETTING INTO THE INLET.
 - MAINTAIN A PROPERLY FUNCTIONING GUTTER INLET BARRIER THROUGHOUT CONSTRUCTION OR UNTIL DISTURBED AREAS CONTRIBUTING TO THE INLET HAVE BEEN PAVED OR VEGETATED.
 - REMOVE SEDIMENT AS IT ACCUMULATES AND PLACE IT IN A STABLE AREA APPROVED BY THE CITY, OR REMOVE FROM PROJECT.

5 GUTTER INLET PROTECTION DETAIL
C109 NTS




6 CONCRETE WASHOUT DETAIL
C109 NO SCALE




A SECTION A-A
NO SCALE

- NOTES:
- DO NOT WASH OUT CONCRETE INTO STORM DRAINS, OPEN DITCHES, STREETS OR STREAMS
 - WHEN WASHING CONCRETE TO REMOVE FINE PARTICLES, AVOID CREATING RUNOFF, ONLY WASH CONCRETE EQUIPMENT IN DESIGNATED AREAS.
 - INSPECT AND MAINTAIN CONCRETE WASHOUT AREA WEEKLY AND REMOVE HARDENED CONCRETE ON A REGULAR BASIS.



7 TEMPORARY SANITARY FACILITY DETAIL
C109 NO SCALE




B SECTION A-A
NO SCALE

- NOTES:
- PORTABLE TOILETS MUST BE MAINTAINED IN GOOD WORKING ORDER WITH DAILY OBSERVATION FOR LEAK DETECTION
 - REGULAR WASTE COLLECTION MUST BE ARRANGED WITH LICENSED SERVICE.
 - ALL WASTE COLLECTION MUST BE DEPOSITED IN A SANITARY SEWER SYSTEM FOR TREATMENT WITH APPROPRIATE AGENCY APPROVAL

DRI

This design and any ideas portrayed here-in are the sole property of DRI and the original client may use this design for their own project only. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-8851



JACOBS LADDER DEV.

MICHAEL MOYAL

UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN




Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

CIVIL DETAILS

C-5.4

COORDINATION SET - NOT FOR CONSTRUCTION



DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. Contact number: 435-7646851

PROFESSIONAL ENGINEER
02/24/2021
No. 7738648
JOSEPH W. STUART
STATE OF UTAH

JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN



Rev. #	Rev. Date	Rev. Desc.

PROJECT NO: 120138
DESIGN BY: JWS
DRAWN BY: AWF
CHECKED BY: JWS
DATE: 2/24/2021


COORDINATION SET - NOT FOR CONSTRUCTION

TOPO SURVEY

C-1.1



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this design for any other project. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-8851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN


COORDINATION SET - NOT FOR CONSTRUCTION



Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021


SITE PLAN

C-1.2





This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without the written consent of DRI is strictly prohibited. Contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN





COORDINATION SET - NOT FOR CONSTRUCTION

Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021


GRADING PLAN

C-1.4




SANITARY MAIN PROFILE
 HORIZ SCALE: 1" = 30'; VERT SCALE: 1" = 10'

ACCESS ROAD
 HORIZ SCALE: 1" = 30'; VERT SCALE: 1" = 10'



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction or reuse of this design without express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.

MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN


Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

PLAN & PROFILE


C-1.5

COORDINATION SET - NOT FOR CONSTRUCTION




JACOBS LADDER ROAD PROFILE
 HORIZ SCALE: 1" = 30'; VERT SCALE: 1" = 10'

COORDINATION SET - NOT FOR CONSTRUCTION



This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for construction. Any other use without the express written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-6851



JACOBS LADDER DEV.



MICHAEL MOYAL
 UNINCORPORATED,
 WEBER COUNTY
 POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

PLAN & PROFILE


C-1.6



COORDINATION SET - NOT FOR CONSTRUCTION

DRI

This design and any ideas portrayed here-in are the sole property of DRI. Only the original client may use this set of drawings for one-time use of construction. Any reproduction, copying, or reuse of these drawings without the written permission from an authorized DRI representative is strictly prohibited. contact number: 435-764-8851



JACOBS LADDER DEV.

MICHAEL MOYAL
UNINCORPORATED,
WEBER COUNTY
POWDER MOUNTAIN

Rev. #	Rev. Date	Rev. Desc.

PROJECT NO:	120138
DESIGN BY:	JWS
DRAWN BY:	AWF
CHECKED BY:	JWS
DATE:	2/24/2021

SWPPP

C-1.7