


Project Narrative/Notes/Revisions


- 1) 11/8/13 RH - COMPLETED DESIGN FOR CLIENT & CITY REVIEW.
- 2) 1/14/14 ST - PROVIDED RETENTION PONDS/CURB & GUTTER.
- 3) 3/10/14 ST - UPDATED PER COUNTY COMMENTS
- 4) 5/2/14 ST - UPDATED PER COUNTY COMMENTS
- 5) 9/4/14 ST - UPDATED PER COUNTY COMMENTS

MALLARD SPRINGS SUBDIVISION Improvement Plans

WEBER COUNTY, UTAH
SEPTEMBER 2014




Vicinity Map
NOT TO SCALE



Sheet Index Key Map
NOT TO SCALE

Sheet Index

- Sheet 1 - Cover/Index Sheet
- Sheet 2 - Notes/Legend/Street Cross-Section
- Sheet 3 - 4050 West Street 5+50.00 - 11+00.00
- Sheet 4 - 2475 South Street 16+00.00 - 20+00.00
- Sheet 5 - 2475 South Street 20+00.00 - 25+00.00
- Sheet 6 - 4000 West Street 10+00.00 - 14+50.00
- Sheet 7 - 4000 West Street 14+50.00 - 18+50.00
- Sheet 8 - 2400 South Street 20+00.00 - 24+50.00
- Sheet 9 - 2400 South Street 24+50.00 - 30+00.00
- Sheet 10 - Sewer Outfall 5+50.00 - 11+00.00
- Sheet 11 - Sewer Outfall 10+00.00 - 16+00.00
- Sheet 12 - Sewer Outfall 16+00.00 - 22+00.00
- Sheet 13 - Sewer Outfall/4300 W 29+00.00 - 34+50.00
- Sheet 14 - Sewer Outfall/4300 W 34+50.00 - 40+00.00
- Sheet 15 - Storm Water Pollution Prevention Plan Exhibit
- Sheet 16 - Storm Water Pollution Prevention Plan Details



Reeve & Associates, Inc.
RA
REGISTERED PROFESSIONAL ENGINEERS & ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments

Mallard Springs Subdivision
WEBER COUNTY, UTAH
Cover/Index Sheet

Revised: 9-4-14

REGISTERED PROFESSIONAL ENGINEER
375328
J. NATE REEVE
STATE OF UTAH

Engineer's Notice To Contractors
THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM AVAILABLE INFORMATION PROVIDED BY OTHERS. THE LOCATIONS SHOWN ARE APPROXIMATE AND SHALL BE CONFIRMED IN THE FIELD BY THE CONTRACTOR, SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO CONTACT THE UTILITY COMPANIES AND TAKE DUE PRECAUTIONARY MEASURE TO PROTECT ANY UTILITY LINES SHOWN, AND ANY OTHER LINES OBTAINED BY THE CONTRACTOR'S RESEARCH, AND OTHERS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.

Developer Contact:
Doug Hamblin
Hamblin Investments
1613 North 2000 West
Clinton, Utah, 84015
PH: (801) 731-7703

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Project Info.

Engineer: J. NATE REEVE, P.E.
 Drafter: R. HANSEN
 Begin Date: NOVEMBER 4, 2013
 Name: MALLARD SPRINGS SUBDIVISION
 Number: 3442-A30

Sheet	16
1	Sheets

General Notes:

- 1. ALL CONSTRUCTION MUST STRICTLY FOLLOW THE STANDARDS AND SPECIFICATIONS SET FORTH BY: THE DESIGN ENGINEER, GOVERNING UTILITY MUNICIPALITY, GOVERNING CITY OR COUNTY (IF UN-INCORPORATED), INDIVIDUAL PRODUCT MANUFACTURERS, AND THE AMERICAN PUBLIC WORKS ASSOCIATION (APWA)...

Utility Notes:

- 1. CONTRACTOR SHALL COORDINATE LOCATION OF NEW "DRY UTILITIES" WITH THE APPROPRIATE UTILITY COMPANY, INCLUDING BUT NOT LIMITED TO: TELEPHONE SERVICE, GAS SERVICE, POWER...

Master Legend

Legend table listing symbols for various utilities: PROPOSED CULINARY WATER LINE, EXISTING CULINARY WATER LINE, PROPOSED SANITARY SEWER LINE, etc.

General Notes

- 1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE DEVELOPMENT STANDARDS OF WEBER COUNTY AND THE STANDARD DRAWINGS CONTAINED THEREIN...

Erosion Control General Notes:

THE CONTRACTOR TO USE BEST MANAGEMENT PRACTICES FOR PROVIDING EROSION CONTROL FOR CONSTRUCTION OF THIS PROJECT. ALL MATERIAL AND EROSION CONTROL FOR CONSTRUCTION OF THIS PROJECT...

CONTRACTOR SHALL KEEP THE SITE WATERED TO CONTROL DUST. CONTRACTOR TO LOCATE A NEARBY HYDRANT FOR USE AND TO INSTALL TEMPORARY METER. CONSTRUCTION WATER COST TO BE INCLUDED IN BID.

WHEN GRADING OPERATIONS ARE COMPLETED AND THE DISTURBED GROUND IS LEFT "OPEN" FOR 14 DAYS OR MORE, THE AREA SHALL BE FURROWED PARALLEL TO THE CONTOURS.

THE CONTRACTOR SHALL MODIFY EROSION CONTROL MEASURES TO ACCOMMODATE PROJECT PLANNING.

ALL ACCESS TO PROPERTY WILL BE FROM PUBLIC RIGHT-OF-WAYS. THE CONTRACTOR IS REQUIRED BY STATE AND FEDERAL REGULATIONS TO PREPARE A STORM WATER POLLUTION PREVENTION PLAN AND FILE A "NOTICE OF INTENT" WITH THE GOVERNING AGENCIES.

Maintenance:

ALL BEST MANAGEMENT PRACTICES (BMP'S) SHOWN ON THIS PLAN MUST BE MAINTAINED AT ALL TIMES UNTIL PROJECT CLOSE-OUT.


THE CONTRACTOR'S RESPONSIBILITY SHALL INCLUDE MAKING BI-WEEKLY CHECKS ON ALL EROSION CONTROL MEASURES TO DETERMINE IF REPAIR OR SEDIMENT REMOVAL IS NECESSARY. CHECKS SHALL BE DOCUMENTED AND COPIES OF THE INSPECTIONS KEPT ON SITE.

SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL. THEY MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF BARRIER.

SEDIMENT TRACKED ONTO PAVED ROADS MUST BE CLEANED UP AS SOON AS PRACTICAL, BUT IN NO CASES LATER THAN THE END OF THE NORMAL WORK DAY. THE CLEAN UP WILL INCLUDE SWEEPING OF THE TRACKED MATERIAL, PICKING IT UP, AND DEPOSITING IT TO A CONTAINED AREA.


EXPOSED SLOPES:

ANY EXPOSED SLOPE THAT WILL REMAIN UNTOUCHED FOR LONGER THAN 14 DAYS MUST BE STABILIZED BY ONE OR MORE OF THE FOLLOWING METHODS: A) SPRAYED DISTURBED AREAS WITH A TACKIFIER VIA HYDROSEED...



Street Section (60' R.O.W.)

*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.



Connection to Central Weber Sewer Improvement District - Existing Manhole

SCALE: NONE

Reeve & Associates, Inc. logo and contact information including address, phone, and website.

Table with 3 columns: REVISIONS, DATE, DESCRIPTION. Contains revision history for County Comments.


Central Weber Sewer District Notes

- 1. CONNECTION TO MANHOLE SHALL BE MADE USING A FLEXIBLE, WATERTIGHT CONNECTION METHOD, KOR-N-SEAL OR EQUAL...

Mallard Springs Subdivision Notes/Legend/Street Cross-Section. Includes vertical text and a registered professional engineer seal for J. Nate Reeve.




Revised: 9-4-14

Project Info. section containing Engineer (J. NATE REEVE, P.E.), Drafter (R. HANSEN), and other project details.



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE



Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
 Two Working Days **268** You Dig

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF REEVE & ASSOCIATES, INC., 920 CHAMBERS STREET #14, OGDEN, UTAH 84403, AND SHALL NOT BE PHOTOCOPIED, RE-DRAWN, OR USED ON ANY PROJECT OTHER THAN THE PROJECT SPECIFICALLY DESIGNED FOR. WITHOUT THEIR WRITTEN PERMISSION. THE OWNERS AND ENGINEERS OF REEVE & ASSOCIATES, INC. DISCLAIM ANY LIABILITY FOR ANY CHANGES OR MODIFICATIONS MADE TO THESE PLANS OR THE DESIGN THEREON WITHOUT THEIR CONSENT.

Reeve & Associates, Inc.
 920 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
 TEL: (801) 621-3000 FAX: (801) 621-2668 www.reeve-assoc.com
 RAMP, BRIDGES & STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments

Mallard Springs Subdivision
 WEBER COUNTY, UTAH

4050 West Street
5+50.00 - 11+00.00


Revised: 9-4-14

Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: R. HANSEN
 Begin Date: NOVEMBER 4, 2013
 Name: MALLARD SPRINGS SUBDIVISION
 Number: 3442-A30



RETENTION #2 VOLUME CALCULATIONS
 HIGH WATER AREA (51.97') = 9,153 S.F.
 BOTTOM AREA (47.72') = 4,556 S.F.
 $(9,153 + 4,556) / 2 = 6,905$ S.F. AVG.
 $6,905 \text{ S.F.} \times 4.25' \text{ DEEP} = 29,346 \text{ C.F.}$
 $29,346 \text{ C.F.} > 28,882 \text{ C.F. (REQ'D)} = \text{OK}$

2475 South Street



Storm Runoff Calculations
 Mallard Springs Subdivision-Basin 2
 6/2/2014

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken from data compiled by NOAA Atlas 14, using a 100 year storm.

Runoff storm water has been calculated for two different sets of conditions, one being the existing undeveloped land and the other with land fully improved. The difference between the two quantities will be retained in a holding pond.

The calculations are as follows:

- Runoff from the undeveloped existing land.

Runoff Quantity	Q =	0 cfs
Acreage	A =	7.99 ACRES
Perc Rate		27.00 mpi
Q(out) =		0.05 CFS
- Runoff from developed land

Runoff Coefficients		
Paved Area	59.655	C = 0.9
Landscaped Area	256.068	C = 0.2
Roof	32.409	C = 0.8
Weighted Runoff Coefficient		C = 0.38
Rainfall Intensity	i =	varies with time
Runoff Quantity	Q =	CIA
- Detention Basin

Volume in	Q * t
Volume out	0.05 * t

The capacity of the retention basin is calculated as the maximum difference between the volume flowing in and the volume flowing out.

The outflow from the retention basin is limited to outflow if undeveloped. Use 0.05 cfs for Q outflow

The required volume of the retention basin is 28,371 cubic feet


Bottom Area of Basin	Percolation out of Basin	
9150 s.f.	$(1 \text{ in/Perc}) * (1 \text{ ft}/12 \text{ in}) * (1 \text{ min}/60 \text{ sec}) * \text{Area of Basin}$	0.471

RETENTION BASIN
 Cumulative Volume For Detention Pond
 Mallard Springs Subdivision-Basin 2

C =	0.38
A =	7.99
Q(out) =	0.05

time (min)	time (sec)	i (in/hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0.00	0.00	0.00
5	300	6.64	19.94	5982.87	14.12	5968.75
10	600	5.05	15.17	9100.45	28.24	9072.21
15	900	4.17	12.52	11271.95	42.36	11229.59
30	1800	2.81	8.44	15191.45	84.72	15106.73
60	3600	1.74	5.23	18813.61	169.44	18644.17
180	10800	0.85	1.96	21116.66	508.33	20608.33
360	21600	0.36	1.09	23549.45	1016.67	22532.79
720	43200	0.22	0.66	28544.79	2033.33	26511.46
1440	86400	0.13	0.38	32437.26	4066.67	28370.60

West Haven UT
 NOAA Atlas 14



Construction Notes:

- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.

- CULINARY WATER**
 W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
 SS/8 - 8" ASTM D3034 SDR 35 SEWER
 SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
 SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE


Reeve & Associates, Inc.
 620 CHAMBERS STREET, SUITE 14, ODEN, UTAH 84403
 TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
 RAINFALL ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

RA

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
 WEBER COUNTY, UTAH

2475 South Street
 16+00.00 - 20+00.00






Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: R. HANSEN
 Begin Date: NOVEMBER 4, 2013
 Name: MALLARD SPRINGS SUBDIVISION
 Number: 3442-A30

Revised: 9-4-14



2475 South Street



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE

Reeve & Associates, Inc.
620 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-1000 FAX: (801) 621-2668 www.reeve-assoc.com

RA

TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments





Mallard Springs Subdivision
WEBER COUNTY, UTAH

2475 South Street
20+00.00 - 25+00.00

Revised: 9-4-14

Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig




- Construction Notes:**
- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE

Reeve & Associates, Inc.
320 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
WEBER COUNTY, UTAH

4000 West Street
10+00.00 - 14+50.00



Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig




Construction Notes:

- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE


Reeve & Associates, Inc.
230 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 671-3100 FAX: (801) 671-2668 www.reeve-assoc.com

RA
REGISTERED PROFESSIONAL ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments



RETENTION #3 VOLUME CALCULATIONS
HIGH WATER AREA (48.25') = 9,060 S.F.
BOTTOM AREA (44.65') = 5,023 S.F.
[9,060 + 5,023]/2 = 7,042 S.F. AVG.
7,042 S.F. x 3.6' DEEP = 25,351 C.F.
25,351 C.F. > 24,866 C.F. (REQ'D.) = OK



Storm Runoff Calculations
Mallard Springs Subdivision-Basin 3
6/2/2014

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken from data compiled by NOAA Atlas 14, using a 100 year storm.

Runoff storm water has been calculated for two different sets of conditions, one being the existing undeveloped land and the other with land fully improved. The difference between the two quantities will be retained in a holding pond.

The calculations are as follows:

- Runoff from the undeveloped existing land.

Runoff Quantity	Q =	0 cfs
Acreage	A =	6.69 ACRES
Perc Rate		40.00 mpi
Q(out) =		0.03 CFS
- Runoff from developed land

Runoff Coefficients		
Paved Area	48,809	C = 0.9
Landscaped Area	215,609	C = 0.2
Roof	27,142	C = 0.8
Weighted Runoff Coefficient		C = 0.37
Rainfall Intensity	i =	varies with time
Runoff Quantity	Q =	CIA
- Detention Basin

Volume in	Q * t
Volume out	0.03 * t

The capacity of the retention basin is calculated as the maximum difference between the volume flowing in and the volume flowing out.

The outflow from the retention basin is limited to outflow if undeveloped. Use 0.03 cfs for Q outflow.

The required volume of the retention basin is **24,266 cubic feet**


Bottom Area of Basin	9000 s.f.	Percolation out of Basin	(1in/Perco)*(10/12in)*(1min/60sec)*Area of Basin	0.313
----------------------	-----------	--------------------------	--	-------

RETENTION BASIN
Cumulative Volume For Detention Pond
Mallard Springs Subdivision-Basin 3

C =	0.37
A =	6.69
Q(out) =	0.03


time (min)	time (sec)	i (in./hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0.00	0.00	0.00
5	300	6.64	16.58	4973.76	9.98	4964.38
10	600	5.05	12.61	7565.51	18.75	7546.76
15	900	4.17	10.41	9370.74	28.13	9342.61
30	1800	2.81	7.02	12829.15	56.25	12572.90
60	3600	1.74	4.34	15840.37	112.50	15527.87
180	10800	0.85	1.83	17554.97	337.50	17217.47
360	21600	0.36	0.91	19577.43	675.00	18902.43
720	43200	0.22	0.55	23730.22	1350.00	22380.22
1440	86400	0.13	0.31	26966.16	2700.00	24266.16

West Haven UT
NOAA Atlas 14




Blue Stakes Location Center
Call Toll Free 1-800-662-4111
Two Working Days Before You Dig


Revised: 9-4-14



Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30



2400 South Street



RETENTION #1 VOLUME CALCULATIONS
 HIGH WATER AREA (45.67') = 13,990 S.F.
 BOTTOM AREA (42.67') = 9,524 S.F.
 $[13,990 + 9,524] / 2 = 11,757$ S.F. AVG.
 $11,757$ S.F. x $3.00'$ DEEP = $35,271$ C.F.
 $35,271$ C.F. > $35,094$ C.F. (REQ'D.) = OK

Storm Runoff Calculations

Mallard Springs Subdivision-Basin 1

6/2/2014 set
 The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the West Haven, UT area taken from data compiled by NOAA Atlas 14, using a 100 year storm.
 Runoff storm water has been calculated for two different sets of conditions, one being the existing undeveloped land and the other with land fully improved. The difference between the two quantities will be retained in a holding pond.

The calculations are as follows:

1. Runoff from the undeveloped existing land.			
Runoff Quantity	Q =	0 cfs	
Area	A =	9.93 ACRES	
Perc Rate		27.00 mpi	
Q(out) =		0.07 CFS	
2. Runoff from developed land			
Runoff Coefficients			
Paved Area		72,310	C = 0.9
Landscaped Area		320,014	C = 0.2
Roof		40,227	C = 0.8
Weighted Runoff Coefficient			C = 0.37
Rainfall Intensity	i =	varies with time	
Runoff Quantity	Q =	CIA	
3. Detention Basin			
Volume in	Q * t		
Volume out	0.07 * t		

The capacity of the retention basin is calculated as the maximum difference between the volume flowing in and the volume flowing out.
 The outflow from the retention basin is limited to outflow if undeveloped. Use 0.07 cfs for Q outflow

The required volume of the retention basin is 33,760 cubic feet
 Bottom Area of Basin Percolation out of Basin
 14000 s.f. $(1 \text{ in} / \text{Parc}) * (1 \text{ ft} / 12 \text{ in}) * (1 \text{ min} / 60 \text{ sec}) * \text{Area of Basin}$ 0.72


RETENTION BASIN

Cumulative Volume For Detention Pond
 Mallard Springs Subdivision-Basin 1


C = 0.37
 A = 9.93
 Q(out) = 0.07

time (min)	time (sec)	i (in./hr.)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0.00	0.00	0.00
5	300	6.64	24.58	7374.58	21.60	7352.97
10	600	5.05	18.70	11217.36	43.21	11174.15
15	900	4.17	15.44	13893.97	64.81	13829.16
30	1800	2.81	10.40	18725.21	129.63	18595.58
60	3600	1.74	6.44	23189.94	259.26	22930.68
180	10800	0.65	2.41	26028.71	777.78	25250.93
360	21600	0.36	1.34	29027.41	1555.56	27471.86
720	43200	0.22	0.83	35664.53	3111.11	32553.42
1440	86400	0.13	0.46	39982.66	6222.22	33760.44

West Haven UT
 NOAA Atlas 14



Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
 Two Working Days Before You Dig



Construction Notes:

- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
- CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.

CULINARY WATER

W/8 - 8" PVC C-900 CLASS 200 WATER

SANITARY SEWER

SS/8 - 8" ASTM D3034 SDR 35 SEWER
 SS/10 - 10" ASTM D3034 SDR 35 SEWER

STORM DRAIN

SD/15 - 15" RCP STORM DRAIN

SECONDARY WATER

SW/8 - 8" PVC C-900 SECONDARY WATER LINE


Reeve & Associates, Inc.
 920 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
 TEL: (801) 621-1100 FAX: (801) 621-2668 www.reeve-assoc.com
 CIVIL ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS



REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
 WEBER COUNTY, UTAH
2400 South Street
20+00.00 - 24+50.00

Revised: 9-4-14




Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: R. HANSEN
 Begin Date: NOVEMBER 4, 2013
 Name: MALLARD SPRINGS SUBDIVISION
 Number: 3442-A30

Sheet **16**
 8 Sheets




2400 South Street
 Horizontal Scale: 1" = 20'
 Vertical Scale: 1" = 2'



Construction Notes:

- ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
 W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
 SS/8 - 8" ASTM D3034 SDR 35 SEWER
 SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
 SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
 SW/8 - 8" PVC C-900 SECONDARY WATER LINE



Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
 Two Working Days Before You Dig


Reeve & Associates, Inc.
 820 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
 TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

RA

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
 WEBER COUNTY, UTAH

2400 South Street
 24+50.00 - 30+00.00






Project Info.
 Engineer: J. NATE REEVE, P.E.
 Drafter: R. HANSEN
 Begin Date: NOVEMBER 4, 2013
 Name: MALLARD SPRINGS SUBDIVISION
 Number: 3442-A30

Key Map NOT TO SCALE



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE




Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Reeve & Associates, Inc.
320 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com



REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments

Mallard Springs Subdivision
WEBER COUNTY, UTAH
Sanitary Sewer Outfall
5+50.00 - 11+00.00




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Sheet **16**
10 Sheets




Reeve & Associates, Inc. - Solutions You Can Build On

Revised: 9-4-14



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE




Reeve & Associates, Inc.
220 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
RAMP, BUSINESS & STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments

Mallard Springs Subdivision
WEBER COUNTY, UTAH

Sanitary Sewer Outfall
10+00.00 - 16+00.00




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION

Number: 3442-A30

Sheet **16**
11 Sheets

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Key Map NOT TO SCALE



Construction Notes:

1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.




2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.

CULINARY WATER
W/8 - 8" PVC C-900 CLASS 200 WATER

SANITARY SEWER
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER

STORM DRAIN
SD/15 - 15" RCP STORM DRAIN

SECONDARY WATER
SW/8 - 8" PVC C-900 SECONDARY WATER LINE




Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Reeve & Associates, Inc.
320 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
RAMP ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
WEBER COUNTY, UTAH
Sanitary Sewer Outfall
16+00.00 - 22+00.00





Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Sheet **16**
12 Sheets

Revised: 9-4-14



Sanitary Sewer Outfall 4300 West Street




- Construction Notes:**
- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE

Reeve & Associates, Inc.
220 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 621-3100 FAX: (801) 621-2668 www.reeve-assoc.com
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Reeve & Associates, Inc. - Solutions You Can Build On



Reeve & Associates, Inc. - Solutions You Can Build On

Mallard Springs Subdivision
WEBER COUNTY, UTAH

Sanitary Sewer Outfall - 4300 West St.
29+00.00 - 34+50.00



Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig

Key Map NOT TO SCALE


- Construction Notes:**
- 1) ALL CONSTRUCTION IS TO CONFORM TO THE STANDARD DRAWINGS AND SPECIFICATIONS OF WEBER COUNTY.
 - 2) CONSTRUCT HANDICAP RAMP PER ADA AND CITY REQUIREMENTS.
- CULINARY WATER**
W/8 - 8" PVC C-900 CLASS 200 WATER
- SANITARY SEWER**
SS/8 - 8" ASTM D3034 SDR 35 SEWER
SS/10 - 10" ASTM D3034 SDR 35 SEWER
- STORM DRAIN**
SD/15 - 15" RCP STORM DRAIN
- SECONDARY WATER**
SW/8 - 8" PVC C-900 SECONDARY WATER LINE

Reeve & Associates, Inc.
200 CHAMBERS STREET, SUITE 14, OGDEN, UTAH 84403
TEL: (801) 671-3100 FAX: (801) 671-2668 www.reeve-assoc.com
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments


Mallard Springs Subdivision
WEBER COUNTY, UTAH

Sanitary Sewer Outfall - 4300 West St.
34+50.00 - 40+00.00




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30

Sheet **16**
14 Sheets



Sanitary Sewer Outfall 4300 West Street

Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 2'




Blue Stakes Location Center
Call: Toll Free 1-800-662-4111
Two Working Days Before You Dig


MALLARD SPRINGS SUBDIVISION

Storm Water Pollution Prevention Plan Exhibit

WEBER COUNTY, UTAH
NOVEMBER 2013



Vicinity Map
NOT TO SCALE



REVISIONS	DATE	DESCRIPTION
5-2-14	RH	County Comments
9-4-14	ST	County Comments

Mallard Springs Subdivision
WEBER COUNTY, UTAH

Storm Water Pollution Prevention Plan Exhibit




Project Info.
Engineer: J. NATE REEVE, P.E.
Drafter: R. HANSEN
Begin Date: NOVEMBER 4, 2013
Name: MALLARD SPRINGS SUBDIVISION
Number: 3442-A30


Construction Activity Schedule	
- PROJECT LOCATION.....	WEBER COUNTY, UTAH
- PROJECT BEGINNING DATE.....	NOVEMBER 2013
- BMP'S DEPLOYMENT DATE.....	NOVEMBER 2013
- STORM WATER MANAGEMENT CONTACT / INSPECTOR.....	DOUG HAMBLIN (801) 731-7703
- SPECIFIC CONSTRUCTION SCHEDULE INCLUDING BMP CONSTRUCTION SCHEDULE TO BE INCLUDED WITH SWPPP BY OWNER/DEVELOPER	

Notes:

- Describe all BMP's to protect storm water inlets:
All storm water inlets to be protected by straw wattle barriers, or gravel bags (see detail).
- Describe BMP's to eliminate/reduce contamination of storm water from:
 - Equipment / building / concrete wash areas:
To be performed in designated areas only and surrounded with silt fence barriers.
 - Soil contaminated by soil amendments:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Areas of contaminated soil:
If any contaminants are found or generated, contact environmental engineer and contacts listed.
 - Fueling area:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle maintenance areas:
To be performed in designated areas only and surrounded with silt fence.
 - Vehicle parking areas:
To be performed in designated areas only and surrounded with silt fence.
 - Equipment storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Materials storage areas:
To be performed in designated areas only and surrounded with silt fence.
 - Waste containment areas:
To be performed in designated areas only and surrounded with silt fence.
 - Service areas:
To be performed in designated areas only and surrounded with silt fence.
- BMP's for wind erosion:
Stockpiles and site as needed to be watered regularly to eliminate / control wind erosion
- Construction Vehicles and Equipment:
 - Maintenance
 - Maintain all construction equipment to prevent oil or other fluid leaks.
 - Keep vehicles and equipment clean, prevent excessive build-up of oil and grease.
 - Regularly inspect on-site vehicles and equipment for leaks, and repair immediately.
 - Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment on-site.
 - Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic, and transmission fluids.
 - Fueling
 - If fueling must occur on-site, use designated areas away from drainage.
 - Locate on-site fuel storage tanks within a bermed area designed to hold the tank volume.
 - Cover retention area with an impervious material and install in a manner to ensure that any spills will be contained in the retention area. To catch spills or leaks when removing or changing fluids.
 - Use drip pans for any oil or fluid changes.
 - Washing
 - Use as little water as possible to avoid installing erosion and sediment controls for the wash area.
 - If washing must occur on-site, use designated, bermed wash areas to prevent waste water discharge into storm water, creeks, rivers, and other water bodies.
 - Use phosphate-free, biodegradable soaps.
 - Do not permit steam cleaning on-site.
- Spill Prevention and Control
 - Minor Spills:
Minor spills are those which are likely to be controlled by on-site personnel. After contacting local emergency response agencies, the following actions should occur upon discovery of a minor spill:
 - Contain the spread of the spill.
 - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (i.e. absorbent materials, cat litter, and / or rags).
 - If the spill occurs in dirt areas, immediately contain the spill by constructing an earth dike. Dig up properly dispose of contaminated soil.
 - If the spill occurs during rain, cover the impacted area to avoid runoff.
 - Record all steps taken to report and contain spill.
 - Major Spills:
On-site personnel should not attempt to control major spills until the appropriate and qualified emergency response staff have arrived at the site. For spills of federal reportable quantities, also notify the National Response Center at (800) 424-8802. A written report should be sent to all notified authorities. Failure to report major spills can result in significant fines and penalties.
- Post Roadway / Utility Construction
 - Maintain good housekeeping practices.
 - Enclose or cover building material storage areas.
 - Properly store materials such as paints and solvents.
 - Store dry and wet materials under cover, away from drainage areas.
 - Avoid mixing excess amounts of fresh concrete or cement on-site.
 - Perform washout of concrete trucks offsite or in designated areas only.
 - Do not wash out concrete trucks into storm drains, open ditches, streets or streams.
 - Do not place material or debris into streams, gutters or catch basins that stop or reduce the flow of runoff water.
 - All public streets and storm drain facilities shall be maintained free of building materials, mud and debris caused by grading or construction operations. Roads will be swept within 1000' of construction entrance daily, if necessary.
 - Install straw wattle around all inlets contained within the development and all others that receive runoff from the development.
- Erosion Control Plan Notes
 - The contractor will designate an emergency contact that can be reached 24 hours a day 7 days a week.
 - A stand-by crew for emergency work shall be available at all times during potential rain or snow runoff events. Necessary materials shall be available on site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain or runoff is eminent.
 - Erosion control devices shown on the plans and approved for the project may not be removed without approval of the engineer of record. If devices are removed, no work may continue that have the potential of erosion without consulting the engineer of record. If deemed necessary erosion control should be reestablished before this work begins.
 - Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of the slope at the conclusion of each working day. This should be confirmed by survey or other means acceptable to the engineer of record.
 - All silt and debris shall be removed from all devices within 24 hours after each rain or runoff event.
 - Except as otherwise approved by the inspector, all removable protective devices shown shall be in place at the end of each working day and through weekends until removal of the system is approved.
 - All loose soil and debris, which may create a potential hazard to offsite property, shall be removed from the site as directed by the Engineer of record of the governing agency.
 - The placement of additional devices to reduce erosion damage within the site is left to the discretion of the Engineer of record.
 - Desilting basins may not be removed or made inoperable without the approval of the engineer of record and the governing agency.
 - Erosion control devices will be modified as need as the project progresses, and plans of these changes submitted for approval by the engineer of record and the governing agency.
- Conduct a minimum of one inspection of the erosion and sediment controls every two weeks. Maintain documentation on site.
 - Part III.D.4 of general permit UTR300000 identifies the minimum inspection requirements.
 - Part II.D.4.C identifies the minimum inspection report requirements.
 - Failure to complete and/or document storm water inspections is a violation of part III.D.4 of Utah General Permit UTR 300000.



Perspective View



Section

INSTALLATION

The silt fence should be installed prior to major soil disturbances in the drainage area. The fence should be placed across the slope along a line of uniform elevation wherever flow of sediment is anticipated. Table 1 shows generally-recommended maximum slope lengths (slope spacing between fences) at various site grades for most silt fence applications.

Slope Steepness (%)	Max. Slope Length (m (ft))
<2%	30.5m (100ft)
2-5%	22.9m (75ft)
5-10%	15.2m (50ft)
10-20%	7.6m (25ft)
>20%	4.5m (15ft)

PREFABRICATED SILT FENCE ROLLS

*Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location.
*Unroll the silt fence, positioning the post against the downstream wall of the trench.
*Adjacent rolls of silt fence should be joined by nesting the end post of one fence into the other. Before nesting the end posts, rotate each post until the geotextile is wrapped completely around the post, then abut the end posts to create a tight seal as shown in Figure 1.

should generally be less than three (3) times the height of the fence.
*If a steel or plastic mesh is required to reinforce the geotextile, it shall have a minimum mesh opening of 15.2cm (6").
*Fasten the mesh to the upslope side of the posts using heavy duty wire staples, tie wires or hog strings. Extend the mesh into the bottom of the trench.
*The geotextile shall then be stapled or wired to the posts. An extra 20-50cm (8-20") of geotextile shall extend into the trench.

INSPECTION

*Inspect the silt fence daily during periods of rainfall, immediately after significant rainfall event and weekly during periods of no rainfall. Make any repairs immediately.
*When sediment deposits behind the silt fence are one-third of the fence height, remove and properly dispose of the silt accumulations. Avoid damage to the fabric during cleanout.

REMOVAL

*Silt fence should not be removed until construction ceases and the upslope area has been properly stabilized and/or revegetated.





Figure 1:
Top View of Roll-to-Roll Connection

FIELD ASSEMBLY:

*Excavate a minimum 15.2cm x 15.2cm (6"x6") trench at the desired location.
*Drive wooden posts, or steel posts with fastening projections, against the downstream wall of the trench. Maximum post spacing should be 2.4-3.0m (8-10ft). Post spacing


Silt Fence Detail

SCALE: NONE




Concrete Washout Area w/ 10 mil Plastic Liner


SCALE: NONE




Inlet Box Protection




Plan View



Drop Inlet Protection



Stake Detail



Cross Section 50' x 20' Construction Entrance

REVISIONS	DATE	DESCRIPTION
	5-2-14	RH County Comments
	9-4-14	ST County Comments

Mallard Springs Subdivision
WEBER COUNTY, UTAH
Storm Water Pollution Prevention Plan Details

Revised: 9-4-14
REGISTERED PROFESSIONAL ENGINEER
375328
J. NATE REEVE
STATE OF UTAH

Project Info.
Engineer:
J. NATE REEVE, P.E.
Drafter:
R. HANSEN
Begin Date:
NOVEMBER 4, 2013
Name:
MALLARD SPRINGS SUBDIVISION
Number: 3442-A30