



**LEGEND**

- = SECTION CORNER
- = BOUNDARY LINE
- = LOT LINE
- = ADJOINING PROPERTY
- = CENTERLINE
- = EASEMENTS
- = SECTION TIE LINE
- = PROPOSED SANITARY SEWER LINE
- = EXISTING SANITARY SEWER LINE
- = PROPOSED SECONDARY WATER LINE
- = EXISTING SECONDARY WATER LINE
- = PROPOSED CULINARY WATER LINE (SIZE VARIES)
- = EXISTING CULINARY WATER LINE
- = PROPOSED STORM DRAIN (SIZE VARIES)
- = EXISTING STORM DRAIN
- = PROPOSED STORM DRAIN (SIZE VARIES)
- = PROPOSED RE-ROUTED SLOUGH
- = EXISTING FENCE LINE
- = PROPOSED TRAIL
- = PROPOSED FIRE HYDRANT
- = EXISTING FIRE HYDRANT
- = PROPOSED SANITARY SEWER MANHOLE
- = EXISTING SANITARY SEWER/STORM DRAIN MANHOLE
- = PLUG W/ 2" BLOW-OFF
- = PROPOSED STORM DRAIN MANHOLE
- = PROPOSED SINGLE GRATE CATCH BASIN WITH BICYCLE-SAFE GRATE
- = P.U.E. = PUBLIC UTILITY EASEMENT
- = FH = FIRE HYDRANT
- = EX.FH = EXISTING FIRE HYDRANT
- = EXISTING PAVEMENT
- = PROPOSED PAVEMENT
- = PROPOSED CONCRETE
- = ROAD DEDICATION

**NOTES**

1. PIPE EXISTING DITCH ON 1800 SOUTH STREET
  2. CONTOURS ARE SHOWN WITH ONE FOOT INTERVALS
  3. PROJECT IS IN ZONE X PER FEMA FLOOD PANEL 49057C0425E, EFFECTIVE 12/16/2005
  4. DRAINAGE SLOUGH WILL BE RE-ROUTED
- PHASE 1:** 27 LOTS  
**PHASE 2:** 35 LOTS  
**PHASE 3:** 28 LOTS  
**PHASE 4:** 26 LOTS  
 TOTAL LOTS: 116



**Developer:**  
 Pat Burns  
 Lync Development  
 1407 N Mtn. Rd  
 Ogden, UT. 84404  
 (801) 710-2234

**Stagecoach Estates Subdivision**

Weber County, Utah

**Reeve & Associates, Inc.**  
 5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405  
 TEL: (801) 821-3100 FAX: (801) 821-2666 www.reeve-associates.com  
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS  
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS


REVISIONS	DATE	DESCRIPTION	COUNT	COMMENTS
	2-28-23	LOTT LAYOUT		
	4-17-23	LOTT LAYOUT		

**Stagecoach Estates Subdivision**  
 PART OF THE SE 1/4 OF SECTION 21 T.6N, R.2W, S.LB & M., U.S. SURVEY  
 WEBER COUNTY, UTAH

**Preliminary Plan**


**Project Info.**  
 Engineers: N. Reeve  
 Planner: C. Cave  
 Designer: E. Roche  
 Date: 8/01/2022  
 Name: STAGECOACH\_ESTATES SUBDIVISION  
 Number: 6298-14

Sheet	<b>2</b>
<b>1</b>	Sheets




### 1800 South Street Street Section (80' R.O.W.)

SCALE: NONE




### Street Section 'A' Street Section (80' R.O.W.)

SCALE: NONE  
\*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.



### Street Section 'C' & 'F' Street Section (66' R.O.W.)

SCALE: NONE  
\*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.



### Street Section (60' R.O.W.)

SCALE: NONE  
\*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.

### BOUNDARY DESCRIPTION

PART OF THE SOUTHEAST QUARTER OF SECTION 21 TOWNSHIP 6 NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY, MORE PARTICULARLY DESCRIBED AS FOLLOWS:  
BEGINNING AT A POINT, SAID POINT BEING 1321.79 FEET NORTH 89°15'11" WEST FROM THE SOUTHWEST CORNER OF SAID SECTION 21 (SAID SOUTHWEST CORNER BEING N00°42'33"E 2633.22 FEET FROM THE EAST QUARTER CORNER OF SAID SECTION 21); THENCE NORTH 89°15'11" WEST 1321.78 FEET; THENCE NORTH 00°42'18" EAST 1317.81 FEET ALONG THE EAST LINE OF DEGIORGIO SUBDIVISION & DEGIORGIO SUBDIVISION PHASE 2; THENCE SOUTH 89°13'37" EAST 1321.82 FEET; THENCE SOUTH 00°42'26" WEST 1317.21 FEET TO THE POINT OF BEGINNING.  
CONTAINING 1,741,488 SQUARE FEET OR 39.979 ACRES.



### Storm Runoff Calculations Stagecoach Estates Subdivision

6298-14 12/16/2022 vba

The following runoff calculations are based on the Rainfall - Intensity - Duration Frequency Curve for the Weber County area taken from the NOAA Atlas 14 database. Calculations have been completed for the 100-yr 24-hr storm event. Storm water runoff has been calculated for a fully developed site and limited to a release rate of 0.1 cfs/acre.

The calculations are as follows:

<b>Drainage Area:</b>	Total Area = 39.98 acre or	1,741,488 ft <sup>2</sup>
	Runoff Coefficients	
	Paved Area	417,838 C = 0.9
	Roof	280,000 C = 0.9
	Landscaped Area	1,043,650 C = 0.2
	Weighted Runoff Coefficient	C = 0.48

**LID Retention**

80 <sup>th</sup> Percentile Rainfall Event (d)	0.45 in
Is the site Feasible for LID?	Yes
Site Imperviousness (I)	0.40
NRCS Soil Group	C/D
Rv Equation	0.83*1.122
Rv (Soil Group A: 0.84*1.302; B: 0.84*1.169; C/D: 0.83*1.122)	0.30
V <sub>ret</sub> = Rv x d x Total Site SF	19427 c.f.

**Volume of Run-off for 100-year Storm Event:**

C	0.48					
I	See Below in/hr					
A	1741488.00 ft <sup>2</sup>					
Q(out) =	4.00 ft <sup>3</sup> /s (0.1 cfs per acre)					
time (min)	time (sec)	i (in./hr)	Q (cfs)	Vol. in (cf)	Vol. out (cf)	Difference (cf)
0	0	0.00	0.00	0	0	0
5	300	6.52	126.29	37888	1199	36688
10	600	4.96	57645	2399	55246	
15	900	4.09	79.22	71301	3598	67703
30	1800	2.76	53.46	96230	7196	89034
60	3600	1.71	33.12	119242	14392	104849
120	7200	0.929	17.99	129562	28785	100777
180	10800	0.634	12.28	132630	43177	89453
360	21600	0.353	6.84	147692	86355	61338
720	43200	0.216	4.18	180745	172710	8036
1440	86400	0.12	2.32	200828	345419	-144591

**Orifice Sizing**

Given: Q = 4.00 cfs  
Z<sub>0</sub> = 64.4 ft/s<sup>2</sup>  
H = 3.00 ft  
Cd = 0.62  
R = SQRT(Q/pi\*(0.7\*(64.4\*H)<sup>0.5</sup>))  
R = 0.38 feet  
D = 4.61 inches  
A = 9.22 inches<sup>2</sup>  
A = 66.84 inches<sup>2</sup> \* 2 = 0.4641 ft<sup>2</sup>

**SUMMARY:**  
The required 100-yr storage volume is **104,849** cubic feet  
The required LID Retention volume is **19,427** cubic feet  
Orifice size is **9.2** inches  
Note: No LID Retention to be provided due to low infiltration rate (Soil Group D)

### LINE TABLE

#	BEARING	DISTANCE
L1	S89°07'55"E	167.98'
L2	S89°07'55"E	40.01'
L3	S89°15'11"E	67.50'
L4	S89°15'11"E	60.00'
L5	S89°15'11"E	60.00'
L6	S89°15'11"E	60.00'
L7	S89°15'11"E	60.00'
L8	S89°15'11"E	60.00'
L9	S89°15'11"E	60.00'
L10	S89°15'11"E	60.00'
L11	S89°15'11"E	67.50'
L12	S89°15'11"E	60.00'
L13	S89°15'11"E	60.00'
L14	S89°15'11"E	60.00'
L15	S89°15'11"E	60.00'
L16	S89°15'11"E	60.00'
L17	S89°15'11"E	60.00'
L18	S89°15'11"E	60.00'
L19	S55°30'14"E	62.08'
L20	S00°41'20"W	72.87'

### CURVE TABLE

CURVE	RADIUS	ARC LTH	CHD LTH	CHD BEARING	DELTA
C1	217.00'	136.74'	134.49'	N72°50'27"E	36°06'12"
C2	217.00'	4.59'	4.59'	N54°11'01"E	1°12'40"
C3	250.00'	162.70'	159.84'	N72°13'20"E	37°17'17"
C4	283.00'	132.74'	131.52'	N77°24'44"E	26°52'26"
C5	283.00'	51.35'	51.28'	N58°46'36"E	10°23'49"
C6	217.00'	93.75'	93.02'	N65°57'17"E	24°45'12"
C7	250.00'	162.18'	159.35'	N72°09'45"E	37°10'08"
C8	250.00'	145.49'	143.44'	N70°14'59"E	33°20'34"
C9	250.00'	16.69'	16.69'	N88°50'03"E	3°49'33"
C10	283.00'	136.67'	135.35'	N67°24'48"E	27°40'13"
C11	30.00'	17.09'	16.88'	N15°36'41"W	32°38'13"
C12	65.00'	54.49'	52.90'	N07°54'58"W	48°01'39"
C13	65.00'	54.49'	52.90'	N40°06'41"E	48°01'39"
C14	65.00'	54.49'	52.90'	N88°08'20"E	48°01'39"
C15	65.00'	12.77'	12.75'	S62°13'07"E	11°15'27"
C16	30.00'	17.09'	16.86'	S72°54'30"E	32°38'13"
C17	20.00'	31.44'	28.30'	N45°44'24"E	90°03'58"
C18	158.00'	43.89'	43.75'	S08°39'55"W	15°55'
C19	158.00'	65.59'	65.12'	S28°30'55"W	23°47'
C20	158.00'	65.59'	65.12'	S52°17'55"W	23°47'
C21	158.00'	65.59'	65.12'	S76°04'55"W	23°47'
C22	158.00'	7.65'	7.65'	S89°21'37"W	2°46'24"
C23	125.00'	196.44'	176.84'	S45°43'37"W	90°02'24"
C24	92.00'	144.61'	130.17'	S45°43'05"W	90°03'29"
C25	92.00'	4.07'	4.06'	S01°58'23"W	2°31'54"
C26	92.00'	140.51'	127.25'	S46°59'35"W	87°30'29"
C27	158.00'	56.83'	56.52'	S80°26'37"W	20°36'25"
C28	158.00'	68.11'	67.58'	S57°47'27"W	24°41'55"
C29	125.00'	196.48'	176.87'	S45°43'02"W	90°03'34"
C30	125.00'	122.72'	117.85'	S62°37'17"W	56°15'04"
C31	125.00'	73.76'	72.69'	S17°35'30"W	33°48'50"
C32	158.00'	63.04'	62.83'	S12°07'11"W	32°51'42"
C33	95.00'	55.96'	55.15'	N72°22'43"W	33°44'56"
C34	125.00'	73.63'	72.57'	N72°22'43"W	33°44'56"
C35	155.00'	41.03'	40.91'	N63°05'15"W	15°10'02"
C36	155.00'	15.59'	15.58'	N73°33'10"W	5°45'48"
C37	155.00'	34.68'	34.61'	N82°50'37"W	12°49'07"
C38	20.00'	12.06'	11.88'	S73°28'01"W	34°33'37"
C39	65.00'	75.69'	71.49'	S89°32'50"W	66°43'15"
C40	65.00'	15.03'	15.00'	N50°27'59"W	13°15'07"
C41	65.00'	55.43'	53.77'	N19°24'36"W	48°51'41"
C42	65.00'	34.31'	33.92'	N20°08'38"E	30°14'48"
C43	20.00'	12.06'	11.88'	N17°59'14"E	34°33'37"
C44	20.00'	31.40'	28.27'	S44°16'23"E	89°57'36"

# Stagecoach Estates Subdivision

Weber County, Utah

**Reeve & Associates, Inc.**  
5160 SOUTH 1500 WEST RIVERDALE, UTAH 84405  
TEL: (801) 821-3100 FAX: (801) 821-2666 WWW.REEVE-ASSOCIATES.COM  
LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS  
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

**REVISIONS**

DATE	DESCRIPTION	COUNT	COMMENTS
2-28-23			
4-17-23			

**Stagecoach Estates Subdivision**  
PART OF THE SE 1/4 OF SECTION 21 T.6N, R.2W, S.LB & M., U.S. SURVEY  
WEBER COUNTY, UTAH

**Preliminary Plan**

**Project Info.**  
Engineer: N. Reeve  
Planner: C. Cave  
Designer: E. Roche  
Date: 8/01/2022  
Name: STAGECOACH\_ESTATES SUBDIVISION  
Number: 6298-14

Sheet	2
2	Sheets